

## Product Change Notification / SYST-17PIBM233

D	a	t	ρ	•
u	a	L	c	

18-Nov-2021

## **Product Category:**

8-bit Microcontrollers

## **PCN Type:**

**Document Change** 

## **Notification Subject:**

Data Sheet - PIC16(L)F15354/55 Full-Featured 28-Pin Microcontrollers Data Sheet

## **Affected CPNs:**

SYST-17PIBM233\_Affected\_CPN\_11182021.pdf SYST-17PIBM233\_Affected\_CPN\_11182021.csv

## **Notification Text:**

SYST-17PIBM233

Microchip has released a new Product Documents for the PIC16(L)F15354/55 Full-Featured 28-Pin Microcontrollers Data Sheet of devices. If you are using one of these devices please read the document located at PIC16(L)F15354/55 Full-Featured 28-Pin Microcontrollers Data Sheet.

Notification Status: Final

#### **Description of Change:**

- 1. Updated terminology used throughout the data sheet: "master" replaced by "host", and "slave" replaced by "client". Replaced ADCRC appearances with FRC.
- 2. Updated package information to include QFN and VQFN (6x6mm) packaging replaces PDIP with SPDIP packaging.
- 3. Updated figures 30-1, 30-2, 30-3 and 30-4. CWGxISM replaced with CWG1DAT. Updated Tables 4-10, 29-2, 31-2, 31-4, 36-3 and 37-6, and Figures 37-5, 37-9 and 37-10.

Impacts to Data Sheet: See above details.

Reason for Change: To Improve Productivity

Change Implementation Status: Complete

**Date Document Changes Effective:** 18 Nov 2021

NOTE: Please be advised that this is a change to the document only the product has not been changed.

Markings to Distinguish Revised from Unrevised Devices: N/A

## **Attachments:**

PIC16(L)F15354/55 Full-Featured 28-Pin Microcontrollers Data Sheet

Please contact your local Microchip sales office with questions or concerns regarding this notification.

### **Terms and Conditions:**

If you wish to <u>receive Microchip PCNs via email</u> please register for our PCN email service at our <u>PCN</u> home page select register then fill in the required fields. You will find instructions about registering for Microchips PCN email service in the <u>PCN FAQ</u> section.

If you wish to <u>change your PCN profile</u>, <u>including opt out</u>, please go to the <u>PCN home page</u> select login and sign into your myMicrochip account. Select a profile option from the left navigation bar and make the applicable selections.



# PIC16(L)F15354/55

## **Full-Featured 28-Pin Microcontrollers**

## Description

PIC16(L)F15354/55 microcontrollers feature analog, Core Independent Peripherals and communication peripherals, combined with eXtreme Low-Power (XLP) technology for a wide range of general purpose and low-power applications.

The devices feature multiple PWMs, multiple communication, temperature sensor, and memory features like Memory Access Partition (MAP) to support customers in data protection and bootloader applications, and Device Information Area (DIA) which stores factory calibration values to help improve temperature sensor accuracy.

#### Core Features

- C Compiler Optimized RISC Architecture
- Operating Speed:
  - DC 32 MHz clock input
  - 125 ns minimum instruction cycle
- Interrupt Capability
- 16-Level Deep Hardware Stack
- - 8-bit Timer2 with Hardware Limit Timer (HLT)
  - 16-bit Timer0/1
- · Low-Current Power-on Reset (POR)
- Configurable Power-up Timer (PWRTE)
- Brown-out Reset (BOR)
- Low-Power BOR (LPBOR) Option
- Windowed Watchdog Timer (WWDT):
  - Variable prescaler selection
  - Variable window size selection
  - All sources configurable in hardware or software
- Programmable Code Protection

### Memory

- Up to 14 KB Flash Program Memory
- Up to 1024 Bytes Data SRAM
- Direct, Indirect and Relative Addressing Modes
- Memory Access Partition (MAP):
  - Write-protect
  - Customizable Partition
- Device Information Area (DIA)
- Device Configuration Information (DCI)
- High-Endurance Flash (HEF)
  - Last 128 words of Program Flash Memory

## Operating Characteristics

- Operating Voltage Range:
  - 1.8V to 3.6V (PIC16LF15354/55)
  - 2.3V to 5.5V (PIC16F15354/55)
- · Temperature Range:
  - Industrial: -40°C to 85°C
  - Extended: -40°C to 125°C

## Power-Saving Functionality

- · Doze mode: Ability to Run the CPU Core Slower Than the System Clock
- · Idle mode: Ability to Halt CPU Core while Internal Peripherals Continue Operating
- · Sleep mode: Lowest Power Consumption
- Peripheral Module Disable (PMD):
  - Ability to disable hardware module to minimize active power consumption of unused peripherals

## eXtreme Low-Power (XLP) Features

- Sleep Mode: 50 nA @ 1.8V, typical
- Watchdog Timer: 500 nA @ 1.8V, typical
- Secondary Oscillator: 500 nA @ 32 kHz
- · Operating Current:
  - 8 μA @ 32 kHz, 1.8V, typical
  - 32 μA/MHz @ 1.8V, typical

## **Digital Peripherals**

- Four Configurable Logic Cells (CLC):
  - Integrated combinational and sequential logic
- Complementary Waveform Generator (CWG):
  - Rising and falling edge dead-band control
  - Full-bridge, half-bridge, 1-channel drive
  - Multiple signal sources
- · Two Capture/Compare/PWM (CCP) Module:
  - 16-bit resolution for Capture/Compare modes
  - 10-bit resolution for PWM mode
- Four 10-Bit PWMs
- · Numerically Controlled Oscillator (NCO):
  - Generates true linear frequency control and increased frequency resolution
  - Input Clock: 0 Hz < F<sub>NCO</sub> < 32 MHz</li>
     Resolution: F<sub>NCO</sub>/2<sup>20</sup>
- Two EUSART, RS-232, RS-485, LIN Compatible
- Two SPI
- Two I<sup>2</sup>C, SMBus, PMBus™ Compatible

## Digital Peripherals (Cont.)

- I/O Pins:
  - Individually programmable pull-ups
  - Slew rate control
  - Interrupt-on-change with edge-select
  - Input level selection control (ST or TTL)
  - Digital open-drain enable
- Peripheral Pin Select (PPS):
  - Enables pin mapping of digital I/O

## **Analog Peripherals**

- Analog-to-Digital Converter (ADC):
  - 10-bit with up to 43 external channels
  - Operates in Sleep
- Two Comparators:
  - FVR, DAC and external input pin available on inverting and noninverting input
  - Software selectable hysteresis
  - Outputs available internally to other modules, or externally through PPS
- · 5-Bit Digital-to-Analog Converter (DAC):
  - 5-bit resolution, rail-to-rail
  - Positive Reference Selection
  - Unbuffered I/O pin output
  - Internal connections to ADCs and comparators
- · Voltage Reference:
  - Fixed Voltage Reference with 1.024V, 2.048V and 4.096V output levels
- · Zero-Cross Detect Module:
  - AC high voltage zero-crossing detection for simplifying TRIAC control
  - Synchronized switching control and timing

## Flexible Oscillator Structure

- · High-Precision Internal Oscillator:
  - Software selectable frequency range up to 32 MHz, ±1% typical
- x2/x4 PLL with Internal and External Sources
- Low-Power Internal 32 kHz Oscillator (LFINTOSC)
- External 32 kHz Crystal Oscillator (SOSC)
- External Oscillator Block with:
  - Three crystal/resonator modes up to 20 MHz
  - Three external clock modes up to 32 MHz
- · Fail-Safe Clock Monitor:
  - Allows for safe shutdown if primary clock stops
- · Oscillator Start-up Timer (OST):
  - Ensures stability of crystal oscillator resources

TABLE 1: PIC16(L)F153XX FAMILY TYPES

Device	Data Sheet Index	Program Flash Memory (KW)	Program Flash Memory (KB)	Storage Area Flash (B)	Data SRAM (bytes)	I/OPins	10-bit ADC	5-bit DAC	Comparator	8-bit/ (with HLT) Timer	16-bit Timer	Window Watchdog Timer	CCP/10-bit PWM	CWG	NCO	CLC	Zero-Cross Detect	Temperature Indicator	Memory Access Partition	Device Information Area	EUSART/ 12C-SPI	Peripheral Pin Select	Peripheral Module Disable	Debug <sup>(1)</sup>
PIC16(L)F15313	(C)	2	3.5	224	256	6	5	1	1	1	2	Y	2/4	1	1	4	Υ	Υ	Υ	Υ	1/1	Y	Υ	I
PIC16(L)F15323	(C)	2	3.5	224	256	12	11	1	2	1	2	Y	2/4	1	1	4	Υ	Υ	Υ	Υ	1/1	Y	Y	1
PIC16(L)F15324	(D)	4	7	224	512	12	11	1	2	1	2	Y	2/4	1	1	4	Υ	Υ	Υ	Υ	2/1	Y	Υ	1
PIC16(L)F15325	(B)	8	14	224	1024	12	11	1	2	1	2	>	2/4	1	1	4	Y	Υ	Υ	Υ	2/1	Y	Υ	I.
PIC16(L)F15344	(D)	4	7	224	512	18	17	1	2	1	2	>	2/4	1	1	4	Υ	Υ	Υ	Υ	2/1	Y	Υ	1
PIC16(L)F15345	(B)	8	14	224	1024	18	17	1	2	1	2	Y	2/4	1	1	4	Υ	Υ	Υ	Υ	2/1	Y	Y	I
PIC16(L)F15354	(A)	4	7	224	512	25	24	1	2	1	2	Y	2/4	1	1	4	Υ	Υ	Υ	Υ	2/2	Y	Y	1
PIC16(L)F15355	(A)	8	14	224	1024	25	24	1	2	1	2	Y	2/4	1	1	4	Y	Y	Y	Υ	2/2	Y	Υ	1
PIC16(L)F15356	(E)	16	28	224	2048	25	24	1	2	1	2	Y	2/4	1	1	4	Υ	Υ	Υ	Υ	2/2	Υ	Υ	1
PIC16(L)F15375	(E)	8	14	224	1024	36	35	1	2	1	2	Υ	2/4	1	1	4	Y	Υ	Υ	Υ	2/2	Y	Υ	1
PIC16(L)F15376	(E)	16	28	224	2048	36	35	1	2	1	2	Υ	2/4	1	1	4	Υ	Υ	Υ	Υ	2/2	Υ	Υ	1
PIC16(L)F15385	(E)	8	14	224	1024	44	43	1	2	1	2	Υ	2/4	1	1	4	Y	Υ	Υ	Υ	2/2	Υ	Y	1
PIC16(L)F15386	(E)	16	28	224	2048	44	43	1	2	1	2	Y	2/4	1	1	4	Y	Υ	Y	Y	2/2	Y	Y	1

Note 1: I - Debugging integrated on chip.

## Data Sheet Index:

A: DS40001853 PIC16(L)F15354/5 Data Sheet, 28-Pin
B: DS40001865 PIC16(L)F15325/45 Data Sheet, 14/20-Pin
C: DS40001897 PIC16(L)F15313/23 Data Sheet, 8/14-Pin
D: DS40001889 PIC16(L)F15324/44 Data Sheet, 14/20-Pin

E: DS40001866 PIC16(L)F15356/75/76/85/86 Data Sheet, 28/40/48-Pin


Note: For other small form-factor package availability and marking information, visit www.microchip.com/ packaging or contact your local sales office.

# PIC16(L)F15354/55

## TABLE 2: PACKAGES

Device	SPDIP	SOIC	SSOP	UQFN (4x4)	VQFN/QFN (6x6)
PIC16(L)F15354	•	•	•	•	•
PIC16(L)F15355	•	•	•	•	•

## **PIN DIAGRAMS**



- Note 1: See Table 3 for location of all peripheral functions.
  - 2: All VDD and all VSS pins must be connected at the circuit board level. Allowing one or more VSS or VDD pins to float may result in degraded electrical performance or non-functionality.

RC1 RC2 RC3 RC4 RC5 RC5 RC5

15 RC7

3: The bottom pad of the QFN/UQFN package must be connected to Vss at the circuit board level.

## PIN ALLOCATION TABLES

28-PIN ALLOCATION TABLE (PIC16(L)F15354, PIC16(L)F15355) TABLE 3:

NO(2)	28-Pin SPDIP/SOIC/SSOP	28-Pin UQFN/VQFN/QFN	ADC	Reference	Comparator	NCO	DAC	Timers	doo	WAM	CWG	MSSP	ZCD	EUSART	CLC	CLKR	Interrupt	dn-IIn-d	Basic
RA0	2	27	ANA0	-	C1IN0- C2IN0-		-	Ī	1		-	+	-	-	CLCINO <sup>(1)</sup>	-	IOCA0	Υ	
RA1	3	28	ANA1	-	C1IN1- C2IN1-	8-8	_	-	1		-	=	-	:	CLCIN1(1)	33—3	IOCA1	Υ	39—3
RA2	4	1	ANA2	-	C1IN0+ C2IN0+		DAC1OUT1	Ī	-	-	-	-	-	2 <del></del> 2	-		IOCA2	Υ	i — i
RA3	5	2	ANA3	VREF+	C1IN1+		DAC1REF+	-	122	-	_			_s=s_		8-1	IOCA3	Υ	8-8
RA4	6	3	ANA4	,	-	1-1	-	TOCKI	-	-			-	s=s	_	-	IOCA4	Υ	
RA5	7	4	ANA5	·	-	; ,—,,,	_	77 <del>-</del> 2	19-00		-	SS1 <sup>(1)</sup>		. —			IOCA5	Υ	, n <del>-</del>
RA6	10	7	ANA6		T.	_		L		_	_	_	=	-	_	-	IOCA6	Υ	CLKOUT OSC2
RA7	9	6	ANA7	-	122	828	==	1-1	<b>2</b>		200	=	1227	3 <b>—</b> 8	_	-	IOCA7	Υ	CLKIN OSC1
RB0	21	18	ANB0	-	C2IN1+	_	_	_		_	CWG1IN <sup>(1)</sup>	SS2 <sup>(1)</sup>	ZCD1	_	-	-	INT <sup>(1)</sup> IOCB0	Υ	_
RB1	22	19	ANB1	12	C1IN3- C2IN3-	NEW	<u> </u>	724	1223	V=#	22	SCK2, SCL2 <sup>(1,4)</sup>	<u>-50</u> 3	REN	(22)	W_8	IOCB1	Υ	N=8
RB2	23	20	ANB2	-	==		_	-	<u></u>	72		SDA2, SDI2 <sup>(1,4)</sup>	222	_	_	-	IOCB2	Υ	-
RB3	24	21	ANB3	1 <u>—</u> 1	C1IN2- C2IN2-	( <u>-</u> 17	+ <u>122-</u> 2	7 <u>—</u> 8	<u> </u>	V=4	23	<u></u> ;	<u>50</u> 1	8 <u>-</u> 87	22	N_B	ЮСВ3	Υ	W <u>-</u> 8
RB4	25	22	ANB4 ADACT <sup>(1)</sup>	-	22			-	\$ <u>550</u>		_	_	_	_		-	ЮСВ4	Υ	_
RB5	26	23	ANB5	33-3	8=	85=88		T1G <sup>(1)</sup>	Feet 1	-	-	<del></del>	750.8	3-2	=	3-3	IOCB5	Υ	35 <b>—</b> 3
RB6	27	24	ANB6	-	-		-	Ī	Ţ	-	-	Ŧ	-	TX2 CK2 <sup>(1)</sup>	CLCIN2 <sup>(1)</sup>		IOCB6	Υ	ICSPCLK
RB7	28	25	ANB7	·	· ·	8 <del>-</del> 8	DAC1OUT2	2-2	-	1 2	-	-	-	RX2 DT2 <sup>(1)</sup>	CLCIN3(1)	35—8	ЮСВ7	Υ	ICSPDAT

Note

This is a PPS remappable input signal. The input function may be moved from the default location shown to one of several other PORTx pins.

All digital output signals shown in this row are PPS remappable. These signals may be mapped to output onto one or more PORTx pin options.

This is a bidirectional signal. For normal module operation, the firmware may map this signal to the same pin in both the PPS input and PPS output registers.

These pins are configured for I<sup>2</sup>C logic levels. PPS assignments to the other pins will operate, but input logic levels will be standard TTL/ST as selected by the INLVL register, instead of the I<sup>2</sup>C specific or SMBus input buffer thresholds. 1: 2: 3: 4:

PIC16(L)F15354/55

TABLE 3:

RE3

VDD

Vss

Vss

OUT(2)

VOFNOFN

26

17

-

C10UT

C2OUT

NCO10UT

20

8 16

19 5

20/1	28-Pin SPDIP/§	28-Pin UQFNA	ADC	Refere	Compar	NCC	DAC	Time	900	PWM	CWC	MSS	ZCD	EUSA	GLC	CLK	Intern	-In-	Basi
RCO	11	8	ANC0	-	-	-		SOSCO T1CKI	_		<u> </u>	<u></u>		-	_	-	IOCC0	Υ	
RC1	12	9	ANC1	25-3	1000	85 <del>-3</del> 8		SOSCI	CCP2(1)		20		220	8-8 J	<u> 22</u> 7	V-3	IOCC1	Υ	
RC2	13	10	ANC2	-	-	-	-	-	CCP1 <sup>(1)</sup>	-	-	-	-	·	-	-	IOCC2	Υ	
RC3	14	11	ANC3	15 <u>—</u> 1	1922 1922	1-21	-	T2IN(1)	( <del>***</del> )	_	-	SCL1, SCK1 <sup>(1,4)</sup>	-	9 <b>—</b> 8	-	-	юссз	Υ	::
RC4	15	12	ANC4	-	-	_	_			-	_	SDA1, SDI1 <sup>(1,4)</sup>	_	-	_	-	IOCC4	Υ	_
RC5	16	13	ANC5	×-2	1500		100	V-19	<u> 220</u>		22		<u>120</u> 9		_		IOCC5	Υ	-
RC6	17	14	ANC6	-	-	-	-	1-	-	) <del>_</del>	-	<del></del>	1856	TX1 CK1 <sup>(1)</sup>			IOCC6	Υ	, s=s
RC7	18	15	ANC7	3-3	-		-	-	=	-	-	-	. Institut	RX1 DT1 <sup>(1)</sup>	-	3:-3	IOCC7	Υ	s==s

-

CCP1

CCP2

MCLR VPP

VDD

Vss

Vss

-

-

PIC16(L)F15354/55

IOCE3

\_

-

DT(1,2)

CK(1,2)

TX(1,2)

\_

CLC10UT

CLC2OUT

CLC3OUT

CLC4OUT

CLKR

SDA1<sup>(3,4)</sup> SDA2<sup>(3,4)</sup> CWG1D CWG2D Note

-

\_

\_

This is a PPS remappable input signal. The input function may be moved from the default location shown to one of several other PORTx pins. All digital output signals shown in this row are PPS remappable. These signals may be mapped to output onto one or more PORTx pin options. 1:

28-PIN ALLOCATION TABLE (PIC16(L)F15354, PIC16(L)F15355) (CONTINUED)

TMRO

This is a bidirectional signal. For normal module operation, the firmware may map this signal to the same pin in both the PPS input and PPS output registers.

These pins are configured for I<sup>2</sup>C logic levels. PPS assignments to the other pins will operate, but input logic levels will be standard TTL/ST as selected by the INLVL register, instead of the I<sup>2</sup>C specific or SMBus input buffer thresholds.

PWM3OUT

PWM4OUT

PWM6OUT

CWG1A

CWG2A CWG1B CWG2B

CWG1C

CWG2C

SDO1/2

SCK1/2

SCL1<sup>(3,4)</sup> SCL2<sup>(3,4)</sup>

# PIC16(L)F15354/55

## **Table of Contents**

1.0 Device Overview	
2.0 Guidelines for Getting Started with PIC16(L)F15354/55 Microcontrollers	19
3.0 Enhanced Mid-Range CPU	22
4.0 Memory Organization	24
5.0 Device Configuration	
6.0 Device Information Area	86
7.0 Device Configuration Information	88
8.0 Resets	89
9.0 Oscillator Module (with Fail-Safe Clock Monitor)	100
10.0 Interrupts	
11.0 Power-Saving Operation Modes	
12.0 Windowed Watchdog Timer (WWDT)	
13.0 Nonvolatile Memory (NVM) Control	154
14.0 /O Ports	
15.0 Peripheral Pin Select (PPS) Module	
16.0 Peripheral Module Disable	203
17.0 Interrupt-On-Change	211
18.0 Fixed Voltage Reference (FVR)	221
19.0 Temperature Indicator Module	224
20.0 Analog-to-Digital Converter (ADC) Module	226
21.0 5-Bit Digital-to-Analog Converter (DAC1) Module	240
22.0 Numerically Controlled Oscillator (NCO) Module	245
23.0 Comparator Module	255
24.0 Zero-Cross Detection (ZCD) Module	265
25.0 Timer0 Module	271
26.0 Timer1 Module with Gate Control	277
27.0 Timer2 Module With Hardware Limit Timer (HLT)	291
28.0 Capture/Compare/PWM Modules	312
29.0 Pulse-Width Modulation (PWM)	323
30.0 Complementary Waveform Generator (CWG) Module	330
31.0 Configurable Logic Cell (CLC)	
32.0 Host Synchronous Serial Port (MSSPx) Modules	
33.0 Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART)	423
34.0 Reference Clock Output Module	
35.0 n-Circuit Serial Programming™ (ICSP™)	455
36.0 Instruction Set Summary	457
37.0 Electrical Specifications	470
38.0 DC and AC Characteristics Graphs and Charts	499
39.0 Development Support	519
40.0 Packaging Information	
Appendix A: Data Sheet Revision History	
The Microchip Website	
Customer Change Notification Service	
Customer Support	538
Product Identification System	530

## TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at docerrors@microchip.com. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Website at:

#### http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000000A is version A of document DS30000000).

#### Errata

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Website; http://www.microchip.com
- Your local Microchip sales office (see last page)

When contacting a sales office, please specify which device, revision of silicon and data sheet (include literature number) you are using.

### **Customer Notification System**

Register on our website at www.microchip.com to receive the most current information on all of our products.

## 1.0 DEVICE OVERVIEW

The PIC16(L)F15354/55 are described within this data sheet. The PIC16(L)F15354/55 devices are available in 28-pin SPDIP, SSOP, SOIC, VQFN, QFN and UQFN packages. Figure 1-1 shows the block diagram of the PIC16(L)F15354/55 devices. Table 1-2 shows the pinout descriptions.

Reference Table 1-1 for peripherals available per device.

TABLE 1-1: DEVICE PERIPHERAL SUMMARY

Peripheral		PIC16(L)F15354/55
Analog-to-Digital Converter		•
Digital-to-Analog Converter (DAC1)	Ÿ	•
Fixed Voltage Reference (FVR)		•
Numerically Controlled Oscillator (NCO1)		•
Temperature Indicator Module (TIM)		•
Zero-Cross Detect (ZCD1)		•
Capture/Compare/PWM Modules (CCP)		
	CCP1	
	CCP2	•
Comparator Module (Cx)		
A	C1	•
	C2	•
Configurable Logic Cell (CLC)		
	CLC1	•
	CLC2	•
	CLC3	•
	CLC4	•
Complementary Waveform Generator (CWG)		
	CWG1	•
Enhanced Universal Synchronous/Asynchron Receiver/Transmitter (EUSART)	ous	
	EUSART1	•
	EUSART2	•
Host Synchronous Serial Ports (MSSP)		
	MSSP1	•
	MSSP2	•
Pulse-Width Modulator (PWM)		
	PWM3	•
	PWM4	•
	PWM5	•
	PWM6	•
Timers		
	Timer0	•
	Timer1	•
	limer2	•

## 1.1 Register and Bit Naming Conventions

### 1.1.1 REGISTER NAMES

When there are multiple instances of the same peripheral in a device, the peripheral control registers will be depicted as the concatenation of a peripheral identifier, peripheral instance, and control identifier. The control registers section will show just one instance of all the register names with an 'x' in the place of the peripheral instance number. This naming convention may also be applied to peripherals when there is only one instance of that peripheral in the device to maintain compatibility with other devices in the family that contain more than one.

## 1.1.2 BIT NAMES

There are two variants for bit names:

- · Short name: Bit function abbreviation
- · Long name: Peripheral abbreviation + short name

#### 1.1.2.1 Short Bit Names

Short bit names are an abbreviation for the bit function. For example, some peripherals are enabled with the EN bit. The bit names shown in the registers are the short name variant.

Short bit names are useful when accessing bits in C programs. The general format for accessing bits by the short name is RegisterNamebits.ShortName. For example, the enable bit, EN, in the COG1CON0 register can be set in C programs with the instruction COG1CON0bits.EN = 1.

Short names are generally not useful in assembly programs because the same name may be used by different peripherals in different bit positions. When this occurs, during the include file generation, all instances of that short bit name are appended with an underscore plus the name of the register in which the bit resides to avoid naming contentions.

#### 1.1.2.2 Long Bit Names

Long bit names are constructed by adding a peripheral abbreviation prefix to the short name. The prefix is unique to the peripheral thereby making every long bit name unique. The long bit name for the COG1 enable bit is the COG1 prefix, G1, appended with the enable bit short name, EN, resulting in the unique bit name G1EN.

Long bit names are useful in both C and assembly programs. For example, in C the COG1CON0 enable bit can be set with the G1EN = 1 instruction. In assembly, this bit can be set with the BSF COG1CON0, G1EN instruction.

#### 1.1.2.3 Bit Fields

Bit fields are two or more adjacent bits in the same register. Bit fields adhere only to the short bit naming convention. For example, the three Least Significant bits of the COG1CON0 register contain the mode control bits. The short name for this field is MD. There is no long bit name variant. Bit field access is only possible in C programs. The following example demonstrates a C program instruction for setting the COG1 to the Push-Pull mode:

```
COG1CON0bits.MD = 0x5;
```

Individual bits in a bit field can also be accessed with long and short bit names. Each bit is the field name appended with the number of the bit position within the field. For example, the Most Significant mode bit has the short bit name MD2 and the long bit name is G1MD2. The following two examples demonstrate assembly program sequences for setting the COG1 to Push-Pull mode:

#### Example 1:

```
MOVLW ~(1<<G1MD1)
ANDWF COG1CON0,F
MOVLW 1<<G1MD2 | 1<<G1MD0
IORWF COG1CON0,F
```

#### Example 2:

BSF	COG1CON0, G1MD2
BCF	COG1CON0, G1MD1
BSF	COG1CONO, G1MDO

## 1.1.3 REGISTER AND BIT NAMING EXCEPTIONS


## 1.1.3.1 Status, Interrupt, and Mirror Bits

Status, interrupt enables, interrupt flags, and mirror bits are contained in registers that span more than one peripheral. In these cases, the bit name shown is unique so there is no prefix or short name variant.

### 1.1.3.2 Legacy Peripherals

There are some peripherals that do not strictly adhere to these naming conventions. Peripherals that have existed for many years and are present in almost every device are the exceptions. These exceptions were necessary to limit the adverse impact of the new conventions on legacy code. Peripherals that do adhere to the new convention will include a table in the registers section indicating the long name prefix for each peripheral instance. Peripherals that fall into the exception category will not have this table. These peripherals include, but are not limited to, the following:

- EUSART
- MSSP



PIC16(L)F15354/55

**TABLE 1-2:** PIC16(L)F15354/55 PINOUT DESCRIPTION

Name	Function	Input Type	Output Type	Description
RA0/ANA0/C1IN0-/C2IN0-/CLCIN0 <sup>(1)</sup> / IOCA0	RA0	πυsτ	CMOS/OD	General purpose I/O.
IOCAU	ANA0	AN	-	ADC Channel A0 input.
	C1IN0-	AN	7 <u></u> 21	Comparator 1 negative input.
	C2IN0-	AN	( <u></u> )	Comparator 2 negative input.
	CLCINO(1)	TTL∕ST	-	Configurable Logic Cell source input.
	IOCA0	TTL/ST		Interrupt on change input.
RA1/ANA1/C1IN1-/C2IN1-/CLCIN1(1)/	RA1	TTL/ST	CMOS/OD	General purpose I/O.
IOCA1	ANA1	AN	-	ADC Channel A1 input.
	C1IN1-	AN		Comparator 1 negative input.
	C2IN1-	AN	<u> </u>	Comparator 2 negative input.
	CLCIN1(1)	TTL∕ST	-	Configurable Logic Cell source input.
	IOCA1	TTL/ST		Interrupt-on-change input.
RA2/ANA2/C1IN0+/C2IN0+/	RA2	TTL/ST	CMOS/OD	General purpose I/O.
DAC1OUT1/IOCA2	ANA2	AN		ADC Channel A2 input.
	C1IN0+	AN	<u> </u>	Comparator 2 positive input.
	C2IN0+	AN		Comparator 2 positive input.
	DAC1OUT1	_	AN	Digital-to-Analog Converter output.
	IOCA2	TTL/ST	-	Interrupt-on-change input.
RA3/ANA3/C1IN1+/VREF+/IOCA3/	RA3	TTL/ST	CMOS/OD	General purpose I/O.
DAC1REF+	ANA3	AN	<u> </u>	ADC Channel A3 input.
	C1IN1+	AN	_	Comparator 1 positive input.
	VREF+	AN		External ADC and/or DAC positive reference input.
	IOCA3	TTL/ST	1 <del></del>	Interrupt-on-change input.
	DAC1REF+	TTL/ST	AN	DAC positive reference.
RA4/ANA4/T0CKI <sup>(1)</sup> /IOCA4	RA4	TTL/ST	CMOS/OD	General purpose I/O.
	ANA4	AN		ADC Channel A4 input.
	T0CKI <sup>(1)</sup>	TTL/ST		Timer0 clock input.
	IOCA4	TTL∕ST	-	Interrupt-on-change input.
RA5/ANA5/SS1 <sup>(1)</sup> /IOCA5	RA5	TTL/ST	CMOS/OD	General purpose I/O.
	ANA5	AN	N-50	ADC Channel A5 input.
	SS1 <sup>(1)</sup>	TTL/ST		MSSP1 SPI client select input.
	IOCA5	TTL∕ST	-	Interrupt-on-change input.

CMOS = CMOS compatible input or output Legend: AN = Analog input or output = Open-Drain

OD I<sup>2</sup>C TTL = TTL compatible input ST Schmitt Trigger input with CMOS levels = Schmitt Trigger input with I<sup>2</sup>C HV = High Voltage = Crystal levels XTAL

This is a PPS remappable input signal. The input function may be moved from the default location shown to one of several other PORTx 1: Note pins. Refer to Table 15-1 for details on which PORT pins may be used for this signal.

All output signals shown in this row are PPS remappable. These signals may be mapped to output onto one of several PORTx pin options as described in Table 15-3.

3: This is a bidirectional signal. For normal module operation, the firmware may map this signal to the same pin in both the PPS input and PPS output registers.

These pins are configured for  $l^2C$  logic levels. The SCLx/SDAx signals may be assigned to any of the RB1/RB2/RC3/RC4 pins. PPS assignments to the other pins (e.g., RA5) will operate, but input logic levels will be standard TTL/ST, as selected by the INLVL register, instead of the  $l^2C$  specific or SMBus input buffer thresholds.

TABLE 1-2: PIC16(L)F15354/55 PINOUT DESCRIPTION (CONTINUED)

Name	Function	Input Type	Output Type	Description
RA6/ANA6/OSC2/CLKOUT/IOCA6	RA6	TTL/ST	CMOS/OD	General purpose I/O.
	ANA6	AN		ADC Channel A6 input.
	OSC2	: <u>-</u>	XTAL	External Crystal/Resonator (LP, XT, HS modes) driver output.
	CLKOUT	1	CMOS/OD	Fosc/4 digital output (in non-crystal/resonator modes).
	IOCA6	TTL/ST		Interrupt-on-change input.
RA7/ANA7/OSC1/CLKIN/IOCA7	RA7	TTL/ST	CMOS/OD	General purpose I/O.
	ANA7	AN	_	ADC Channel A7 input.
	OSC1	XTAL	_	External Crystal/Resonator (LP, XT, HS modes) driver input.
	CLKIN	TTL/ST	-	External digital clock input.
	IOCA7	TTL/ST	-	Interrupt-on-change input.
RB0/ANB0/C2IN1+/ZCD1/SS2 <sup>(1)</sup> / CWG1IN <sup>(1)</sup> /INT <sup>(1)</sup> /IOCB0	RB0	TTL/ST	CMOS/OD	General purpose I/O.
CWG1IN**/IOCBU	ANB0	AN	<u>-</u>	ADC Channel B0 input.
	C2IN1+	AN	-	Comparator 2 positive input.
	ZCD1	AN	AN	Zero-Cross Detect input pin (with constant current sink/ source).
	SS2 <sup>(1)</sup>	TTL/ST		MSSP2 SPI client select input.
	CWG1IN <sup>(1)</sup>	TTL/ST	-	Complementary Waveform Generator 1 input.
	INT <sup>(1)</sup>	TTL/ST	<u> </u>	External interrupt request input.
	IOCB0	TTL/ST	_	Interrupt-on-change input.
RB1/ANB1/C1IN3-/C2IN3-/SCL2 <sup>(3,4)</sup> / SCK2 <sup>(1)</sup> /IOCB1	RB1	TTL/ST	CMOS/OD	General purpose I/O.
SCRZ: /IOCBT	ANB1	AN		ADC Channel B1 input.
	C1IN3-	AN	) <del>-</del>	Comparator 1 negative input.
	C2IN3-	AN	V	Comparator 2 negative input.
	SCL2 <sup>(3,4)</sup>	I <sup>2</sup> C	OD	MSSP2 I <sup>2</sup> C clock input/output.
	SCK2 <sup>(1)</sup>	TTL/ST	CMOS/OD	MSSP2 SPI serial clock (default input location, SCK2 is a PPS remappable input and output).
	IOCB1	TTL/ST	-	Interrupt-on-change input.
RB2/ANB2/SDA2 <sup>(3,4)</sup> /SDI2 <sup>(1)</sup> /IOCB2	RB2	TTL/ST	CMOS/OD	General purpose I/O.
	ANB2	AN	1 <del></del> -	ADC Channel B2 input.
	SDA2 <sup>(3,4)</sup>	I <sup>2</sup> C	OD	MSSP2 I <sup>2</sup> C serial data input/output.
	SDI2 <sup>(1)</sup>	TTL/ST	7 <u></u> 2	MSSP2 SPI serial data input.
	IOCB2	TTL/ST	-	Interrupt-on-change input.

Legend: AN = Analog input or output CMOS = CMOS compatible input or output QD = Open-Drain

TTL = TTL compatible input ST = Schmitt Trigger input with CMOS levels  $1^2$ C = Schmitt Trigger input with  $1^2$ C

HV = High Voltage XTAL = Crystal levels

Note 1: This is a PPS remappable input signal. The input function may be moved from the default location shown to one of several other PORTx pins. Refer to Table 15-1 for details on which PORT pins may be used for this signal.

 All output signals shown in this row are PPS remappable. These signals may be mapped to output onto one of several PORTx pin options as described in Table 15-3.

3: This is a bidirectional signal. For normal module operation, the firmware may map this signal to the same pin in both the PPS input and PPS output registers.

4: These pins are configured for I<sup>2</sup>C logic levels. The SCLx/SDAx signals may be assigned to any of the RB1/RB2/RC3/RC4 pins. PPS assignments to the other pins (e.g., RA5) will operate, but input logic levels will be standard TTL/ST, as selected by the INLVL register, instead of the I<sup>2</sup>C specific or SMBus input buffer thresholds.

**TABLE 1-2:** PIC16(L)F15354/55 PINOUT DESCRIPTION (CONTINUED)

Name	Function	Input Type	Output Type	Description
RB3/ANB3/C1IN2-/C2IN2-/IOCB3	RB3	TTL/ST	CMOS/OD	General purpose I/O.
	ANB3	AN	-	ADC Channel B3 input.
	C1IN2-	AN	-	Comparator 1 negative input.
	C2IN2-	AN	1—1	Comparator 2 negative input.
	IOCB3	TTL/ST	<u> </u>	Interrupt-on-change input.
RB4/ANB4/ADACT <sup>(1)</sup> /IOCB4	RB4	TTL/ST	CMOS/OD	General purpose I/O.
	ANB4	AN	::	ADC Channel B4 input.
	ADACT <sup>(1)</sup>	TTL/ST	1 <del>-</del>	ADC Auto-Conversion Trigger input.
	IOCB4	TTL/ST	7 <u> </u>	Interrupt-on-change input.
RB5/ANB5/T1G <sup>(1)</sup> /IOCB5	RB5	TTL/ST	CMOS/OD	General purpose I/O.
	ANB5	AN	-	ADC Channel B5 input.
	T1G <sup>(1)</sup>	ST		Timer1 Gate input.
	IOCB5	TTL/ST	<u> </u>	Interrupt-on-change input.
RB6/ANB6/CLCIN2 <sup>(1)</sup> /IOCB6/TX2/ CK2 <sup>(3)</sup> /ICSPCLK	RB6	TTL/ST	CMOS/OD	General purpose I/O.
CK2 <sup>(3)</sup> /ICSPCLK	ANB6	AN		ADC Channel B6 input.
	CLCIN2 <sup>(1)</sup>	TTL/ST	-	Configurable Logic Cell source input.
	IOCB6	TTL/ST	_	Interrupt-on-change input.
	TX2	9 <del></del>	CMOS	EUSART2 asynchronous.
	CK2 <sup>(3)</sup>	TTL/ST	CMOS/OD	EUSART2 synchronous mode clock input/output.
	ICSPCLK	ST	-	In-Circuit Serial Programming™ and debugging clock input.
RB7/ANB7/RX2/DT2/CLCIN3 <sup>(1)</sup> /	RB7	TTL/ST	CMOS/OD	General purpose I/O.
IOCB7/DAC1OUT2/ICSPDAT	ANB7	AN		ADC Channel B7 input.
	CLCIN3 <sup>(1)</sup>	TTL/ST	9 <u>-4</u> 5	Configurable Logic Cell source input.
	IOCB7	TTL/ST		Interrupt-on-change input.
	RX2 <sup>(1)</sup>	TTL/ST	: <del></del> :	EUSART2 Asynchronous mode receiver data input.
	DT2 <sup>(3)</sup>	TTL/ST	CMOS/OD	EUSART2 Synchronous mode data input/output.
	DAC1OUT2	( <del>) -</del>	AN	Digital-to-Analog Converter output.
	ICSPDAT	ST	CMOS	In-Circuit Serial Programming™ and debugging data input/ output.
RC0/ANC0/T1CKI(1)/IOCC0/SOSCO	RC0	TTL/ST	CMOS/OD	General purpose I/O.
	ANC0	AN	_	ADC Channel C0 input.
	T1CKI <sup>(1)</sup>	TTL/ST	_	Timer1 external digital clock input.
	IOCC0	TTL/ST	_	Interrupt-on-change input.
			AN	32.768 kHz secondary oscillator crystal driver output.

AN = Analog input or output Legend:

CMOS = CMOS compatible input or output

= Open-Drain

TTL = TTL compatible input HV = High Voltage

= Schmitt Trigger input with CMOS levels ST

= Schmitt Trigger input with I<sup>2</sup>C

This is a PPS remappable input signal. The input function may be moved from the default location shown to one of several other PORTx Note 1:

= Crystal levels XTAL

pins. Refer to Table 15-1 for details on which PORT pins may be used for this signal.

All output signals shown in this row are PPS remappable. These signals may be mapped to output onto one of several PORTx pin options as described in Table 15-3.

3: This is a bidirectional signal. For normal module operation, the firmware may map this signal to the same pin in both the PPS input and PPS output registers.

These pins are configured for I<sup>2</sup>C logic levels. The SCLx/SDAx signals may be assigned to any of the RB1/RB2/RC3/RC4 pins. PPS assignments to the other pins (e.g., RA5) will operate, but input logic levels will be standard TTL/ST, as selected by the INLVL register, instead of the I<sup>2</sup>C specific or SMBus input buffer thresholds.

**TABLE 1-2:** PIC16(L)F15354/55 PINOUT DESCRIPTION (CONTINUED)

Name	Function	Input Type	Output Type	Description
RC1/ANC1/CCP2 <sup>(1)</sup> /IOCC1/SOSCI	RC1	TTL/ST	CMOS/OD	General purpose I/O.
	ANC1	AN	_	ADC Channel C1 input.
	CCP2 <sup>(1)</sup>	TTL/ST	CMOS/OD	CCP2 Capture Input.
	IOCC1	TTL/ST	1 <del></del>	Interrupt-on-change input.
	SOSCI	AN	<u> </u>	32.768 kHz secondary oscillator crystal driver input.
RC2/ANC2/CCP1 <sup>(1)</sup> /IOCC2	RC2	TTL/ST	CMOS/OD	General purpose I/O.
	ANC2	AN	-	ADC Channel C2 input.
	CCP1 <sup>(1)</sup>	TTL/ST	CMOS/OD	CCP1 Capture Input.
	IOCC2	TTL/ST	<u> </u>	Interrupt-on-change input.
RC3/ANC3/SCL1 <sup>(3,4)</sup> /SCK1 <sup>(1)</sup> /T2IN <sup>(1)</sup> /	RC3	TTL/ST	CMOS/OD	General purpose I/O.
IOCC3	ANC3	AN	-	ADC Channel C3 input.
	SCL1 <sup>(3,4)</sup>	I <sup>2</sup> C	OD	MSSP1 I <sup>2</sup> C input/output.
	SCK1 <sup>(1)</sup>	TTL/ST	CMOS/OD	MSSP1 SPI clock input/output (default input location, SCK1 is a PPS remappable input and output).
	T2IN <sup>(1)</sup>	TTL/ST		Timer2 external input.
	IOCC3	TTL/ST	<u> </u>	Interrupt-on-change input.
RC4/ANC4/SDA1 <sup>(3,4)</sup> /SDI1 <sup>(1)</sup> /IOCC4	RC4	TTL/ST	CMOS/OD	General purpose I/O.
	ANC4	AN	-	ADC Channel C4 input.
	SDA1 <sup>(3,4)</sup>	I <sup>2</sup> C	OD	MSSP1 I <sup>2</sup> C serial data input/output.
	SDI1 <sup>(1)</sup>	TTL/ST		MSSP1 SPI serial data input.
	IOCC4	TTL/ST	20-50	Interrupt-on-change input.
RC5/ANC5/IOCC5	RC5	TTL/ST	CMOS/OD	General purpose I/O.
	ANC5	AN	-	ADC Channel C5 input.
	IOCC5	TTL/ST	-	Interrupt-on-change input.
RC6/ANC6/TX1/CK1 <sup>(1)</sup> /IOCC6	RC6	TTL/ST	CMOS/OD	General purpose I/O.
	ANC6	AN	<u>72—4</u> 4	ADC Channel C6 input.
	TX1	-	CMOS	EUSART1 asynchronous transmit.
	CK1 <sup>(1)</sup>	πυsτ	CMOS/OD	EUSART 1 synchronous mode clock input/output.
	IOCC6	TTL/ST		Interrupt-on-change input.
RC7/ANC7/RX1/DT1 <sup>(3)</sup> /IOCC7	RC7	TTL/ST	CMOS/OD	General purpose I/O.
	ANC7	AN	_	ADC Channel C7 input.
	RX1	πυsτ	_	EUSART1 Asynchronous mode receiver data input.
	DT1 <sup>(3)</sup>	TTL/ST	CMOS/OD	EUSART1 Synchronous mode data input/output.
	IOCC7	TTL/ST	_	Interrupt-on-change input.

AN = Analog input or output Legend: TTL = TTL compatible input

CMOS = CMOS compatible input or output

= Open-Drain

HV = High Voltage

= Schmitt Trigger input with CMOS levels ST = Crystal levels

= Schmitt Trigger input with I<sup>2</sup>C

XTAL Note 1:

This is a PPS remappable input signal. The input function may be moved from the default location shown to one of several other PORTx pins. Refer to Table 15-1 for details on which PORT pins may be used for this signal.

- All output signals shown in this row are PPS remappable. These signals may be mapped to output onto one of several PORTx pin options as described in Table 15-3.
- 3: This is a bidirectional signal. For normal module operation, the firmware may map this signal to the same pin in both the PPS input and PPS output registers.
- These pins are configured for I<sup>2</sup>C logic levels. The SCLx/SDAx signals may be assigned to any of the RB1/RB2/RC3/RC4 pins. PPS assignments to the other pins (e.g., RA5) will operate, but input logic levels will be standard TTL/ST, as selected by the INLVL register, instead of the I<sup>2</sup>C specific or SMBus input buffer thresholds.

## TABLE 1-2: PIC16(L)F15354/55 PINOUT DESCRIPTION (CONTINUED)

Name	Function	Input Type	Output Type	Description					
RE3/IOCE3/MCLR/VPP	RE3	TTL/ST		General purpose input only (when MCLR is disabled by Configuration bit).					
	IOCE3	TTL/ST	-	Interrupt-on-change input.					
	MCLR	ST	1-1	Master clear input with internal weak pull-up resistor.					
	VPP	HV	V=0	ICSP™ High-Voltage Programming mode entry input.					
VDD	VDD	Power	_	Positive supply voltage input.					
Vss	Vss	Power	( <del></del> )	Ground reference.					

Legend: AN = Analog input or output CMOS = CMOS compatible input or output QD = Open-Drain

TTL = TTL compatible input ST = Schmitt Trigger input with CMOS levels I<sup>2</sup>C = Schmitt Trigger input with I<sup>2</sup>C

HV = High Voltage XTAL = Crystal levels

Note 1: This is a PPS remappable input signal. The input function may be moved from the default location shown to one of several other PORTx pins. Refer to Table 15-1 for details on which PORT pins may be used for this signal.

- 2: All output signals shown in this row are PPS remappable. These signals may be mapped to output onto one of several PORTx pin options as described in Table 15-3
- options as described in Table 15-3.

  3: This is a bidirectional signal. For normal module operation, the firmware may map this signal to the same pin in both the PPS input and PPS output registers.
- 4: These pins are configured for I<sup>2</sup>C logic levels. The SCLx/SDAx signals may be assigned to any of the RB1/RB2/RC3/RC4 pins. PPS assignments to the other pins (e.g., RA5) will operate, but input logic levels will be standard TTL/ST, as selected by the INLVL register, instead of the I<sup>2</sup>C specific or SMBus input buffer thresholds.

**TABLE 1-2:** PIC16(L)F15354/55 PINOUT DESCRIPTION (CONTINUED)

Name	Function	Input Type	Output Type	Description
OUT <sup>(2)</sup>	C10UT	<u> </u>	CMOS/OD	Comparator 1 output.
	C2OUT	9 <u>—</u> 2	CMOS/OD	Comparator 2 output.
	SDO1	9 <del>1-1</del>	CMOS/OD	MSSP1 SPI serial data output.
	SCK1	_	CMOS/OD	MSSP1 SPI serial clock output.
	SDO2	(A <del>-a</del> y	CMOS/OD	MSSP2 SPI serial data output.
	SCK2	<u> </u>	CMOS/OD	MSSP2 SPI serial clock output.
	TX1	-	CMOS/OD	EUSART1 Asynchronous mode transmitter data output.
	CK1 <sup>(3)</sup>	-	CMOS/OD	EUSART1 Synchronous mode clock output.
	TX2	( <del>)</del>	CMOS/OD	EUSART2 Asynchronous mode transmitter data output.
	CK2 <sup>(3)</sup>		CMOS/OD	EUSART2 Synchronous mode clock output.
	DT <sup>(3)</sup>		CMOS/OD	EUSART Synchronous mode data output.
	TMR0	a <del></del>	CMOS/OD	Timer0 output.
	CCP1	0 <del></del> .	CMOS/OD	CCP2 output (compare/PWM functions).
	CCP2	0	CMOS/OD	CCP2 output (compare/PWM functions).
	PWM3OUT	-	CMOS/OD	PWM3 output.
	PWM4OUT	-	CMOS/OD	PWM4 output.
	PWM5OUT	-	CMOS/OD	PWM5 output.
	PWM6OUT	( <del>)</del>	CMOS/OD	PWM6 output.
	CWG1A	12	CMOS/OD	Complementary Waveform Generator 1 output A.
	CWG1B	-	CMOS/OD	Complementary Waveform Generator 1 output B.
	CWG1C	0 <del></del> 2	CMOS/OD	Complementary Waveform Generator 1 output C.
	CWG1D	0 <del></del>	CMOS/OD	Complementary Waveform Generator 1 output D.
	CLC10UT	0 <u>—</u> 5	CMOS/OD	Configurable Logic Cell 1 output.
	CLC2OUT	-	CMOS/OD	Configurable Logic Cell 2 output.
	CLC3OUT	-	CMOS/OD	Configurable Logic Cell 3 output.
	CLC4OUT	-	CMOS/OD	Configurable Logic Cell 4 output.
	NCO1OUT	2 <del>7 - 5</del> 1	CMOS/OD	Numerically Controller Oscillator output.
	CLKR		CMOS/OD	Clock Reference module output.

CMOS = CMOS compatible input or output Legend: AN = Analog input or output = Open-Drain

OD I<sup>2</sup>C TTL = TTL compatible input = Schmitt Trigger input with I2C ST Schmitt Trigger input with CMOS levels HV = High Voltage XTAL = Crystal levels

Note This is a PPS remappable input signal. The input function may be moved from the default location shown to one of several other PORTx pins. Refer to Table 15-1 for details on which PORT pins may be used for this signal.

- All output signals shown in this row are PPS remappable. These signals may be mapped to output onto one of several PORTx pin options as described in Table 15-3.
- This is a bidirectional signal. For normal module operation, the firmware may map this signal to the same pin in both the PPS input and PPS output registers.
- These pins are configured for  $l^2C$  logic levels. The SCLx/SDAx signals may be assigned to any of the RB1/RB2/RC3/RC4 pins. PPS assignments to the other pins (e.g., RA5) will operate, but input logic levels will be standard TTL/ST, as selected by the INLVL register, instead of the  $l^2C$  specific or SMBus input buffer thresholds.

## 2.0 GUIDELINES FOR GETTING STARTED WITH PIC16(L)F15354/55 MICROCONTROLLERS

## 2.1 Basic Connection Requirements

Getting started with the PIC16(L)F15354/55 family of 8bit microcontrollers requires attention to a minimal set of device pin connections before proceeding with development.

The following pins must always be connected:

- All VDD and VSS pins (see Section 2.2 "Power Supply Pins")
- MCLR pin
  (see Section 2.3 "Master Clear (MCLR) Pin")

These pins must also be connected if they are being used in the end application:


- ICSPCLK/ICSPDAT pins used for In-Circuit Serial Programming™ (ICSP™) and debugging purposes (see Section 2.4 "ICSP™ Pins")
- OSCI and OSCO pins when an external oscillator source is used (see Section 2.5 "External Oscillator Pins")

Additionally, the following pins may be required:

 VREF+/VREF- pins are used when external voltage reference for analog modules is implemented

The minimum mandatory connections are shown in Figure 2-1.

FIGURE 2-1: RECOMMENDED MINIMUM CONNECTIONS



## 2.2 Power Supply Pins

#### 2.2.1 DECOUPLING CAPACITORS

The use of decoupling capacitors on every pair of power supply pins (VDD and VSS) is required.

Consider the following criteria when using decoupling capacitors:

- Value and type of capacitor: A 0.1  $\mu$ F (100 nF), 10-25V capacitor is recommended. The capacitor must be a low-ESR device, with a resonance frequency in the range of 200 MHz and higher. Ceramic capacitors are recommended.
- Placement on the printed circuit board: The
  decoupling capacitors need to be placed as close
  to the pins as possible. It is recommended to
  place the capacitors on the same side of the
  board as the device. If space is constricted, the
  capacitor can be placed on another layer on the
  PCB using a via; however, ensure that the trace
  length from the pin to the capacitor is no greater
  than 0.25 inch (6 mm).
- Handling high-frequency noise: If the board is experiencing high-frequency noise (upward of tens of MHz), add a second ceramic type capacitor in parallel to the above described decoupling capacitor. The value of the second capacitor can be in the range of 0.01 μF to 0.001 μF. Place this second capacitor next to each primary decoupling capacitor. In high-speed circuit designs, consider implementing a decade pair of capacitances as close to the power and ground pins as possible (e.g., 0.1 μF in parallel with 0.001 μF).
- Maximizing performance: On the board layout from the power supply circuit, run the power and return traces to the decoupling capacitors first, and then to the device pins. This ensures that the decoupling capacitors are first in the power chain. Equally important is to keep the trace length between the capacitor and the power pins to a minimum, thereby reducing PCB trace inductance.

#### 2.2.2 TANK CAPACITORS

On boards with power traces running longer than six inches in length, it is suggested to use a tank capacitor for integrated circuits, including microcontrollers, to supply a local power source. The value of the tank capacitor may be determined based on the trace resistance that connects the power supply source to the device, and the maximum current drawn by the device in the application. In other words, select the tank capacitor so that it meets the acceptable voltage sag at the device. Typical values range from  $4.7~\mu F$  to  $47~\mu F$ .


## 2.3 Master Clear (MCLR) Pin

The MCLR pin provides two specific device functions: Device Reset, and Device Programming and Debugging. If programming and debugging are not required in the end application, a direct connection to VDD may be all that is required. The addition of other components, to help increase the application's resistance to spurious Resets from voltage sags, may be beneficial. A typical configuration is shown in Figure 2-1. Other circuit designs may be implemented, depending on the application's requirements.

During programming and debugging, the resistance and capacitance that can be added to the pin must be considered. Device programmers and debuggers drive the MCLR pin. Consequently, specific voltage levels (VIH and VIL) and fast signal transitions must not be adversely affected. Therefore, specific values of R1 and C1 will need to be adjusted based on the application and PCB requirements. For example, it is recommended that the capacitor, C1, be isolated from the MCLR pin during programming and debugging operations by using a jumper (Figure 2-2). The jumper is replaced for normal run-time operations.

Any components associated with the MCLR pin must be placed within 0.25 inch (6 mm) of the pin.

FIGURE 2-2: EXAMPLE OF MCLR PIN CONNECTIONS



- Note 1: R1 ≤ 10 kΩ is recommended. A suggested starting value is 10 kΩ. Ensure that the MCLR pin VIH and VIL specifications are met.
  - 2: R2 ≤ 470Ω will limit any current flowing into MCLR from the external capacitor, C1, in the event of MCLR pin breakdown, due to Electrostatic Discharge (ESD) or Electrical Overstress (EOS). Ensure that the MCLR pin VIH and VIL specifications are met.

#### 2.4 ICSP™ Pins

The ICSPCLK and ICSPDAT pins are used for In-Circuit Serial Programming  $^{\text{TM}}$  (ICSP $^{\text{TM}}$ ) and debugging purposes. It is recommended to keep the trace length between the ICSP connector and the ICSP pins on the device as short as possible. If the ICSP connector is expected to experience an ESD event, a series resistor is recommended, with the value in the range of a few tens of ohms, not to exceed  $100\Omega$ .

Pull-up resistors, series diodes and capacitors on the ICSPCLK and ICSPDAT pins are not recommended as they will interfere with the programmer/debugger communications to the device. If such discrete components are an application requirement, they must be removed from the circuit during programming and debugging. Alternatively, refer to the AC/DC characteristics and timing requirements information in the respective device Flash programming specification for information on capacitive loading limits, and pin input voltage high (VIH) and input low (VIL) requirements.

For device emulation, ensure that the "Communication Channel Select" (i.e., ICSPCLK/ICSPDAT pins), programmed into the device, matches the physical connections for the ICSP to the Microchip debugger/emulator tool.

For more information on available Microchip development tools connection requirements, refer to Section 39.0 "Development Support".

#### 2.5 External Oscillator Pins

Many microcontrollers have options for at least two oscillators: a high-frequency primary oscillator and a low-frequency secondary oscillator (refer to Section 9.0 "Oscillator Module (with Fail-Safe Clock Monitor)" for details).

The oscillator circuit must be placed on the same side of the board as the device. Place the oscillator circuit close to the respective oscillator pins with no more than 0.5 inch (12 mm) between the circuit components and the pins. The load capacitors must be placed next to the oscillator itself, on the same side of the board.

Use a grounded copper pour around the oscillator circuit to isolate it from surrounding circuits. The grounded copper pour must be routed directly to the MCU ground. Do not run any signal traces or power traces inside the ground pour. Also, if using a two-sided board, avoid any traces on the other side of the board where the crystal is placed.

Layout suggestions are shown in Figure 2-3. In-line packages may be handled with a single-sided layout that completely encompasses the oscillator pins. With fine-pitch packages, it is not always possible to completely surround the pins and components. A suitable solution is to tie the broken guard sections to a mirrored ground layer. In all cases, the guard trace(s) must be returned to ground.

In planning the application's routing and I/O assignments, ensure that adjacent port pins, and other signals in close proximity to the oscillator, are benign (i.e., free of high frequencies, short rise and fall times, and other similar noise).


For additional information and design guidance on oscillator circuits, refer to these Microchip Application Notes, available at the corporate website (www.microchip.com):

- AN826, "Crystal Oscillator Basics and Crystal Selection for rfPIC™ and PICmicro® Devices"
- AN849, "Basic PICmicro® Oscillator Design"
- AN943, "Practical PICmicro® Oscillator Analysis and Design"
- AN949, "Making Your Oscillator Work"

#### 2.6 Unused I/Os

Unused I/O pins may be configured as outputs and driven to a logic low state. Alternatively, connect a 1 k $\Omega$  to 10 k $\Omega$  resistor to Vss on unused pins and drive the output to logic low.

FIGURE 2-3: SUGGESTED PLACEMENT OF THE




## 3.0 ENHANCED MID-RANGE CPU

This family of devices contains an enhanced mid-range 8-bit CPU core. The CPU has 48 instructions. Interrupt capability includes automatic context saving.

The hardware stack is 16-levels deep and has Overflow and Underflow Reset capability. Direct, Indirect, and Relative Addressing modes are available. Two File Select Registers (FSRs) provide the ability to read program and data memory.

FIGURE 3-1: CORE DATA PATH DIAGRAM



## 3.1 Automatic Interrupt Context Saving

During interrupts, certain registers are automatically saved in shadow registers and restored when returning from the interrupt. This saves stack space and user code. See Section 10.5 "Automatic Context Saving" for more information.

## 3.2 16-Level Stack with Overflow and Underflow

These devices have a hardware stack memory 15 bits wide and 16 words deep. A Stack Overflow or Underflow will set the appropriate bit (STKOVF or STKUNF) in the PCON0 register, and if enabled, will cause a software Reset. See Section 4.5 "Stack" for more details.

## 3.3 File Select Registers

There are two 16-bit File Select Registers (FSR). FSRs can access all file registers and program memory, which allows one Data Pointer for all memory. When an FSR points to program memory, there is one additional instruction cycle in instructions using INDF to allow the data to be fetched. General purpose memory can also be addressed linearly, providing the ability to access contiguous data larger than 80 bytes. See Section 4.6 "Indirect Addressing" for more details.

## 3.4 Instruction Set

There are 48 instructions for the enhanced mid-range CPU to support the features of the CPU. See Section 36.0 "Instruction Set Summary" for more details.

## 4.0 MEMORY ORGANIZATION

These devices contain the following types of memory:

- Program Memory
  - Configuration Words
  - Device ID
  - User ID
  - Program Flash Memory
  - Device Information Area (DIA)
  - Device Configuration Information (DCI)
  - Revision ID
- Data Memory
  - Core Registers
  - Special Function Registers
  - General Purpose RAM
  - Common RAM

The following features are associated with access and control of program memory and data memory:

- PCL and PCLATH
- Stack
- Indirect Addressing
- NVMREG access

## 4.1 Program Memory Organization

The enhanced mid-range core has a 15-bit program counter capable of addressing 32K x 14 program memory space. Table 4-1 shows the memory sizes implemented. The Reset vector is at 0000h and the interrupt vector is at 0004h (see Figure 4-1).

## TABLE 4-1: DEVICE SIZES AND ADDRESSES

Device	Program Memory Size (Words)	Last Program Memory Address
PIC16(L)F15354	4096	0FFFh
PIC16(L)F15355	8192	1FFFh

FIGURE 4-1: PROGRAM MEMORY MAP AND STACK FOR PIC16(L)F15354





FIGURE 4-2: PROGRAM MEMORY MAP AND STACK FOR PIC16(L)F15355



## 4.1.1 READING PROGRAM MEMORY AS DATA

There are three methods of accessing constants in program memory. The first method is to use tables of RETLW instructions. The second method is to set an FSR to point to the program memory. The third method is to use the NVMREG interface to access the program memory. For an example of NVMREG interface use, reference Section 13.3, NVMREG Access.

#### 4.1.1.1 RETLW Instruction

The RETLW instruction can be used to provide access to tables of constants. The recommended way to create such a table is shown in Example 4-1.

#### EXAMPLE 4-1: RETLW INSTRUCTION

```
constants
   BRW
                       ;Add Index in W to
                      ;program counter to
                      ; select data
    RETLW DATAO
                      ;Index0 data
   RETLW DATA1
                      ;Index1 data
   RETLW DATA2
   RETLW DATA3
my function
    ;... LOTS OF CODE ...
   MOVLW DATA INDEX
   call constants
    ;... THE CONSTANT IS IN W
```

The BRW instruction makes this type of table very simple to implement.

#### 4.1.1.2 Indirect Read with FSR

The program memory can be accessed as data by setting bit 7 of an FSRxH register and reading the matching INDFx register. The MOVIW instruction will place the lower eight bits of the addressed word in the W register. Writes to the program memory cannot be performed via the INDF registers. Instructions that read the program memory via the FSR require one extra instruction cycle to complete. Example 4-2 demonstrates reading the program memory via an FSR.

The HIGH directive will set bit 7 if a label points to a location in the program memory. This applies to the assembly code Example 4-2 shown below.

## EXAMPLE 4-2: ACCESSING PROGRAM MEMORY VIA FSR

```
CONSTANTS

RETLW DATA0 ; Index0 data

RETLW DATA1 ; Index1 data

RETLW DATA2

RETLW DATA3

my_function
;... LOTS OF CODE...

MOVLW LOW constants

MOVWF FSR1L

MOVLW HIGH constants

MOVWF FSR1H

MOVIW 0[FSR1]
;THE PROGRAM MEMORY IS IN W
```

## 4.2 Memory Access Partition (MAP)

User Flash is partitioned into:

- Application Block
- · Boot Block, and
- · Storage Area Flash (SAF) Block

The user can allocate the memory usage by setting the BBEN bit, selecting the size of the partition defined by BBSIZE[2:0] bits and enabling the Storage Area Flash by the SAFEN bit of the Configuration Word (see Register 5-4). Refer to Table 4-2 for the different user Flash memory partitions.

## 4.2.1 APPLICATION BLOCK

Default settings of the Configuration bits ( $\overline{BBEN} = 1$  and  $\overline{SAFEN} = 1$ ) assign all memory in the user Flash area to the Application Block.

#### 4.2.2 BOOT BLOCK

If  $\overline{\mathsf{BBEN}} = 0$ , the Boot Block is enabled and a specific address range is alloted as the Boot Block based on the value of the BBSIZE bits of Configuration Word (Register 5-4) and the sizes provided in Table 5-1.

## 4.2.3 STORAGE AREA FLASH

Storage Area Flash (SAF) is enabled by clearing the SAFEN bit of the Configuration Word in Register 5-4. If enabled, the SAF block is placed at the end of memory and spans 128 words. If the Storage Area Flash (SAF) is enabled, the SAF area is not available for program execution. The 128 words of the SAF quality as High Endurance Flash (HEF) memory.

## 4.2.4 MEMORY WRITE PROTECTION

All the memory blocks have corresponding write protection fuses WRTAPP, WRTB and WRTC bits in the Configuration Word 4 (Register 5-4). If write-protected locations are written from NVMCON registers, memory is not changed and the WRERR bit defined in Register 12-5 is set as explained in Section 13.3.8 "WRERR Bit".

## 4.2.5 MEMORY VIOLATION

A Memory Execution Violation Reset occurs while executing an instruction that has been fetched from outside a valid execution area, clearing the MEMV bit. Refer to Section 8.12 "Memory Execution Violation" for the available valid program execution areas and the PCON1 register definition (Register 8-3) for MEMV bit conditions.

TABLE 4-2: MEMORY ACCESS PARTITION

	Ö	2	Par	tition				
REG	Address	BBEN = 1 SAFEN = 1	BBEN = 1 SAFEN = 0	BBEN = 0 SAFEN = 1	BBEN = 0 SAFEN = 0			
	00 0000h Last Boot Block Memory Address		APPLICATION	BOOT BLOCK <sup>(4)</sup>	BOOT BLOCK <sup>(4)</sup>			
PFM	Last Boot Block Memory Address + 1 <sup>(1)</sup> Last Program Memory Address - 80h	APPLICATION BLOCK <sup>(4)</sup>	APPLICATION BLOCK <sup>(4)</sup>	APPLICATION	APPLICATION BLOCK <sup>(4)</sup>			
	Last Program Memory Address - 7Fh <sup>(2)</sup> ••• Last Program Memory Address		SAF <sup>(4)</sup>	BLOCK <sup>(4)</sup>	SAF <sup>(4)</sup>			
CONFIG	Config Memory Address <sup>(3)</sup>	CONFIG						

Note 1: Last Boot Block Memory Address is based on BBSIZE<2:0> given in Table 5-1.

<sup>2:</sup> Last Program Memory Address is the Flash size given in Table 4-1.

<sup>3:</sup> Config Memory Address are the address locations of the Configuration Words given in Table 13-2.


<sup>4:</sup> Each memory block has a corresponding write protection fuse defined by the WRTAPP, WRTB and WRTC bits in the Configuration Word (Register 5-4).

## 4.3 Data Memory Organization

The data memory is partitioned into 64 memory banks with 128 bytes in each bank. Each bank consists of:

- 12 core registers
- · Up to 100 Special Function Registers (SFR)
- Up to 80 bytes of General Purpose RAM (GPR)
- · 16 bytes of common RAM

## FIGURE 4-3: BANKED MEMORY PARTITIONING



#### 4.3.1 BANK SELECTION

The active bank is selected by writing the bank number into the Bank Select Register (BSR). All data memory can be accessed either directly (via instructions that use the file registers) or indirectly via the two File Select Registers (FSR). See Section 4.6 "Indirect Addressing" for more information.

Data memory uses a 13-bit address. The upper six bits of the address define the Bank address and the lower seven bits select the registers/RAM in that bank.

### 4.3.2 CORE REGISTERS

The core registers contain the registers that directly affect the basic operation. The core registers occupy the first 12 addresses of every data memory bank (addresses x00h/x08h through x0Bh/x8Bh). These registers are listed below in Table 4-3.

TABLE 4-3: CORE REGISTERS

Addresses	BANKX
x00h or x80h	INDF0
x01h or x81h	INDF1
x02h or x82h	PCL
x03h or x83h	STATUS
x04h or x84h	FSR0L
x05h or x85h	FSR0H
x06h or x86h	FSR1L
x07h or x87h	FSR1H
x08h or x88h	BSR
x09h or x89h	WREG
x0Ah or x8Ah	PCLATH
x0Bh or x8Bh	INTCON

## 4.3.2.1 STATUS Register

The STATUS register, shown in Register 4-1, contains:

- · the arithmetic status of the ALU
- the Reset status

The STATUS register can be the destination for any instruction, like any other register. If the STATUS register is the destination for an instruction that affects the Z, DC or C bits, then the write to these three bits is disabled. These bits are set or cleared according to the device logic. Furthermore, the  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits are not writable. Therefore, the result of an instruction with the STATUS register as destination may be different than intended.

For example, CLRF STATUS will clear bits <4:3> and <1:0>, and set the Z bit. This leaves the STATUS register as '000u uluu' (where u = unchanged).

It is recommended, therefore, that only BCF, BSF, SWAPF and MOVWF instructions are used to alter the STATUS register, because these instructions do not affect any Status bits. For other instructions not affecting any Status bits, refer to Section 36.0 "Instruction Set Summary".

Note 1: The C and DC bits operate as Borrow and Digit Borrow out bits, respectively, in subtraction.

#### REGISTER 4-1: STATUS: STATUS REGISTER

U-0	U-0	U-0	R-1/q	R-1/q	R/W-0/u	R/W-0/u	R/W-0/u
<del></del> .			TO	PD	Z	DC <sup>(1)</sup>	C <sup>(1)</sup>
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7-5	Unimplemented: Read as '0'
DIT /-5	Unimplemented Read as 11

bit 4 TO: Time-Out bit

1 = After power-up, CLRWDT instruction or SLEEP instruction

0 = A WDT time-out occurred

bit 3 PD: Power-Down bit

1 = After power-up or by the CLRWDT instruction

0 = By execution of the SLEEP instruction

bit 2 Z: Zero bit

1 = The result of an arithmetic or logic operation is zero

0 = The result of an arithmetic or logic operation is not zero

bit 1 DC: Digit Carry/Digit Borrow bit (ADDWF, ADDLW, SUBLW, SUBWF instructions)(1)

1 = A carry-out from the 4th low-order bit of the result occurred

0 = No carry-out from the 4th low-order bit of the result

bit 0 C: Carry/Borrow bit(1) (ADDWF, ADDLW, SUBLW, SUBWF instructions)(1)

1 = A carry-out from the Most Significant bit of the result occurred

0 = No carry-out from the Most Significant bit of the result occurred

Note 1: For Borrow, the polarity is reversed. A subtraction is executed by adding the two's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the high-order or low-order bit of the source register.

### 4.3.3 SPECIAL FUNCTION REGISTER

The Special Function Registers are registers used by the application to control the desired operation of peripheral functions in the device. The Special Function Registers occupy the 20 bytes of the data banks 0-59 and 100 bytes of the data banks 60-63, after the core registers.

The SFRs associated with the operation of the peripherals are described in the appropriate peripheral chapter of this data sheet.

### 4.3.4 GENERAL PURPOSE RAM

There are up to 80 bytes of GPR in each data memory bank.

### 4.3.4.1 Linear Access to GPR

The general purpose RAM can be accessed in a non-banked method via the FSRs. This can simplify access to large memory structures. See **Section 4.6.2 "Linear Data Memory"** for more information.

### 4.3.5 COMMON RAM

There are 16 bytes of common RAM accessible from all banks.

#### 4.3.6 DEVICE MEMORY MAPS

The memory maps are as shown in Table 4-4 through Table 4-9.

TABLE 4-4:

PIC16(L)F15354/55 MEMORY MAP, BANKS 0-7

Core Register (Table 4-3)  00Bh 00Ch PORTA 00Dh PORTB 00Eh PORTC 00Fh — 010h PORTE 011h — 012h TRISA 013h TRISB 014h TRISC 015h — 016h TRISE 017h — 018h LATA 019h LATB 014h LATC		BANK 1		BANK 2		BANK 3		BANK 4		BANK 5		BANK 6		BANK 7
00Ch	080h	Core Register (Table 4-3)	100h	Core Register (Table 4-3)	180h	Core Register (Table 4-3)	200h	Core Register (Table 4-3)	280h	Core Register (Table 4-3)	300h	Core Register (Table 4-3)	380h	Core Register (Table 4-3)
00Dh PORTB 00Eh PORTC 00Fh — 010h PORTE 011h — 012h TRISA 013h TRISB 014h TRISC 015h — 016h TRISE 017h — 016h TRISE 017h — 018h LATA 019h LATB 01Ah LATC	08Bh	Harrier .	10Bh	100000000	18Bh		20Bh		28Bh		30Bh		38Bh	
00Eh PORTC 00Fh — 010h PORTE 011h — 012h TRISA 013h TRISB 014h TRISC 015h — 016h TRISE 017h — 018h LATA 019h LATB 01AH LATC	08Ch	-	10Ch	-	18Ch	SSP1BUF	20Ch	TMR1L	28Ch	TMR2	30Ch	CCPR1L	38Ch	PWM6DCL
00Fh — 010h PORTE 011h — 012h TRISA 013h TRISB 014h TRISC 015h — 016h TRISE 017h — 018h LATA 019h LATB 01Ah LATC 018h — 018h LATC 018h — 018h LATC 018h — 018h —	08Dh	-	10Dh	-	18Dh	SSP1ADD	20Dh	TMR1H	28Dh	PR2	30Dh	CCPR1H	38Dh	PWM6DCH
010h PORTE 011h — 012h TRISA 013h TRISB 014h TRISC 015h — 016h TRISE 017h — 018h LATA 019h LATB 01Ah LATC 018h LATC	08Eh		10Eh	¥ <del>=</del> (	18Eh	SSP1MASK	20Eh	T1CON	28Eh	T2CON	30Eh	CCP1CON	38Eh	PWM6CON
011h — 012h TRISA 013h TRISB 014h TRISC 015h — 016h TRISE 017h — 018h LATA 019h LATB 01Ah LATC 018h — 018h LATC 018h LATC 018h LATC 018h LATC 018h — 018h LATC 018h — 018h LATC 018h — 018h LATC 018h — 018h	08Fh	-	10Fh		18Fh	SSP1STAT	20Fh	T1GCON	28Fh	T2HLT	30Fh	CCP1CAP	38Fh	-
012h TRISA 013h TRISB 014h TRISC 015h — 016h TRISE 017h — 018h LATA 019h LATB 01Ah LATC 018h LATC	090h	1	110h	-	190h	SSP1CON1	210h	T1GATE	290h	T2CLK	310h	CCPR2L	390h	:—:
013h TRISB 014h TRISC 015h — 016h TRISE 017h — 018h LATA 019h LATB 01Ah LATC 01Bh —	091h	-	111h	·—	191h	SSP1CON2	211h	T1CLK	291h	T2ERS	311h	CCPR2H	391h	-
014h TRISC 015h — 016h TRISE 017h — 018h LATA 019h LATB 01Ah LATC 01Bh —	092h		112h		192h	SSP1CON3	212h	_	292h		312h	CCP2CON	392h	·
015h —	093h		113h		193h		213h	_	293h	_	313h	CCP2CAP	393h	-
016h TRISE 017h — 018h LATA 019h LATB 01Ah LATC 01Bh —	094h	-	114h	-	194h		214h	-	294h	2-3	314h	PWM3DCL	394h	-
017h — 018h LATA 019h LATB 01Ah LATC 01Bh —	095h	-	115h	-	195h	-	215h	-	295h		315h	PWM3DCH	395h	-
018h LATA 019h LATB 01Ah LATC 01Bh —	096h		116h	, <del>-</del> ,	196h	SSP2BUF	216h	_	296h	_	316h	PWM3CON	396h	
019h LATB 01Ah LATC 01Bh —	097h		117h	:-:	197h	SSP2ADD	217h	_	297h	_	317h	_	397h	-
01Ah LATC 01Bh —	098h	_	118h	_	198h	SSP2MASK	218h	-	298h	:-:	318h	PWM4DCL	398h	1:1
01Bh —	099h	-	119h	RC1REG1	199h	SSP2STAT	219h	-	299h		319h	PWM4DCH	399h	
UIDII	09Ah	100	11Ah	TX1REG1	19Ah	SSP2CON1	21Ah	_	29Ah		31Ah	PWM4CON	39Ah	·
01Ch LATE	09Bh	ADRESL	11Bh	SP1BRG1L	19Bh	SSP2CON2	21Bh	_	29Bh	_	31Bh	_	39Bh	_
	09Ch	ADRESH	11Ch	SP1BRG1H	19Ch	SSP2CON3	21Ch	-	29Ch	::	31Ch	PWM5DCL	39Ch	-
01Dh —	09Dh	ADCON0	11Dh	RC1STA1	19Dh	-	21Dh	-	29Dh		31Dh	PWM5DCH	39Dh	(;—)
01Eh -	09Eh	ADCON1	11Eh	TX1STA1	19Eh		21Eh		29Eh	-	31Eh	PWM5CON	39Eh	·
01Fh —	09Fh	ADACT	11Fh	BAUD1CON1	19Fh	-	21Fh	_	29Fh	_	31Fh	120	39Fh	_
020h	0A0h	General	120h	General	1A0h	General	220h	General	2A0h	General	320h 32Fh	General Purpose Register 16 Bytes	3A0h	General
General Purpose Register 96 Bytes		Purpose Register 80 Bytes		Purpose Register 80 Bytes		Purpose Register 80 Bytes		Purpose Register 80 Bytes		Purpose Register 80 Bytes	330h	General Purpose Register 64 Bytes <sup>(2)</sup>		Purpose Register 80 Bytes <sup>(2)</sup>
	0EFh	á	16Fh		1EFh	a l	26Fh		2EFh		36Fh		3EFh	
	0F0h	Common RAM Accesses 70h-7Fh	170h	Accesses 70h-7Fh	1F0h	Common RAM Accesses 70h-7Fh	270h	Common RAM Accesses 70h-7Fh	2F0h	Common RAM Accesses 70h-7Fh	370h	Common RAM Accesses 70h-7Fh	3F0h 3FFh	Common RAM Accesses 70h-7Fh

Note 1: Unimplemented locations read as '0'.

DS40001853D-page 32

2: Present only in PIC16(L)F15355.

DS40001853D-page 33

<b>TABLE 4-5</b> :	PIC16	(L)F15354/55 M	EMORY MAP,	<b>BANKS 8-15</b>

	BANK 8		BANK 9		BANK 10		BANK 11		BANK 12		BANK 13		BANK 14		BANK 15
400h	Core Register (Table 4-3)	480h	Core Register (Table 4-3)	500h	Core Register (Table 4-3)	580h	Core Register (Table 4-3)	600h	Core Register (Table 4-3)	680h	Core Register (Table 4-3)	700h	Core Register (Table 4-3)	780h	Core Register (Table 4-3)
40Bh	100000	48Bh	11. 14.34	50Bh	100000	58Bh	10.25 (1)	60Bh		68Bh	1111-111	70Bh		78Bh	111111221.1
40Ch	_	48Ch	_	50Ch	_	58Ch	NCO1ACCL	60Ch	CWG1CLK	68Ch	Į	70Ch	PIR0	78Ch	
40Dh	Ţ	48Dh	- <del>100</del> 1	50Dh		58Dh	NCO1ACCH	60Dh	CWG1DAT	68Dh	Į	70Dh	PIR1	78Dh	1
40Eh		48Eh	-	50Eh		58Eh	NCO1ACCU	60Eh	CWG1DBR	68Eh	1	70Eh	PIR2	78Eh	-
40Fh		48Fh	<del>100</del> 1	50Fh		58Fh	NCO1INCL	60Fh	CWG1DBF	68Fh	Į	70Fh	PIR3	78Fh	1
410h		490h		510h	_	590h	NCO1INCH	610h	CWG1CON0	690h	Į	710h	PIR4	790h	1
411h		491h		511h	==:	591h	NC01INCU	611h	CWG1CON1	691h	]	711h	PIR5	791h	1
412h		492h	22	512h	==:	592h	NCO1CON	612h	CWG1AS0	692h	j	712h	PIR6	792h	: <u>-</u> :
413h	1	493h		513h		593h	NCO1CLK	613h	CWG1AS1	693h	J	713h	PIR7	793h	1
414h	1	494h		514h		594h	_	614h	CWG1STR	694h	j	714h		794h	1
415h	_ =	495h		515h		595h		615h		695h	j	715h	1	795h	_
416h	1	496h	[12]	516h	_	596h	_	616h		696h	1	716h	PIE0	796h	PMD0
417h	1	497h	122	517h	_	597h	=	617h		697h	Ţ	717h	PIE1	797h	PMD1
418h	_	498h	<u> </u>	518h	_	598h	_	618h		698h	1	718h	PIE2	798h	PMD2
419h	_	499h		519h	_	599h	_	619h		699h	\—\-	719h	PIE3	799h	PMD3
41Ah	_	49Ah	122	51Ah	_	59Ah		61Ah		69Ah	-	71Ah	PIE4	79Ah	PMD4
41Bh		49Bh		51Bh		59Bh	_	61Bh		69Bh	<del></del>	71Bh	PIE5	79Bh	PMD5
41Ch	ì	49Ch	-	51Ch	:-:	59Ch	TMR0	61Ch	-	69Ch	Ĭ	71Ch	PIE6	79Ch	ĵ
41Dh	_	49Dh	===	51Dh	2-2	59Dh	PR0	61Dh		69Dh	1	71Dh	PIE7	79Dh	
41Eh		49Eh		51Eh	-	59Eh	TMR0CON0	61Eh		69Eh	\—\(\)	71Eh	_	79Eh	
41Fh	1	49Fh	_	51Fh	:-:	59Fh	TMR0CON1	61Fh	_	69Fh	-	71Fh	-	79Fh	_
420h		4A0h		520h	P. C.	5A0h		620h	General	6A0h	Ĭ	720h		7A0h	
200353	General	25657.5000	General	0.253060	General	0.646.62.0	General	60000014	Purpose	10.600(800)		Spiedole		100000000000000000000000000000000000000	
									Register		Unimplemented		Unimplemented		Unimplemented
	Purpose		Purpose		Purpose		Purpose	64Fh	48 Bytes(2)		Read as '0'		Read as '0'		Read as '0'
	Register 80 Bytes <sup>(2)</sup>		Register 80 Bytes <sup>(2)</sup>		Register 80 Bytes <sup>(2)</sup>	04 at 1620 h.	Register 80 Bytes <sup>(2)</sup>	650h	Unimplemented Read as '0'						
46Fh		4EFh		56Fh		5EFh		66Fh		6EFh		76Fh		7EFh	
470h	Common RAM Accesses	4F0h	Common RAM Accesses	570h	Common RAM Accesses	5F0h	Common RAM Accesses	670h	Common RAM Accesses	6F0h	Common RAM Accesses	770h	Common RAM Accesses	7F0h	Common RAM Accesses
47Fh	70h-7Fh	4FFh	70h-7Fh	57Fh	70h-7Fh	5FFh	70h-7Fh	67Fh	70h-7Fh	6FFh	70h-7Fh	77Fh	70h-7Fh	7FFh	70h-7Fh

Note 1: Unimplemented locations read as '0'.

2: Present only in PIC16(L)F15355.

DS40001853D-page 34

TABLE 4-6: PIC16(L)F15354/55 MEMORY MAP, BANKS 16-23

	BANK 16		<b>BANK 17</b>		BANK 18		BANK 19		BANK 20		BANK 21		BANK 22		BANK 23
800h 80Bh	Core Register (Table 4-3)	880h 88Bh	Core Register (Table 4-3)	900h	Core Register (Table 4-3)	980h	Core Register (Table 4-3)	A00h	Core Register (Table 4-3)	A80h	Core Register (Table 4-3)	B00h B0Bh	Core Register (Table 4-3)	B80h B8Bh	Core Register (Table 4-3)
80Ch	WDTCON0	88Ch	CPUDOZE	90Ch	FVRCON	98Ch		AOCh	_	A8Ch		BOCh	_	B8Ch	
80Dh	WDTCON1	88Dh	OSCCON1	90Dh		98Dh		AODh		A8Dh		BODh		B8Dh	
80Eh	WDTL	88Eh	OSCCON2	90Eh	DAC1CON0	98Eh		A0Eh	<u>==</u> :	A8Eh		B0Eh	2	B8Eh	% <u>—</u> :
80Fh	WDTH	88Fh	OSCCON3	90Fh	DAC1CON1	98Fh	CMOUT	AOFh	<u></u>	A8Fh		BOFh	22	B8Fh	1 <u>—</u> 1
810h	WDTU	890h	OSCSTAT1	910h	_	990h	CM1CON0	A10h	<u>==</u> :	A90h		B10h	2	B90h	% <u>—</u> :
811h	BORCON	891h	OSCEN	911h		991h	CM1CON1	A11h		A91h	_	B11h		B91h	-
812h	VREGCON(2)	892h	OSCTUNE	912h	=	992h	CM1NCH	A12h	_	A92h	_	B12h	_	B92h	<u>-</u> :
813h	PCON0	893h	OSCFRQ	913h		993h	CM1PCH	A13h	_	A93h	_	B13h		B93h	-
814h	PCON1	894h	_	914h		994h	CM2CON0	A14h	_	A94h	_	B14h		B94h	
815h		895h	CLKRCON	915h		995h	CM2CON1	A15h		A95h		B15h		B95h	: <u>—</u> :
816h	_	896h	CLKCLK	916h	-	996h	CM2NCH	A16h		A96h	j	B16h	_	B96h	-
817h	1	897h		917h	J	997h	CM2PCH	A17h	-	A97h	Ţ	B17h	-	B97h	-
818h	)	898h	120	918h	j	998h	_	A18h		A98h	j	B18h	_	B98h	_
819h		899h	120	919h		999h		A19h	RC2REG	A99h	ĵ	B19h	_	B99h	-
81Ah	NVMADRL	89Ah	12.0	91Ah	J	99Ah	_	A1Ah	TX2REG	A9Ah	Ţ	B1Ah	_	B9Ah	-
81Bh	NVMADRH	89Bh		91Bh	-	99Bh	_	A1Bh	SP2BRGL	A9Bh		B1Bh	-	B9Bh	( <del></del> 8)
81Ch	NVMDATL	89Ch	_	91Ch		99Ch	-	A1Ch	SP2BRGH	A9Ch	::	B1Ch	_	B9Ch	-
81Dh	NVMDATH	89Dh		91Dh		99Dh	-	A1Dh	RC2STA	A9Dh	\—\(\)	B1Dh	_	B9Dh	: <del>_</del> :
81Eh	NVMCON1	89Eh	_	91Eh	-	99Eh	_	A1Eh	TX2STA	A9Eh	2-3	B1Eh	_	B9Eh	::
81Fh	NVMCON2	89Fh	_	91Fh	ZCDCON	99Fh		A1Fh	BAUD2CON	A9Fh	-	B1Fh	-	B9Fh	_
820h		8A0h		920h	2018 C 15	9A0h		A20h		AA0h	Colored to the second	B20h		BA0h	
	Unimplemented		Unimplemented		Unimplemented		Unimplemented		Unimplemented		Unimplemented		Unimplemented		Unimplemented
	Read as '0'		Read as '0'		Read as '0'		Read as '0'		Read as '0'	-	Read as '0'		Read as '0'		Read as '0'
86Fh		8EFh		96Fh		9EFh		A6Fh		AEFh		B6Fh		BEFh	
870h	Common RAM	8F0h	Common RAM	970h	Common RAM	9F0h	Common RAM	A70h	Common RAM	AF0h	Common RAM	B70h	Common RAM	BF0h	Common RAM
58,50,000	Accesses	57.972.000	Accesses	0.0000000000000000000000000000000000000	Accesses	377070	Accesses	774WX	Accesses	252223360	Accesses	5500000	Accesses		Accesses
87Fh	70h-7Fh	8FFh	70h-7Fh	97Fh	70h-7Fh	9FFh	70h-7Fh	A7Fh	70h-7Fh	AFFh	70h-7Fh	B7Fh	70h-7Fh	BFFh	70h-7Fh

1:Unimplemented locations read as '0'.
 Register not implemented on LF devices.

DS40001853D-page 35

	BANK 56		BANK 57		BANK 58		BANK 59		BANK 60		BANK 61		BANK 62		BANK 63
1C00h	Core Register (Table 4-3)	1C80h	Core Register (Table 4-3)	1D00h	Core Register (Table 4-3)	1D80h	Core Register (Table 4-3)	1E00h	Core Register (Table 4-3)	1E80h	Core Register (Table 4-3)	1F00h	Core Register (Table 4-3)	1F80h	Core Register (Table 4-3)
1C0Bh 1C0Ch	_	1C8Ch		1D0Bh	_	1D8Bh		1E0Ch		1E8Ch		1F0Ch		1F8Ch	
1C0Dh		1C8Dh		1D0Dh		D8Dh1		1E0Dh		1E8Dh		1F0Dh		1F8Dh	
1C0Eh		1C8Eh		1D0Eh		1D8Eh		1E0Eh		1E8Eh		1F0Eh		1F8Eh	
1C0Fh	_	1C8Fh		1D0Fh	_	1D8Fh		1E0Fh		1E8Fh		1F0Fh		1F8Fh	
1C10h	_	1C90h		1D10h	_	1D90h		1E10h		1E90h		1F10h	1	1F90h	
1C11h	_	1C91h	_	1D11h	_	1D91h		1E11h		1E91h		1F11h		1F91h	
1C12h	_	1C92h	_	1D12h	_	1D92h		1E12h		1E92h		1F12h		1F92h	
1C13h	_	1C93h		1D13h	_	1D93h		1E13h		1E93h		1F13h		1F93h	
1C14h	_	1C94h	_	1D14h	-	1D94h	_	1E14h		1E94h		1F14h		1F94h	
1C15h	.—	1C95h	_	1D15h	-	1D95h	_	1E15h		1E95h		1F15h		1F95h	
1C16h	-	1C96h	_	1D16h		1D96h	_	1E16h		1E96h		1F16h		1F96h	
1C17h	-	1C97h	_	1D17h	-	1D97h	_	1E17h	CLC Controls	1E97h	nnnPPS Controls	1F17h	RxyPPS Controls	1F97h	22 M (1920) 10 (1920)
1C18h	-	1C98h	_	1D18h	-	1D98h	_	1E18h	(See Table 4-8 for	1E98h	(See Table 4-8 for	1F18h	(See Table 4-8 for	1F98h	(See Table 4-8 f register mapping
1C19h	_	1C99h	_	1D19h	-	1D99h	_	1E19h	register mapping	1E99h	register mapping	1F19h	register mapping	1F99h	details)
1C1Ah	. —	1C9Ah	_	1D1Ah	_	1D9Ah	-	1E1Ah	details)	1E9Ah	details)	1F1Ah		1F9Ah	
1C1Bh	_	1C9Bh	_	1D1Bh	_	1D9Bh	_	1E1Bh		1E9Bh		1F1Bh		1F9Bh	ķ.
1C1Ch	-	1C9Ch	_	1D1Ch	_	1D9Ch	_	1E1Ch		1E9Ch		1F1Ch		1F9Ch	
1C1Dh	-	1C9Dh	-	1D1Dh	-	1D9Dh	_	1E1Dh		1E9Dh		1F1Dh		1F9Dh	
1C1Eh	(s <del></del> ):	1C9Eh		1D1Eh	.—.	1D9Eh	_	1E1Eh		1E9Eh		1F1Eh		1F9Eh	
1C1Fh	· -	1C9Fh	_	1D1Fh		1D9Fh	_	1E1Fh		1E9Fh		1F1Fh		1F9Fh	
1C20h		1CA0h		1D20h		1DA0h		1E20h		1EA0h		1F20h		1FA0h	
	Unimplemented Read as '0'		Unimplemented Read as '0'		Unimplemented Read as '0'		Unimplemented Read as '0'								
1C6Fh		1CEFh		1D6Fh		1DEFh		1E6Fh		1EEFh		1F6Fh		1FEFh	
1C70h	Common RAM Accesses	1CF0h	Common RAM Accesses	1D70h	Common RAM Accesses	1DF0h	Common RAM Accesses	1E70h	Common RAM Accesses	1EF0h	Common RAM Accesses	1F70h	Common RAM Accesses	1FF0h	Common RAM Accesses
1C7Fh	70h-7Fh	1CFFh	70h-7Fh	1D7Fh	70h-7Fh	1DFFh	70h-7Fh	1E7Fh	70h-7Fh	1EFFh		1F7Fh		1FFFh	70h-7Fh
	ron-ri n		1911-1111		7011-7711		701-7111	1-11	ron-ri n		roierin		/ VIII-III		runefill

Note 1: Unimplemented locations read as '0'.

<sup>2:</sup> The banks 24-55 have been omitted from the tables in the data sheet since the banks have unimplemented registers.

TABLE 4-8: PIC16(L)F15354/55 MEMORY MAP, BANKS 60, 61, 62, AND 63

	Bank 60	Store	Bank 61	4300	Bank 62		Bank 63
1E0Ch	_	1E8Ch	<u>—</u> 8	1F0Ch	F <u>=</u>	1F8Ch	_
1E0Dh	-	1E8Dh	<del>==</del> :	1F0Dh	:	1F8Dh	=
1E0Eh	-	1E8Eh	<del>-</del>	1F0Eh	<del>-</del>	1F8Eh	<del>:</del> :
1E0Fh	CLCDATA	1E8Fh	PPSLOCK	1F0Fh	-	1F8Fh	_
1E10h	CLC1CON	1E90h	INTPPS	1F10h	RA0PPS	1F90h	_
1E11h	CLC1POL	1E91h	T0CKIPPS	1F11h	RA1PPS	1F91h	
1E12h	CLC1SEL0	1E92h	T1CKIPPS	1F12h	RA2PPS	1F92h	==
1E13h	CLC1SEL1	1E93h	T1GPPS	1F13h	RA3PPS	1F93h	-
1E14h	CLC1SEL2	1E94h	<del></del> :	1F14h	RA4PPS	1F94h	<del>_</del>
1E15h	CLC1SEL3	1E95h	<del></del> 0	1F15h	RA5PPS	1F95h	<u></u>
1E16h	CLC1GLS0	1E96h	<u>=</u> :	1F16h	RA6PPS	1F96h	_
1E17h	CLC1GLS1	1E97h		1F17h	RA7PPS	1F97h	-
1E18h	CLC1GLS2	1E98h	<del></del> :	1F18h	RB0PPS	1F98h	_
1E19h	CLC1GLS3	1E99h	-	1F19h	RB1PPS	1F99h	_
1E1Ah	CLC2CON	1E9Ah	<del></del> .	1F1Ah	RB2PPS	1F9Ah	_
1E1Bh	CLC2POL	1E9Bh	<u></u>	1F1Bh	RB3PPS	1F9Bh	<u> </u>
1E1Ch	CLC2SEL0	1E9Ch	T2INPPS	1F1Ch	RB4PPS	1F9Ch	
1E1Dh	CLC2SEL1	1E9Dh	12111110	1F1Dh	RB5PPS	1F9Dh	
THE PORT OF STREET	CLC2SEL2	10.000000000000000000000000000000000000		1F1Eh	RB6PPS	1F9Eh	
1E1Eh	CLC2SEL2	1E9Eh	<del></del>		RB7PPS	1F9Fh	<del>-</del>
1E1Fh		1E9Fh	<del></del>	1F1Fh			<del></del>
1E20h	CLC2GLS0	1EA0h	—	1F20h	RC0PPS	1FA0h	_
1E21h	CLC2GLS1	1EA1h	CCP1PPS	1F21h	RC1PPS	1FA1h	
1E22h	CLC2GLS2	1EA2h	CCP2PPS	1F22h	RC2PPS	1FA2h	
1E23h	CLC2GLS3	1EA3h	<del></del> 2	1F23h	RC3PPS	1FA3h	<del>-</del>
1E24h	CLC3CON	1EA4h	<del></del> 1	1F24h	RC4PPS	1FA4h	<del>-</del>
1E25h	CLC3POL	1EA5h	==:	1F25h	RC5PPS	1FA5h	
1E26h	CLC3SEL0	1EA6h	<u>=</u> 11	1F26h	RC6PPS	1FA6h	<del>-</del>
1E27h	CLC3SEL1	1EA7h		1F27h	RC7PPS	1FA7h	
1E28h	CLC3SEL2	1EA8h		1F28h		1FA8h	
1E29h	CLC3SEL3	1EA9h		1F29h		1FA9h	<del>-</del>
1E2Ah	CLC3GLS0	1EAAh		1F2Ah	<del>-</del>	1FAAh	<del>-</del>
1E2Bh	CLC3GLS1	1EABh	<u>=</u> *	1F2Bh		1FABh	
1E2Ch	CLC3GLS2	1EACh	<u>==</u> 3	1F2Ch	F <u></u>	1FACh	
1E2Dh	CLC3GLS3	1EADh	<del></del> :	1F2Dh	_	1FADh	-
1E2Eh	CLC4CON	1EAEh	-	1F2Eh	<del>-</del>	1FAEh	-
1E2Fh	CLC4POL	1EAFh	<del>-</del> -	1F2Fh	<del>-</del>	1FAFh	A <del>rea</del> ti
1E30h	CLC4SEL0	1EB0h	<del>5</del>	1F30h		1FB0h	-
1E31h	CLC4SEL1	1EB1h	CWG1PPS	1F31h	_	1FB1h	
1E32h	CLC4SEL2	1EB2h	<u>—</u> :	1F32h	-	1FB2h	
1E33h	CLC4SEL3	1EB3h	-	1F33h	-	1FB3h	-
1E34h	CLC4GLS0	1EB4h	—	1F34h	: <del></del>	1FB4h	-
1E35h	CLC4GLS1	1EB5h	<del></del>	1F35h	11-31	1FB5h	Sec. 15
1E36h	CLC4GLS2	1EB6h	52=0.	1F36h		1FB6h	-
1E37h	CLC4GLS3	1EB7h	2007	1F37h	% <u></u>	1FB7h	
1E38h	:	1EB8h		1F38h	ANSELA	1FB8h	-
1E39h	:—:	1EB9h	-	1F39h	WPUA	1FB9h	<del>-</del>
1E3Ah	-	1EBAh	<del></del> ::	1F3Ah	ODCONA	1FBAh	
1E3Bh	_	1EBBh	CLCIN0PPS	1F3Bh	SLRCONA	1FBBh	_
1E3Ch	12	1EBCh	CLCIN1PPS	1F3Ch	INLVLA	1FBCh	<u> </u>
1E3Dh	_	1EBDh	CLCIN2PPS	1F3Dh	IOCAP	1FBDh	_
1E3Eh	· · · · · · · · · · · · · · · · · · ·	1EBEh	CLCIN3PPS	1F3Eh	IOCAN	1FBEh	:—:
1E3Fh	_	1EBFh	-	1F3Fh	IOCAF	1FBFh	_
No-continue of the continue of		The second second second	<del></del>	1F40h	-	1FC0h	X. 8.
1E40h 1E41h		1EC0h	<u></u>	1F41h		1FC1h	<u> </u>
1F4 ID 1	_	IEUIN		1174111		II O III	

Legend: = Unimplemented data memory locations, read as '0'

TABLE 4-8: PIC16(L)F15354/55 MEMORY MAP, BANKS 60, 61, 62, AND 63 (CONTINUED)

Bank 60 Bank 61 Bank 62 Bank 6

300	Bank ou		Bank of		Bank 62		Bank 63
1E43h	1 <del></del>	1EC3h	ADACTPPS	1F43h	ANSELB	1FC3h	_
1E44h	_	1EC4h	-	1F44h	WPUB	1FC4h	_
1E45h	<del>-</del>	1EC5h	SSP1CLKPPS	1F45h	ODCONB	1FC5h	_
1E46h	_	1EC6h	SSP1DATPPS	1F46h	SLRCONB	1FC6h	_
1E47h	_	1EC7h	SSP1SSPPS	1F47h	INLVLB	1FC7h	_
1E48h	_	1EC8h	SSP2CLKPPS	1F48h	IOCBP	1FC8h	_
1E49h	-	1EC9h	SSP2DATPPS	1F49h	IOCBN	1FC9h	_
1E4Ah	_	1ECAh	SSP2SSPPS	1F4Ah	IOCBF	1FCAh	_
1E4Bh	* <u>=</u>	1ECBh	RX1DTPPS	1F4Bh	_	1FCBh	_
1E4Ch	_	1ECCh	TX1CKPPS	1F4Ch	—	1FCCh	-
1E4Dh	_	1ECDh	RX2DTPPS	1F4Dh	_	1FCDh	-
1E4Eh	_	1ECEh	TX2CKPPS	1F4Eh	ANSELC	1FCEh	<del></del>
1E4Fh	_	1ECFh	<del>1 -</del> 0	1F4Fh	WPUC	1FCFh	_
1E50h	· <u> </u>	1ED0h	<u></u>	1F50h	ODCONC	1FD0h	
1E51h	-	1ED1h		1F51h	SLRCONC	1FD1h	<del></del> 1
1E52h	_	1ED2h	-	1F52h	INLVLC	1FD2h	-
1E53h	-	1ED3h	<del></del> :	1F53h	IOCCP	1FD3h	<del></del>
1E54h	_	1ED4h	-	1F54h	IOCCN	1FD4h	<del>-</del>
1E55h	* <u></u>	1ED5h	<u>45—</u> 81	1F55h	IOCCF	1FD5h	2 <u>4—1</u> 1
1E56h	_	1ED6h		1F56h	_	1FD6h	<del>:</del> :
1E57h	:	1ED7h		1F57h	<del>-</del>	1FD7h	<del>:</del> :
1E58h	<del>-</del>	1ED8h	-	1F58h	<del>-</del>	1FD8h	<del>-</del>
1E59h	<del>-</del>	1ED9h	<del>1. 1</del> 8	1F59h	_	1FD9h	_
1E5Ah	<del>-</del>	1EDAh	<del>5-</del> 0.	1F5Ah	<del>-</del>	1FDAh	_
1E5Bh	<u> </u>	1EDBh	<u></u> /	1F5Bh	_	1FDBh	_
1E5Ch	_	1EDCh		1F5Ch	-	1FDCh	<del></del> -
1E5Dh	_	1EDDh		1F5Dh	_	1FDDh	-
1E5Eh	<del>-</del>	1EDEh	<del></del>	1F5Eh	·—	1FDEh	-
1E5Fh	_	1EDFh	<del></del> .	1F5Fh	i <del>-</del>	1FDFh	<del></del> .
1E60h	_	1EE0h	<u>=</u> 1	1F60h	_	1FE0h	-
1E61h	_	1EE1h		1F61h	_	1FE1h	_
1E62h	-	1EE2h		1F62h	_	1FE2h	<del>-</del>
1E63h	S <del></del>	1EE3h	<del></del> :	1F63h	-	1FE3h	BSR_ICDSHAD
1E64h	-	1EE4h	-	1F64h	: <del>-</del>	1FE4h	STATUS_SHAD
1E65h	<del>-</del>	1EE5h	<del></del> 2	1F65h	WPUE	1FE5h	WREG_SHAD
1E66h	_	1EE6h	<u>12—17</u>	1F66h	_	1FE6h	BSR_SHAD
1E67h	_	1EE7h	25.5	1F67h	_	1FE7h	PCLATH_SHAD
1E68h	-	1EE8h		1F68h	INLVLE	1FE8h	FSR0L_SHAD
1E69h	-	1EE9h		1F69h	IOCEP	1FE9h	FSR0H_SHAD
1E6Ah	-	1EEAh	<del>1  </del> 1	1F6Ah	IOCEN	1FEAh	FSR1L_SHAD
1E6Bh	_	1EEBh	<del>1</del>	1F6Bh	IOCEF	1FEBh	FSR1H_SHAD
1E6Ch	<del>-</del>	1EECh	<del>2=</del> 0.	1F6Ch	_	1FECh	_
1E6Dh	Y=2	1EEDh	<u>=</u> #	1F6Dh	-	1FEDh	STKPTR
1E6Eh	_	1EEEh	23	1F6Eh		1FEEh	TOSL
1E6Fh	1 <u></u>	1EEFh	2-31	1F6Fh	_	1FEFh	TOSH

Legend: = Unimplemented data memory locations, read as '0'

TABLE 4-9: SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (ALL BANKS)

Bank Offset Bank 0-Bank 63	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
All Banks	.60	199								Asi S	
x00h or x80h	INDF0	Addressing physical re	g this location egister)	n uses con	tents of FSF	ROH/FSROL	to address	data memo	ory (not a	xxxx xxxx	xxxx xxxx
x01h or x81h	INDF1	Addressing physical re	g this location egister)	n uses con	ory (not a	****	xxxx xxxx				
x02h or x82h	PCL				0000 0000	0000 0000					
x03h or x83h	STATUS				TO	PD	Z	DC	С	1 1000	q quuu
x04h or x84h	FSR0L	FSR0L	Indirect Da	ta Memory	Address U I	ow Pointer		100		0000 0000	uuuu uuuu
x05h or x85h	FSR0H	FSR0H	Indirect Da	ta Memory	Address 0 l	High Pointe	r			0000 0000	0000 0000
x06h or x86h	FSR1L	FSR1L	Indirect Da	ta Memory	Address 1 l	ow Pointer	r			0000 0000	uuuu uuuu
x07h or x87h	FSR1H	FSR1H	Indirect Da	ta Memory	Address 1	High Pointe	r			0000 0000	0000 0000
x08h or x88h	BSR	_	_	BSR<5:0>							00 0000
x09h or x89h	WREG	Working R	egister	•	0000 0000	uuuu uuuu					
x0Ah or x8Ah	PCLATH	_	Write Buffe	Write Buffer for the upper 7 bits of the Program Counter -00							
x0Bh or x8Bh	INTCON	GIE	PEIE	_			-	_	INTEDG	001	001

**Legend:**  $\mathbf{x}$  = unknown,  $\mathbf{u}$  = unchanged,  $\mathbf{q}$  = depends on condition, -= unimplemented, read as '0',  $\mathbf{r}$  = reserved. Shaded locations unimplemented, read as '0'.

Note 1: These Registers can be accessed from any bank.

Ch.
-
CD .
1.3
~

TABLE 4 40.	CDECIAL	CUNCTION DECICE	FR SUMMARY BANKS 0-63
TABLE 4-10.	SPECIAL	FUNCTION REGIST	FR SUMMARY BANKS U-63

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR		
Bank 0													
				CPU CO	RE REGISTERS;	see Table 4-9 for	specifics						
00Ch	PORTA	RA7	RA6	RA5	RA4	RA3	RA2	RA1	RA0	XXXX XXXX	uuuu uuuu		
00Dh	PORTB	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0	XXXX XXXX	uuuu uuuu		
00Eh	PORTC	RC7	RC6	RC5	RC4	RC3	RC2	RC1	RC0	XXXX XXXX	uuuu uuuu		
00Fh	55.0 A		Unimplemented										
010h	PORTE	-	·	-	- "	RE3	_	-	-	x	u		
011h	227	ė.			Unimple	mented	· >			V			
012h	TRISA	TRISA7	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	1111 1111	1111 1111		
013h	TRISB	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	1111 1111	1111 1111		
014h	TRISC	TRISC7 <sup>(1)</sup>	TRISC6 <sup>(1)</sup>	TRISC5	TRISC4	TRISC3	TRISC2	TRISC1	TRISC0	1111 1111	1111 1111		
015h	-				Unimple	mented				-	-		
016h	TRISE	_		_	-	(1)	2.2	420		1	1		
017h	<del></del> :				Unimple	mented				-	<del></del>		
018h	LATA	LATA7	LATA6	LATA5	LATA4	LATA3	LATA2	LATA1	LATA0	xxxx xxxx	uuuu uuuu		
019h	LATB	LATB7	LATB6	LATB5	LATB4	LATB3	LATB2	LATB1	LATB0	XXXX XXXX	uuuu uuuu		
01Ah	LATC	LATC7 <sup>(1)</sup>	LATC6 <sup>(1)</sup>	LATC5	LATC4	LATC3	LATC2	LATC1	LATC0	xxxx xxxx	uuuu uuuu		
01Bh	<del>55.</del> 8				Unimple	mented				_			
01Ch	-		Unimplemented										
01Dh	<u>122</u> 7	ė.	_	_ =									
01Eh	==:		Unimplemented										
01Fh	244.1		_										

Legend: Note 1: x = unknown, u = unchanged, q = depends on condition, -= unimplemented, read as '0', r = reserved. Shaded locations unimplemented, read as '0'. Unimplemented, read as '1'.

<b>TABLE 4-10:</b>	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
--------------------	--

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR	
Bank 1												
				CPU CO	RE REGISTERS	; see Table 4-3 fo	r specifics					
0001						_						
08Ch — 09Ah	-		Unimplemented									
09Bh	ADRESL	ADC Result Register I	Low							XXXX XXXX	uuuu uuuu	
09Ch	ADRESH	ADC Result Register I	High							XXXX XXXX	uuuu uuuu	
09Dh	ADCON0	CHS<5:0> GO/DONE ADON								0000 0000	0000 0000	
09Eh	ADCON1	ADFM	ĵ	ADCS<2:0>			_	ADP	REF<1:0>	000000	000000	
09Fh	ADACT	<u>~</u>	_	ADACT<4:0>						0 0000	0 0000	

TADIE 4 10.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IADLE 4-10.	SECUAL FUNCTION REGISTER SUMMART DANKS 0-03 ICONTINUEDI

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR		
Bank 2													
				CPU COF	RE REGISTERS	see Table 4-3 for	specifics						
		-		155 357 55672		**************************************	1445 C 444 C 44						
10Ch	2000		Unimplemented										
118h	_	į.	Onlingue/fierned										
119h	RC1REG	EUSART Receive Dat	ta Register							0000 0000	0000 0000		
11Ah	TX1REG	EUSART Transmit Da	ta Register							0000 0000	0000 0000		
11Bh	SP1BRGL				SP1BR	G<7:0>				0000 0000	0000 0000		
11Ch	SP1BRGH				SP1BR0	3<15:8>				0000 0000	0000 0000		
11Dh	RC1STA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 0000	0000 0000		
11Eh	TX1STA	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	0000 0010	0000 0010		
11Fh	BAUD1CON	ABDOVF	RCIDL		SCKP	BRG16		WUE	ABDEN	01-0 0-00	01-0 0-00		

TABLE 4 40.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IABLE 4-10.	SPECIAL FUNCTION REGISTER SUMMART BANKS 0-03 (CONTINUED)

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 3											
				CPU COI	RE REGISTERS;	see Table 4-3 for	specifics				
18Ch	SSP1BUF	Synchronous Serial	Port Receive Buffer/	Transmit Registe	r	-				xxxx xxxx	xxxx xxxx
18Dh	SSP1ADD	, x			ADD<	7:0>				0000 0000	0000 0000
18Eh	SSP1MSK		1-2 25a	-22	MSK<	7:0>				1111 1111	1111 1111
18Fh	SSP1STAT	SMP	CKE	D/Ā	Р	S	R/W	UA	BF	0000 0000	0000 0000
190h	SSP1CON1	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	0000 0000	0000 0000
191h	SSP1CON2	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN	0000 0000	0000 0000
192h	SSP1CON3	ACKTIM	PCIE	SCIE	BOEN	SDAHT	SBCDE	AHEN	DHEN	0000 0000	0000 0000
193h	44		- 100 miles	-30	Unimple	mented	\$			-	1
194h	<del>177</del> 5				Unimple	mented				_	
195h	-			10001	Unimple	mented				-	1
196h	SSP2BUF	Synchronous Serial	Port Receive Buffer/	Transmit Registe	r					xxxx xxxx	xxxx xxxx
197h	SSP2ADD	3	181	111	ADD<	7:0>				0000 0000	0000 0000
198h	SSP2MSK				MSK<	7:0>				1111 1111	1111 1111
199h	SSP2STAT	SMP	CKE	D/Ā	Р	S	R/W	UA	BF	0000 0000	0000 0000
19Ah	SSP2CON1	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	0000 0000	0000 0000
19Bh	SSP2CON2	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN	0000 0000	0000 0000
19Ch	SSP2CON3	ACKTIM	PCIE	SCIE	BOEN	SDAHT	SBCDE	AHEN	DHEN	0000 0000	0000 0000
19Dh	-				Unimple	mented				_	-
19Eh	227		Unimplemented							_	_ 22
19Fh	<del></del> :				Unimplei	mented			<u> </u>	_	_

TADIE 4 10.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IADLE 4-10.	SECUAL FUNCTION REGISTER SUMMART DANKS 0-03 ICONTINUEDI

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 4											
				CPU COI	RE REGISTERS	; see Table 4-3 for	specifics				
20Ch	TMR1L	Holding Register for	the Least Significa	ant Byte of the 16	6-bit TMR1 Regi	ster				0000 0000	uuuu uuuu
20Dh	TMR1H	Holding Register for th	ne Most Significant	Byte of the 16-bit	TMR1 Register		0000 0000	uuuu uuuu			
20Eh	T1CON	_	_	CKPS	S<1:0>		00 -000	uu -u0u			
20Fh	T1GCON	GE	GPOL	GTM	GSPM	GGO/DONE	0000 0x	uuuu ux			
210h	T1GATE	_	-			100	GSS<4:0>	i		0 0000	u uuuu
211h	T1CLK	-	:		<del></del> :		0000	uuuu			
212h										<u> </u>	

TADIE 4 10.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IADLE 4-10.	SECUAL FUNCTION REGISTER SUMMART DANKS 0-03 ICONTINUEDI

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 5											
				CPU COF	RE REGISTERS	; see Table 4-3 fo	r specifics				
28Ch	T2TMR	Holding Register for	the 8-bit TMR2 R	egister			a menu eta dantar dantar dan			0000 0000	0000 0000
28Dh	T2PR	TMR2 Period Registe	er			CHC				1111 1111	1111 1111
28Eh	T2CON	ON		CKPS<2:0>			OUT	PS<3:0>		0000 0000	0000 0000
28Fh	T2HLT	PSYNC	CKPOL	CKSYNC			MODE<4:0>			0000 0000	0000 0000
290h	T2CLKCON		_	==	222		С	S<3:0>		0000	0000
291h	T2RST	-	1 <del>-</del> 1		<del></del> :		RS	EL<3:0>		0000	0000
292h 29Fh	<del></del>		96 A	: Fig. 1	Unimple	mented				122	2

TABLE 4-1	0: SPECI	AL FUNCTION	N REGISTER	SUMMARY	BANKS 0-	63 (CONTIN	NUED)
- TENTO	2002 111	20000000	18375023	100000000000000000000000000000000000000	Haddeles	\$45,963463	5-1198012

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 6											
				CPU COI	RE REGISTERS;	see Table 4-3 for	rspecifics				
30Ch	CCPR1L	Capture/Compare/	PWM Register 1 (LS	SB)		_				xxxx xxxx	uuuu uuuu
30Dh	CCPR1H	Capture/Compare/	PWM Register 1 (M	SB)						XXXX XXXX	uuuu uuuu
30Eh	CCP1CON	EN	· <del>-</del> ·	OUT	FMT		МО	DE<3:0>		0-00 0000	0-00 0000
30Fh	CCP1CAP	_		_	_	-	000	000			
310h	CCPR2L	Capture/Compare/	PWM Register 2 (LS	SB)			ž.	XXXX XXXX	uuuu uuuu		
311h	CCPR2H	Capture/Compare/	pture/Compare/PWM Register 2 (MSB)								
312h	CCP2CON	EN	N — OUT FMT MODE<3:0>								0-00 0000
313h	CCP2CAP	_	,	-	<del>100</del> 2			CTS<2:0>		000	000
314h	PWM3DCL	DC<	:1:0>	_		_	-	::	-	xx	uu
315h	PWM3DCH			91	DC<	9:0>	11	315 105		XXXX XXXX	uuuu uuuu
316h	PWM3CON	EN	·	OUT	POL		<del></del>	5 <b>—</b> 5	-	0-00	0-00
317h	<u> </u>			27A	Unimple	mented	:	10 10		-	
318h	PWM4DCL	DC<	:1:0>	-	<del>121</del> 2	-	=		_	xx	uu
319h	PWM4DCH		70 70	E84 E84	DC<	9:0>	8	50 50 50 16		xxxx xxxx	uuuu uuuu
31Ah	PWM4CON	EN	<del>-</del>	OUT	POL		-			0-00	0-00
31Bh	-				Unimple	mented				-	-
31Ch	PWM5DCL	DC<	:1:0>		222		2.2	_	<u>-200</u> 2	хх	uu
31Dh	PWM5DCH				DC<	9:0>				XXXX XXXX	uuuu uuuu
31Eh	PWM5CON	EN		OUT	POL	_	-	-	_	0-00	0-00
31Fh					Unimple	mented					_

TABLE 4-10:	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED	))

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 7											
				CPU COF	RE REGISTERS	see Table 4-3 for	r specifics				
38Ch	PWM6DCL	DC<1:	0>	_	_			- 1	_	xx	uu
38Dh	PWM6DCH		X2	500 400	DC<	9:0>	~			XXXX XXXX	uuuu uuuu
38Eh	PWM6CON	EN	_	OUT	POL	_	2.22	_	<u>-200</u>	0-00	0-00
38Fh 39Fh			Unimplemented								

TABLE 4-10: SPECIAL FUNCTION REGISTER SUMMART BANKS 0-03 (CONTINUEL	<b>TABLE 4-10:</b>	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
---	--------------------	--

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 8-10						_					
				CPU COR	RE REGISTERS;	see Table 4-3 for	specifics				
x0Ch/ x8Ch — x1Fh/ x9Fh	-		Unimplemented								

Name

TMROL

TMROH

T0CON0

T0CON1

Address Bank 11

597h

598h

599h

59Ah

59Bh

59Ch

59Dh

59Eh

Bit 7

T0EN

				CPLLCO	RE REGISTERS;	see Table 4-3 for	specifics				
7.509000	E succession of the second			01000			оресинов			Strong Averages	
58Ch	NCO1ACCL				NCO1AC	C<7:0>				0000 0000	0000 0000
58Dh	NCO1ACCH		we.	5 <u>=</u> -5	NCO1AC	C<15:8>				0000 0000	0000 0000
58Eh	NCO1ACCU			_	-		NCO1A	CC<19:16>		0000	0000
58Fh	NCO1INCL				NCO1ING	C<7:0>	0000 0001	0000 0001			
590h	NCO1INCH				NCO1ING	<15:8>	0000 0000	0000 0000			
591h	NCO1INCU	_	1-1	_	<del></del>		NCO1II	0000	0000		
592h	NCO1CON	N1EN	-	N1OUT	N1POL	-	-	·	N1PFM	0-000	0-000
593h	NCO1CLK	į.	N1PWS<2:0>		-			N1CKS<2:0	)>	000000	000000
594h	ш.		Unimplemented							-	-
595h	<u> </u>		Unimplemented								_
596h	-				Unimpler	mented				-	-

Unimplemented

Unimplemented

Unimplemented

Unimplemented

Unimplemented

T016BIT

Bit 4

Bit 3

Bit 2

Bit 1

T0OUTPS<3:0>

Bit 0

Value on: POR, BOR

0000 0000

1111 1111

0-00 0000

0000 0000

0000 0000

1111 1111

0-00 0000

0000 0000

PIC16(L)F15354/55

59Fh T0CS<2:0> TOASYNC T0CKPS<3:0> x = unknown, u = unchanged, q = depends on condition, - = unimplemented, read as '0', x = reserved. Shaded locations unimplemented, read as '0'. Legend:

TOOUT

Holding Register for the Least Significant Byte of the 16-bit TMR0 Register

Holding Register for the Most Significant Byte of the 16-bit TMR0 Register

TABLE 4-10: SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)

Bit 5

Bit 6

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 12											
				CPU COF	RE REGISTERS;	see Table 4-3 for	specifics				
60Ch	CWG1CLKCON	_	_	T =	_	_	-	_	cs	0	0
60Dh	CWG1DAT	_	_	_			DA	T<3:0>		0000	0000
60Eh	CWG1DBR	5==	, <del>-</del> ,		-	DB	R<5:0>			00 0000	00 0000
60Fh	CWG1DBF	-	·			DB	F<5:0>			00 0000	00 0000
610h	CWG1CON0	EN	LD	<u>==</u>	227	_		MODE<2:0>		00000	00000
611h	CWG1CON1	-	_	IN		POLD	POLC	POLB	POLA	x- 0000	u- 0000
612h	CWG1AS0	SHUTDOWN	REN	LSBD	)<2:0>	LSAC	<2:0>	-	-	0001 01	0001 01
613h	CWG1AS1	_	_	-	AS4E	AS3E	AS2E	AS1E	AS0E	0 0000	u 0000
614h	CWG1STR	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA	0000 0000	0000 0000
615h 61Fh	Take (		Unimplemented								=

TADIE 4 10.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IADLE 4-10.	SECUAL FUNCTION REGISTER SUMMART DANKS 0-03 ICONTINUEDI

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 13											
				CPU COR	RE REGISTERS;	see Table 4-3 for	specifics				
68Ch 69Fh	-				Unimple	mented				-	-

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR	
Bank 14												
				CPU COI	RE REGISTERS;	see Table 4-3 for	r specifics					
70Ch	PIR0	_	TMR0IF IOCIF INTF									
70Dh	PIR1	OSFIF	CSWIF	1		_	_	·	ADIF	0000	0000	
70Eh	PIR2	_	ZCDIF	_		_	<u>- 22</u>	C2IF	C1IF	-000	-000	
70Fh	PIR3	RC2IF	TX2IF	RC1IF	TX1IF	BCL2IF	SSP2IF	BCL1IF	SSP1IF	0000 0000	0000 0000	
710h	PIR4	-	-	-		_	-	TMR2IF	TMR1IF	00	00	
711h	PIR5	CLC4IF	CLC3IF	CLC2IF	CLC1IF		_	<del></del>	TMR1GIF	00000	00000	
712h	PIR6	_	<u> </u>	-	500	_	-	CCP2IF	CCP1IF	00	00	
713h	PIR7	_	;—:	N∨MIF	NCO1IF		_	.—:	CWG1IF	000	000	
714h	227				Unimple	mented			1	_	_	
715h	-				Unimple	mented				-	-	
716h	PIE0	_	_	TMR0IE	IOCIE	_	_		INTE	000	000	
717h	PIE1	OSFIE	CSWIE	_	-	: <u>-</u> :	-		ADIE	0000	0000	
718h	PIE2	-	ZCDIE	-		_	_	C2IE	C1IE	-000	-000	
719h	PIE3	RC2IE	TX2IE	RC1IE	TX1IE	BCL2IE	SSP2IE	BCL1IE	SSP1IE	0000 0000	0000 0000	
71Ah	PIE4	=	_	_	125	_	(2.2)	TMR2IE	TMR1IE	00	00	
71Bh	PIE5	CLC4IE	CLC3IE	CLC2IE	CLC1IE		-	-	TMR1GIE	00000	00000	
71Ch	PIE6	_	_	_	_	_	_	CCP2IE	CCP1IE	00	00	
71Dh	PIE7	_	-	NVMIE	NCO1IE	. <del>-</del> :	(50)	5 <del></del>	CWG1IE	000	000	
71Eh					Unimple	mented					-	
71Fh	<u> 22</u> 0				Unimple	mented						

TABLE 4-10:	SPECIAL FUNCTION REGISTER SUMMARY BA	ANKS 0-63 (CONTINUED)

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 15											
				CPU COF	RE REGISTERS;	see Table 4-3 for	specifics				
78Ch 795h	Unimplemented									-	-
796h	PMD0	SYSCMD	FVRMD				NVMMD	CLKRMD	IOCMD	00000	00000
797h	PMD1	NCO1MD	_	_	-	-	TMR2MD	TMR1MD	TMR0MD	0000	0000
798h	PMD2		DAC1MD	ADCMD		_	CMP2MD	CMP1MD	ZCDMD	-00000	-00000
799h	PMD3	=	_	PWM6MD	PWM5MD	PWM4MD	PWM3MD	CCP2MD	CCP1MD	00 0000	00 0000
79Ah	PMD4	UART2MD	UART1MD	MSSP2MD	MSSP1MD	_	100		CWG1MD	00000	00000
79Bh	PMD5	_	_	_	CLC4MD	CLC3MD	CLC2MD	CLC1MD	_	0 000-	0 000-
79Ch	=				Unimple	mented				_	
79Dh	-		Unimplemented							-	-
79Eh	2007				Unimple	mented			•	=	_
79Fh	-				Unimple	mented				_	-

TABLE 4 40.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IADLE 4-10.	SPECIAL FUNCTION REGISTER SUMMART DANKS 0-03 ICONTINUEDI

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 16											
				CPU COI	RE REGISTERS;	see Table 4-3 for	specifics				
80Ch	WDTCONO	=	WDTPS<4:0> SWDTEN								
80Dh	WDTCON1			WDTCS<2:0>				WINDOW<2:0	<b> &gt;</b>	-ddd -ddd	-ddd -ddd
80Eh	WDTPSL				PSCNT	<7:0>				0000 0000	0000 0000
80Fh	WDTPSH				PSCNT	<15:8>				0000 0000	0000 0000
810h	WDTTMR	_		WDTTN	MR<3:0>		STATE	PSCNT17	PSCNT16	NXXX X000	000x xxxx
811h	BORCON	SBOREN	9. <del></del> 9	2.00		_	<u> </u>	1_0	BORRDY	1q	uu
812h	VREGCON	-	-	_	-	_	_	VREGPM <sup>(1)</sup>	_	0-	0-
813h	PCON0	STKOVF	STKUNF	WDTWV	RWDT	RMCLR	RI	POR	BOR	0011 110q	qqqq qquu
814h	PCON1	:		: <del></del>	<del>20</del> 1	-	100	MEMV	_	1-	u-
815h	225		147	(A)	Unimple	mented				_	=
816h	<del>27</del> 8				Unimple	mented					-
817h	-				Unimple	mented				_	1
818h	_				Unimple	mented				_	_
819h	-				Unimple	mented				-	-
81Ah	NVMADRL				NVMAD	R<7:0>				xxxx xxxx	uuuu uuuu
81Bh	NVMADRH	-				NVMADR<14:8	<b>&gt;</b>			-xxx xxxx	-uuu uuuu
81Ch	NVMDATL	3	700 700 700	677	NVMDA	T<7:0>				0000 0000	0000 0000
81Dh	NVMDATH	_				NVMD	AT<13:8>			00 0000	00 0000
81Eh	NVMCON1	_	NVMREGS	LWLO	FREE	WRERR	WREN	WR	RD	-000 x000	-000 <b>q</b> 000
81Fh	NVMCON2				NVMCON	N2<7:0>				XXXX XXXX	uuuu uuuu

x = unknown, u = unchanged, q = depends on condition, -= unimplemented, read as '0', r = reserved. Shaded locations unimplemented, read as '0'. Present only on PIC16F15354/55. Legend: Note 1:

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 17											
				CPU COF	RE REGISTERS	; see Table 4-3 for	specifics				
88Ch	CPUDOZE	IDLEN	DOZEN	ROI	DOE	T -		DOZE<2:0>		0000 -000	u000 -000
88Dh	OSCCON1	-		NOSC<2:0>			NDI	V<3:0>		-qqq 0000	-qqq 0000
88Eh	OSCCON2	_		COSC<2:0>		1111	CDIV<3:0>				-ddd dddd
88Fh	OSCCON3	CSWHOLD	SOSCPWR	_	ORDY	NOSCR	-	2 <del></del> 5	-	00-0 0	00-0 0
890h	OSCSTAT	EXTOR	HFOR	MFOR	LFOR	SOR	ADOR	_	PLLR	q000 qq-0	qqqq qq-q
891h	OSCEN	EXTOEN	HFOEN	MFOEN	LFOEN	SOSCEN	ADOEN			0000 00	0000 00
892h	OSCTUNE	-	_			HFTU	JN<5:0>	3		10 0000	10 0000
893h	OSCFRQ	_	_	_	51	T -		HFFRQ<2:0>		qqq	qqq
894h	-				Unimple	mented				_	-
895h	CLKRCON	CLKREN	_	_	CLKRI	DC<1:0>		CLKRDIV<2:0	>	0ж жжж	0u uuuu
896h	CLKRCLK	_	_	_	-		CLKR	CLK<3:0>		0000	0000
897h 89Fh	_		Unimplemented							<u></u>	

TABLE 4 40.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IADLE 4-10.	SPECIAL FUNCTION REGISTER SUMMART DANKS 0-03 ICONTINUEDI

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 18						_					
				CPU COF	RE REGISTERS;	see Table 4-3 fo	r specifics				
90Ch	FVRCON	FVREN	FVRRDY	TSEN	TSRNG	CDAF	/R<1:0>	ADF	VR<1:0>	0x00 xxxx	0q00 uuuu
90Dh	-				Unimplen	mented				-	_
90Eh	DAC1CON0	EN	, . <del></del>	OE1	OE2	PSS	<1:0>	_	NSS	0-00 00-0	0-00 00-0
90Fh	DAC1CON1	_	.—	-			DAC1R<4:0	>		0 0000	0 0000
910h 91Eh	<del>127</del> 2				Unimplen	nented					=
91Fh	ZCDCON	ZCDSEN		ZCDOUT	ZCDPOL		(44)	ZCDINTP	ZCDINTN	0-x000	00 0x-0

TADIE 4 10.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IADLE 4-10.	SECUAL FUNCTION REGISTER SUMMART DANKS 0-03 ICONTINUEDI

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 19											
				CPU COI	RE REGISTERS;	see Table 4-3 for	r specifics				
98Ch	==				Unimple	mented				_	_
98Dh					Unimple	mented					-
98Eh	<del>22.</del> 8				Unimple	mented		1111			=
98Fh	CMOUT	-	-	-	-	1	-	MC2OUT	MC1OUT	00	00
990h	CM1CON0	EN	OUT	_ =	POL	_	12.00	HYS	SYNC	00-000	00-000
991h	CM1CON1		-	- <del></del>	<del></del> :		-	INTP	INTN	00	00
992h	CM1NCH	_	_	-		_		NCH<2:0>	3	000	000
993h	CM1PCH	-	-	_	-			PCH<2:0>		000	000
994h	CM2CON0	EN	OUT	-	POL	_	-	HYS	SYNC	00-000	00-000
995h	CM2CON1	2	_		<u></u>	_	1910	INTP	INTN	00	00
996h	CM2NCH	-	_	_	-			NCH<2:0>		000	000
997h	CM2PCH	_	_	_		_		PCH<2:0>		000	000
998h 99Fh			•		Unimple	mented				-	_

TABLE 4 40.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IADLE 4-10.	SPECIAL FUNCTION REGISTER SUMMART DANKS 0-03 ICONTINUEDI

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR		
Bank 20													
				CPU COF	RE REGISTERS	see Table 4-3 for	specifics						
1001 I				3.30.00.00.00.00.00.00.00.00.00.00.00.00			700.3 Car (\$60.00 - 00) Car						
A0Ch A18h	-		Unimplemented										
A19h	RC2REG				RC2RE	G<7:0>				0000 0000	0000 0000		
A1Ah	TX2REG				TX2RE	G<7:0>				0000 0000	0000 0000		
A1Bh	SP2BRGL				SP2BR0	GL<7:0>				0000 0000	0000 0000		
A1Ch	SP2BRGH				SP2BRG	H<7:0>				0000 0000	0000 0000		
A1Dh	RC2STA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 0000	0000 0000		
A1Eh	TX2STA	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	0000 0010	0000 0010		
A1Fh	BAUD2CON	ABDOVF	RCIDL	-	SCKP	BRG16	_	WUE	ABDEN	01-0 0-00	01-0 0-00		

<b>TABLE 4-10:</b>	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
--------------------	--

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 21-59	-										
				CPU COF	RE REGISTERS;	see Table 4-3 for	specifics				
x0Ch/ x8Ch  x1Fh/ x9Fh	-				Unimple	mented				-	<del>770</del> )

C1
6
(L
)F
П
_
S
W
(J
4/
5
5

TADLE 4 40.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IABLE 4-10.	SPECIAL FUNCTION REGISTER SUMMART BANKS 0-03 (CONTINUED)

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 60									4		
				CPU COF	RE REGISTERS;	see Table 4-3 fo	r specifics				
1E0Ch					Unimple	mented				_	-
1E0Dh	-				Unimple	mented				_	_
1E0Eh	+				Unimple	mented				_	-
1E0Fh	CLCDATA	_		_	<del>55</del> 4	MLC4OUT	MLC3OUT	MLC2OUT	MLC10UT	хххх	uuu
1E10h	CLCCON	LC1EN	-	LC10UT	LC1INTP	LC1INTN		LC1MODE<2:	0>	0-00 0000	0-00 000
1E11h	CLC1POL	LC1POL		_		LC1G4POL	LC1G3POL	LC1G2POL	LC1G1POL	0 жжж	0 uuu
1E12h	CLC1SEL0	-	:=:			LC10	01S<5:0>			xx xxxx	uu uuu
1E13h	CLC1SEL1	_	-			LC1I	)2S<5:0>			жж жжжж	uu uuu
1E14h	CLC1SEL2	-	-			LC1I	03S<5:0>			xx xxxx	uu uuu
1E15h	CLC1SEL3	_	×—-	8		LC1I	04S<5:0>			xx xxxx	uu uuu
1E16h	CLC1GLS0	LC1G1D4T	LC1G1D4N	LC1G1D3T	LC1G1D3N	LC1G1D2T	LC1G1D2N	LC1G1D1T	LC1G1D1N	XXXX XXXX	uuuu uut
1E17h	CLC1GLS1	LC1G2D4T	LC1G2D4N	LC1G2D3T	LC1G2D3N	LC1G2D2T	LC1G2D2N	LC1G2D1T	LC1G2D1N	XXXX XXXX	uuuu uut
1E18h	CLC1GLS2	LC1G3D4T	LC1G3D4N	LC1G3D3T	LC1G3D3N	LC1G3D2T	LC1G3D2N	LC1G3D1T	LC1G3D1N	XXXX XXXX	uuuu uut
1E19h	CLC1GLS3	LC1G4D4T	LC1G4D4N	LC1G4D3T	LC1G4D3N	LC1G4D2T	LC1G4D2N	LC1G4D1T	LC1G4D1N	xxxx xxxx	uuuu uut
1E1Ah	CLC2CON	LC2EN	_	LC2OUT	LC2INTP	LC2INTN		LC2MODE<2:	0>	0-00 0000	0-00 000
1E1Bh	CLC2POL	LC2POL	_	_	<del>20</del> 0	LC2G4POL	LC2G3POL	LC2G2POL	LC2G1POL	0 xxxx	0 uuı
1E1Ch	CLC2SEL0	_	· .—			LC2I	01S<5:0>			xx xxxx	uu uuu
1E1Dh	CLC2SEL1	~	_			LC2I	)2S<5:0>			xx xxxx	uu uuu
1E1Eh	CLC2SEL2	-	-			LC2I	03S<5:0>			xx xxxx	uu uut
1E1Fh	CLC2SEL3	_	_			LC2I	04S<5:0>			xx xxxx	uu uuu
1E20h	CLC2GLS0	LC2G1D4T	LC2G1D4N	LC2G1D3T	LC2G1D3N	LC2G1D2T	LC2G1D2N	LC2G1D1T	LC2G1D1N	XXXX XXXX	uuuu uuu
1E21h	CLC2GLS1	LC2G2D4T	LC2G2D4N	LC2G2D3T	LC2G2D3N	LC2G2D2T	LC2G2D2N	LC2G2D1T	LC2G2D1N	XXXX XXXX	uuuu uuu
1E22h	CLC2GLS2	LC2G3D4T	LC2G3D4N	LC2G3D3T	LC2G3D3N	LC2G3D2T	LC2G3D2N	LC2G3D1T	LC2G3D1N	xxxx xxxx	uuuu uuu
1E23h	CLC2GLS3	LC2G4D4T	LC2G4D4N	LC2G4D3T	LC2G4D3N	LC2G4D2T	LC2G4D2N	LC2G4D1T	LC2G4D1N	XXXX XXXX	uuuu uuu
1E24h	CLC3CON	LC3EN	_	LC3OUT	LC3INTP	LC3INTN		LC3MODE		0-00 0000	0-00 000
1E25h	CLC3POL	LC3POL	-	_	-	LC3G4POL	LC3G3POL	LC3G2POL	LC3G1POL	0 жжжж	0 uuı
1E26h	CLC3SEL0	_	_				01S<5:0>			xx xxxx	uu uuu
1E27h	CLC3SEL1	_	_				)2S<5:0>			** ****	uu uuu
1E28h	CLC3SEL2	-	_			LC3I	03S<5:0>			xx xxxx	uu uuu
1E29h	CLC3SEL3	_	_	3			04S<5:0>			xx xxxx	uu uuu
1E2Ah	CLC3GLS0	LC3G1D4T	LC3G1D4N	LC3G1D3T	LC3G1D3N	LC3G1D2T	LC3G1D2N	LC3G1D1T	LC3G1D1N	XXXX XXXX	uuuu uuu

TABLE 4-10: SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 60 (Co	ontinued)										
1E2Bh	CLC3GLS1	LC3G2D4T	LC3G2D4N	LC3G2D3T	LC3G2D3N	LC3G2D2T	LC3G2D2N	LC3G2D1T	LC3G2D1N	XXXX XXXX	uuuu uuuu
1E2Ch	CLC3GLS2	LC3G3D4T	LC3G3D4N	LC3G3D3T	LC3G3D3N	LC3G3D2T	LC3G3D2N	LC3G3D1T	LC3G3D1N	xxxx xxxx	uuuu uuuu
1E2Dh	CLC3GLS3	LC3G4D4T	LC3G4D4N	LC3G4D3T	LC3G4D3N	LC3G4D2T	LC3G4D2N	LC3G4D1T	LC3G4D1N	XXXX XXXX	uuuu uuuu
1E2Eh	CLC4CON	LC4EN	_	LC4OUT	LC4INTP	LC4INTN		LC4MODE<2:0>			0-00 0000
1E2Fh	CLC4POL	LC4POL	:	-		LC4G4POL	LC4G3POL	LC4G2POL	LC4G1POL	0 жжж	0 uuuu
1E30h	CLC4SEL0	_	-		8 9		xx xxxx	uu uuuu			
1E31h	CLC4SEL1					LC4I	)2S<5:0>			xx xxxx	uu uuuu
1E32h	CLC4SEL2	-	:	100		LC4I	)3S<5:0>			xx xxxx	uu uuuu
1E33h	CLC4SEL3	2		25		LC4I	04S<5:0>	pe: 60		xx xxxx	uu uuuu
1E34h	CLC4GLS0	LC4G1D4T	LC4G1D4N	LC4G1D3T	LC4G1D3N	LC4G1D2T	LC4G1D2N	LC4G1D1T	LC4G1D1N	XXXX XXXX	uuuu uuuu
1E35h	CLC4GLS1	LC4G2D4T	LC4G2D4N	LC4G2D3T	LC4G2D3N	LC4G2D2T	LC4G2D2N	LC4G2D1T	LC4G2D1N	XXXX XXXX	uuuu uuuu
1E36h	CLC4GLS2	LC4G3D4T	LC4G3D4N	LC4G3D3T	LC4G3D3N	LC4G3D2T	LC4G3D2N	LC4G3D1T	LC4G3D1N	XXXX XXXX	uuuu uuuu
1E37h	CLC4GLS3	LC4G4D4T	LC4G4D4N	LC4G4D3T	LC4G4D3N	LC4G4D2T	LC4G4D2N	LC4G4D1T	LC4G4D1N	XXXX XXXX	uuuu uuuu
1E38h 1E6Fh	- Table		Unimplemented								-

C1	
6	
F1	
5	
3	
54	
5	

TABLE 4 40.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IABLE 4-10	SPECIAL FUNCTION REGISTER SUMMART BANKS U-03 (CONTINUED)

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR		
Bank 61													
				ODU COD	E DECISTEDS	T-bl- 4 2 6							
				CPU COR	E REGISTERS	see Table 4-3 fo	or specifics						
1E8Ch	<del>22</del> 2				Unimple	mented				-	200		
1E8Dh	==:				Unimple	mented				-	-		
1E8Eh	-				Unimple	mented				_	-		
1E8Fh	PPSLOCK	-	:	-	-	1 :	-	::	PPSLOCKED	0			
E90h	INTPPS	<u> 220</u>	_			INT	PPS<5:0>	50	244 1000	00 1000	uu uuu		
E91h	T0CKIPPS	1 <del>177</del>	:				00 0100	uu uuu					
1E92h	T1CKIPPS	_	_			01 0000	uu uuu						
1E93h	T1GPPS	1 <del></del>	: <del></del> :			00 1101	uu uuu						
1E94h													
1E9Bh	_		Unimplemented										
IE9Ch	T2INPPS	-	·—·			T2IN	IPPS<5:0>			01 0011	uu uuu		
1E9Dh					Unimple	Water St.							
1EA0h	=			80	Unimpie	mented				_	_		
1EA1h	CCP1PPS	\$ <del></del>		·		CCP	1PPS<5:0>			01 0010	uu uuu		
1EA2h	CCP2PPS	-	·			CCP	2PPS<5:0>			01 0001	uu uuu		
1EA3h			- 17-	300									
1EB0h	<del></del>				Unimple	mented				=	77		
1EB1h	CWG1PPS	- 22	* <u>-</u> -			cwg	1PPS<5:0>			00 1000	uu uuu		
1EB2h													
1EBAh	-				Unimple	mented				_	_		
1EBBh	CLCINOPPS		:			CLCIN	10PPS<5:0>			00 0000	uu uuu		
1EBCh	CLCIN1PPS	==	_	0.0		CLCIN	11PPS<5:0>			00 0001	uu uuu		
1EBDh	CLCIN2PPS	-	-			CLCIN	12PPS<5:0>			00 1110	uu uuu		
1EBEh	CLCIN3PPS	_	::			CLCIN	13PPS<5:0>			00 1111	uu uuu		
1EBFh						N. 7. 2. 2. 2							
1EC2h	===				Unimple	mented				-	750		
IEC3h	ADACTPPS	4.00				ADAC	TPPS<5:0>			001100	uuuuu		
EC4h	_				Unimple	mented				_			

TABLE 4-10: SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR
Bank 61 (C	ontinued)										
1EC5h	SSP1CLKPPS	-	·—·	1) 10		SSP1CI	.KPPS<5:0>			01 0011	uu uuuu
1EC6h	SSP1DATPPS	. <del></del>	_	į.		SSP1D/	ATPPS<5:0>			01 0100	uu uuuu
1EC7h	SSP1SSPPS	-	_			SSP1S		00 0101	uu uuuu		
1EC8h	SSP2CLKPPS	=	-				00 1001	uu uuuu			
1EC9h	SSP2DATPPS	-	:-				00 1000	uu uuuu			
1ECAh	SSP2SSPPS	-	_			SSP2S	SPPS<5:0>			00 1000	uu uuuu
1ECBh	RX1DTPPS	. <del></del>	, <del>-</del>			RX1D	PPS<5:0>			01 0111	uu uuuu
1ECCh	TX1CKPPS	_	_			TX1C	(PPS<5:0>			01 0110	uu uuuu
1ECDh	RX2DTPPS	_	-			RX2D	PPS<5:0>			00 1111	uu uuuu
1ECEh	TX2CKPPS	-	:				00 1110	uu uuuu			
1ECFh 1EEFh			Unimplemented								

TABLE 4	4-10:	SPECI	AL FUNCTION	REGISTER	SUMMARY	BANKS 0-	63 (CONTIN	UED)
Address	N	ame	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR	
Bank 62											***	
				CPU CO	RE REGISTERS	; see Table 4-3 fo	r specifics					
1F0Ch	=				Unimple	emented				_	_	
1F0Dh	<u></u>				Unimple	emented				_	-	
1F0Eh					Unimple	emented				_	_	
1F0Fh	-				_	-						
1F10h	RA0PPS	<u>=</u>	_	_			RA0PPS<4:0	>		0 0000	u uuuu	
1F11h	RA1PPS	-	:	-			RA1PPS<4:0	>		0 0000	u uuuu	
1F12h	RA2PPS	_	_	_			RA2PPS<4:0		0 0000	u uuuu		
1F13h	RA3PPS	_	_	-			RA3PPS<4:0	>		0 0000	u uuuu	
1F14h	RA4PPS	_	·	-			RA4PPS<4:0	>		0 0000	u uuuu	
1F15h	RA5PPS		_	_			RA5PPS<4:0	>		0 0000	u uuuu	
1F16h	RA6PPS	-	. —	-			RA6PPS<4:0	>		0 0000	u uuuu	
1F17h	RA7PPS	_	_	_			RA7PPS<4:0	>		0 0000	u uuuu	
1F18h	RB0PPS	-	_	-			RB0PPS<4:0	>		0 0000	u uuuu	
1F19h	RB1PPS	_	-	_			RB1PPS<4:0	>		0 0000	u uuuu	
1F1Ah	RB2PPS		, , <del>, ,</del> , , ,	·			RB2PPS<4:0	>		0 0000	u uuuu	
1F1Bh	RB3PPS	-	-	-	e e		RB3PPS<4:0	>		0 0000	u uuuu	
1F1Ch	RB4PPS	_		_			RB4PPS<4:0	>		0 0000	u uuuu	
1F1Dh	RB5PPS	_	( <del></del>	1 <del>177</del>			RB5PPS<4:0	>		0 0000	u uuuu	
1F1Eh	RB6PPS	_	_	-			RB6PPS<4:0	>		0 0000	u uuuu	
1F1Fh	RB7PPS	<del>-</del>	y. <del></del> y	1			RB7PPS<4:0	>		0 0000	u uuuu	
1F20h	RC0PPS	-	:—:	-			RCOPPS<4:0	>		0 0000	u uuuu	
1F21h	RC1PPS		_				RC1PPS<4:0	>		0 0000	u uuuu	
1F22h	RC2PPS	-	1 <del></del>	-			RC2PPS<4:0	>		0 0000	u uuuu	
1F23h	RC3PPS	_	_	_			RC3PPS<4:0	>		0 0000	u uuuu	
1F24h	RC4PPS	-	×	-			RC4PPS<4:0	>		0 0000	u uuuu	
1F25h	RC5PPS	_	:—:	_			RC5PPS<4:0	>		0 0000	u uuuu	
1F26h	RC6PPS	-	, <u> </u>				RC6PPS<4:0	>		0 0000	u uuuu	
1F27h	RC7PPS	_	(	· -			RC7PPS<4:0	>		0 0000	u uuuu	
1F28h 1F37h	<del>100</del> 2		Unimplemented									

TABLE 4-10: SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR	
Bank 62 (Co	ontinued)											
1F38h	ANSELA	ANSA7	ANSA6	ANSA5	ANSA4	ANSA3	ANSA2	ANSA1	ANSA0	1111 1111	1111 1111	
1F39h	WPUA	WPUA7	WPUA6	WPUA5	WPUA4	WPUA3	WPUA2	WPUA1	WPUA0	0000 0000	0000 0000	
1F3Ah	ODCONA	ODCA7	ODCA6	ODCA5	ODCA4	ODCA3	ODCA2	ODCA1	ODCA0	0000 0000	0000 0000	
1F3Bh	SLRCONA	SLRA7	SLRA6	SLRA5	SLRA4	SLRA3	SLRA2	SLRA1	SLRAD	1111 1111	1111 1111	
1F3Ch	INLVLA	INLVLA7	INLVLA6	INLVLA5	INLVLA4	INLVLA3	INLVLA2	INLVLA1	INLVLA0	1111 1111	1111 1111	
1F3Dh	IOCAP	IOCAP7	IOCAP6	IOCAP5	IOCAP4	IOCAP3	IOCAP2	IOCAP1	IOCAP0	0000 0000	0000 0000	
1F3Eh	IOCAN	IOCAN7	IOCAN6	IOCAN5	IOCAN4	IOCAN3	IOCAN2	IOCAN1	IOCAN0	0000 0000	0000 0000	
1F3Fh	IOCAF	IOCAF7	IOCAF6	IOCAF5	IOCAF4	IOCAF3	IOCAF2	IOCAF1	IOCAF0	0000 0000	0000 0000	
1F40h 1F42h	1002				Unimple	mented				-		
1F43h	ANSELB	ANSB7	ANSB6	ANSB5	ANSB4	ANSB3	ANSB2	ANSB1	ANSB0	1111 1111	1111 1111	
1F44h	WPUB	WPUB7	WPUB6	WPUB5	WPUB4	WPUB3	WPUB2	WPUB1	WPUB0	0000 0000	0000 0000	
1F45h	ODCONB	ODCB7	ODCB6	ODCB5	ODCB4	ODCB3	ODCB2	ODCB1	ODCB0	0000 0000	0000 0000	
1F46h	SLRCONB	SLRB7	SLRB6	SLRB5	SLRB4	SLRB3	SLRB2	SLRB1	SLRB0	1111 1111	1111 1111	
1F47h	INLVLB	INLVLB7	INLVLB6	INLVLB5	INLVLB4	INLVLB3	INLVLB2	INLVLB1	INLVLB0	1111 1111	1111 1111	
1F48h	IOCBP	IOCBP7	IOCBP6	IOCBP5	IOCBP4	IOCBP3	IOCBP2	IOCBP1	IOCBP0	0000 0000	0000 0000	
1F49h	IOCBN	IOCBN7	IOCBN6	IOCBN5	IOCBN4	IOCBN3	IOCBN2	IOCBN1	IOCBN0	0000 0000	0000 0000	
1F4Ah	IOCBF	IOCBF7	IOCBF6	IOCBF5	IOCBF4	IOCBF3	IOCBF2	IOCBF1	IOCBF0	0000 0000	0000 0000	
1F4Bh 1F4Dh	-	٠			Unimple	mented				-	_	
1F4Eh	ANSELC	ANSC7	ANSC6	ANSC5	ANSC4	ANSC3	ANSC2	ANSC1	ANSC0	1111 1111	1111 1111	
1F4Fh	WPUC	WPUC7	WPUC6	WPUC5	WPUC4	WPUC3	WPUC2	WPUC1	WPUC0	0000 0000	0000 0000	
1F50h	ODCONC	ODCC7	ODCC6	ODCC5	ODCC4	ODCC3	ODCC2	ODCC1	ODCC0	0000 0000	0000 0000	
1F51h	SLRCONC	SLRC7	SLRC6	SLRC5	SLRC4	SLRC3	SLRC2	SLRC1	SLRC0	1111 1111	1111 1111	
1F52h	INLVLC	INLVLC7	INLVLC6	INLVLC5	INLVLC4	INLVLC3	INLVLC2	INLVLC1	INLVLCO	1111 1111	1111 1111	
1F53h	IOCCP	IOCCP7	IOCCP6	IOCCP5	IOCCP4	IOCCP3	IOCCP2	IOCCP1	IOCCP0	0000 0000	0000 0000	
1F54h	IOCCN	IOCCN7	IOCCN6	IOCCN5	IOCCN4	IOCCN3	IOCCN2	IOCCN1	IOCCND	0000 0000	0000 0000	
1F55h	IOCCF	IOCCF7	IOCCF6	IOCCF5	IOCCF4	IOCCF3	IOCCF2	IOCCF1	IOCCF0	0000 0000	0000 0000	
1F56h 1F64h	227				Unimple	mented	×		·	=		
1F65h	WPUE	-		_	244	WPUE3	_	_	_	0	u	
1F66h	550				Unimple	mented				_	_	
1F67h	_		Unimplemented									

TABLE 4-10: SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	V <u>alue o</u> n: MCLR		
Bank 62 (Cor	ntinued)					_							
1F68h	INLVLE	-	:—:	_	-	INLVLE3	-	-	-	1	u		
1F69h	IOCEP	_	_	-		IOCEP3	222	4_0	1200	0	0		
1F6Ah	IOCEN	-	_	_	-	IOCEN3	<del></del>	i—,	-	0	0		
1F6Bh	IOCEF	_	_	_	==:	IOCEF3	_	_	_	0	0		
1F6Ch 1F6Fh	_		Unimplemented										


TADLE 4 40.	SPECIAL FUNCTION REGISTER SUMMARY BANKS 0-63 (CONTINUED)
IADLE 4-10.	SPECIAL FUNCTION REGISTER SUMMART BANKS U-03 (CONTINUED)

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on: MCLR	
Bank 63							•			-		
				CPU C	ORE REGISTERS	see Table 4-3 fo	r specifics					
1F8Ch 1FE3h	-				Unimple	mented	,			=	-	
1FE4h	STATUS_SHAD		( <del></del>	i <del></del>	57.67	<del>-</del>	Z	DC	С	жхх	uuu	
1FE5h	WREG_SHAD	WREG_SHAD Working Register Shadow										
1FE6h	BSR_SHAD		y <del></del> .	100	Bank Select Re	gister Shadow				х хххх	u uuuu	
1FE7h	PCLATH_SHAD	-	Program Counte	r Latch High Re	egister Shadow					-xxx xxxx	uuuu uuuu	
1FE8h	FSR0L_SHAD	Indirect Data Memory	Address 0 Low Po	inter Shadow						XXXX XXXX	uuuu uuuu	
1FE9h	FSR0H_SHAD	Indirect Data Memory	Address 0 High Po	ointer Shadow						XXXX XXXX	uuuu uuuu	
1FEAh	FSR1L_SHAD	Indirect Data Memory	Address 1 Low Po	inter Shadow						XXXX XXXX	uuuu uuuu	
1FEBh	FSR1H_SHAD	Indirect Data Memory	Address 1 High Po	ointer Shadow						XXXX XXXX	uuuu uuuu	
1FECh	_	Unimplemented	and the state of t	=,11						_		
1FEDh	STKPTR	_	_		Current Stack P	ointer				1 1111	1 1111	
1FEEh	TOSL	Top of Stack Low byte	е							XXXX XXXX	uuuu uuuu	
1FEFh	TOSH	_	Top of Stack High	n byte						-xxx xxxx	-uuu uuuu	

## 4.4 PCL and PCLATH

The Program Counter (PC) is 15 bits wide. The low byte comes from the PCL register, which is a readable and writable register. The high byte (PC<14:8>) is not directly readable or writable and comes from PCLATH. On any Reset, the PC is cleared. Figure 4-4 shows the five situations for the loading of the PC.

FIGURE 4-4: LOADING OF PC IN DIFFERENT SITUATIONS



## 4.4.1 MODIFYING PCL

Executing any instruction with the PCL register as the destination simultaneously causes the Program Counter PC<14:8> bits (PCH) to be replaced by the contents of the PCLATH register. This allows the entire contents of the program counter to be changed by writing the desired upper seven bits to the PCLATH register. When the lower eight bits are written to the PCL register, all 15 bits of the program counter will change to the values contained in the PCLATH register and those being written to the PCL register.

## 4.4.2 COMPUTED GOTO

A computed GOTO is accomplished by adding an offset to the program counter (ADDWF PCL). When performing a table read using a computed GOTO method, care must be exercised if the table location crosses a PCL memory boundary (each 256-byte block). Refer to Application Note AN556, "Implementing a Table Read" (DS00556).

## 4.4.3 COMPUTED FUNCTION CALLS

A computed function CALL allows programs to maintain tables of functions and provide another way to execute state machines or look-up tables. When performing a table read using a computed function CALL, care must be exercised if the table location crosses a PCL memory boundary (each 256-byte block).

If using the CALL instruction, the PCH<2:0> and PCL registers are loaded with the operand of the CALL instruction. PCH<6:3> is loaded with PCLATH<6:3>.

The CALLW instruction enables computed calls by combining PCLATH and W to form the destination address. A computed CALLW is accomplished by loading the W register with the desired address and executing CALLW. The PCL register is loaded with the value of W and PCH is loaded with PCLATH.

#### 4.4.4 BRANCHING

The branching instructions add an offset to the PC. This allows relocatable code and code that crosses page boundaries. There are two forms of branching, BRW and BRA. The PC will have incremented to fetch the next instruction in both cases. When using either branching instruction, a PCL memory boundary may be crossed.

If using BRW, load the W register with the desired unsigned address and execute BRW. The entire PC will be loaded with the address PC + 1 + W.

If using BRA, the entire PC will be loaded with PC + 1 + the signed value of the operand of the BRA instruction.

## 4.5 Stack

All devices have a 16-level x 15-bit wide hardware stack (refer to Figure 4-5 through Figure 4-8). The stack space is not part of either program or data space. The PC is PUSHed onto the stack when CALL or CALLW instructions are executed or an interrupt causes a branch. The stack is POPed in the event of a RETURN, RETLW or a RETFIE instruction execution. PCLATH is not affected by a PUSH or POP operation.

The stack operates as a circular buffer if the STVREN bit is programmed to '0' (Configuration Words). This means that after the stack has been PUSHed sixteen times, the seventeenth PUSH overwrites the value that was stored from the first PUSH. The eighteenth PUSH overwrites the second PUSH (and so on). The STKOVF and STKUNF flag bits will be set on an Overflow/Underflow, regardless of whether the Reset is enabled.

Note 1: There are no instructions/mnemonics called PUSH or POP. These are actions that occur from the execution of the CALL, CALLW, RETURN, RETLW and RETFIE instructions or the vectoring to an interrupt address.

#### 4.5.1 ACCESSING THE STACK

The stack is accessible through the TOSH, TOSL and STKPTR registers. STKPTR is the current value of the Stack Pointer. TOSH:TOSL register pair points to the TOP of the stack. Both registers are read/writable. TOS is split into TOSH and TOSL due to the 15-bit size of the PC. To access the stack, adjust the value of STKPTR, which will position TOSH:TOSL, then read/write to TOSH:TOSL. STKPTR is five bits to allow detection of overflow and underflow.

Note: Care must be taken when modifying the STKPTR while interrupts are enabled.

During normal program operation, CALL, CALLW and interrupts will increment STKPTR while RETLW, RETURN, and RETFIE will decrement STKPTR. STKPTR can be monitored to obtain to value of stack memory left at any given time. The STKPTR always points at the currently used place on the stack. Therefore, a CALL or CALLW will increment the STKPTR and then write the PC, and a return will unload the PC value from the stack and then decrement the STKPTR.

Reference Figure 4-5 through Figure 4-8 for examples of accessing the stack.

FIGURE 4-5: ACCESSING THE STACK EXAMPLE 1






FIGURE 4-6: **ACCESSING THE STACK EXAMPLE 2** 0x0F 0x0E 0x0D 0x0C 0x0B 0x0A This figure shows the stack configuration 0x09 after the first CALL or a single interrupt. 0x08 If a RETURN instruction is executed, the 0x07 return address will be placed in the Program Counter and the Stack Pointer 0x06 decremented to the empty state (0x1F). 0x05 0x04 0x03 0x02 0x01 TOSH:TOSL STKPTR = 0x00 0x00 Return Address





# 4.5.2 OVERFLOW/UNDERFLOW RESET


If the STVREN bit in Configuration Words (Register 5-2) is programmed to '1', the device will be Reset if the stack is PUSHed beyond the sixteenth level or POPed beyond the first level, setting the appropriate bits (STKOVF or STKUNF, respectively) in the PCON register.

# 4.6 Indirect Addressing

The INDFn registers are not physical registers. Any instruction that accesses an INDFn register actually accesses the register at the address specified by the File Select Registers (FSR). If the FSRn address specifies one of the two INDFn registers, the read will return '0' and the write will not occur (though Status bits may be affected). The FSRn register value is created by the pair FSRnH and FSRnL.

The FSR registers form a 16-bit address that allows an addressing space with 65536 locations. These locations are divided into three memory regions:

- Traditional/Banked Data Memory
- Linear Data Memory
- Program Flash Memory




INDIRECT ADDRESSING PIC16(L)F15355 **FIGURE 4-10:** Rev. 10-000044C 9/16/2016 0x0000 0x0000 Traditional **Data Memory** 0x1FFF 0x2000 Linear **Data Memory** 0X2FEF 0X2FF0 Reserved 0x7FFF **FSR** 0x8000 PC value = 0x0000Address Range Program Flash Memory 0x9FFF PC value = 0x1FFF

# 4.6.1 TRADITIONAL/BANKED DATA MEMORY

The traditional or banked data memory is a region from FSR address 0x000 to FSR address 0x1FFF. The addresses correspond to the absolute addresses of all SFR, GPR and common registers.

FIGURE 4-11: TRADITIONAL/BANKED DATA MEMORY MAP



#### 4.6.2 LINEAR DATA MEMORY


The linear data memory is the region from FSR address 0x2000 to FSR address 0X2FEF. This region is a virtual region that points back to the 80-byte blocks of GPR memory in all the banks. Refer to Figure 4-12 for the Linear Data Memory Map.

Note: The address range 0x2000 to 0x2FF0 represents the complete addressable Linear Data Memory up to Bank 50. The actual implemented Linear Data Memory will differ from one device to the other in a family. Confirm the memory limits on every device.

Unimplemented memory reads as  $0 \times 00$ . Use of the linear data memory region allows buffers to be larger than 80 bytes because incrementing the FSR beyond one bank will go directly to the GPR memory of the next bank.

The 16 bytes of common memory are not included in the linear data memory region.


FIGURE 4-12: LINEAR DATA MEMORY MAP



#### 4.6.3 PROGRAM FLASH MEMORY

To make constant data access easier, the entire Program Flash Memory is mapped to the upper half of the FSR address space. When the MSB of FSRnH is set, the lower 15 bits are the address in program memory which will be accessed through INDF. Only the lower eight bits of each memory location is accessible via INDF. Writing to the Program Flash Memory cannot be accomplished via the FSR/INDF interface. All instructions that access Program Flash Memory via the FSR/INDF interface will require one additional instruction cycle to complete.

FIGURE 4-13: PROGRAM FLASH MEMORY MAP



# 5.0 DEVICE CONFIGURATION

Device configuration consists of the Configuration Words, User ID, Device ID, Device Information Area (DIA), (see Section 6.0 "Device Information Area"), and the Device Configuration Information (DCI) regions, (see Section 7.0 "Device Configuration Information").

# 5.1 Configuration Words

The devices have several Configuration Words starting at address 8007h. The Configuration bits establish configuration values prior to the execution of any software; Configuration bits enable or disable device-specific features.

In terms of programming, consider these important Configuration bits:

### 1. LVP: Low-Voltage Programming Enable bit

- 1 = ON Low-Voltage Programming is enabled. MCLR/VPP pin function is MCLR. MCLRE Configuration bit is ignored.
- 0 = OFF HV on MCLR/VPP must be used for programming.

# 2. CP: User Nonvolatile Memory (NVM) Program Memory Code Protection bit

- 1 = OFF User NVM code protection disabled
- 0 = ON User NVM code protection enabled

# 5.2 Register Definitions: Configuration Words

#### REGISTER 5-1: CONFIGURATION WORD 1: OSCILLATORS

R/P-1	U-1	R/P-1	U-1	U-1	R/P-1
FCMEN	-	CSWEN	<u></u>	-	CLKOUTEN
bit 13				Z1:	bit 8

U-1	R/P-1	R/P-1	R/P-1	U-1	R/P-1	R/P-1	R/P-1
<del>-</del>	RSTOSC2	RSTOSC1	RSTOSC0	_	FEXTOSC2	FEXTOSC1	FEXTOSC0
bit 7							bit 0

Legend:			
R = Readable bit	P = Programmable bit	x = Bit is unknown	U = Unimplemented bit, read as '1'
'0' = Bit is cleared	'1' = Bit is set	W = Writable bit	n = Value when blank or after Bulk Erase

bit 13 FCMEN: Fail-Safe Clock Monitor Enable bit

1 = FSCM timer enabled 0 = FSCM timer disabled

bit 12 Unimplemented: Read as '1'

bit 11

CSWEN: Clock Switch Enable bit

1 = Writing to NOSC and NDIV is allowed

0 = The NOSC and NDIV bits cannot be changed by user software

bit 10-9 Unimplemented: Read as '1'
bit 8 CLKOUTEN: Clock Out Enable bit

KEEVTOOD EO (bish soid as low) as N

If FEXTOSC = EC (high, mid or low) or Not Enabled:

1 = CLKOUT function is disabled; I/O or oscillator function on OSC2
 0 = CLKOUT function is enabled; FOSC/4 clock appears at OSC2

Otherwise:

This bit is ignored.

bit 7 Unimplemented: Read as '1'

bit 6-4 RSTOSC<2:0>: Power-up Default Value for COSC bits

This value is the Reset-default value for COSC and selects the oscillator first used by user software.

111 = EXTOSC operating per FEXTOSC bits

110 = HFINTOSC (1 MHz) with OSCFRQ = '010' (4 MHz) and CDIV = '0010' (4:1)

101 = LFINTOSC 100 = SOSC

011 = Reserved

010 = EXTOSC with 4x PLL, with EXTOSC operating per FEXTOSC bits

001 = HFINTOSC with 2x PLL (32 MHz), with OSCFRQ = '101' (16 MHz) and CDIV = '0000' (1:1)

000 = HFINTOSC (32 MHz), with OSCFRQ = '110' (32 MHz) and CDIV = '0000' (1:1)

bit 3 Unimplemented: Read as '1'

bit 2-0 FEXTOSC <2:0>:FEXTOSC External Oscillator Mode Selection bits

111 = EC (External Clock) above 8 MHz

110 = EC (External Clock) for 100 kHz to 8 MHz

101 = EC (External Clock) below 100 kHz

100 = Oscillator not enabled

011 = Reserved (do not use)

010 = HS (Crystal oscillator) above 4 MHz

001 = XT (Crystal oscillator) above 100 kHz, below 4 MHz 000 = LP (Crystal oscillator) optimized for 32.768 kHz

#### REGISTER 5-2:

#### **CONFIGURATION WORD 2: SUPERVISORS**

R/P-1	R/P-1	R/P-1	R/P-1	R/P-1	U-1
DEBUG	STVREN	PPS1WAY	ZCDDIS	BORV	-
bit 13				-	bit 8

R/P-1	R/P-1	R/P-1	U-1	U-1	U-1	R/P-1	R/P-1
BOREN1	BOREN0	LPBOREN	_	_	- <u> </u>	PWRTE	MCLRE
bit 7	3.3			·			bit 0

Legend:			
R = Readable bit	P = Programmable bit	x = Bit is unknown	U = Unimplemented bit, read as '1'
'0' = Bit is cleared	'1' = Bit is set	W = Writable bit	n = Value when blank or after Bulk Erase

bit 13 DEBUG: Debugger Enable bit

1 = Background debugger disabled

0 = Background debugger enabled

bit 12 STVREN: Stack Overflow/Underflow Reset Enable bit

1 = Stack Overflow or Underflow will cause a Reset

0 = Stack Overflow or Underflow will not cause a Reset

bit 11 PPS1WAY: PPSLOCK One-Way Set Enable bit

1 = The PPSLOCK bit can be cleared and set only once; PPS registers remain locked after one clear/set cycle

0 = The PPSLOCK bit can be set and cleared repeatedly (subject to the unlock sequence)

bit 10 ZCDDIS: Zero-Cross Detect Disable bit

1 = ZCD disabled. ZCD can be enabled by setting the ZCDSEN bit of the ZCDCON register

0 = ZCD always enabled (ZCDSEN bit is ignored)

bit 9 BORV: Brown-out Reset Voltage Selection bit (1)

1 = Brown-out Reset voltage (VBOR) set to lower trip point level

0 = Brown-out Reset voltage (VBOR) set to higher trip point level

bit 8 Unimplemented: Read as '1'

bit 7-6 BOREN<1:0>: Brown-out Reset Enable bits

When enabled, Brown-out Reset Voltage (VBOR) is set by the BORV bit

11 = Brown-out Reset is enabled; SBOREN bit is ignored

10 = Brown-out Reset is enabled while running, disabled in Sleep; SBOREN bit is ignored

01 = Brown-out Reset is enabled according to SBOREN

00 = Brown-out Reset is disabled

bit 5 LPBOREN: Low-Power BOR Enable bit

1 = ULPBOR is disabled

0 = ULPBOR is enabled

bit 4-2 Unimplemented: Read as '1'

bit 1 PWRTE: Power-up Timer Enable bit

1 = PWRT is disabled

0 = PWRT is enabled

bit 0 MCLRE: Master Clear (MCLR) Enable bit

If LVP = 1:

RE3 pin function is MCLR (it will reset the device when driven low)

If LVP = 0

1 = MCLR pin is MCLR (it will reset the device when driven low)

0 = MCLR pin may be used as general purpose RE3 input

Note 1: See Vbor parameter for specific trip point voltages.

2: The DEBUG bit in Configuration Words is managed automatically by device development tools including debuggers and programmers. For normal device operation, this bit must be maintained as a '1'.

# REGISTER 5-3: CONFIGURATION WORD 3: WINDOWED WATCHDOG

R/P-1	R/P-1	R/P-1	R/P-1	R/P-1	R/P-1
WDTCCS2	WDTCCS1	WDTCCS0	WDTCWS2	WDTCWS1	WDTCWS0
bit 13	3				bit 8

U-1	R/P-1	R/P-1	R/P-1	R/P-1	R/P-1	R/P-1	R/P-1
<del></del>	WDTE1	WDTE0	WDTCPS4	WDTCPS3	WDTCPS2	WDTCPS1	WDTCPS0
bit 7							bit 0

Legend:

R = Readable bit P = Programmable bit x = Bit is unknown U = Unimplemented bit, read as '1' 
'0' = Bit is cleared '1' = Bit is set W = Writable bit n = Value when blank or after Bulk Erase

bit 13-11 WDTCCS<2:0>: WDT Input Clock Selector bits

111 = Software Control

110 = Reserved

100

.....

010 = SOSC 32 kHz

001 = WDT reference clock is the 31.25 kHz HFINTOSC (MFINTOSC) output

000 = WDT reference clock is the 31.0 kHz LFINTOSC

bit 10-8 WDTCWS<2:0>: WDT Window Select bits

		WDTWS at POR		0-5	IZd	
WDTCWS	Value	Window delay Percent of time	Window opening Percent of time	Software control of WDTWS?	Keyed access required?	
111	111	n/a	100	Yes	No	
110	111	n/a	100	2		
101	101	25	75			
100	100	37.5	62.5			
011	011	50	50	No	Yes	
010	010	62.5	37.5			
001	001	75	25			
000	000	87.5	12.5			

# bit 7 Unimplemented: Read as '1'

bit 6-5 WDTE<1:0>: WDT Operating mode:

11 = WDT enabled regardless of Sleep; SWDTEN is ignored

10 = WDT enabled while Sleep = 0, suspended when Sleep = 1; SWDTEN ignored

01 = WDT enabled/disabled by SWDTEN bit in WDTCON0

00 = WDT disabled, SWDTEN is ignored

# REGISTER 5-3: CONFIGURATION WORD 3: WINDOWED WATCHDOG (CONTINUED)

bit 4-0 WDTCPS<4:0>: WDT Period Select bits

		WDTPS at	POR			
WDTCPS	Value	Divider R	atio	Typical Time Out (Fin = 31 kHz)	of WDTPS?	
11111(1)	01011	1:65536	2 <sup>16</sup>	2 s	Yes	
11110	11110		0.000			
		1:32	2 <sup>5</sup>	1 ms	No	
10011	10011		00			
10010	10010	1:8388608	2 <sup>23</sup>	256 s		
10001	10001	1:4194304	2 <sup>22</sup>	128 s	,	
10000	10000	1:2097152	221	64 s		
01111	01111	1:1048576	2 <sup>20</sup>	32 s	T <sup>*</sup>	
01110	01110	1:524299	219	16 s	1	
01101	01101	1:262144	218	8 s	1	
01100	01100	1:131072	217	4 s	1	
01011	01011	1:65536	2 <sup>16</sup>	2 s	1	
01010	01010	1:32768	2 <sup>15</sup>	1 s	1	
01001	01001	1:16384	214	512 ms	No	
01000	01000	1:8192	213	256 ms	1	
00111	00111	1:4096	212	128 ms	1	
00110	00110	1:2048	211	64 ms		
00101	00101	1:1024	210	32 ms	ľ	
00100	00100	1:512	2 <sup>9</sup>	16 ms	1	
00011	00011	1:256	28	8 ms	1	
00010	00010	1:128	27	4 ms	1	
00001	00001	1:64	2 <sup>6</sup>	2 ms	1	
00000	00000	1:32	2 <sup>5</sup>	1 ms	1	

Note 1: 0b11111 is the default value of the WDTCPS bits.

#### REGISTER 5-4: CONFIGURATION WORD 4: MEMORY

R/W-1	U-1	R/W-1	U-1	R/W-1	R/W-1
LVP	_	WRTSAF <sup>(1)</sup>	_	WRTC <sup>(1)</sup>	WRTB <sup>(1)</sup>
bit 13	12	11	10	9	bit 8

R/W-1	U-1	U-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
WRTAPP(1)	_	_	SAFEN <sup>(1)</sup>	BBEN <sup>(1)</sup>	BBSIZE2	BBSIZE1	BBSIZE0
bit 7	6	5	4	3	2	1	bit 0

Legend:			
R = Readable bit	P = Programmable bit	x = Bit is unknown	U = Unimplemented bit, read as '1'
'0' = Bit is cleared	'1' = Bit is set	W = Writable bit	n = Value when blank or after Bulk Erase

bit 13 LVP: Low Voltage Programming Enable bit

1 = Low voltage programming enabled. MCLR/VPP pin function is MCLR. MCLRE Configuration bit is ignored.

0 = HV on MCLR/VPP must be used for programming.

The LVP bit cannot be written (to zero) while operating from the LVP programming interface. The purpose of this rule is to prevent the user from dropping out of LVP mode while programming from LVP mode, or accidentally eliminating LVP mode from the configuration state.

The preconditioned (erased) state for this bit is critical.

bit 12 Unimplemented: Read as '1'

bit 11 WRTSAF: Storage Area Flash Write Protection bit

1 = SAF NOT write-protected

0 = SAF write-protected

Unimplemented, if SAF is not supported in the device family and only applicable if SAFEN = 0.

bit 10 Unimplemented: Read as '1'

bit 9 WRTC: Configuration Register Write Protection bit

1 = Configuration Register NOT write-protected

= Configuration Register write-protected

bit 8 WRTB: Boot Block Write Protection bit

1 = Boot Block NOT write-protected0 = Boot Block write-protected

Only applicable if  $\overline{BBEN} = 0$ .

bit 7 WRTAPP: Application Block Write Protection bit

1 = Application Block NOT write-protected

0 = Application Block write-protected

bit 6-5 Unimplemented: Read as '1'

bit 4 SAFEN: SAF Enable bit

1 = SAF disabled

0 = SAF enabled

bit 3 BBEN: Boot Block Enable bit

1 = Boot Block disabled

0 = Boot Block enabled

bit 2-0 BBSIZE<2:0>: Boot Block Size Selection bits (See Table 5-1)

BBSIZE is used only when  $\overline{BBEN} = 0$ 

BBSIZ bits can only be written while  $\overline{BBEN} = 1$ ; after  $\overline{BBEN} = 0$ , BBSIZ is write-protected.

Note 1: Bits are implemented as sticky bits. Once protection is enabled, it can only be reset through a Bulk Erase.

TABLE 5-1: BOOT BLOCK SIZE BITS

BBEN	BBSIZE<2:0>	Actual Boo User Program Me	Last Boot Block	
***		PIC16(L)F15354	PIC16(L)F15355	- Memory Access
1	xxx	0	0	12
0	111	512	512	01FFh
0	110	1024	1024	03FFh
0	101	2048	2048	07FFh
0	100-000	2048	4096	0FFFh

Note: The maximum boot block size is half the user program memory size. All selections higher than the maximum are set to half size. For example, all BBSIZE = 000 - 100 produce a boot block size of 4kW on a 8kW device.

# REGISTER 5-5: CONFIGURATION WORD 5: CODE PROTECTION

U-1	U-1	U-1	U-1	U-1	U-1
_	_		=	_	_
bit 13					bit 8

U-1	U-1	U-1	U-1	U-1	U-1	U-1	R/P-1
-	-		<del>-</del>	_	-	-	CP
bit 7	*	<i>5</i>	Š		*	20	bit 0

Legend	4.

R = Readable bit P = Programmable bit x = Bit is unknown U = Unimplemented bit, read as '1' '0' = Bit is cleared '1' = Bit is set W = Writable bit n = Value when blank or after Bulk Erase

bit 13-1 Unimplemented: Read as '1'

bit 0 CP: Program Flash Memory Code Protection bit

1 = Program Flash Memory code protection disabled 0 = Program Flash Memory code protection enabled

#### 5.3 Code Protection

Code protection allows the device to be protected from unauthorized access. Program memory protection and data memory are controlled independently. Internal access to the program memory is unaffected by any code protection setting.

#### 5.3.1 PROGRAM MEMORY PROTECTION

The entire program memory space is protected from external reads and writes by the  $\overline{CP}$  bit in Configuration Words. When  $\overline{CP}=0$ , external reads and writes of program memory are inhibited and a read will return all '0's. The CPU can continue to read program memory, regardless of the protection bit settings. Self-writing the program memory is dependent upon the write protection setting. See Section 5.4 "Write Protection" for more information.

#### 5.4 Write Protection

Write protection allows the device to be protected from unintended self-writes. Applications, such as boot loader software, can be protected while allowing other regions of the program memory to be modified.

The WRTAPP, WRTSAF, WRTB, WRTC bits in Configuration Words (Register 5-4) define whether the corresponding region of the program memory block is protected or not.

#### 5.5 User ID

Four memory locations (8000h-8003h) are designated as ID locations where the user can store checksum or other code identification numbers. These locations are readable and writable during normal execution. See Section 13.3.6 "NVMREG Access to Device Information Area, Device Configuration Area, User ID, Device ID and Configuration Words" for more information on accessing these memory locations. For more information on checksum calculation, see the "PIC16(L)F153XX Memory Programming Specification" (DS40001838).

# 5.6 Device ID and Revision ID

The 14-bit Device ID word is located at 8006h and the 14-bit Revision ID is located at 8005h. These locations are read-only and cannot be erased or modified.

Development tools, such as device programmers and debuggers, may be used to read the Device ID, Revision ID and Configuration Words. These locations can also be read from the NVMCON register.

# 5.7 Register Definitions: Device and Revision

# REGISTER 5-6: DEVID: DEVICE ID REGISTER

R	R	R	R	R	R				
	DEV<13:8>								
bit 13					bit 8				

R	R	R	R	R	R	R	R		
	DEV<7:0>								
bit 7									

Legend:		
R = Readable bit		
'1' = Bit is set	'0' = Bit is cleared	

#### bit 13-0 DEV<13:0>: Device ID bits

Device	DEVID<13:0> Values
PIC16F15354	11 0000 1010 1100 (30ACh)
PIC16LF15354	11 0000 1010 1101 (30ADh)
PIC16F15355	11 0000 1010 1110 (30AEh)
PIC16LF15355	11 0000 1010 1111 (30AFh)

# REGISTER 5-7: REVISIONID: REVISION ID REGISTER

R	R	R	R	R	R	R	R	R	R	R	R	R	R
1	0		MJRREV<5:0>					MNRREV<5:0>					
bit 13													bit 0

Legend:

R = Readable bit

'0' = Bit is cleared '1' = Bit is set x = Bit is unknown

bit 13-12 Fixed Value: Read-only bits

These bits are fixed with value '10' for all devices included in this data sheet.

bit 11-6 MJRREV<5:0>: Major Revision ID bits

These bits are used to identify a major revision.

bit 5-0 MNRREV<5:0>: Minor Revision ID bits

These bits are used to identify a minor revision.

# 6.0 DEVICE INFORMATION AREA

The Device Information Area (DIA) is a dedicated region in the program memory space; it is a new feature in the PIC16(L)F15354/55 family of devices. The DIA contains the calibration data for the internal temperature indicator module, stores the Microchip Unique Identifier words and the Fixed Voltage Reference voltage readings measured in mV.

The complete DIA table is shown in Table 6-1: Device Information Area, followed by a description of each region and its functionality. The data is mapped from 8100h to 811Fh in the PIC16(L)F15354/55 family. These locations are read-only and cannot be erased or modified. The data is programmed into the device during manufacturing.

TABLE 6-1: DEVICE INFORMATION AREA

Address Range	Name of Region	Standard Device Information			
	MUI0				
	MUI1				
	MUI2				
	MUI3				
8100h-8108h	MUI4	Microchip Unique Identifier (9 Words)			
	MUI5				
	MUI6				
	MUI7				
	MUI8				
8109h	MUI9	1 Word Reserved			
	EUI0				
810Ah-8111h -	EUI1				
	EUI2				
	EUI3	Unancianad (O.Warda)			
	EUI4	Unassigned (8 Words)			
	EUI5				
	EUI6				
	EU17				
8112h	Reserved	Unassigned (1 word)			
8113h	TSLR2	Temperature indicator ADC reading at 90°C (low range setting)			
8114h	Reserved	Unassigned (1 word)			
8115h	Reserved	Unassigned (1 word)			
8116h	TSHR2	Temperature indicator ADC reading at 90°C (high range setting)			
8117h	Reserved	Unassigned (1 Word)			
8118h	FVRA1X	ADC FVR1 Output voltage for 1x setting (in mV)			
8119h	FVRA2X	ADC FVR1 Output Voltage for 2x setting (in mV)			
811Ah	FVRA4X <sup>(1)</sup>	ADC FVR1 Output Voltage for 4x setting (in mV)			
811Bh	FVRC1X	Comparator FVR2 output voltage for 1x setting (in mV)			
811Ch	FVRC2X	Comparator FVR2 output voltage for 2x setting (in mV)			
811Dh	FVRC4X <sup>(1)</sup>	Comparator FVR2 output voltage for 4x setting (in mV)			
811Eh-811Fh		Unassigned (2 Words)			

Note 1: Value not present on LF devices.

# 6.1 Microchip Unique identifier (MUI)

The PIC16(L)F15354/55 devices are individually encoded during final manufacturing with a Microchip Unique Identifier, or MUI. The MUI cannot be erased by a Bulk Erase command or any other user-accessible means. This feature allows for manufacturing traceability of Microchip Technology devices in applications where this is a required. It may also be used by the application manufacturer for a number of functions that require unverified unique identification, such as:

- · Tracking the device
- Unique serial number

The MUI consists of nine program words. When taken together, these fields form a unique identifier. The MUI is stored in nine read-only locations, located between 8100h to 8109h in the DIA space. Table 6-1 lists the addresses of the identifier words.

Note:

For applications that require verified unique identification, contact the Microchip Technology sales office to create a Serialized Quick Turn Programming option.

# 6.2 External Unique Identifier (EUI)

The EUI data is stored at locations 810Ah to 8111h in the program memory region. This region is an optional space for placing application specific information. The data is coded per customer requirements during manufacturing. The EUI cannot be erased by a Bulk Erase command.

Note:

Data is stored in this address range on receiving a request from the customer. The customer may contact the local sales representative or Field Applications Engineer, and provide them the unique identifier information that is required to be stored in this region.

# 6.3 Analog-to-Digital Conversion Data of the Temperature Sensor

The purpose of the temperature indicator module is to provide a temperature-dependent voltage that can be measured by an analog module. Section 19.0 "Temperature Indicator Module" explains the operation of the Temperature Indicator module and defines terms such as the low range and high range settings of the sensor.

The DIA table contains the internal ADC measurement values of the temperature sensor for low and high range at fixed points of reference. The values are measured during test and are unique to each device. The right-justified ADC readings are stored in the DIA memory region. The calibration data can be used to plot the approximate sensor output voltage, VTSENSE vs. Temperature curve.

- TSLR2: Address 8113h stores the measurements for the low range setting of the temperature sensor at VDD = 3V.
- TSHR2: Address 8116h stores the measurements for the high range setting of the temperature sensor at VDD = 3V.

The stored measurements are made by the device ADC using the internal VREF = 2.048V.

# 6.4 Fixed Voltage Reference Data

The Fixed Voltage Reference, or FVR, is a stable voltage reference, independent of VDD, with 1.024V, 2.048V or 4.096V selectable output levels. The output of the FVR can be configured to supply a reference voltage to the following:

- · ADC input channel
- ADC positive reference
- · Comparator positive input
- Digital-to-Analog Converter

For more information on the FVR, refer to **Section 18.0** "Fixed Voltage Reference (FVR)".

The DIA stores measured FVR voltages for this device in mV for the different buffer settings of 1x, 2x or 4x at program memory locations 8118h to 811Dh.

- FVRA1X stores the value of ADC FVR1 Output voltage for 1x setting (in mV)
- FVRA2X stores the value of ADC FVR1 Output Voltage for 2x setting (in mV)
- FVRA4X stores the value of ADC FVR1 Output Voltage for 4x setting (in mV)
- FVRC1X stores the value of Comparator FVR2 output voltage for 1x setting (in mV)
- FVRC2X stores the value of Comparator FVR2 output voltage for 2x setting (in mV)
- FVRC4X stores the value of Comparator FVR2 output voltage for 4x setting (in mV)

# 7.0 DEVICE CONFIGURATION INFORMATION

The Device Configuration Information (DCI) is a dedicated region in the Program Flash Memory mapped from 8200h to 821Fh. The data stored in the DCI memory is hard-coded into the device during manufacturing.

Refer to Table 7-1 for the complete DCI table address and description. The DCI holds information about the device which is useful for programming and bootloader applications. These locations are read-only and cannot be erased or modified.

TABLE 7-1: DEVICE CONFIGURATION INFORMATION FOR PIC16(L)F15354/55 DEVICES

ADDRESS Name	DESCRIPTION	VAL	UNITS		
	DESCRIPTION	PIC16(L)F15354	PIC16(L)F15355	UNITS	
8200h	ERSIZ	Erase Row Size	32	32	Words
8201h	WLSIZ	Number of write latches	32	32	Latches
8202h	URSIZ	Number of User Rows	128	256	Rows
8203h	EESIZ	EE Data memory size	0	0	Bytes
8204h	PCNT	Pin Count	28	28	Pins

#### 7.1 DIA and DCI Access

The DIA and DCI data are read-only and cannot be erased or modified. See 13.3.6 "NVMREG Access to Device Information Area, Device Configuration Area, User ID, Device ID and Configuration Words" for more information on accessing these memory locations.

Development tools, such as device programmers and debuggers, may be used to read the DIA and DCI regions, similar to the Device ID and Revision ID.

# 8.0 RESETS


There are multiple ways to reset this device:

- · Power-on Reset (POR)
- · Brown-out Reset (BOR)
- Low-Power Brown-out Reset (LPBOR)
- MCLR Reset
- WWDT Reset
- RESET instruction
- Stack Overflow
- · Stack Underflow
- · Programming mode exit
- Memory Violation Reset (MEMV)

To allow VDD to stabilize, an optional Power-up Timer can be enabled to extend the Reset time after a BOR or POR event.

A simplified block diagram of the On-Chip Reset Circuit is shown in Figure 8-1.

FIGURE 8-1: SIMPLIFIED BLOCK DIAGRAM OF ON-CHIP RESET CIRCUIT



# 8.1 Power-on Reset (POR)

The POR circuit holds the device in Reset until VDD has reached an acceptable level for minimum operation. Slow rising VDD, fast operating speeds or analog performance may require greater than minimum VDD. The PWRT, BOR or MCLR features can be used to extend the start-up period until all device operation conditions have been met.

# 8.2 Brown-out Reset (BOR)

The BOR circuit holds the device in Reset when VDD reaches a selectable minimum level. Between the POR and BOR, complete voltage range coverage for execution protection can be implemented.

The Brown-out Reset module has four operating modes controlled by the BOREN<1:0> bits in Configuration Words. The four operating modes are:

- · BOR is always on
- · BOR is off when in Sleep
- · BOR is controlled by software
- · BOR is always off

Refer to Table 8-1 for more information.

The Brown-out Reset voltage level is selectable by configuring the BORV bit in Configuration Words.

A VDD noise rejection filter prevents the BOR from triggering on small events. If VDD falls below VBOR for a duration greater than parameter TBORDC, the device will reset. See Figure 8-2 for more information.

TABLE 8-1: BOR OPERATING MODES

BOREN<1:0>	SBOREN	Device Mode	BOR Mode	Instruction Execution upon: Release of POR or Wake-up from Sleep
11	X	X	Active	Wait for release of BOR <sup>(1)</sup> (BORRDY = 1)
10		Awake	Active	Waits for release of BOR (BORRDY = 1)
10	X	Sleep	Disabled	Waits for BOR Reset release
0.1	1	X	Active	Waits for BOR Reset release (BORRDY = 1
01	0	Х	Disabled	D
00	X	Х	Disabled	Begins immediately (BORRDY = x)

Note 1:In this specific case, "Release of POR" and "Wake-up from Sleep", there is no delay in start-up. The BOR ready flag, (BORRDY = 1), will be set before the CPU is ready to execute instructions because the BOR circuit is forced on by the BOREN<1:0> bits.

#### 8.2.1 BOR IS ALWAYS ON

When the BOREN bits of Configuration Words are programmed to '11', the BOR is always on. The device start-up will be delayed until the BOR is ready and VDD is higher than the BOR threshold.

BOR protection is active during Sleep. The BOR does not delay wake-up from Sleep.

#### 8.2.2 BOR IS OFF IN SLEEP

When the BOREN bits of Configuration Words are programmed to '10', the BOR is on, except in Sleep. The device start-up will be delayed until the BOR is ready and VDD is higher than the BOR threshold.

BOR protection is not active during Sleep. The device wake-up will be delayed until the BOR is ready.

#### 8.2.3 BOR CONTROLLED BY SOFTWARE

When the BOREN bits of Configuration Words are programmed to '01', the BOR is controlled by the SBOREN bit of the BORCON register. The device startup is not delayed by the BOR ready condition or the VDD level.


BOR protection begins as soon as the BOR circuit is ready. The status of the BOR circuit is reflected in the BORRDY bit of the BORCON register.

BOR protection is unchanged by Sleep.

#### 8.2.4 **BOR IS ALWAYS OFF**

When the BOREN bits of the Configuration Words are programmed to '00', the BOR is off at all times. The device start-up is not delayed by the BOR ready condition or the VDD level.

#### FIGURE 8-2: **BROWN-OUT SITUATIONS**



# 8.3 Register Definitions: Brown-out Reset Control

# REGISTER 8-1: BORCON: BROWN-OUT RESET CONTROL REGISTER

R/W-1/u	U-0	U-0	U-0	U-0	U-0	U-0	R-q/u
SBOREN <sup>(1)</sup>		_	-	_	S	:	BORRDY
bit 7							

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared q = Value depends on condition

bit 7 SBOREN: Software Brown-out Reset Enable bit (1)

If BOREN <1:0> in Configuration Words ≠ 01:

SBOREN is read/write, but has no effect on the BOR.

If BOREN <1:0> in Configuration Words = 01:

1 = BOR Enabled

0 = BOR Disabled

bit 6-1 Unimplemented: Read as '0'

bit 0 BORRDY: Brown-out Reset Circuit Ready Status bit

1 = The Brown-out Reset circuit is active

0 = The Brown-out Reset circuit is inactive

Note 1: BOREN<1:0> bits are located in Configuration Words.

# 8.4 Low-Power Brown-out Reset (LPBOR)

The Low-Power Brown-out Reset (LPBOR) is an important part of the Reset subsystem. Refer to Figure 8-1 to see how the BOR and LPBOR interact with other modules.

The LPBOR is used to monitor the external VDD pin. When too low of a voltage is detected, the device is held in Reset.

#### 8.4.1 ENABLING LPBOR

The LPBOR is controlled by the LPBOR bit of the Configuration Word (Register 5-1). When the device is erased, the LPBOR module defaults to disabled.

#### 8.4.2 LPBOR MODULE OUTPUT

The output of the LPBOR module is a signal indicating whether or not a Reset is to be asserted. When this occurs, a register bit (BOR) is changed to indicate that a BOR Reset has occurred. The same bit is set for either the BOR or the LPBOR (refer to Register 8-3). This signal is OR'd with the output of the BOR module to provide the generic BOR signal, which goes to the PCON register and to the power control block. Refer to Figure 8-1 for the OR gate connections of the BOR and LPBOR Reset signals, which eventually generates one common BOR Reset.

### 8.5 MCLR

The MCLR is an optional external input that can reset the device. The MCLR function is controlled by the MCLRE bit of Configuration Words and the LVP bit of Configuration Words (Table 8-2).

TABLE 8-2: MCLR CONFIGURATION

MCLRE	LVP	MCLR
0	0	Disabled
1	0	Enabled
Х	1	Enabled

## 8.5.1 MCLR ENABLED

When MCLR is enabled and the pin is held low, the device is held in Reset. The MCLR pin is connected to VDD through an internal weak pull-up. Refer to Section 2.3 "Master Clear (MCLR) Pin" for recommended MCLR connections.

The device has a noise filter in the MCLR Reset path. The filter will detect and ignore small pulses.

Note: A Reset does not drive the MCLR pin low.

#### 8.5.2 MCLR DISABLED

When MCLR is disabled, the pin functions as a general purpose input and the internal weak pull-up is under software control. See Section 14.1 "I/O Priorities" for more information.

# 8.6 Windowed Watchdog Timer (WWDT) Reset

The Watchdog Timer generates a Reset if the firmware does not issue a CLRWDT instruction within the time-out period and the window is open. The TO and PD bits in the STATUS register and the WDT bit in PCON are changed to indicate a WDT Reset caused by the timer overflowing, and WDTWV bit in the PCON register is changed to indicate a WDT Reset caused by a window violation. See Section 12.0 "Windowed Watchdog Timer (WWDT)" for more information.

#### 8.7 RESET Instruction

A RESET instruction will cause a device Reset. The RI bit in the PCON register will be set to '0'. See Table 8-4 for default conditions after a RESET instruction has occurred.

#### 8.8 Stack Overflow/Underflow Reset

The device can reset when the Stack Overflows or Underflows. The STKOVF or STKUNF bits of the PCON register indicate the Reset condition. These Resets are enabled by setting the STVREN bit in Configuration Words. See Section 4.5.2 "Overflow/Underflow Reset" for more information.

# 8.9 Programming Mode Exit

Upon exit of In-Circuit Serial Programming™ (ICSP™) mode, the device will behave as if a POR had just occurred (the device does not reset upon run time self-programming/erase operations).

### 8.10 Power-up Timer

The Power-up Timer optionally delays device execution after a BOR or POR event. This timer is typically used to allow VDD to stabilize before allowing the device to start running.

The Power-up Timer is controlled by the PWRTE bit of the Configuration Words.

The Power-up Timer provides a nominal 64 ms time out on POR or Brown-out Reset. The device is held in Reset as long as PWRT is active. The PWRT delay allows additional time for the VDD to rise to an acceptable level. The Power-up Timer is enabled by clearing the PWRTE bit in the Configuration Words. The Power-up Timer starts after the release of the POR and BOR. For additional information, refer to Application Note AN607, "Power-up Trouble Shooting" (DS00607).

# 8.11 Start-up Sequence


Upon the release of a POR or BOR, the following must occur before the device will begin executing:

- Power-up Timer runs to completion (if enabled).
- Oscillator start-up timer runs to completion (if required for oscillator source).
- 3. MCLR must be released (if enabled).

The total time-out will vary based on oscillator configuration and Power-up Timer Configuration. See Section 9.0 "Oscillator Module (with Fail-Safe Clock Monitor)" for more information.

The Power-up Timer runs independently of MCLR Reset. If MCLR is kept low long enough, the Power-up Timer and oscillator start-up timer will expire. This is useful for testing purposes or to synchronize more than one device operating in parallel. See Figure 8-3.

FIGURE 8-3: RESET START-UP SEQUENCE



# 8.12 Memory Execution Violation

A Memory Execution Violation Reset occurs if executing an instruction being fetched from outside the valid execution area. The different valid execution areas are defined as follows:

- Flash Memory: Table 4-1 shows the addresses available on the PIC16(L)F15354/55 devices based on user Flash size. Execution outside this region generates a memory execution violation.
- Storage Area Flash (SAF): If Storage Area Flash (SAF) is enabled (Section 4.2.3 "Storage Area Flash"), the SAF area (Table 4-2) is not a valid execution area.

Prefetched instructions that are not executed do not cause memory execution violations. For example, a GOTO instruction in the last memory location will prefetch from an invalid location; this is not an error. If an instruction from an invalid location tries to execute, the memory violation is generated immediately, and any concurrent interrupt requests are ignored. When a memory execution violation is generated, the device is reset and flag MEMV is cleared in PCON1 (Register 8-3) to signal the cause. The flag needs to be set in code after a memory execution violation.

# 8.13 Determining the Cause of a Reset

Upon any Reset, multiple bits in the STATUS and PCON registers are updated to indicate the cause of the Reset. Table 8-3 and Table 8-4 show the Reset conditions of these registers.

TABLE 8-3: RESET STATUS BITS AND THEIR SIGNIFICANCE

STOVF	STKUNF	RWDT	RMCLR	I≅	POR	BOR	101	IG.	MEMV	Condition
0	0	1	1	1	0	Х	1	1	1	Power-on Reset
0	0	1	1	1	0	х	0	X	u	Illegal, TO is set on POR
0	0	1	1	1	0	х	X	0	u	Illegal, PD is set on POR
0	0	u	1	1	u	0	1	1	u	Brown-out Reset
u	u	0	u	u	u	u	0	u	u	WWDT Reset
u	u	u	u	u	u	u	0	0	u	WWDT Wake-up from Sleep
u	u	u	u	u	u	u	1	0	u	Interrupt Wake-up from Sleep
u	u	u	0	u	u	u	u	u	1	MCLR Reset during normal operation
u	u	u	0	u	u	u	1	0	u	MCLR Reset during Sleep
u	u	u	u	0	u	u	u	u	u	RESET Instruction Executed
1	u	u	u	u	u	u	u	u	u	Stack Overflow Reset (STVREN = 1)
u	1	u	u	u	u	u	u	u	u	Stack Underflow Reset (STVREN = 1)
u	u	u	u	u	u	u	u	u	0	Memory violation Reset

TABLE 8-4: RESET CONDITION FOR SPECIAL REGISTERS

Condition	Program Counter	STATUS Register	PCON0 Register	PCON1 Register
Power-on Reset	0000h	1 1000	0011 110x	1-
MCLR Reset during normal operation	0000h	u uuuu	uuuu 0uuu	1-
MCLR Reset during Sleep	0000h	1 0uuu	uuuu 0uuu	u-
WWDT Time-out Reset	0000h	0 uuuu	uuu0 uuuu	u-
WWDT Wake-up from Sleep	PC + 1	0 0uuu	uuuu uuuu	u-
WWDT Window Violation	0000h	u uuuu	uu0u uuuu	u-
Brown-out Reset	0000h	1 1000	0011 11u0	u-
Interrupt Wake-up from Sleep	PC + 1 <sup>(1)</sup>	1 Ouuu	uuuu uuuu	u-
RESET Instruction Executed	0000h	u uuuu	uuuu u0uu	u-
Stack Overflow Reset (STVREN = 1)	0000h	u uuuu	1uuu uuuu	u-
Stack Underflow Reset (STVREN = 1)	0000h	u uuuu	u1uu uuuu	u-
Memory Violation Reset (MEMV = 0)	0	-uuu uuuu	uuuu uuuu	0-

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, reads as '0'.

Note 1: When the wake-up is due to an interrupt and Global Enable (GIE) bit is set, the return address is pushed on the stack and PC is loaded with the interrupt vector (0004h) after execution of PC + 1.

# 8.14 Power Control (PCONx) Registers

The Power Control (PCONx) registers contain flag bits to differentiate between a:

- Power-on Reset (POR)
- Brown-out Reset (BOR)
- Reset Instruction Reset (RI)
- MCLR Reset (RMCLR)
- Watchdog Timer Reset (RWDT)
- Watchdog Timer Window Violation Reset (WDTWV)
- Stack Underflow Reset (STKUNF)
- Stack Overflow Reset (STKOVF)
- Memory Violation Reset (MEMV)

The PCON0 register bits are shown in Register 8-2. The PCON1 register bits are shown in Register 8-3.

Hardware will change the corresponding register bit during the Reset process; if the Reset was not caused by the condition, the bit remains unchanged (Table 8-4).

Software will reset the bit to the inactive state after the restart (hardware will not reset the bit).

Software may also set any PCON bit to the active state, so that user code may be tested, but no Reset action will be generated.

# 8.15 Register Definitions: Power Control

# REGISTER 8-2: PCON0: POWER CONTROL REGISTER 0

R/W/HS-0/q	R/W/HS-0/q	R/W/HC-1/q	R/W/HC-1/q	R/W/HC-1/q	R/W/HC-1/q	R/W/HC-q/u	R/W/HC-q/u
STKOVF	STKUNF	WDTWV	RWDT	RMCLR	RI	POR	BOR
bit 7							bit 0

Legend:

HC = Bit is cleared by hardware

R = Readable bit

U = Unimplemented bit, read as '0'

u = Bit is unchanged

x = Bit is unknown

-m/n = Value at POR/Value at all other Resets

'1' = Bit is set

'0' = Bit is cleared

q = Value depends on condition

bit 7	STKOVF: Stack Overflow Flag bit  1 = A Stack Overflow occurred  0 = A Stack Overflow has not occurred or cleared by firmware
bit 6	STKUNF: Stack Underflow Flag bit  1 = A Stack Underflow occurred  0 = A Stack Underflow has not occurred or cleared by firmware
bit 5	WDTWV: WDT Window Violation Flag bit  1 = A WDT Window Violation Reset has not occurred or set to '1' by firmware  0 = A WDT Window Violation Reset has occurred (a CLRWDT instruction was executed either without arming the window or outside the window (cleared by hardware)
bit 4	RWDT: Watchdog Timer Reset Flag bit  1 = A Watchdog Timer Reset has not occurred or set to '1' by firmware  0 = A Watchdog Timer Reset has occurred (cleared by hardware)
bit 3	RMCLR: MCLR Reset Flag bit  1 = A MCLR Reset has not occurred or set to '1' by firmware  0 = A MCLR Reset has occurred (cleared by hardware)
bit 2	RI: RESET Instruction Flag bit  1 = A RESET instruction has not been executed or set to '1' by firmware  0 = A RESET instruction has been executed (cleared by hardware)
bit 1	POR: Power-on Reset Status bit  1 = No Power-on Reset occurred  0 = A Power-on Reset occurred (must be set in software after a Power-on Reset occurs)
bit 0	BOR: Brown-out Reset Status bit  1 = No Brown-out Reset occurred  0 = A Brown-out Reset occurred (must be set in software after a Power-on Reset or Brown-out Reset

occurs)

# REGISTER 8-3: PCON1: POWER CONTROL REGISTER 0

U-0	U-0	U-0	U-0	U-0	U-0	R/W/HC-1/u	U-0
		_	-	_	S <del></del> X	MEMV	·—·
bit 7				-	-	•	bit 0

Legend:

HC = Bit is cleared by hardware

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -m/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared q = Value depends on condition

bit 7-2 Unimplemented: Read as '0'
bit 1 MEMV: Memory Violation Flag bit

1 = No Memory Violation Reset occurred or set to '1' by firmware.

0 = A Memory Violation Reset occurred (set to '0' in hardware when a Memory Violation occurs))

bit 0 Unimplemented: Read as '0'

# TABLE 8-5: SUMMARY OF REGISTERS ASSOCIATED WITH RESETS

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
BORCON	SBOREN	<u> 20 - 1</u> 0	1	_		-	_	BORRDY	92
PCON0	STKOVF	STKUNF	WDTWV	RWDT	RMCLR	RI	POR	BOR	99
PCON1	× <del></del> -	<del>10-1</del> 0	-	_	-	<del>10 1</del> 8	MEMV	_	99
STATUS	-	-	-	TO	PD	Z	DC	С	30
WDTCON0	1011	<u>141—7</u> 6		V	SWDTEN	150			

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by Resets.

# 9.0 OSCILLATOR MODULE (WITH FAIL-SAFE CLOCK MONITOR)

### 9.1 Overview

The oscillator module has a wide variety of clock sources and selection features that allow it to be used in a wide range of applications while maximizing performance and minimizing power consumption. Figure 9-1 illustrates a block diagram of the oscillator module.

Clock sources can be supplied from external oscillators, quartz-crystal resonators. In addition, the system clock source can be supplied from one of two internal oscillators and PLL circuits, with a choice of speeds selectable via software. Additional clock features include:

- Selectable system clock source between external or internal sources via software.
- Fail-Safe Clock Monitor (FSCM) designed to detect a failure of the external clock source (LP, XT, HS, ECH, ECM, ECL) and switch automatically to the internal oscillator.
- Oscillator Start-up Timer (OST) ensures stability of crystal oscillator sources.

The RSTOSC bits of Configuration Word 1 determine the type of oscillator that will be used when the device resets, including when it is first powered up.


The internal clock modes, LFINTOSC, HFINTOSC (set at 1 MHz), or HFINTOSC (set at 32 MHz) can be set through the RSTOSC bits.

If an external clock source is selected, the FEXTOSC bits of Configuration Word 1 must be used to select the external clock mode.

The external oscillator module can be configured in one of the following clock modes, by setting the FEXTOSC<2:0> bits of Configuration Word 1:

- ECL External Clock Low Power mode ECL ≤ 500 kHz
- ECM External Clock Medium Power mode ECM ≤ 8 MHz
- ECH External Clock High Power mode ECH ≤ 32 MHz
- 4. LP 32 kHz Low-Power Crystal mode.
- XT Medium Gain Crystal or Ceramic Resonator Oscillator mode (between 100 kHz and 4 MHz)
- HS High Gain Crystal or Ceramic Resonator mode (above 4 MHz)

The ECH, ECM, and ECL clock modes rely on an external logic level signal as the device clock source. The LP, XT and HS clock modes require an external crystal or resonator to be connected to the device. Each mode is optimized for a different frequency range. The INTOSC internal oscillator block produces low and high-frequency clock sources, designated LFINTOSC and HFINTOSC. (see Internal Oscillator Block, Figure 9-1). A wide selection of device clock frequencies may be derived from these clock sources.



PIC16(L)F15354/55

# 9.2 Clock Source Types

Clock sources can be classified as external or internal.

External clock sources rely on external circuitry for the clock source to function. Examples are: oscillator modules (ECH, ECM, ECL mode), quartz crystal resonators or ceramic resonators (LP, XT and HS modes).

There is also a secondary oscillator block which is optimized for a 32.768 kHz external clock source, which can be used as an alternate clock source.

There are two internal oscillator blocks:

- HFINTOSC
- LFINTOSC

The HFINTOSC can produce clock frequencies from 1-32 MHz, and is responsible for generating the two MFINTOSC frequencies (500 kHz and 32 kHz) that can be used by some peripherals. The LFINTOSC generates a 31 kHz clock frequency.

There is a 4x PLL that can be used by the external oscillator. See Section 9.2.1.4 "4x PLL" for more details. Additionally, there is a PLL that can be used by the HFINTOSC at certain frequencies. See Section 9.2.2.2 "Internal Oscillator Frequency Adjustment" for more details.

#### 9.2.1 EXTERNAL CLOCK SOURCES

An external clock source can be used as the device system clock by performing one of the following actions:

- Program the RSTOSC<2:0> bits in the Configuration Words to select an external clock source that will be used as the default system clock upon a device Reset
- Write the NOSC<2:0> and NDIV<3:0> bits in the OSCCON1 register to switch the system clock source

See Section 9.3 "Clock Switching" for more information.

## 9.2.1.1 EC Mode


The External Clock (EC) mode allows an externally generated logic level signal to be the system clock source. When operating in this mode, an external clock source is connected to the OSC1/CLKIN input. OSC2/CLKOUT is available for general purpose I/O or CLKOUT. Figure 9-2 shows the pin connections for EC mode.

EC mode has three Power modes to select from through Configuration Words:

- ECH High Power, ≤ 32 MHz
- ECM Medium Power, ≤ 8 MHz
- ECL Low Power, ≤ 0.1 MHz

The Oscillator Start-up Timer (OST) is disabled when EC mode is selected. Therefore, there is no delay in operation after a Power-on Reset (POR) or wake-up from Sleep. Because the PIC® MCU design is fully static, stopping the external clock input will have the effect of halting the device while leaving all data intact. Upon restarting the external clock, the device will resume operation as if no time had elapsed.

FIGURE 9-2: EXTERNAL CLOCK (EC) MODE OPERATION



## 9.2.1.2 LP, XT, HS Modes

The LP, XT and HS modes support the use of quartz crystal resonators or ceramic resonators connected to OSC1 and OSC2 (Figure 9-3). The three modes select a low, medium or high gain setting of the internal inverter-amplifier to support various resonator types and speed.


LP Oscillator mode selects the lowest gain setting of the internal inverter-amplifier. LP mode current consumption is the least of the three modes. This mode is designed to drive only 32.768 kHz tuning-fork type crystals (watch crystals), but can operate up to 100 kHz.

XT Oscillator mode selects the intermediate gain setting of the internal inverter-amplifier. XT mode current consumption is the medium of the three modes. This mode is best suited to drive crystals and resonators with a frequency range up to 4 MHz.

**HS** Oscillator mode selects the highest gain setting of the internal inverter-amplifier. HS mode current consumption is the highest of the three modes. This mode is best suited for resonators that require operating frequencies up to 20 MHz.


Figure 9-3 and Figure 9-4 show typical circuits for quartz crystal and ceramic resonators, respectively.

# FIGURE 9-3: QUARTZ CRYSTAL OPERATION (LP, XT OR HS MODE)



- Note 1: Quartz crystal characteristics vary according to type, package and manufacturer. The user needs to consult the manufacturer data sheets for specifications and recommended application.
  - 2: Always verify oscillator performance over the VDD and temperature range that is expected for the application.
  - 3: For oscillator design assistance, reference the following Microchip Application Notes:
    - AN826, "Crystal Oscillator Basics and Crystal Selection for rfPIC<sup>®</sup> and PIC<sup>®</sup> Devices" (DS00826)
    - AN849, "Basic PIC® Oscillator Design" (DS00849)
    - AN943, "Practical PIC® Oscillator Analysis and Design" (DS00943)
    - AN949, "Making Your Oscillator Work" (DS00949)

# FIGURE 9-4: CERAMIC RESONATOR OPERATION (XT OR HS MODE)



- Note 1: A series resistor (Rs) may be required for ceramic resonators with low drive level.
  - The value of RF varies with the Oscillator mode selected (typically between 2 MΩ to 10 MΩ).
  - An additional parallel feedback resistor (RP) may be required for proper ceramic resonator operation.

# 9.2.1.3 Oscillator Start-up Timer (OST)

If the oscillator module is configured for LP, XT or HS modes, the Oscillator Start-up Timer (OST) counts 1024 oscillations from OSC1. This occurs following a Power-on Reset (POR), Brown-out Reset (BOR) or a wake-up from Sleep. The OST ensures that the oscillator circuit, using a quartz crystal resonator or ceramic resonator, has started and is providing a stable system clock to the oscillator module.

# 9.2.1.4 4x PLL

The oscillator module contains a PLL that can be used with external clock sources to provide a system clock source. The input frequency for the PLL must fall within specifications. See the PLL Clock Timing Specifications in Table 37-9.


The PLL may be enabled for use by one of two methods:

- Program the RSTOSC bits in the Configuration Word 1 to enable the EXTOSC with 4x PLL (RSTOSC<2:0> = '010').
- Write the NOSC bits in the OSCCON1 register to enable the EXTOSC with 4x PLL (NOSC<2:0> = '010').

# 9.2.1.5 Secondary Oscillator

The secondary oscillator is a separate oscillator block that can be used as an alternate system clock source. The secondary oscillator is optimized for 32.768 kHz, and can be used with an external crystal oscillator connected to the SOSCI and SOSCO device pins, or an external clock source connected to the SOSCIN pin. Refer to Section 9.3 "Clock Switching" for more information.

FIGURE 9-5: QUARTZ CRYSTAL OPERATION (SECONDARY OSCILLATOR)



- Note 1: Quartz crystal characteristics vary according to type, package and manufacturer. The user needs to consult the manufacturer data sheets for specifications and recommended application.
  - Always verify oscillator performance over the VDD and temperature range that is expected for the application.
  - 3: For oscillator design assistance, reference the following Microchip Application Notes:
    - AN826, "Crystal Oscillator Basics and Crystal Selection for rfPIC<sup>®</sup> and PIC<sup>®</sup> Devices" (DS00826)
    - AN849, "Basic PIC® Oscillator Design" (DS00849)
    - AN943, "Practical PIC® Oscillator Analysis and Design" (DS00943)
    - AN949, "Making Your Oscillator Work" (DS00949)
    - TB097, "Interfacing a Micro Crystal MS1V-T1K 32.768 kHz Tuning Fork Crystal to a PIC16F690/SS" (DS91097)
    - AN1288, "Design Practices for Low-Power External Oscillators" (DS01288)

#### 9.2.2 INTERNAL CLOCK SOURCES

The device may be configured to use an internal oscillator block as the system clock by performing one of the following actions:

- Program the RSTOSC<2:0> bits in Configuration Words to select the INTOSC clock source, which will be used as the default system clock upon a device Reset.
- Write the NOSC<2:0> bits in the OSCCON1
  register to switch the system clock source to the
  internal oscillator during run-time. See
  Section 9.3 "Clock Switching" for more
  information.

In **INTOSC** mode, the OSC1/CLKIN pin is available for general purpose I/O. The OSC2/CLKOUT pin is available for general purpose I/O or CLKOUT.

The function of the OSC2/CLKOUT pin is determined by the CLKOUTEN bit in Configuration Words.

The internal oscillator block has two independent oscillators that can produce two internal system clock sources.

- The HFINTOSC (High-Frequency Internal Oscillator) is factory calibrated and operates up to 32 MHz.
- The LFINTOSC (Low-Frequency Internal Oscillator) is factory-calibrated and operates at 31 kHz.

#### 9.2.2.1 HFINTOSC

The High-Frequency Internal Oscillator (HFINTOSC) is a precision digitally-controlled internal clock source that produces a stable clock up to 32 MHz. The HFINTOSC can be enabled through one of the following methods:

- Programming the RSTOSC<2:0> bits in Configuration Word 1 to '110' (1 MHz) or '001' (32 MHz) to set the oscillator upon device Power-up or Reset.
- Write to the NOSC<2:0> bits of the OSCCON1 register during run-time.

The HFINTOSC frequency can be selected by setting the HFFRQ<2:0> bits of the OSCFRQ register. The MFINTOSC is an internal clock source within the HFINTOSC that provides two (500 kHz, 32 kHz) constant clock outputs. These constant clock outputs are available for selection to various peripherals, internally.

The NDIV<3:0> bits of the OSCCON1 register allow for division of the HFINTOSC output from a range between 1:1 and 1:512.

# 9.2.2.2 Internal Oscillator Frequency Adjustment

The HFINTOSC and LFINTOSC internal oscillators are both factory-calibrated. The HFINTOSC oscillator can be adjusted in software by writing to the OSCTUNE register (Register 9-7). OSCTUNE does not affect the LFINTOSC frequency.

The default value of the OSCTUNE register is 00h. The value is a 6-bit two's complement number. A value of 1Fh will provide an adjustment to the maximum frequency. A value of 20h will provide an adjustment to the minimum frequency.

When the OSCTUNE register is modified, the current HFINTOSC oscillator frequency will begin shifting to the new frequency. Code execution continues during this shift. There is no indication that the shift has occurred.

#### 9.2.2.3 LFINTOSC

The Low-Frequency Internal Oscillator (LFINTOSC) is a factory-calibrated 31 kHz internal clock source.

The LFINTOSC is the clock source for the Power-up Timer (PWRT), Watchdog Timer (WDT), and Fail-Safe Clock Monitor (FSCM). The LFINTOSC can also be used as the system clock, or as a clock or input source to certain peripherals.

The LFINTOSC is selected as the clock source through one of the following methods:

- Programming the RSTOSC<2:0> bits of Configuration Word 1 to enable LFINTOSC (RSTOSC<2:0> = '101')
- Write to the NOSC<2:0> bits of the OSCCON1 register (NOSC<2:0> = '101')

Peripherals that use the LFINTOSC are:

- Power-up Timer (PWRT)
- Windowed Watchdog Timer (WWDT)
- Timer1
- Timer0
- Timer2
- Fail-Safe Clock Monitor (FSCM)
- CLKR
- CLC

#### 9.2.2.4 Oscillator Status and Manual Enable

The 'ready' status of each oscillator is displayed in the OSCSTAT register (Register 9-4). The oscillators can also be manually enabled through the OSCEN register (Register 9-7). Manual enabling makes it possible to verify the operation of the EXTOSC or SOSC crystal oscillators. This can be achieved by enabling the selected oscillator, then watching the corresponding 'ready' state of the oscillator in the OSCSTAT register.

## 9.3 Clock Switching

The system clock source can be switched between external and internal clock sources via software using the New Oscillator Source (NOSC) and New Divider selection request (NDIV) bits of the OSCCON1 register. The following clock sources can be selected:

- External Oscillator (EXTOSC)
- High-Frequency Internal Oscillator (HFINTOSC)
- Low-Frequency Internal Oscillator (LFINTOSC)
- Secondary Oscillator (SOSC)
- · EXTOSC with 4x PLL
- . HFINTOSC with 2x PLL

# 9.3.1 NEW OSCILLATOR SOURCE (NOSC) AND NEW DIVIDER SELECTION REQUEST (NDIV) BITS

The New Oscillator Source (NOSC) and New Divider selection request (NDIV) bits of the OSCCON1 register select the system clock source and the frequency that are used for the CPU and peripherals.

When new values of NOSC and NDIV are written to OSCCON1, the current oscillator selection will continue to operate while waiting for the new clock source to indicate that it is stable and ready. In some cases, the newly requested source may already be in use, and is ready immediately. In the case of a divider-only change, the new and old sources are the same, and will be immediately ready. The device may enter Sleep while waiting for the switch as described in Section 9.3.3 "Clock Switch and Sleep".

When the new oscillator is ready, the New Oscillator is Ready (NOSCR) bit of OSCCON3 and the Clock Switch Interrupt Flag (CSWIF) bit of PIR1 become set (CSWIF = 1). If Clock Switch Interrupts are enabled (CSWIE = 1), an interrupt will be generated at that time. The Oscillator Ready (ORDY) bit of OSCCON3 can also be polled to determine when the oscillator is ready in lieu of an interrupt.

If the Clock Switch Hold (CSWHOLD) bit of OSCCON3 is clear, the oscillator switch will occur when the New Oscillator is Ready (NOSCR) bit is set, and the interrupt (if enabled) will be serviced at the new oscillator setting.

If CSWHOLD is set, the oscillator switch is suspended, while execution continues using the current (old) clock source. When the NOSCR bit is set, software may:

- · set CSWHOLD = 0 so the switch can complete, or
- · copy COSC into NOSC to abandon the switch.

If Doze mode is in effect, the switch occurs on the next clock cycle, whether or not the CPU is operating during that cycle.

Changing the clock post-divider without changing the clock source (e.g., changing FOSC from 1 MHz to 2 MHz) is handled in the same manner as a clock source change, as described previously. The clock source will already be active, so the switch is relatively quick. CSWHOLD must be clear (CSWHOLD = 0) for the switch to complete.

The current COSC and CDIV are indicated in the OSCCON2 register up to the moment when the switch actually occurs, at which time OSCCON2 is updated and ORDY is set. NOSCR is cleared by hardware to indicate that the switch is complete.

#### 9.3.2 PLL INPUT SWITCH

Switching between the PLL and any non-PLL source is managed as described above. The input to the PLL is established when NOSC selects the PLL, and maintained by the COSC setting.

When NOSC and COSC select the PLL with different input sources, the system continues to run using the COSC setting, and the new source is enabled per NOSC. When the new oscillator is ready (and CSWHOLD = 0), system operation is suspended while the PLL input is switched and the PLL acquires lock.

Note: If the PLL fails to lock, the FSCM will trigger.


## 9.3.3 CLOCK SWITCH AND SLEEP

If OSCCON1 is written with a new value and the device is put to Sleep before the switch completes, the switch will not take place and the device will enter Sleep mode.

When the device wakes from Sleep and the CSWHOLD bit is clear, the device will wake with the 'new' clock active, and the clock switch interrupt flag bit (CSWIF) will be set.


When the device wakes from Sleep and the CSWHOLD bit is set, the device will wake with the 'old' clock active and the new clock will be requested again.

TICLIDE 0.6. CLOCK SWITCH (CSWILD) D =




Note 1:CSWIF is asserted coincident with NOSCR; interrupt is serviced at OSC#2 speed.

2: The assertion of NOSCR is hidden from the user because it appears only for the duration of the switch.








#### 9.4 Fail-Safe Clock Monitor

The Fail-Safe Clock Monitor (FSCM) allows the device to continue operating should the external oscillator fail. The FSCM is enabled by setting the FCMEN bit in Configuration Word 1. The FSCM is applicable to all external Oscillator modes (LP, XT, HS, ECL, ECM, ECH and Secondary Oscillator).

FIGURE 9-9: FSCM BLOCK DIAGRAM



#### 9.4.1 FAIL-SAFE DETECTION

The FSCM module detects a failed oscillator by comparing the external oscillator to the FSCM sample clock. The sample clock is generated by dividing the LFINTOSC by 64. See Figure 9-9. Inside the fail detector block is a latch. The external clock sets the latch on each falling edge of the external clock. The sample clock clears the latch on each rising edge of the sample clock. A failure is detected when an entire half-cycle of the sample clock elapses before the external clock goes low.

#### 9.4.2 FAIL-SAFE OPERATION

When the external clock fails, the FSCM switches the device clock to the HFINTOSC at 1 MHz clock frequency and sets the bit flag OSFIF of the PIR1 register. Setting this flag will generate an interrupt if the OSFIE bit of the PIE1 register is also set. The device firmware can then take steps to mitigate the problems that may arise from a failed clock. The system clock will continue to be sourced from the internal clock source until the device firmware successfully restarts the external oscillator and switches back to external operation, by writing to the NOSC and NDIV bits of the OSCCON1 register.


### 9.4.3 FAIL-SAFE CONDITION CLEARING

The Fail-Safe condition is cleared after a Reset, executing a SLEEP instruction or changing the NOSC and NDIV bits of the OSCCON1 register. When switching to the external oscillator, or external oscillator and PLL, the OST is restarted. While the OST is running, the device continues to operate from the INTOSC selected in OSCCON1. When the OST times out, the Fail-Safe condition is cleared after successfully switching to the external clock source. The OSFIF bit must be cleared prior to switching to the external clock source. If the Fail-Safe condition still exists, the OSFIF flag will again become set by hardware.

#### 9.4.4 RESET OR WAKE-UP FROM SLEEP

The FSCM is designed to detect an oscillator failure after the Oscillator Start-up Timer (OST) has expired. The OST is used after waking up from Sleep and after any type of Reset. The OST is not used with the EC Clock modes so that the FSCM will be active as soon as the Reset or wake-up has completed. Therefore, the device will always be executing code while the OST is operating.

FIGURE 9-10: FSCM TIMING DIAGRAM



## 9.5 Register Definitions: Oscillator Control

#### REGISTER 9-1: OSCCON1: OSCILLATOR CONTROL REGISTER1

U-0	R/W-f/f <sup>(1)</sup>	R/W-f/f <sup>(1)</sup>	R/W-f/f <sup>(1)</sup>	R/W-q/q	R/W-q/q	R/W-q/q	R/W-q/q
,	NOSC<2:0>(2,3)			NDIV<3:0>(2,3,4)			
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	f = determined by fuse setting

bit 7 Unimplemented: Read as '0'

bit 6-4 NOSC<2:0>: New Oscillator Source Request bits

The setting requests a source oscillator and PLL combination per Table 9-1.

POR value = RSTOSC (Register 5-1).

bit 3-0 NDIV<3:0>: New Divider Selection Request bits

The setting determines the new postscaler division ratio per Table 9-1.

Note 1: The default value (f/f) is set equal to the RSTOSC Configuration bits.

- 2: If NOSC is written with a reserved value (Table 9-1), the operation is ignored and neither NOSC nor NDIV is written.
- 3: When CSWEN = 0, this register is read-only and cannot be changed from the POR value.
- 4: When NOSC = 110 (HFINTOSC 1 MHz), the NDIV bits will default to '0010' upon Reset; for all other NOSC settings the NDIV bits will default to '0000' upon Reset.

#### REGISTER 9-2: OSCCON2: OSCILLATOR CONTROL REGISTER 2

U-0	R-n/n <sup>(2)</sup>							
_	COSC<2:0>			CDIV<3:0>				
bit 7	7						bit 0	

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7 Unimplemented: Read as '0'

bit 6-4 COSC<2:0>: Current Oscillator Source Select bits (read-only)

Indicates the current source oscillator and PLL combination per Table 9-1.

bit 3-0 CDIV<3:0>: Current Divider Select bits (read-only)

Indicates the current postscaler division ratio per Table 9-1.

Note 1: The POR value is the value present when user code execution begins.

2: The Reset value (n/n) is the same as the NOSC/NDIV bits.

TABLE 9-1: NOSC/COSC BIT SETTINGS

NOSC<2:0>/ COSC<2:0>	Clock Source				
111	EXTOSC <sup>(1)</sup>				
110	HFINTOSC (1 MHz) <sup>(2)</sup>				
101	LFINTOSC				
100	SOSC				
011	Reserved				
010	EXTOSC with 4x PLL <sup>(1)</sup>				
001	HFINTOSC with 2x PLL (32 MHz)(1)				
000	HFINTOSC (32 MHz)				

Note 1: EXTOSC configured by the FEXTOSC bits of Configuration Word 1 (Register 5-1).

 HFINTOSC settings are configured with the HFFRQ bits of the OSCFRQ register (Register 9-6).

TABLE 9-2:	NDIV/CDI	V RIT	SETTINGS	

NDIV<3:0>/ CDIV<3:0>	Clock divider		
1111-1010	Reserved		
1001	512		
1000	256		
0111	128		
0110	64		
0101	32		
0100	16		
0011	8		
0010	4		
0001	2		
0000	1		

## REGISTER 9-3: OSCCON3: OSCILLATOR CONTROL REGISTER 3

R/W/HC-0/0	R/W-0/0	U-0	R-0/0	R-0/0	U-0	U-0	U-0
CSWHOLD	SOSCPWR	( <del></del> )	ORDY	NOSCR	-	-	
bit 7				4 <del>8</del>	-		bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7 CSWHOLD: Clock Switch Hold bit

1 = Clock switch will hold (with interrupt) when the oscillator selected by NOSC is ready

0 = Clock switch may proceed when the oscillator selected by NOSC is ready; if this bit is clear at the time that NOSCR becomes '1', the switch will occur

bit 6 SOSCPWR: Secondary Oscillator Power Mode Select bit

1 = Secondary oscillator operating in High Power mode

0 = Secondary oscillator operating in Low Power mode

bit 5 Unimplemented: Read as '0'.

bit 4 ORDY: Oscillator Ready bit (read-only)

1 = OSCCON1 = OSCCON2; the current system clock is the clock specified by NOSC

0 = A clock switch is in progress

bit 3 NOSCR: New Oscillator is Ready bit (read-only)

1 = A clock switch is in progress and the oscillator selected by NOSC indicates a "ready" condition

0 = A clock switch is not in progress, or the NOSC-selected oscillator is not yet ready

bit 2-0 Unimplemented: Read as '0'

## REGISTER 9-4: OSCSTAT: OSCILLATOR STATUS REGISTER 1

R-q/q	R-q/q	R-q/q	R-q/q	R-q/q	R-q/q	U-0	R-q/q
EXTOR	HFOR	MFOR	LFOR	SOR	ADOR	_	PLLR
bit 7 bit 0							

 Legend:

 R = Readable bit
 W = Writable bit
 U = Unimplemented bit, read as '0'

 u = Bit is unchanged
 x = Bit is unknown
 -n/n = Value at POR and BOR/Value at all other Resets

 '1' = Bit is set
 '0' = Bit is cleared
 q = Reset value is determined by hardware

bit 7 EXTOR: EXTOSC (external) Oscillator Ready bit 1 = The oscillator is ready to be used 0 = The oscillator is not enabled, or is not yet ready to be used. bit 6 HFOR: HFINTOSC Oscillator Ready bit 1 = The oscillator is ready to be used 0 = The oscillator is not enabled, or is not yet ready to be used. bit 5 MFOR: MFINTOSC Oscillator Ready bit 1 = The oscillator is ready to be used 0 = The oscillator is not enabled, or is not yet ready to be used. LFOR: LFINTOSC Oscillator Ready bit bit 4 1 = The oscillator is ready to be used 0 = The oscillator is not enabled, or is not yet ready to be used. bit 3 SOR: Secondary (Timer1) Oscillator Ready bit 1 = The oscillator is ready to be used The oscillator is not enabled, or is not yet ready to be used. ADOR: CRC Oscillator Ready bit bit 2 1 = The oscillator is ready to be used 0 = The oscillator is not enabled, or is not yet ready to be used.

bit 1 Unimplemented: Read as '0'

bit 0

1 = The PLL is ready to be used

PLLR: PLL is Ready bit

0 = The PLL is not enabled, the required input source is not ready, or the PLL is not locked.

## REGISTER 9-5: OSCEN: OSCILLATOR MANUAL ENABLE REGISTER

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	U-0	U-0
EXTOEN	HFOEN	MFOEN	LFOEN	SOSCEN	ADOEN	-	-
bit 7 bit 0							

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	<b>EXTOEN:</b> External Oscillator Manual Request Enable bit <sup>(1)</sup> 1 = EXTOSC is explicitly enabled, operating as specified by FEXTOSC 0 = EXTOSC can be enabled by some modules
bit 6	HFOEN: HFINTOSC Oscillator Manual Request Enable bit  1 = HFINTOSC is explicitly enabled, operating as specified by OSCFRQ  0 = HFINTOSC can be enabled by another module
bit 5	MFOEN: MFINTOSC Oscillator Manual Request Enable bit  1 = MFINTOSC is explicitly enabled  0 = MFINTOSC can be enabled by another module
bit 4	LFOEN: LFINTOSC (31 kHz) Oscillator Manual Request Enable bit  1 = LFINTOSC is explicitly enabled  0 = LFINTOSC can be enabled by another module
bit 3	SOSCEN: Secondary (Timer1) Oscillator Manual Request bit  1 = Secondary oscillator is explicitly enabled, operating as specified by SOSCPWR  0 = Secondary oscillator can be enabled by another module
bit 2	ADOEN: FRC Oscillator Manual Request Enable bit  1 = FRC is explicitly enabled  0 = FRC can be enabled by another module
bit 1-0	Unimplemented: Read as '0'

## REGISTER 9-6: OSCFRQ: HFINTOSC FREQUENCY SELECTION REGISTER

U-0	U-0	U-0	U-0	U-0	R/W-q/q	R/W-q/q	R/W-q/q
_	_		h <del>-</del> 2	-	ŀ	HFFRQ<2:0>(1)	
bit 7	-						bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-3 Unimplemented: Read as '0'

bit 2-0 HFFRQ<2:0>: HFINTOSC Frequency Selection bits

Nominal Freq (MHz):

111 = Reserved

110 = 32

101 = 16

100 = 12

011 = 8

010 = 4

001 = 2

000 = 1

Note 1: When RSTOSC=110 (HFINTOSC 1 MHz), the HFFRQ bits will default to '010' upon Reset; when RSTOSC = 001 (HFINTOSC 32 MHz), the HFFRQ bits will default to '101' upon Reset.

## REGISTER 9-7: OSCTUNE: HFINTOSC TUNING REGISTER

U-0	U-0	R/W-1/1	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
<u> </u>	-			HFTU	N<5:0>		·
bit 7	812	86					bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-6 Unimplemented: Read as '0'.

bit 5-0 HFTUN<5:0>: HFINTOSC Frequency Tuning bits

01 1111 = Maximum frequency

01 1110 =

00 0001 =

00 0000 = Center frequency. Oscillator module is running at the calibrated frequency (default value).

11 1111 =

•••

10 0001 =

10 0000 = Minimum frequency.

TABLE 9-3: SUMMARY OF REGISTERS ASSOCIATED WITH CLOCK SOURCES

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
OSCCON1	_		NOSC<2:0>			NDIV<	3:0>	19	110
OSCCON2	-		COSC<2:0>			CDIV<3:0>			
OSCCON3	CWSHOLD	SOSCPWR	-	ORDY	NOSCR	-	-	1 <del>2-0</del> 1	111
OSCFRQ	_	_	_	-	_	Н	FFRQ<2:0>		114
OSCSTAT	EXTOR	HFOR	MFOR	LFOR	SOR	ADOR	5 <del></del> 3	PLLR	112
OSCTUNE	<u></u>	1-1			HFTUN	<5:0>			115
OSCEN	EXTOEN	HFOEN	MFOEN	LFOEN	SOSCEN	ADOEN		8 <del></del>	113

Legend: — = unimplemented location, read as '0'. Shaded cells are not used by clock sources.

TABLE 9-4: SUMMARY OF CONFIGURATION WORD WITH CLOCK SOURCES

Name	Bits	Bit -/7	Bit -/6	Bit 13/5	Bit 12/4	Bit 11/3	Bit 10/2	Bit 9/1	Bit 8/0	Register on Page
CONFIG1	13:8	-	14 <del>-14</del>	FCMEN	ş <u>—</u>	CSWEN	-	-	CLKOUTEN	76
CONFIGI	7:0	_	ı	RSTOSC<2:0>		_		EXTOSC<2:0	<b> &gt;</b>	76

Legend: — = unimplemented location, read as '0'. Shaded cells are not used by clock sources.

## 10.0 INTERRUPTS

The interrupt feature allows certain events to preempt normal program flow. Firmware is used to determine the source of the interrupt and act accordingly. Some interrupts can be configured to wake the MCU from Sleep mode.


This chapter contains the following information for Interrupts:

- Operation
- Interrupt Latency
- · Interrupts During Sleep
- INT Pin
- Automatic Context Saving

Many peripherals produce interrupts. Refer to the corresponding chapters for details.

A block diagram of the interrupt logic is shown in Figure 10-1.

FIGURE 10-1: INTERRUPT LOGIC



## 10.1 Operation

Interrupts are disabled upon any device Reset. They are enabled by setting the following bits:

- GIE bit of the INTCON register
- Interrupt Enable bit(s) of the PIEx[y] registers for the specific interrupt event(s)
- PEIE bit of the INTCON register (if the Interrupt Enable bit of the interrupt event is contained in the PIEx registers)

The PIR1, PIR2, PIR3, PIR4, PIR5, PIR6, and PIR7 registers record individual interrupts via interrupt flag bits. Interrupt flag bits will be set, regardless of the status of the GIE, PEIE and individual interrupt enable bits.

The following events happen when an interrupt event occurs while the GIE bit is set:

- · Current prefetched instruction is flushed
- GIE bit is cleared
- Current Program Counter (PC) is pushed onto the stack
- Critical registers are automatically saved to the shadow registers (See Section 10.5 "Automatic Context Saving")
- PC is loaded with the interrupt vector 0004h

The firmware within the Interrupt Service Routine (ISR) may determine the source of the interrupt by polling the interrupt flag bits. The interrupt flag bits must be cleared before exiting the ISR to avoid repeated interrupts. Because the GIE bit is cleared, any interrupt that occurs while executing the ISR will be recorded through its interrupt flag, but will not cause the processor to redirect to the interrupt vector.

The RETFIE instruction exits the ISR by popping the previous address from the stack, restoring the saved context from the shadow registers and setting the GIE bit


For additional information on a specific interrupts operation, refer to its peripheral chapter.

- Note 1: Individual interrupt flag bits are set, regardless of the state of any other enable bits.
  - 2: All interrupts will be ignored while the GIE bit is cleared. Any interrupt occurring while the GIE bit is clear will be serviced when the GIE bit is set again.


## 10.2 Interrupt Latency

Interrupt latency is defined as the time from when the interrupt event occurs to the time code execution at the interrupt vector begins. The interrupt is sampled during Q1 of the instruction cycle. The actual interrupt latency then depends on the instruction that is executing at the time the interrupt is detected. See Figure 10-2 and Figure 10-3 for more details.





## FIGURE 10-3: INT PIN INTERRUPT TIMING



3: For minimum width of INT pulse, refer to AC specifications in Section 37.0 "Electrical Specifications".

Latency is the same whether Inst (PC) is a single cycle or a two-cycle instruction.

4: INTF may be set any time during the Q4-Q1 cycles.

## 10.3 Interrupts During Sleep

Interrupts can be used to wake from Sleep. To wake from Sleep, the peripheral must be able to operate without the system clock. The interrupt source must have the appropriate Interrupt Enable bit(s) set prior to entering Sleep.

On waking from Sleep, if the GIE bit is also set, the processor will branch to the interrupt vector. Otherwise, the processor will continue executing instructions after the SLEEP instruction. The instruction directly after the SLEEP instruction will always be executed before branching to the ISR. Refer to Section 11.0 "Power-Saving Operation Modes" for more details.

## 10.4 INT Pin

The INT pin can be used to generate an asynchronous edge-triggered interrupt. Refer to Figure 10-3. This interrupt is enabled by setting the INTE bit of the PIE0 register. The INTEDG bit of the INTCON register determines on which edge the interrupt will occur. When the INTEDG bit is set, the rising edge will cause the interrupt. When the INTEDG bit is clear, the falling edge will cause the interrupt. The INTF bit of the PIR0 register will be set when a valid edge appears on the INT pin. If the GIE and INTE bits are also set, the processor will redirect program execution to the interrupt vector.

## 10.5 Automatic Context Saving

Upon entering an interrupt, the return PC address is saved on the stack. Additionally, the following registers are automatically saved in the shadow registers:

- W register
- STATUS register (except for TO and PD)
- BSR register
- FSR registers
- PCLATH register

Upon exiting the Interrupt Service Routine, these registers are automatically restored. Any modifications to these registers during the ISR will be lost. If modifications to any of these registers are desired, the corresponding shadow register may be modified and the value will be restored when exiting the ISR. The shadow registers are available in Bank 31 and are readable and writable. Depending on the user's application, other registers may also need to be saved.

## 10.6 Register Definitions: Interrupt Control

## REGISTER 10-1: INTCON: INTERRUPT CONTROL REGISTER

R/W-0/0	R/W-0/0	U-0	U-0	U-0	U-0	U-0	R/W-1/1
GIE	PEIE	<u></u> -	1		() <u>"</u> ")	<u> </u>	INTEDG
bit 7				38			bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	GIE: Global Interrupt Enable bit
	<ul><li>1 = Enables all active interrupts</li><li>0 = Disables all interrupts</li></ul>
bit 6	<b>PEIE:</b> Peripheral Interrupt Enable bit 1 = Enables all active peripheral interrupts 0 = Disables all peripheral interrupts
bit 5-1	Unimplemented: Read as '0'
bit 0	INTEDG: Interrupt Edge Select bit 1 = Interrupt on rising edge of INT pin 0 = Interrupt on falling edge of INT pin

Note:	Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of						
	The state of the s						
	its corresponding enable bit or the Global						
	Enable (GIE) bit of the INTCON register.						
	Enable (GIE) bit of the hyrodiv register.						
	User software must ensure the						
	appropriate interrupt flag bits are clear prior to enabling an interrupt.						
	prior to criability art interrupt.						

## REGISTER 10-2: PIE0: PERIPHERAL INTERRUPT ENABLE REGISTER 0

U-0	U-0	R/W-0/0	R/W-0/0	U-0	U-0	U-0	R/W-0/0
<u>8—</u> 8		TMR0IE	IOCIE		9 <u></u> 9	4 <u></u>	INTE
bit 7		110					bit 0

 Legend:
 R = Readable bit
 W = Writable bit
 U = Unimplemented bit, read as '0'

 u = Bit is unchanged
 x = Bit is unknown
 -n/n = Value at POR and BOR/Value at all other Resets

 '1' = Bit is set
 '0' = Bit is cleared
 HS = Hardware set

bit 7-6

Unimplemented: Read as '0'

TMR0IE: Timer0 Overflow Interrupt Enable bit

1 = Enables the Timer0 interrupt

0 = Disables the Timer0 interrupt

bit 4

IOCIE: Interrupt-on-Change Interrupt Enable bit

1 = Enables the IOC change interrupt

0 = Disables the IOC change interrupt

bit 3-1

Unimplemented: Read as '0'

bit 0

INTE: INT External Interrupt Flag bit<sup>(1)</sup>

1 = Enables the INT external interrupt

Note 1: The External Interrupt INT pin is selected by INTPPS (Register 15-1).

0 = Disables the INT external interrupt

Note: Bit PEIE of the INTCON register must be set to enable any peripheral interrupt controlled by PIE1-PIE7. Interrupt sources controlled by the PIE0 register do not require PEIE to be set in order to allow interrupt vectoring (when GIE is set).

## REGISTER 10-3: PIE1: PERIPHERAL INTERRUPT ENABLE REGISTER 1

R/W-0/0	R/W-0/0	U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0
OSFIE	CSWIE	<del>10 1</del> 8	: <del>-</del> :	_	-	_	ADIE
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown
'1' = Bit is set '0' = Bit is cleared

U = Unimplemented bit, read as '0'

-n/n = Value at POR and BOR/Value at all other Resets

bit 7

OSFIE: Oscillator Fail Interrupt Enable bit

1 = Enables the Oscillator Fail Interrupt
0 = Disables the Oscillator Fail Interrupt
bit 6

CSWIE: Clock Switch Complete Interrupt Enable bit
1 = The clock switch module interrupt is enabled
0 = The clock switch module interrupt is disabled
bit 5-1

Unimplemented: Read as '0'
bit 0

ADIE: Analog-to-Digital Converter (ADC) Interrupt Enable bit
1 = Enables the ADC interrupt
0 = Disables the ADC interrupt

Note: Bit PEIE of the INTCON register must be set to enable any peripheral interrupt controlled by registers PIE1-PIE7

## REGISTER 10-4: PIE2: PERIPHERAL INTERRUPT ENABLE REGISTER 2

U-0	R/W-0/0	U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0
<del>2(1−−7</del> 4)	ZCDIE		-	_	_	C2IE	C1IE
bit 7			_				bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 Unimplemented: Read as '0'

bit 6 ZCDIE: Zero-Cross Detection (ZCD) Interrupt Enable bit

1 = Enables the ZCD interrupt0 = Disables the ZCD interrupt

bit 5-2 Unimplemented: Read as '0'

bit 1 C2IE: Comparator C2 Interrupt Enable bit

1 = Enables the Comparator C2 interrupt 0 = Disables the Comparator C2 interrupt

bit 0 C1IE: Comparator C1 Interrupt Enable bit

1 = Enables the Comparator C1 interrupt0 = Disables the Comparator C1 interrupt

Note: Bit PEIE of the INTCON register must be

set to enable any peripheral interrupt

controlled by registers PIE1-PIE7.

## REGISTER 10-5: PIE3: PERIPHERAL INTERRUPT ENABLE REGISTER 3

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| RC2IE   | TX2IE   | RC1IE   | TX1IE   | BCL2IE  | SSP2IE  | BCL1IE  | SSP1IE  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	RC2IE: USART2 Receive Interrupt Enable bit
	1 = Enables the USART2 receive interrupt
	0 = Enables the USART2 receive interrupt
bit 6	TX2IE: USART2 Transmit Interrupt Enable bit
	1 = Enables the USART2 transmit interrupt
	0 = Disables the USART2 transmit interrupt
bit 5	RC1IE: USART1 Receive Interrupt Enable bit
	1 = Enables the USART1 receive interrupt
	0 = Enables the USART1 receive interrupt
bit 4	TX1IE: USART1 Transmit Interrupt Enable bit
	1 = Enables the USART1 transmit interrupt
	0 = Disables the USART1 transmit interrupt
bit 3	BCL2IE: MSSP2 Bus Collision Interrupt Enable bit
	1 = MSSP bus Collision interrupt enabled
	0 = MSSP bus Collision interrupt disabled
bit 2	SSP2IE: MSSP2 Interrupt Enable bit
	1 = Enables the MSSP2 Interrupt
	0 = Disables the MSSP Interrupt
bit 1	BCL1IE: MSSP1 Bus Collision Interrupt Enable bit
	1 = MSSP1 bus collision interrupt enabled
	0 = MSSP1 bus collision interrupt disabled
bit 0	SSP1IE: MSSP1 Interrupt Enable bit
	1 = Enables the MSSP1 interrupt
	0 = Disables the MSSP1 interrupt

Note: Bit PEIE of the INTCON register must be set to enable any peripheral interrupt controlled by PIE1-PIE7.

#### REGISTER 10-6: PIE4: PERIPHERAL INTERRUPT ENABLE REGISTER 4

U-0	U-0	U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0
<u>=</u> :	-	<u></u>			9 <b>—</b> 3	TMR2IE	TMR1IE
bit 7	,						bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HS = Hardware set

bit 7-2 Unimplemented: Read as '0'

bit 1 TMR2IE: TMR2 to PR2 Match Interrupt Enable bit

1 = Enables the Timer2 to PR2 match interrupt 0 = Disables the Timer2 to PR2 match interrupt

bit 0 TMR1IE: Timer1 Overflow Interrupt Enable bit

1 = Enables the Timer1 overflow interrupt

0 = Enables the Timer1 overflow interrupt

Note: Bit PEIE of the INTCON register must be

set to enable any peripheral interrupt

controlled by registers PIE1-PIE7.

## REGISTER 10-7: PIE5: PERIPHERAL INTERRUPT ENABLE REGISTER 5

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	U-0	U-0	U-0	R/W-0/0
CLC4IE	CLC3IE	CLC2IE	CLC1IE	_	n <del></del> n	,	TMR1GIE
bit 7 bit 0							

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HS = Hardware set

bit 7	CLC4IE: CLC4 Interrupt Enable bit  1 = CLC4 interrupt enabled  0 = CLC4 interrupt disabled
bit 6	CLC3IE: CLC3 Interrupt Enable bit 1 = CLC3 interrupt enabled 0 = CLC3 interrupt disabled
bit 5	CLC2IE: CLC2 Interrupt Enable bit 1 = CLC2 interrupt enabled 0 = CLC2 interrupt disabled
bit 4	CLC1IE: CLC1 Interrupt Enable bit  1 = CLC1 interrupt enabled  0 = CLC1 interrupt disabled
bit 3-1	Unimplemented: Read as '0'
bit 0	TMR1GIE: Timer1 Gate Interrupt Enable bit  1 = Enables the Timer1 gate acquisition interrupt  0 = Disables the Timer1 gate acquisition interrupt

Note: Bit PEIE of the INTCON register must be set to enable any peripheral interrupt controlled by registers PIE1-PIE7.

#### REGISTER 10-8: PIE6: PERIPHERAL INTERRUPT ENABLE REGISTER 6

U-0	U-0	U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0
	:		_	_	: <del></del> 17	CCP2IE	CCP1IE
bit 7	2	38		300 000		34	bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HS = Hardware set

bit 7-2

Unimplemented: Read as '0'.

bit 1

CCP2IE: CCP2 Interrupt Enable bit

1 = CCP2 interrupt is enabled

0 = CCP2 interrupt is disabled

bit 0

CCP1IE: CCP1 Interrupt Enable bit

1 = CCP1 interrupt is enabled

0 = CCP1 interrupt is disabled

Note: Bit PEIE of the INTCON register must be set to enable any peripheral interrupt controlled by registers PIE1-PIE7.

## REGISTER 10-9: PIE7: PERIPHERAL INTERRUPT ENABLE REGISTER 7

U-0	U-0	R/W-0/0	R/W-0/0	U-0	U-0	U-0	R/W-0/0
	::	NVMIE	NCO1IE	-	:	-	CWG1IE
bit 7	*	0.	·			<del>Rt.</del>	bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HS = Hardware set

bit 7-6	Unimplemented: Read as '0'.
bit 5	NVMIE: NVM Interrupt Enable bit 1 = NVM task complete interrupt enabled
2.2002	0 = NVM interrupt not enabled
bit 4	NCO1IE: NCO Interrupt Enable bit  1 = NCO rollover interrupt enabled  0 = NCO rollover interrupt disabled
bit 3-1	Unimplemented: Read as '0'.
bit 0	CWG1IE: CWG1 Interrupt Enable bit 1 = CWG1 interrupt is enabled 0 = CWG1 interrupt disabled

Note: Bit PEIE of the INTCON register must be set to enable any peripheral interrupt controlled by registers PIE1-PIE7.

#### REGISTER 10-10: PIR0: PERIPHERAL INTERRUPT STATUS REGISTER 0

U-0	U-0	R/W/HS-0/0	R-0	U-0	U-0	U-0	R/W/HS-0/0
<del></del> :	_	TMR0IF	IOCIF	_	_	_	INTF <sup>(1)</sup>
bit 7						bit 0	

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HS= Hardware Set

bit 7-6 Unimplemented: Read as '0'

bit 5 TMR0IF: Timer0 Overflow Interrupt Flag bit

1 = Timer0 register has overflowed (must be cleared in software)

0 = Timer0 register did not overflow

bit 4 IOCIF: Interrupt-on-Change Interrupt Flag bit (read-only)(2)

1 = One or more of the IOCAF-IOCEF register bits are currently set, indicating an enabled edge was

detected by the IOC module.

0 = None of the IOCAF-IOCEF register bits are currently set

bit 3-1 Unimplemented: Read as '0'

bit 0 INTF: INT External Interrupt Flag bit<sup>(1)</sup>

1 = The INT external interrupt occurred (must be cleared in software)

0 = The INT external interrupt did not occur

Note 1: The External Interrupt INT pin is selected by INTPPS (Register 15-1).

2: The IOCIF bit is the logical OR of all the IOCAF-IOCEF flags. Therefore, to clear the IOCIF flag, application firmware must clear all of the lower level IOCAF-IOCEF register bits.

## REGISTER 10-11: PIR1: PERIPHERAL INTERRUPT REQUEST REGISTER 1

R/W/HS-0/0	R/W/HS-0/0	U-0	U-0	U-0	U-0	U-0	R/W/HS-0/0
OSFIF	CSWIF		: <del></del> :	_	_	_	ADIF
bit 7 bit 0							

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HS = Hardware set

bit 7 OSFIF: Oscillator Fail-Safe Interrupt Flag bit

1 = Oscillator fail-safe interrupt has occurred (must be cleared in software)

0 = No oscillator fail-safe interrupt

bit 6 CSWIF: Clock Switch Complete Interrupt Flag bit

1 = The clock switch module indicates an interrupt condition and is ready to complete the clock switch

operation (must be cleared in software)

0 = The clock switch does not indicate an interrupt condition bit 5-1 **Unimplemented:** Read as '0'

bit 0 ADIF: Analog-to-Digital Converter (ADC) Interrupt Flag bit

1 = An A/D conversion or complex operation has completed (must be cleared in software)

0 = An A/D conversion or complex operation is not complete

#### REGISTER 10-12: PIR2: PERIPHERAL INTERRUPT REQUEST REGISTER 2

U-0	R/W/HS-0/0	U-0	U-0	U-0	U-0	R/W/HS-0/0	R/W/HS-0/0
_	ZCDIF	<u> 24 - 1</u> 2	_	_	-	C2IF	C1IF
bit 7				165 4.0			bit 0

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is clearedHS = Hardware set

bit 7 Unimplemented: Read as '0'

bit 6 ZCDIF: Zero-Cross Detect (ZCD1) Interrupt Flag bit

1 = An enabled rising and/or falling ZCD1 event has been detected (must be cleared in software)

0 = No ZCD1 event has occurred

bit 5-2 Unimplemented: Read as '0'

bit 1 C2IF: Comparator C2 Interrupt Flag bit

1 = Comparator 2 interrupt asserted (must be cleared in software)

0 = Comparator 2 interrupt not asserted

bit 0 C1IF: Comparator C1 Interrupt Flag bit

1 = Comparator 1 interrupt asserted (must be cleared in software)

0 = Comparator 1 interrupt not asserted

#### REGISTER 10-13: PIR3: PERIPHERAL INTERRUPT REQUEST REGISTER 3

R/HS-0/0	R/HS-0/0	R/HS-0/0	R/HS-0/0	R/W/HS-0/0	R/W/HS-0/0	R/W/HS-0/0	R/W/HS-0/0
RC2IF	TX2IF	RC1IF	TX1IF	BCL2IF	SSP2IF	BCL1IF	SSP1IF
bit 7	- 1			The second		1	bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HS = Hardware clearable

bit 7 RC2IF: EUSART2 Receive Interrupt Flag bit(1) 1 = The EUSART2 receive buffer is not empty (contains at least one byte) 0 = The EUSART2 receive buffer is empty TX2IF: EUSART2 Transmit Interrupt Flag bit(2) bit 6 1 = The EUSART2 transmit buffer contains at least one unoccupied space 0 = The EUSART2 transmit buffer is currently full. The application firmware must not write to TXxREG RC1IF: EUSART1 Receive Interrupt Flag bit (1) bit 5 1 = The EUSART1 receive buffer is not empty (contains at least one byte) 0 = The EUSART1 receive buffer is empty TX1IF: EUSART1 Transmit Interrupt Flag bit (2) bit 4 1 = The EUSART1 transmit buffer contains at least one unoccupied space 0 = The EUSART1 transmit buffer is currently full. The application firmware must not write to TXxREG. bit 3 BCL2IF: MSSP2 Bus Collision Interrupt Flag bit 1 = A bus collision was detected (must be cleared in software) 0 = No bus collision was detected bit 2 SSP2IF: MSSP2 Interrupt Flag bit 1 = The Transmission/Reception/Bus Condition is complete (must be cleared in software) 0 = Waiting for the Transmission/Reception/Bus Condition in progress bit 1 BCL1IF: MSSP1 Bus Collision Interrupt Flag bit 1 = A bus collision was detected (must be cleared in software) 0 = No bus collision was detected bit 0

SSP1IF: MSSP1 Interrupt Flag bit

1 = The Transmission/Reception/Bus Condition is complete (must be cleared in software)

0 = Waiting for the Transmission/Reception/Bus Condition in progress

Note 1: The RCxIF flag is a read-only bit. To clear the RCxIF flag, the firmware must read from RCxREG enough times to remove all bytes from the receive buffer.

2: The TXxIF flag is a read-only bit, indicating if there is room in the transmit buffer. To clear the TX1IF flag, the firmware must write enough data to TXxREG to completely fill all available bytes in the buffer. The TXxIF flag does not indicate transmit completion (use TRMT for this purpose instead).

#### REGISTER 10-14: PIR4: PERIPHERAL INTERRUPT REQUEST REGISTER 4

U-0	U-0	U-0	U-0	U-0	U-0	R/W/HS-0/0	R/W/HS-0/0
	_		-	_		TMR2IF	TMR1IF
bit 7	7	7		-03		10.	bit 0

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is clearedHS = Hardware set

bit 7-2 Unimplemented: Read as '0' bit 1 TRM2IF: Timer2 Interrupt Flag bit

1 = The TMR2 postscaler overflowed, or in 1:1 mode, a TMR2 to PR2 match occurred (must be cleared

in software)

0 = No TMR2 event has occurred

bit 0 TRM1IF: Timer1 Overflow Interrupt Flag bit

1 = Timer1 overflow occurred (must be cleared in software)

0 = No Timer1 overflow occurred

## REGISTER 10-15: PIR5: PERIPHERAL INTERRUPT REQUEST REGISTER 5

R/W/HS-0/0	R/W/HS-0/0	R/W/HS-0/0	R/W/HS-0/0	U-0	U-0	U-0	R/W/HS-0/0
CLC4IF	CLC3IF	CLC2IF	CLC1IF	_	2	-	TMR1GIF
bit 7 bit 0							

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HS = Hardware set

bit 7	CLC4IF: CLC4 Interrupt Flag bit
	<ul><li>1 = A CLC4OUT interrupt condition has occurred (must be cleared in software)</li><li>0 = No CLC4 interrupt event has occurred</li></ul>
bit 6	CLC3IF: CLC3 Interrupt Flag bit
	<ul><li>1 = A CLC3OUT interrupt condition has occurred (must be cleared in software)</li><li>0 = No CLC3 interrupt event has occurred</li></ul>
bit 5	CLC2IF: CLC2 Interrupt Flag bit
	<ul><li>1 = A CLC2OUT interrupt condition has occurred (must be cleared in software)</li><li>0 = No CLC2 interrupt event has occurred</li></ul>
bit 4	CLC1IF: CLC1 Interrupt Flag bit
	<ul><li>1 = A CLC1OUT interrupt condition has occurred (must be cleared in software)</li><li>0 = No CLC1 interrupt event has occurred</li></ul>
bit 3-1	Unimplemented: Read as '0'
bit 0	TMR1GIF: Timer1 Gate Interrupt Flag bit
	<ul><li>1 = The Timer1 Gate has gone inactive (the acquisition is complete)</li><li>0 = The Timer1 Gate has not gone inactive</li></ul>

## REGISTER 10-16: PIR6: PERIPHERAL INTERRUPT REQUEST REGISTER 6

U-0	U-0	U-0	U-0	U-0	U-0	R/W/HS-0/0	R/W/HS-0/0
				_	-	CCP2IF	CCP1IF
bit 7	×	e e	-			84	bit 0

Legend:

bit 0

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HS - Hardware set

bit 7-2 Unimplemented: Read as '0' bit 1 CCP2IF: CCP2 Interrupt Flag bit

Malara	CCPM Mode						
Value	Capture	Compare	PWM				
1	Capture occurred (must be cleared in software)	Compare match occurred (must be cleared in software)	Output trailing edge occurred (must be cleared in software)				
0	Capture did not occur	Compare match did not occur	Output trailing edge did not occur				

CCP1IF: CCP1 Interrupt Flag bit

	CCPM Mode						
Value	Capture	Compare	PWM				
1	Capture occurred (must be cleared in software)	Compare match occurred (must be cleared in software)	Output trailing edge occurred (must be cleared in software)				
0	Capture did not occur	Compare match did not occur	Output trailing edge did not occur				

#### REGISTER 10-17: PIR7: PERIPHERAL INTERRUPT REQUEST REGISTER 7

U-0	U-0	R/W/HS-0/0	R/W/HS-0/0	U-0	U-0	U-0	R/W/HS-0/0
<del></del>	10	NVMIF	NCO1IF	_	-	( <del>1</del>	CWG1IF
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HS = Hardware set

bit 7-6 Unimplemented: Read as '0' bit 5 NVMIF: Nonvolatile Memory (NVM) Interrupt Flag bit 1 = The requested NVM operation has completed 0 = NVM interrupt not asserted bit 4 NCO1IF: Numerically Controlled Oscillator (NCO) Interrupt Flag bit 1 = The NCO has rolled over 0 = No NCO interrupt event has occurred bit 3-1 Unimplemented: Read as '0' bit 0 CWG1IF: CWG1 Interrupt Flag bit 1 = CWG1 has gone into shutdown 0 = CWG1 is operating normally, or interrupt cleared

TABLE 10-1: SUMMARY OF REGISTERS ASSOCIATED WITH INTERRUPTS

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
INTCON	GIE	PEIE	-			_	_	INTEDG	121
PIE0	-	_	TMR0IE	IOCIE	_	-	_	INTE	122
PIE1	OSFIE	CSWIE	_	_	_	_	_	ADIE	123
PIE2	_	ZCDIE					C2IE	C1IE	124
PIE3	RC2IE	TX2IE	RC1IE	TX1IE	BCL2IE	SSP2IE	BCL1IE	SSP1IE	125
PIE4	_	_			_	-	TMR2IE	TMR1IE	126
PIE5	CLC4IE	CLC3IE	CLC2IE	CLC1IE			-	TMR1GIE	127
PIE6	-	-	_	-	-	-	CCP2IE	CCP1IE	128
PIE7	_	- 1	NVMIE	NCO1IE	- 1	-	_	CWG1IE	129
PIR0	_	-	TMR0IF	IOCIF	-	-	-	INTF	130
PIR1	OSFIF	CSWIF		2-2	_	-	=	ADIF	131
PIR2	<u> </u>	ZCDIF	_		_	-	C2IF	C1IF	132
PIR3	RC2IF	TX2IF	RC1IF	TX1IF	BCL2IF	SSP2IF	BCL1IF	SSP1IF	133
PIR4	_	_	_	_	-	_	TMR2IF	TMR1IF	134
PIR5	CLC4IF	CLC3IF	CLC2IF	CLC1IF	_	_	_	TMR1GIF	135
PIR6	_	_	— ·	-	_	-	CCP2IF	CCP1IF	136
PIR7	_	_	NVMIF	NCO1IF	-	_	-	CWG1IF	137

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by interrupts.


# 11.0 POWER-SAVING OPERATION MODES

The purpose of the Power-Down modes is to reduce power consumption. There are three Power-Down modes: Doze mode, Idle mode, and Sleep mode.

#### 11.1 Doze Mode

Doze mode saves power by reducing CPU execution and program memory access, without affecting peripheral operation. Doze mode differs from Sleep mode because the system oscillators continue to operate, while only the CPU and program memory are affected. The reduced execution saves power by eliminating unnecessary operations within the CPU and memory.

When the Doze Enable (DOZEN) bit is set (DOZEN = 1), the CPU executes only one instruction cycle out of every N cycles as defined by the DOZE<2:0> bits of the CPUDOZE register. For example, if DOZE<2:0> = 100, the instruction cycle ratio is 1:32. The CPU and memory execute for one instruction cycle and then lay Idle for 31 instruction cycles. During the unused cycles, the peripherals continue to operate at the system clock speed.



#### 11.1.1 DOZE OPERATION

The Doze operation is illustrated in Figure 11-1. For example, if ROI = 1 and DOZE<2:0> = '001', the instruction cycle ratio is 1:4. The CPU and memory operate for one instruction cycle and stay Idle for the next three instruction cycles.

As with normal operation, the program memory fetches for the next instruction cycle. The system clock to the peripherals continue throughout.

#### 11.1.2 INTERRUPTS DURING DOZE

If an interrupt occurs during Doze mode, system behavior can be configured using the Recover-On-Interrupt (ROI) bit and the Doze-On-Exit (DOE) bit. Refer to Table 11-1 for details about system behavior in all cases for a transition from Main to ISR back to Main.

TABLE 11-1: INTERRUPTS DURING DOZE

DOZEN	ROI	Code Flow							
		Main	ISR <sup>(1)</sup>	Return to Main					
0	0	Normal operation	Normal operation and DOE = DOZEN (in hardware) DOZEN = 0 (unchanged)						
0	1	Normal operation	Normal operation and DOE = DOZEN (in hardware) DOZEN = 0 (unchanged)	If DOE = 1 when return from interrupt:  If DOE = 0 when return from interrupt:					
1	0	Doze operation	Doze operation and DOE = DOZEN (in hardware) DOZEN = 1 (unchanged)	Doze operation and DOZEN = 1 (in hardware)  Normal operation and DOZEN = 0 (in hardware)					
1	1	Doze operation	Normal operation and DOE = DOZEN (in hardware) DOZEN = 0 (unchanged)						

Note 1: User software can change the DOE bit in the ISR.

## 11.2 Sleep Mode

Sleep mode is entered by executing the SLEEP instruction, while the Idle Enable (IDLEN) bit of the CPUDOZE register is clear (IDLEN = 0). If the SLEEP instruction is executed while the IDLEN bit is set (IDLEN = 1), the CPU will enter the Idle mode (Section 11.2.3 "Low-Power Sleep Mode").

Upon entering Sleep mode, the following conditions exist:

- WDT will be cleared but keeps running if enabled for operation during Sleep.
- 2. The PD bit of the STATUS register is cleared.
- 3. The TO bit of the STATUS register is set.
- 4. CPU Clock and System Clock.
- 31 kHz LFINTOSC, HFINTOSC and SOSC are unaffected and peripherals using them may continue operation in Sleep.
- ADC is unaffected if the dedicated FRC oscillator is selected the conversion will be left abandoned if FOSC is selected and ADRES will have an incorrect value.
- I/O ports maintain the status they had before Sleep was executed (driving high, low, or highimpedance). This does not apply in the case of any asynchronous peripheral which is active and may affect the I/O port value.
- Resets other than WDT are not affected by Sleep mode.

Refer to individual chapters for more details on peripheral operation during Sleep.

To minimize current consumption, consider the following conditions:

- I/O pins must not be floating
- External circuitry sinking current from I/O pins
- Internal circuitry sourcing current from I/O pins
- Current draw from pins with internal weak pull-ups
- Modules using any oscillator

I/O pins that are high-impedance inputs may be pulled to VDD or VSS externally to avoid switching currents caused by floating inputs.

Any module with a clock source that is not FOSC can be enabled. Examples of internal circuitry that might be sourcing current include modules such as the DAC and FVR modules. See Section 21.0 "5-Bit Digital-to-Analog Converter (DAC1) Module", Section 18.0 "Fixed Voltage Reference (FVR)" for more information on these modules.

#### 11.2.1 WAKE-UP FROM SLEEP

The device can wake-up from Sleep through one of the following events:

- External Reset input on MCLR pin, if enabled.
- 2. BOR Reset, if enabled.
- POR Reset.
- Watchdog Timer, if enabled.
- Any external interrupt.
- Interrupts by peripherals capable of running during Sleep (see individual peripheral for more information).

The first three events will cause a device Reset. The last three events are considered a continuation of program execution. To determine whether a device Reset or wake-up event occurred, refer to Section 8.12 "Memory Execution Violation".

When the SLEEP instruction is being executed, the next instruction (PC + 1) is prefetched. For the device to wake-up through an interrupt event, the corresponding interrupt enable bit must be enabled. Wake-up will occur regardless of the state of the GIE bit. If the GIE bit is disabled, the device continues execution at the instruction after the SLEEP instruction. If the GIE bit is enabled, the device executes the instruction after the SLEEP instruction after the SLEEP instruction, the device will then call the Interrupt Service Routine. In cases where the execution of the instruction following SLEEP is not desirable, the user may have a NOP after the SLEEP instruction.

The WDT is cleared when the device wakes-up from Sleep, regardless of the source of wake-up.


#### 11.2.2 WAKE-UP USING INTERRUPTS

When global interrupts are disabled (GIE cleared) and any interrupt source, with the exception of the clock switch interrupt, has both its interrupt enable bit and interrupt flag bit set, one of the following will occur:

- If the interrupt occurs before the execution of a SLEEP instruction
  - STEEP instruction will execute as a NOP
  - WDT and WDT prescaler will not be cleared
  - TO bit of the STATUS register will not be set
  - PD bit of the STATUS register will not be cleared
- If the interrupt occurs during or after the execution of a SLEEP instruction
  - SLEEP instruction will be completely executed
  - Device will immediately wake-up from Sleep
  - WDT and WDT prescaler will be cleared
  - TO bit of the STATUS register will be set
  - PD bit of the STATUS register will be cleared

Even if the flag bits were checked before executing a SLEEP instruction, it may be possible for flag bits to become set before the SLEEP instruction completes. To determine whether a SLEEP instruction executed, test





- Note 1: External clock. High, Medium, Low mode assumed.
  - 2: CLKOUT is shown here for timing reference.
  - : Tost = 1024 Tosc. This delay does not apply to EC and INTOSC Oscillator modes.
  - 4: GIE = 1 assumed. In this case after wake-up, the processor calls the ISR at 0004h. If GIE = 0, execution will continue in-line.

#### 11.2.3 LOW-POWER SLEEP MODE

The PIC16F15354/55 device contains an internal Low Dropout (LDO) voltage regulator, which allows the device I/O pins to operate at voltages up to 5.5V while the internal device logic operates at a lower voltage. The LDO and its associated reference circuitry must remain active when the device is in Sleep mode.

The PIC16F15354/55 allows the user to optimize the operating current in Sleep, depending on the application requirements.

Low-Power Sleep mode can be selected by setting the VREGPM bit of the VREGCON register. Depending on the configuration of these bits, the LDO and reference circuitry are placed in a low-power state when the device is in Sleep.

#### 11.2.3.1 Sleep Current vs. Wake-up Time

In the default operating mode, the LDO and reference circuitry remain in the normal configuration while in Sleep. The device is able to exit Sleep mode quickly since all circuits remain active. In Low-Power Sleep mode, when waking-up from Sleep, an extra delay time is required for these circuits to return to the normal configuration and stabilize.

The Low-Power Sleep mode is beneficial for applications that stay in Sleep mode for long periods of time. The Normal mode is beneficial for applications that need to wake from Sleep quickly and frequently.

#### 11.2.3.2 Peripheral Usage in Sleep

Some peripherals that can operate in Sleep mode will not operate properly with the Low-Power Sleep mode selected. The Low-Power Sleep mode is intended for use with these peripherals:

- Brown-out Reset (BOR)
- Watchdog Timer (WDT)
- External interrupt pin/interrupt-on-change pins
- Timer1 (with external clock source)

It is the responsibility of the end user to determine what is acceptable for their application when setting the VREGPM settings to ensure operation in Sleep.

Note: The PIC16LF15354/55 does not have a configurable Low-Power Sleep mode. PIC16LF15354/55 is an unregulated device and is always in the lowest power state when in Sleep, with no wake-up time penalty. This device has a lower maximum VDD and I/O voltage than the PIC16F15354/55. See Section 37.0 "Electrical Specifications" for more information.

#### 11.3 Idle Mode

When the Idle Enable (IDLEN) bit is clear (IDLEN = 0), the SLEEP instruction will put the device into full Sleep mode (see Section 11.2 "Sleep Mode"). When IDLEN is set (IDLEN = 1), the SLEEP instruction will put the device into Idle mode. In Idle mode, the CPU and memory operations are halted, but the peripheral clocks continue to run. This mode is similar to Doze mode, except that in Idle both the CPU and program memory are shut off.

Note:	Peripherals using Fos running while in Idle (b				
	Peripherals using	HFINTOSC,			
	LFINTOSC, or SOSC	will continue			
	running in both Idle and Sleep.				

Note:	If CLKOUT is enabled (CLKOUT = 0,
	Configuration Word 1), the output will
	continue operating while in Idle.

#### 11.3.1 IDLE AND INTERRUPTS

Idle mode ends when an interrupt occurs (even if GIE = 0), but IDLEN is not changed. The device can reenter Idle by executing the SLEEP instruction.

If Recover-on-Interrupt is enabled (ROI = 1), the interrupt that brings the device out of Idle also restores full-speed CPU execution when Doze mode is also enabled.

#### 11.3.2 IDLE AND WDT

When in Idle, the WDT Reset is blocked and will instead wake the device. The WDT wake-up is not an interrupt, therefore ROI does not apply.

The WDT can bring the device out of Idle,
in the same way it brings the device out of
Sleep. The DOZEN bit is not affected.

# 11.4 Register Definitions: Voltage Regulator and DOZE Control

# REGISTER 11-1: VREGCON: VOLTAGE REGULATOR CONTROL REGISTER<sup>(1)</sup>

U-0	U-0	U-0	U-0	U-0	U-0	R/W-0/0	U-1
-	·—	-	-	_	· <del></del> -	VREGPM	1 <del></del> >
bit 7	2	5 0	_	Š: Si		5	bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-2 Unimplemented: Read as '0'

bit 1 VREGPM: Voltage Regulator Power Mode Selection bit

1 = Low-Power Sleep mode enabled in Sleep<sup>(2)</sup> Draws lowest current in Sleep, slower wake-up

0 = Normal Power mode enabled in Sleep<sup>(2)</sup>
Draws higher current in Sleep, faster wake-up

bit 0 Unimplemented: Read as '1'. Maintain this bit set

Note 1: PIC16F15354/55 only.

2: See Section 37.0 "Electrical Specifications".

#### REGISTER 11-2: CPUDOZE: DOZE AND IDLE REGISTER

R/W-0/0	R/W/HC/HS-0/0	R/W-0/0	R/W/HS/HC-0/0	U-0	R/W-0/0	R/W-0/0	R/W-0/0
IDLEN	DOZEN <sup>(1)</sup>	ROI <sup>(1)</sup>	DOE <sup>(1)</sup>	14 <u>—</u> 81	DOZE<2:0>		
bit 7	ToPes		100				bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown
HC = Bit is cleared by hardware

'1' = Bit is set

'0' = Bit is cleared

HS = Bit is set by hardware

bit 7 IDLEN: Idle Enable bit 1 = A SLEEP instruction places the device into Idle mode 0 = A SLEEP instruction places the device into Sleep mode bit 6 DOZEN: Doze Enable bit 1 = Places the device into Doze mode 0 = Places the device into Normal mode bit 5 ROI: Recover-on-Interrupt bit 1 = Entering the Interrupt Service Routine (ISR) makes DOZEN = 0 0 = Entering the Interrupt Service Routine (ISR) does not change DOZEN bit 4 DOE: Doze on Exit bit 1 = Exiting the ISR makes DOZEN = 1 0 = Exiting the ISR does not change DOZEN bit 3 Unimplemented: Read as '0' bit 2-0 DOZE<2:0>: Ratio of CPU Instruction Cycles to Peripheral Instruction Cycles 111 =1:256 110 =1:128 101 =1:64 100 =1:32 011 =1:16 010 =1:8 001 =1:4 000 =1:2

Note 1: Refer to Table 11-1 for more details.

TABLE 11-2: SUMMARY OF REGISTERS ASSOCIATED WITH POWER-DOWN MODE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
STATUS	_	-	_	TO	PD	Z	DC	С	30
VREGCON				<del>!</del> :	-	-	VREGPM	8 <b>—</b> 8	143
CPUDOZE	IDLEN	DOZEN	ROI	DOE	<del>-</del>	DOZE<2:0>			144


Legend: — = unimplemented location, read as '0'. Shaded cells are not used in Power-Down mode.

# 12.0 WINDOWED WATCHDOG TIMER (WWDT)

The Watchdog Timer (WDT) is a system timer that generates a Reset if the firmware does not issue a CLRWDT instruction within the time-out period. The Watchdog Timer is typically used to recover the system from unexpected events. The Windowed Watchdog Timer (WWDT) differs in that CLRWDT instructions are only accepted when they are performed within a specific window during the time-out period.

The WDT has the following features:

- · Selectable clock source
- Multiple operating modes
  - WDT is always on
  - WDT is off when in Sleep
  - WDT is controlled by software
  - WDT is always off
- Configurable time-out period is from 1 ms to 256 seconds (nominal)
- Configurable window size from 12.5 to 100 percent of the time-out period
- · Multiple Reset conditions
- · Operation during Sleep



# 12.1 Independent Clock Source

The WDT can derive its time base from either the 31 kHz LFINTOSC or 31.25 kHz MFINTOSC internal oscillators, or the secondary oscillator SOSC, depending on the value of either the WDTCCS<2:0> Configuration bits or the WDTCS<2:0> bits of WDTCON1. Time intervals in this chapter are based on a minimum nominal interval of 1 ms. See Section 37.0 "Electrical Specifications" for LFINTOSC and MFINTOSC tolerances.

# 12.2 WDT Operating Modes

The Watchdog Timer module has four operating modes controlled by the WDTE<1:0> bits in Configuration Words. See Table 12-1.

#### 12.2.1 WDT IS ALWAYS ON

When the WDTE bits of Configuration Words are set to '11', the WDT is always on.

WDT protection is active during Sleep.

#### 12.2.2 WDT IS OFF IN SLEEP

When the WDTE bits of Configuration Words are set to '10', the WDT is on, except in Sleep.

WDT protection is not active during Sleep.

## 12.2.3 WDT CONTROLLED BY SOFTWARE

When the WDTE bits of Configuration Words are set to '01', the WDT is controlled by the SWDTEN bit of the WDTCON0 register.

# 12.2.4 WDT IS OFF

When the WDTE bits of the Configuration Word are set to '00', the WDT is always OFF.

WDT protection is unchanged by Sleep. See Table 12-1 for more details.

TABLE 12-1: WDT OPERATING MODES

WDTE<1:0>	SWDTEN	Device Mode	WDT Mode	
11	Х	Χ	Active	
10		Awake	Active	
10	Х	Sleep	Disabled	
01	1	X	Active	
01	0	Χ	Disabled	
00	Х	Х	Disabled	

## 12.3 Time-Out Period

The WDTPS bits of the WDTCON0 register set the time-out period from 1 ms to 256 seconds (nominal). After a Reset, the default time-out period is two seconds.

# 12.4 Watchdog Window

The Watchdog Timer has an optional Windowed mode that is controlled by the WDTCWS<2:0> Configuration bits and WINDOW<2:0> bits of the WDTCON1 register. In the Windowed mode, the CLRWDT instruction must occur within the allowed window of the WDT period. Any CLRWDT instruction that occurs outside of this window will trigger a window violation and will cause a WDT Reset, similar to a WDT time out. See Figure 12-2 for an example.

The window size is controlled by the WDTCWS<2:0> Configuration bits, or the WINDOW<2:0> bits of WDTCON1, if WDTCWS<2:0> = 111.

In the event of a  $\underline{\text{window}}$  violation, a Reset will be generated and the  $\overline{\text{WDTWV}}$  bit of the PCON register will be cleared. This bit is set by a POR or can be set in firmware.

# 12.5 Clearing the WDT

The WDT is cleared when any of the following conditions occur:

- Any Reset
- Valid CLRWDT instruction is executed
- · Device enters Sleep
- · Device wakes up from Sleep
- · WDT is disabled

- Oscillator Start-up Timer (OST) is running
- · Any write to the WDTCON0 or WDTCON1 registers

# 12.5.1 CLRWDT CONSIDERATIONS (WINDOWED MODE)

When in Windowed mode, the WDT must be armed before a CLRWDT instruction will clear the timer. This is performed by reading the WDTCON0 register. Executing a CLRWDT instruction without performing such an arming action will trigger a window violation.

See Table 12-2 for more information.

# 12.6 Operation During Sleep

When the device enters Sleep, the WDT is cleared. If the WDT is enabled during Sleep, the WDT resumes counting. When the device exits Sleep, the WDT is cleared again.


The WDT remains clear until the OST, if enabled, completes. See Section 9.0 "Oscillator Module (with Fail-Safe Clock Monitor)" for more information on the OST.

When a WDT time-out occurs while the device is in Sleep, no Reset is generated. Instead, the device wakes up and resumes operation. The TO and PD bits in the STATUS register are changed to indicate the event. The RWDT bit in the PCON register can also be used. See Section 4.3.2.1 "STATUS Register" for more information.

TABLE 12-2: WDT CLEARING CONDITIONS

Conditions	WDT
WDTE<1:0> = 00	
WDTE<1:0> = 01 and SWDTEN = 0	
WDTE<1:0> = 10 and enter Sleep	
CLRWDT Command	Cleared
Oscillator Fail Detected	
Exit Sleep + System Clock = SOSC, EXTOSC, INTOSC	
Change INTOSC divider (IRCF bits)	Unaffected

#### FIGURE 12-2: WINDOW PERIOD AND DELAY



# 12.7 Register Definitions: Windowed Watchdog Timer Control

#### REGISTER 12-1: WDTCON0: WATCHDOG TIMER CONTROL REGISTER 0

U-0	U-0	R/W <sup>(3)</sup> -q/q <sup>(2)</sup>	R/W-0/0					
: <u></u>	-		WDTPS<4:0>(1)					
bit 7							bit 0	

 Legend:
 V = Writable bit
 U = Unimplemented bit, read as '0'

 u = Bit is unchanged
 x = Bit is unknown
 -n/n = Value at POR and BOR/Value at all other Resets

 '1' = Bit is set
 '0' = Bit is cleared
 q = Value depends on condition

bit 7-6 Unimplemented: Read as '0' WDTPS<4:0>: Watchdog Timer Prescale Select bits(1) bit 5-1 Bit Value = Prescale Rate 11111 =Reserved. Results in minimum interval (1:32) 10011 =Reserved. Results in minimum interval (1:32) 10010 =1:8388608 (2<sup>23</sup>) (Interval 256s nominal) 10001 =1:4194304 (2<sup>22</sup>) (Interval 128s nominal) 10000 =1:2097152 (2<sup>21</sup>) (Interval 64s nominal) 01111 =1:1048576 (2<sup>20</sup>) (Interval 32s nominal) 01110 =1:524288 (2<sup>19</sup>) (Interval 16s nominal) 01101 =1:262144 (2<sup>18</sup>) (Interval 8s nominal) 01100 =1:131072 (2<sup>17</sup>) (Interval 4s nominal) 01011 =1:65536 (Interval 2s nominal) (Reset value) 01010 =1:32768 (Interval 1s nominal) 01001 =1:16384 (Interval 512 ms nominal) 01000 =1:8192 (Interval 256 ms nominal) 00111 =1:4096 (Interval 128 ms nominal) 00110 =1:2048 (Interval 64 ms nominal) 00101 =1:1024 (Interval 32 ms nominal) 00100 =1:512 (Interval 16 ms nominal) 00011 =1:256 (Interval 8 ms nominal) 00010 =1:128 (Interval 4 ms nominal) 00001 =1:64 (Interval 2 ms nominal) 00000 =1:32 (Interval 1 ms nominal) bit 0 SWDTEN: Software Enable/Disable for Watchdog Timer bit If WDTE<1:0> = 1x: This bit is ignored. If WDTE<1:0> = 01: 1 = WDT is turned on 0 = WDT is turned off If WDTE<1:0> = 00: This bit is ignored.

Note 1: Times are approximate. WDT time is based on 31 kHz LFINTOSC.

- 2: When WDTCPS <4:0> in CONFIG3 = 11111, the Reset value of WDTPS<4:0> is 01011. Otherwise, the Reset value of WDTPS<4:0> is equal to WDTCPS<4:0> in CONFIG3.
- 3: When WDTCPS <4:0> in CONFIG3 ≠ 111111, these bits are read-only.

# REGISTER 12-2: WDTCON1: WATCHDOG TIMER CONTROL REGISTER 1

U-0	$R/W^{(3)}-q/q^{(1)}$ $R/W^{(3)}-q/q^{(1)}$ $R/W^{(3)}-q/q^{(1)}$	U-0	R/W <sup>(4)</sup> -q/q <sup>(2)</sup>	R/W <sup>(4)</sup> -q/q <sup>(2)</sup>	R/W <sup>(4)</sup> -q/q <sup>(2)</sup>
<u></u>	WDTCS<2:0>	_			
bit 7			•		bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared q = Value depends on condition

bit 7 Unimplemented: Read as '0'

bit 6-4 WDTCS<2:0>: Watchdog Timer Clock Select bits

111 = Reserved

•

010 =SOSC 32 kHz

001 =MFINTOSC 31.25 kHz

000 =LFINTOSC 31 kHz

bit 3 Unimplemented: Read as '0'

bit 2-0 WINDOW<2:0>: Watchdog Timer Window Select bits

WINDOW<2:0>	Window delay Percent of time	Window opening Percent of time		
111	N/A	100		
110	12.5	87.5		
101	25	75		
100	37.5	62.5		
011	50	50		
010	62.5	37.5		
001	75	25		
000	87.5	12.5		

Note 1: If WDTCCS <2:0> in CONFIG3 = 111, the Reset value of WDTCS<2:0> is 000.

2: The Reset value of WINDOW<2:0> is determined by the value of WDTCWS<2:0> in the CONFIG3 register.

3: If WDTCCS<2:0> in CONFIG3 ≠ 111, these bits are read-only.

4: If WDTCWS<2:0> in CONFIG3 # 111, these bits are read-only.

## REGISTER 12-3: WDTPSL: WDT PRESCALE SELECT LOW BYTE REGISTER

R-0/0	R-0/0	R-0/0	R-0/0	R-0/0	R-0/0	R-0/0	R-0/0			
PSCNT<7:0>(1)										
bit 7	POLITICAL PROPERTY AND ADMINISTRATION ADMINISTRATION ADMINISTRATION AND ADMINISTRATION AND ADMINISTRATION AND ADMINISTRATION AND ADMINISTRATION AND ADMINISTRATION AN									

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 PSCNT<7:0>: Prescale Select Low Byte bits(1)

Note 1: The 18-bit WDT prescale value, PSCNT<17:0>, includes the WDTPSL, WDTPSH, and the lower bits of the WDTTMR registers. PSCNT<17:0> is intended for debug operations and must be read during normal operation.

## REGISTER 12-4: WDTPSH: WDT PRESCALE SELECT HIGH BYTE REGISTER

R-0/0	R-0/0	R-0/0	R-0/0	R-0/0	R-0/0	R-0/0	R-0/0		
PSCNT<15:8>(1)									
bit 7									

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 PSCNT<15:8>: Prescale Select High Byte bits<sup>(1)</sup>

Note 1: The 18-bit WDT prescale value, PSCNT<17:0>, includes the WDTPSL, WDTPSH, and the lower bits of the WDTTMR registers. PSCNT<17:0> is intended for debug operations and must be read during normal operation.

# REGISTER 12-5: WDTTMR: WDT TIMER REGISTER

U-0	R-0/0	R-0/0	R-0/0	R-0/0	R-0/0	R-0/0	R-0/0
<u></u> -		WDTTMR<3:0>				PSCNT<	17:16> <sup>(1)</sup>
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 Unimplemented: Read as '0'

bit 6-3 WDTTMR<3:0>: Watchdog Timer Value bits

bit 2 STATE: WDT Armed Status bit

1 = WDT is armed 0 = WDT is not armed

bit 1-0 PSCNT<17:16>: Prescale Select Upper Byte bits<sup>(1)</sup>

Note 1: The 18-bit WDT prescale value, PSCNT<17:0>, includes the WDTPSL, WDTPSH, and the lower bits of the WDTTMR registers. PSCNT<17:0> is intended for debug operations and must be read during normal operation.

TABLE 12-3: SUMMARY OF REGISTERS ASSOCIATED WITH WATCHDOG TIMER

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
OSCCON1	-	1	NOSC<2:0>				110		
OSCCON2	-	(	COSC<2:0>			CDIV<	3:0>		110
OSCCON3	CSWHOLD	SOSCPWR	_	ORDY	NOSCR	A		·—	111
PCON0	STKOVF	STKUNF	WDTWV	RWDT	RMCLR	RI	POR	BOR	99
STATUS	-	_	_	TO	PD	Z	DC	С	30
WDTCON0	_	-	50 S		WDTPS<4:0	)>		SWDTEN	150
WDTCON1	2.0	V	VDTCS<2:0>	3	_	WI	NDOW<2:0	>	151
WDTPSL		•		PSCN	IT<7:0>				152
WDTPSH		PSCNT<15:8>							
WDTTMR	5 ST - 5		WDTTM	R<4:0>	4	STATE	PSCNT	<17:16>	152

**Legend:** – = unimplemented locations read as '0'. Shaded cells are not used by Watchdog Timer.

TABLE 12-4: SUMMARY OF CONFIGURATION WORD WITH WATCHDOG TIMER

Name	Bits	Bit -/7	Bit -/6	Bit 13/5	Bit 12/4	Bit 11/3	Bit 10/2	Bit 9/1	Bit 8/0	Register on Page
CONFICA	13:8	-	19 <del></del>	FCMEN	_	CSWEN	-	-	CLKOUTEN	76
CONFIG1			RSTOSC<2:0	>		FEXTOSC<2:0>			76	

Legend: — = unimplemented location, read as '0'. Shaded cells are not used by Watchdog Timer.

# 13.0 NONVOLATILE MEMORY (NVM) CONTROL

NVM consists of the Program Flash Memory.

NVM is accessible by using both the FSR and INDF registers, or through the NVMREG register interface.

The write time is controlled by an on-chip timer. The write/erase voltages are generated by an on-chip charge pump rated to operate over the operating voltage range of the device.

NVM can be protected in two ways; by either code protection or write protection.

Code protection ( $\overline{\text{CP}}$  bit in Configuration Word 5) disables access, reading and writing, to the program memory via external device programmers. Code protection does not affect the self-write and erase functionality. Code protection can only be Reset by a device programmer performing a Bulk Erase to the device, clearing all nonvolatile memory, Configuration bits, and User IDs.

Write protection prohibits self-write and erase to a portion or all of the program memory, as defined by the WRT<1:0> bits of Configuration Word 4. Write protection does not affect a device programmer's ability to read, write, or erase the device.

# 13.1 Program Flash Memory

The program memory consists of an array of 14-bit words as user memory, with additional words for User ID information, Configuration words, and interrupt vectors. The program memory provides storage locations for:

- User program instructions
- · User defined data

Program memory data can be read and/or written to through:

- CPU instruction fetch (read-only)
- FSR/INDF indirect access (read-only) (Section 13.2 "FSR and INDF Access")
- NVMREG access (Section 13.3 "NVMREG Access"
- In-Circuit Serial Programming™ (ICSP™)

Read operations return a single word of memory. When write and erase operations are done on a row basis, the row size is defined in Table 13-1. Program memory will erase to a logic '1' and program to a logic '0'.

TABLE 13-1: FLASH MEMORY ORGANIZATION BY DEVICE

Device	Row Erase (words)	Write Latches (words)	Total Program Flash (words)
PIC16(L)F15354	22	22	4096
PIC16(L)F15355	32	32	8192

It is important to understand the program memory structure for erase and programming operations. The program memory is arranged in rows. A row consists of 32 14-bit program memory words. A row is the minimum size that can be erased by user software.

All or a portion of a row can be programmed. Data to be written into the program memory row is written to 14-bit wide data write latches. These latches are not directly accessible, but may be loaded via sequential writes to the NVMDATH:NVMDATL register pair.

Note: To modify only a portion of a previously programmed row, the contents of the entire row must be read. Then, the new data and retained data can be written into the write latches to reprogram the row of program memory. However, any unprogrammed locations can be written without first erasing the row. In this case, it is not necessary to save and rewrite the other previously programmed locations

# 13.1.1 PROGRAM MEMORY VOLTAGES

The program memory is readable and writable during normal operation over the full VDD range.

#### 13.1.1.1 Programming Externally

The program memory cell and control logic support write and Bulk Erase operations down to the minimum device operating voltage. Special BOR operation is enabled during Bulk Erase (Section 8.2.4 "BOR is always OFF").

#### 13.1.1.2 Self-programming

The program memory cell and control logic will support write and row erase operations across the entire VDD range. Bulk Erase is not available when self-programming.

#### 13.2 FSR and INDF Access

The FSR and INDF registers allow indirect access to the program memory.

#### 13.2.1 FSR READ

With the intended address loaded into an FSR register a MOVIW instruction or read of INDF will read data from the program memory.

Reading from NVM requires one instruction cycle. The CPU operation is suspended during the read, and resumes immediately after. Read operations return a single byte of memory.

## 13.2.2 FSR WRITE

Writing/erasing the NVM through the FSR registers (ex. MOVWI instruction) is not supported in the PIC16(L)F15354/55 devices.

## 13.3 NVMREG Access

The NVMREG interface allows read/write access to all the locations accessible by FSRs, and also read/write access to the User ID locations, and read-only access to the device identification, revision, and Configuration data.

Writing or erasing of NVM via the NVMREG interface is prevented when the device is write-protected.

# 13.3.1 NVMREG READ OPERATION

To read a NVM location using the NVMREG interface, the user must:


- Clear the NVMREGS bit of the NVMCON1 register if the user intends to access the program memory locations, or set NMVREGS if the user intends to access User ID, or Configuration locations.
- Write the desired address into the NVMADRH:NVMADRL register pair (Table 13-2).
- Set the RD bit of the NVMCON1 register to initiate the read.

Once the read control bit is set, the CPU operation is suspended during the read, and resumes immediately after. The data is available in the very next cycle, in the NVMDATH:NVMDATL register pair; therefore, it can be read as two bytes in the following instructions.

NVMDATH:NVMDATL register pair will hold this value until another read or until it is written to by the user.

Upon completion, the RD bit is cleared by hardware.

FIGURE 13-1: FLASH PROGRAM MEMORY READ FLOWCHART



# **EXAMPLE 13-1: PROGRAM MEMORY READ**

```
* This code block will read 1 word of program
* memory at the memory address:
   PROG ADDR HI : PROG ADDR LO
  data will be returned in the variables;
  PROG DATA HI, PROG DATA LO
   BANKSELNVMADRL; Select Bank for NVMCON registers
   MOVLWPROG ADDR LO;
   MOVWFNVMADRL; Store LSB of address
   MOVLWPROG ADDR HI;
   MOVWFNVMADRH; Store MSB of address
   BCF NVMCON1, NVMREGS; Do not select Configuration Space
   BSF NVMCON1, RD; Initiate read
   MOVFNVMDATL, W; Get LSB of word
   MOVWFPROG DATA LO; Store in user location
   MOVFNVMDATH, W; Get MSB of word
   MOVWFPROG_DATA_HI; Store in user location
```

#### 13.3.2 NVM UNLOCK SEQUENCE

The unlock sequence is a mechanism that protects the NVM from unintended self-write programming or erasing. The sequence must be executed and completed without interruption to successfully complete any of the following operations:

- · Program memory Row Erase
- · Load of program memory write latches
- Write of program memory write latches to program memory
- Write of program memory write latches to User IDs

The unlock sequence consists of the following steps and must be completed in order:


- Write 55h to NVMCON2
- Write AAh to NMVCON2
- Set the WR bit of NVMCON1

Once the WR bit is set, the processor will stall internal operations until the operation is complete and then resume with the next instruction.

Note: The two NOP instructions after setting the WR bit that were required in previous devices are not required for PIC16(L)F15354/55 devices. See Figure 13-2.

Since the unlock sequence must not be interrupted, global interrupts must be disabled prior to the unlock sequence and re-enabled after the unlock sequence is completed.

# FIGURE 13-2: NVM UNLOCK SEQUENCE FLOWCHART



# **EXAMPLE 13-2: NVM UNLOCK SEQUENCE**

BCF INTCON, GIE; Recommended so sequence is not interrupted BANKSELNVMCON1;
BSF NVMCON1, WREN; Enable write/erase
MOVLW55h; Load 55h
MOVWFNVMCON2; Step 1: Load 55h into NVMCON2
MOVLWAAh; Step 2: Load W with AAh
MOVWFNVMCON2; Step 3: Load AAH into NVMCON2
BSF NVMCON1, WR; Step 4: Set WR bit to begin write/erase
BSF INTCON, GIE; Re-enable interrupts

- Note 1: Sequence begins when NVMCON2 is written; steps 1-4 must occur in the cycle-accurate order shown.
  - 2: Opcodes shown are illustrative; any instruction that has the indicated effect may be used.

# 13.3.3 NVMREG ERASE OF PROGRAM MEMORY

Before writing to program memory, the word(s) to be written must be erased or previously unwritten. The program memory can only be erased one row at a time. No automatic erase occurs upon the initiation of the write to program memory.

To erase a program memory row:


- Clear the NVMREGS bit of the NVMCON1 register to erase program memory locations, or set the NMVREGS bit to erase User ID locations.
- Write the desired address into the NVMADRH:NVMADRL register pair (Table 13-2).
- Set the FREE and WREN bits of the NVMCON1 register.
- Perform the unlock sequence as described in Section 13.3.2 "NVM Unlock Sequence".

If the program memory address is write-protected, the WR bit will be cleared and the erase operation will not take place.

While erasing the program memory, CPU operation is suspended, and resumes when the operation is complete. Upon completion, the NVMIF is set, and an interrupt will occur if the NVMIE bit is also set.

Write latch data is not affected by erase operations, and WREN will remain unchanged.

FIGURE 13-3: NVM ERASE FLOWCHART



# EXAMPLE 13-3: ERASING ONE ROW OF PROGRAM FLASH MEMORY (PFM)

; This sample row erase routine assumes the following: ; 1.A valid address within the erase row is loaded in variables ADDRH: ADDRL ; 2.ADDRH and ADDRL are located in common RAM (locations 0x70 - 0x7F) BANKSEL NVMADRL MOVE ADDRL, W MOVWF NVMADRL ; Load lower 8 bits of erase address boundary MOVF ADDRH, W MOVWF NVMADRH ; Load upper 6 bits of erase address boundary ; Choose PFM memory area BCF NVMCON1, NVMREGS BSF NVMCON1, FREE ; Specify an erase operation NVMCON1, WREN BSF ; Enable writes BCF INTCON, GIE ; Disable interrupts during unlock sequence ; ------REQUIRED UNLOCK SEQUENCE:-----MOVLW ; Load 55h to get ready for unlock sequence MOVWF NVMCON2 ; First step is to load 55h into NVMCON2 ; Second step is to load AAh into W W.TVOM AAh MOVWF NVMCON2 ; Third step is to load AAh into NVMCON2 NVMCON1, WR BSF ; Final step is to set WR bit BSF INTCON, GIE ; Re-enable interrupts, erase is complete NVMCON1, WREN ; Disable writes BCF

#### TABLE 13-2: NVM ORGANIZATION AND ACCESS INFORMATION

	Host Values		N	NVMREG Acce	FSR Access			
Memory Function	Program Counter (PC), ICSP™ Address	Memory Type	NVMREGS bit (NVMCON1)	NVMADR< 14:0>	Allowed Operations	FSR Address	FSR Programming Address	
Reset Vector	0000h		0	0000h		8000h		
Hara Mariana	0001h	Ì	0	0001h		8001h		
User Memory	0003h	D	0	0003h	Read Write	8003h	Read-0nly	
INT Vector	0004h	Program Flash Memory	0	0004h		8004h		
	0005h	Welliory		0005h	vviite	8005h		
User Memory	0FFFh <sup>(1)</sup>	Ī	0	0FFFh		8FFFh		
	1FFFh <sup>(2)</sup>			1FFFh		9FFFh	2	
Heer ID	8000h	Program Flash Memory	2 C C C C C C C C C C C C C C C C C C C	0000h	Read			
User ID	8003h			0003h	Write			
Reserved	8004h	1 <del>1 12</del>	:=	0004h	_			
Rev ID	8005h		1	0005h	Danid Only			
Device ID	8006h		1	0006h	Read-Only	No	Access	
CONFIG1	8007h		1	0007h		INO	Access	
CONFIG2	8008h	Program Flash Memory	1	0008h	I E I I			
CONFIG3	8009h	ivientory	1	0009h	Read Write			
CONFIG4	800Ah	1	1	000Ah	VVIICE			
CONFIG5	800Bh	1	1	000Bh				
DIA and DCI	8100h-82FFh	Program Flash Memory and Hard coded	1	0100h- 02FFh	Read-Only	No	Access	

Note 1: PIC16(L)F15354 only. 2: PIC16(L)F15355 only.

# 13.3.4 NVMREG WRITE TO PROGRAM MEMORY

Program memory is programmed using the following steps:

- Load the address of the row to be programmed into NVMADRH:NVMADRL.
- 2. Load each write latch with data.
- 3. Initiate a programming operation.
- Repeat steps 1 through 3 until all data is written.

Before writing to program memory, the word(s) to be written must be erased or previously unwritten. Program memory can only be erased one row at a time. No automatic erase occurs upon the initiation of the write.

Program memory can be written one or more words at a time. The maximum number of words written at one time is equal to the number of write latches. See Figure 13-4 (row writes to program memory with 32 write latches) for more details.

The write latches are aligned to the Flash row address boundary defined by the upper ten bits of NVMADRH:NVMADRL, (NVMADRH<6:0>:NVMADRL<7:5>) with the lower five bits of NVMADRL, (NVMADRL<4:0>) determining the write latch being loaded. Write operations do not cross these boundaries. At the completion of a program memory write operation, the data in the write latches is reset to contain 0x3FFF.


The following steps must be completed to load the write latches and program a row of program memory. These steps are divided into two parts. First, each write latch is loaded with data from the NVMDATH:NVMDATL using the unlock sequence with LWLO = 1. When the last word to be loaded into the write latch is ready, the LWLO bit is cleared and the unlock sequence executed. This initiates the programming operation, writing all the latches into Flash program memory.

Note: The special unlock sequence is required to load a write latch with data or initiate a Flash programming operation. If the unlock sequence is interrupted, writing to the latches or program memory will not be initiated.


- Set the WREN bit of the NVMCON1 register.
- Clear the NVMREGS bit of the NVMCON1 register.
- Set the LWLO bit of the NVMCON1 register. When the LWLO bit of the NVMCON1 register is '1', the write sequence will only load the write latches and will not initiate the write to Flash program memory.
- Load the NVMADRH:NVMADRL register pair with the address of the location to be written.
- Load the NVMDATH:NVMDATL register pair with the program memory data to be written.
- Execute the unlock sequence (Section 13.3.2 "NVM Unlock Sequence"). The write latch is now loaded.
- Increment the NVMADRH:NVMADRL register pair to point to the next location.
- Repeat steps 5 through 7 until all but the last write latch has been loaded.
- Clear the LWLO bit of the NVMCON1 register. When the LWLO bit of the NVMCON1 register is '0', the write sequence will initiate the write to Flash program memory.
- Load the NVMDATH:NVMDATL register pair with the program memory data to be written.
- Execute the unlock sequence (Section 13.3.2
   "NVM Unlock Sequence"). The entire program
   memory latch content is now written to Flash
   program memory.

Note: The program memory write latches are reset to the blank state (0x3FFF) at the completion of every write or erase operation. As a result, it is not necessary to load all the program memory write latches. Unloaded latches will remain in the blank state.

An example of the complete write sequence is shown in Example 13-4. The initial address is loaded into the NVMADRH:NVMADRL register pair; the data is loaded using indirect addressing.



PIC16(L)F15354/55



# **EXAMPLE 13-4: WRITING TO PROGRAM FLASH MEMORY**


```
; This write routine assumes the following:
; 1. 64 bytes of data are loaded, starting at the address in DATA ADDR
; 2. Each word of data to be written is made up of two adjacent bytes in DATA ADDR,
     stored in little endian format
; 3. A valid starting address (the least significant bits = 00000) is loaded in ADDRH:ADDRL
; 4. ADDRH and ADDRL are located in common RAM (locations 0x70 - 0x7F)
; 5. NVM interrupts are not taken into account
       BANKSEL
                     NVMADRH
       MOVF
                     ADDRH, W
       MOVWF
                     NVMADRH
                                              ; Load initial address
       MOVF
                     ADDRL, W
       MOVWF
                     NVMADRI.
                                              ; Load initial data address
                     LOW DATA ADDR
       MOVLW
       MOVWF
                      FSR0L
       MOVLW
                      HIGH DATA ADDR
       MOVWF
                     FSR0H
       BCF
                                             ; Set Program Flash Memory as write location
                     NVMCON1, NVMREGS
       BSF
                     NVMCON1, WREN
                                             ; Enable writes
                     NVMCON1, LWLO
                                             ; Load only write latches
       BSF
LOOP
       MOVIW
                     FSR0++
       MOVWF
                      NVMDATL
                                              ; Load first data byte
       MOVIW
                      FSR0++
       MOVWF
                      NVMDATH
                                              ; Load second data byte
       MOVE
                      NVMADRL, W
                                              ; Check if lower bits of address are 00000
       XORLW
                      0x1F
                                              ; and if on last of 32 addresses
                      0x1F
       ANDLW
                      STATUS, Z
                                              ; Last of 32 words?
       BTFSC
       GOTO
                      START WRITE
                                             ; If so, go write latches into memory
                      UNLOCK_SEQ
       CALL
                                             ; If not, go load latch
        INCF
                      NVMADRL, F
                                              ; Increment address
       GOTO
                      LOOP
START WRITE
       BCF
                      NVMCON1, LWLO
                                             ; Latch writes complete, now write memory
       CALL
                      UNLOCK SEQ
                                              ; Perform required unlock sequence
       BCF
                      NVMCON1, WREN
                                              ; Disable writes
UNLOCK SEQ
       MOVLW
                      55h
                                             ; Disable interrupts
       BCF
                      INTCON, GIE
                     NVMCON2
       MOVWF
                                              ; Begin unlock sequence
       MOVLW
                      AAh
       MOVWF
                      NVMCON2
       BSF
                      NVMCON1, WR
       BSF
                      INTCON, GIE
                                              ; Unlock sequence complete, re-enable interrupts
       return
```

# 13.3.5 MODIFYING FLASH PROGRAM MEMORY

When modifying existing data in a program memory row, and data within that row must be preserved, it must first be read and saved in a RAM image. Program memory is modified using the following steps:

- Load the starting address of the row to be modified.
- Read the existing data from the row into a RAM image.
- Modify the RAM image to contain the new data to be written into program memory.
- Load the starting address of the row to be rewritten.
- 5. Erase the program memory row.
- Load the write latches with data from the RAM image.
- 7. Initiate a programming operation.

FIGURE 13-6: FLASH PROGRAM MEMORY MODIFY FLOWCHART



13.3.6 NVMREG ACCESS TO DEVICE INFORMATION AREA, DEVICE CONFIGURATION AREA, USER ID, DEVICE ID AND CONFIGURATION WORDS

NVMREGS can be used to access the following memory regions:

- · Device Information Area (DIA)
- · Device Configuration Information (DCI)
- User ID region
- · Device ID and Revision ID
- Configuration Words

The value of NVMREGS is set to '1' in the NVMCON1 register to access these regions. The memory regions listed above would be pointed to by PC<15> = 1, but not all addresses reference valid data. Different access may exist for reads and writes. Refer to Table 13-3.

When read access is initiated on an address outside the parameters listed in Table 13-3, the NVMDATH: NVMDATL register pair is cleared, reading back '0's.

TABLE 13-3: NVMREGS ACCESS TO DEVICE INFORMATION AREA, DEVICE CONFIGURATION AREA, USER ID, DEVICE ID AND CONFIGURATION WORDS (NVMREGS = 1)

Address	Function	Read Access	Write Access	
8000h-8003h	User IDs	Yes	Yes	
8005h-8006h	Device ID/Revision ID	Yes	No	
8007h-800Bh	Configuration Words 1-5	Yes	No	
8100h-82FFh	DIA and DCI	Yes	No	


## **EXAMPLE 13-5: DEVICE ID ACCESS**

```
; This write routine assumes the following:
; 1. A full row of data are loaded, starting at the address in DATA_ADDR
; 2. Each word of data to be written is made up of two adjacent bytes in DATA_ADDR,
; stored in little endian format
; 3. A valid starting address (the least significant bits = 00000) is loaded in ADDRH: ADDRL
; 4. ADDRH and ADDRL are located in common RAM (locations 0x70 - 0x7F)
; 5. NVM interrupts are not taken into account
          BANKSEL
                               NVMADRH
          MOVE
                               ADDRH, W
          MOVWF
                               NVMADRH
                                                      ; Load initial address
          MOVE
                              ADDRL, W
          MOVWF
                              NVMADRL
          MOVLW
                              LOW DATA ADDR
                                                      ; Load initial data address
          MOVWF
                               FSR0L
                              HIGH DATA ADDR
          MOVLW
          MOVWF
                              FSR0H
                                                      ; Set PFM as write location
          BCF
                              NVMCON1.NVMREGS
          BSF
                               NVMCON1, WREN
                                                      ; Enable writes
          BSF
                               NVMCON1, LWLO
                                                      ; Load only write latches
LOOP
          MOVIW
                               FSR0++
                               NVMDATL
                                                      ; Load first data byte
          MOVIW
                               FSR0++
          MOVWF
                               NVMDATH
                                                      ; Load second data byte
                               UNLOCK SEQ
                                                      ; If not, go load latch
          CALL
          INCE
                               NVMADRL, F
                                                      ; Increment address
          MOVE
                               NVMADRL, W
          XORT-W
                               0x1F
                                                      ; Check if lower bits of address are 00000
                                                      ; and if on last of 32 addresses
          ANDLW
                               0x1F
          BTFSC
                               STATUS, Z
                                                      ; Last of 32 words?
          GOTO
                               START WRITE
                                                      ; If so, go write latches into memory
                               TOOP
          GOTO
START WRITE
          BCF
                               NVMCON1, LWLO
                                                      ; Latch writes complete, now write memory
                               UNLOCK SEQ
                                                      ; Perform required unlock sequence
          CALL
          BCF
                               NVMCON1, LWLO
                                                      ; Disable writes
UNLOCK SEQ
          MOVLW
                              55h
          BCF
                               INTCON.GIE
                                                     ; Disable interrupts
                               NVMCON2
          MOVWF
                                                      ; Begin unlock sequence
          MOVLW
                              AAh
          MOVWF
                              NVMCON2
          BSF
                               NVMCON1, WR
          BSF
                               INTCON, GIE
                                                      ; Unlock sequence complete, re-enable interrupts
          return
```

## 13.3.7 WRITE VERIFY

It is considered good programming practice to verify that program memory writes agree with the intended value. Since program memory is stored as a full row then the stored program memory contents are compared with the intended data stored in RAM after the last write is complete.

FIGURE 13-7: FLASH PROGRAM MEMORY VERIFY FLOWCHART



## 13.3.8 WRERR BIT

The WRERR bit can be used to determine if a write error occurred.

WRERR will be set if one of the following conditions occurs:

- If WR is set while the NVMADRH:NMVADRL points to a write-protected address
- A Reset occurs while a self-write operation was in progress
- An unlock sequence was interrupted

The WRERR bit is normally set by hardware, but can be set by the user for test purposes. Once set, WRERR must be cleared in software.

TABLE 13-4: ACTIONS FOR PFM WHEN WR = 1

Free	LWLO	Actions for PFM when WR = 1	Comments
1	х	Erase the 32-word row of NVMADRH:NVMADRL location. See Section 13.3.3 "NVMREG Erase of Program Memory"	If WP is enabled, WR is cleared and WRERR is set All 32 words are erased NVMDATH:NVMDATL is ignored
0	1	Copy NVMDATH:NVMDATL to the write latch corresponding to NVMADR LSBs. See Section 13.3.3 "NVMREG Erase of Program Memory"	Write protection is ignored     No memory access occurs
0	0	Write the write-latch data to PFM row. See Section 13.3.3 "NVMREG Erase of Program Memory"	If WP is enabled, WR is cleared and WRERR is set Write latches are reset to 3FFh NVMDATH:NVMDATL is ignored

# 13.4 Register Definitions: Flash Program Memory Control

# REGISTER 13-1: NVMDATL: NONVOLATILE MEMORY DATA LOW BYTE REGISTER

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
|         |         |         | NVMD/   | \T<7:0> |         |         |         |
| bit 7   |         |         | _       |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 NVMDAT<7:0>: Read/write value for Least Significant bits of program memory

# REGISTER 13-2: NVMDATH: NONVOLATILE MEMORY DATA HIGH BYTE REGISTER

U-0	U-0	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
	- <del></del> 8			NVMD/	AT<13:8>		
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-6 Unimplemented: Read as '0'

bit 5-0 NVMDAT<13:8>: Read/write value for Most Significant bits of program memory

# REGISTER 13-3: NVMADRL: NONVOLATILE MEMORY ADDRESS LOW BYTE REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
|         |         |         | NVMAE   | )R<7:0> |         |         |         |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 NVMADR<7:0>: Specifies the Least Significant bits for program memory address

# REGISTER 13-4: NVMADRH: NONVOLATILE MEMORY ADDRESS HIGH BYTE REGISTER

U-1	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
(1)			_	NVMADR<14:8	3>		
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 Unimplemented: Read as '1'

bit 6-0 NVMADR<14:8>: Specifies the Most Significant bits for program memory address

Note 1: Bit is undefined while WR = 1

## REGISTER 13-5: NVMCON1: NONVOLATILE MEMORY CONTROL 1 REGISTER

U-0	R/W-0/0	R/W-0/0	R/W/HC-0/0	R/W/HC-x/q	R/W-0/0	R/S/HC-0/0	R/S/HC-0/0
_	NVMREGS	LWLO	FREE	WRERR <sup>(1,2,3)</sup>	WREN	WR <sup>(4,5,6)</sup>	RD
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
S = Bit can only be set	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HC = Bit is cleared by hardware

bit 7 Unimplemented: Read as '0'

bit 6 NVMREGS: Configuration Select bit

1 = Access DIA, DCI, Configuration, User ID and Device ID Registers

0 = Access Program Flash Memory

bit 5 LWLO: Load Write Latches Only bit

When FREE = 0:

1 = The next WR command updates the write latch for this word within the row; no memory operation is initiated.

0 = The next WR command writes data or erases

Otherwise: The bit is ignored

bit 4 FREE: Program Flash Memory Erase Enable bit

1 = Performs an erase operation with the next WR command; the 32-word pseudo-row containing the indicated address is erased (to all 1s) to prepare for writing.

0 = All erase operations have completed normally

bit 3 WRERR: Program/Erase Error Flag bit (1,2,3)

This bit is normally set by hardware.

1 = A write operation was interrupted by a Reset, interrupted unlock sequence, or WR was written to one while NVMADR points to a write-protected address.

0 = The program or erase operation completed normally

bit 2 WREN: Program/Erase Enable bit

1 = Allows program/erase cycles

0 = Inhibits programming/erasing of program Flash

bit 1 WR: Write Control bit (4,5,6)

When NVMREG:NVMADR points to a Program Flash Memory location:

1 = Initiates the operation indicated by Table 13-4

0 = NVM program/erase operation is complete and inactive.

bit 0 RD: Read Control bit(7)

1 = Initiates a read at address = NVMADR1, and loads data to NVMDAT Read takes one instruction cycle and the bit is cleared when the operation is complete. The bit can only be set (not cleared) in software.

0 = NVM read operation is complete and inactive

Note 1: Bit is undefined while WR = 1.

2: Bit must be cleared by software; hardware will not clear this bit.

3: Bit may be written to '1' by software to implement test sequences.

4: This bit can only be set by following the unlock sequence of Section 13.3.2 "NVM Unlock Sequence".

5: Operations are self-timed, and the WR bit is cleared by hardware when complete.

Once a write operation is initiated, setting this bit to zero will have no effect.

# REGISTER 13-6: NVMCON2: NONVOLATILE MEMORY CONTROL 2 REGISTER

W-0/0	W-0/0	W-0/0	W-0/0	W-0/0	W-0/0	W-0/0	W-0/0		
	NVMCON2<7:0>								
bit 7							bit 0		

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

S = Bit can only be set x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 NVMCON2<7:0>: Flash Memory Unlock Pattern bits

To unlock writes, a 55h must be written first followed by an AAh before setting the WR bit of the NVMCON1 register. The value written to this register is used to unlock the writes.

TABLE 13-5: SUMMARY OF REGISTERS ASSOCIATED WITH NONVOLATILE MEMORY (NVM)

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
INTCON	GIE	PEIE	_	_	_	_	-	INTEDG	121
PIE7	-	-	NVMIE	NCO1IE	=	-		CWG1IE	129
PIR7	-	_	NVMIF	NCO1IF	-	-	-	CWG1IF	137
NVMCON1	-	NVMREGS	LWLO	FREE	WRERR	WREN	WR	RD	170
NVMCON2		-	*	NVMCC	N2<7:0>				171
NVMADRL				NVMAI	OR<7:0>				169
NVMADRH	(1) NVMADR<14:8>								169
NVMDATL	NVMDAT<7:0>							169	
NVMDATH	·—-	- NVMDAT<13:8>							169

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by NVM.

Note 1: Unimplemented, read as '1'.

#### 14.0 I/O PORTS

TABLE 14-1: PORT AVAILABILITY PER DEVICE

Device	PORTA	PORTB	PORTC	PORTE
PIC16(L)F15354/55	•	•	•	•

Each port has standard registers for its operation. These registers are:

- PORTx registers (reads the levels on the pins of the device)
- LATx registers (output latch)
- TRISx registers (data direction)
- ANSELx registers (analog select)
- WPUx registers (weak pull-up)
- INLVLx (input level control)
- SLRCONx registers (slew rate)
- · ODCONx registers (open-drain)

Most port pins share functions with device peripherals, both analog and digital. In general, when a peripheral is enabled on a port pin, that pin cannot be used as a general purpose output; however, the pin can still be read.


The Data Latch (LATx registers) is useful for readmodify-write operations on the value that the I/O pins are driving.

A write operation to the LATx register has the same effect as a write to the corresponding PORTx register. A read of the LATx register reads of the values held in the I/O PORT latches, while a read of the PORTx register reads the actual I/O pin value.

Ports that support analog inputs have an associated ANSELx register. When an ANSEL bit is set, the digital input buffer associated with that bit is disabled.

Disabling the input buffer prevents analog signal levels on the pin between a logic high and low from causing excessive current in the logic input circuitry. A simplified model of a generic I/O port, without the interfaces to other peripherals, is shown in Figure 14-1.

FIGURE 14-1: GENERIC I/O PORT OPERATION



#### 14.1 I/O Priorities

Each pin defaults to the PORT data latch after Reset. Other functions are selected with the peripheral pin select logic. See Section 15.0 "Peripheral Pin Select (PPS) Module" for more information.

Analog input functions, such as ADC and comparator inputs, are not shown in the peripheral pin select lists. These inputs are active when the I/O pin is set for Analog mode using the ANSELx register. Digital output functions may continue to control the pin when it is in Analog mode.

Analog outputs, when enabled, take priority over the digital outputs and force the digital output driver to the high-impedance state.

# 14.2 PORTA Registers

#### 14.2.1 DATA REGISTER

PORTA is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISA (Register 14-2). Setting a TRISA bit (= 1) will make the corresponding PORTA pin an input (i.e., disable the output driver). Clearing a TRISA bit (= 0) will make the corresponding PORTA pin an output (i.e., enables output driver and puts the contents of the output latch on the selected pin). Example 14.2.8 shows how to initialize PORTA.

Reading the PORTA register (Register 14-1) reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified and then written to the PORT data latch (LATA).

The PORT data latch LATA (Register 14-3) holds the output port data, and contains the latest value of a LATA or PORTA write.

#### EXAMPLE 14-1: INITIALIZING PORTA

```
; This code example illustrates
; initializing the PORTA register. The
; other ports are initialized in the same
: manner.
BANKSEL PORTA;
CLRF
       PORTA: Init PORTA
BANKSEL LATA; Data Latch
CLRF
       LATA;
BANKSEL ANSELA;
      ANSELA; digital I/O
CLRF
BANKSEL TRISA;
MOVLW B'00111000'; Set RA<5:3> as inputs
MOVWF
      TRISA; and set RA<2:0> as
           ;outputs
```

# 14.2.2 DIRECTION CONTROL

The TRISA register (Register 14-2) controls the PORTA pin output drivers, even when they are being used as analog inputs. The user must ensure the bits in the TRISA register are maintained set when using them as analog inputs. I/O pins configured as analog inputs always read '0'.

#### 14.2.3 OPEN-DRAIN CONTROL

The ODCONA register (Register 14-6) controls the open-drain feature of the port. Open-drain operation is independently selected for each pin. When an ODCONA bit is set, the corresponding port output becomes an open-drain driver capable of sinking current only. When an ODCONA bit is cleared, the corresponding port output pin is the standard push-pull drive capable of sourcing and sinking current.

Note: It is not necessary to set open-drain control when using the pin for I<sup>2</sup>C; the I<sup>2</sup>C module controls the pin and makes the pin open-drain.

#### 14.2.4 SLEW RATE CONTROL

The SLRCONA register (Register 14-7) controls the slew rate option for each port pin. Slew rate control is independently selectable for each port pin. When an SLRCONA bit is set, the corresponding port pin drive is slew rate limited. When an SLRCONA bit is cleared, The corresponding port pin drive slews at the maximum rate possible.

# 14.2.5 INPUT THRESHOLD CONTROL

Note:

The INLVLA register (Register 14-8) controls the input voltage threshold for each of the available PORTA input pins. A selection between the Schmitt Trigger CMOS or the TTL Compatible thresholds is available. The input threshold is important in determining the value of a read of the PORTA register and also the level at which an interrupt-on-change occurs, if that feature is enabled. See Table 37-4 for more information on threshold levels.

Changing the input threshold selection may be performed while all peripheral modules are disabled. Changing the threshold level during the time a module is active may inadvertently generate a transition associated with an input pin, regardless of the actual voltage level on that pin.

#### 14.2.6 ANALOG CONTROL

The ANSELA register (Register 14-4) is used to configure the Input mode of an I/O pin to analog. Setting the appropriate ANSELA bit high will cause all digital reads on the pin to be read as '0' and allow analog functions on the pin to operate correctly.

The state of the ANSELA bits has no effect on digital output functions. A pin with its TRIS bit clear and its ANSEL bit set will still operate as a digital output, but the Input mode will be analog. This can cause unexpected behavior when executing read-modify-write instructions on the affected port.

Note: The ANSELA bits default to the Analog mode after Reset. To use any pins as digital general purpose or peripheral inputs, the corresponding ANSEL bits must be initialized to '0' by user software.

## 14.2.7 WEAK PULL-UP CONTROL

The WPUA register (Register 14-5) controls the individual weak pull-ups for each PORT pin.

# 14.2.8 PORTA FUNCTIONS AND OUTPUT PRIORITIES

Each PORTA pin is multiplexed with other functions.

Each pin defaults to the PORT latch data after Reset. Other output functions are selected with the peripheral pin select logic or by enabling an analog output, such as the DAC. See Section 15.0 "Peripheral Pin Select (PPS) Module" for more information.

Analog input functions, such as ADC and comparator inputs are not shown in the peripheral pin select lists. Digital output functions may continue to control the pin when it is in Analog mode.

# 14.3 Register Definitions: PORTA

#### REGISTER 14-1: PORTA: PORTA REGISTER

R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R-x/u	R/W-x/u	R/W-x/u	R/W-x/u
RA7	RA6	RA5	RA4	RA3	RA2	RA1	RA0
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 RA<7:0>: PORTA I/O Value bits(1)

1 = Port pin is  $\ge$  VIH 0 = Port pin is  $\le$  VIL

Note 1: Writes to PORTA are actually written to corresponding LATA register. Reads from PORTA register returns of actual I/O pin values.

## REGISTER 14-2: TRISA: PORTA TRI-STATE REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| TRISA7  | TRISA6  | TRISA5  | TRISA4  | TRISA3  | TRISA2  | TRISA1  | TRISA0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 TRISA<7:0>: PORTA Tri-State Control bit

1 = PORTA pin configured as an input (tri-stated)

0 = PORTA pin configured as an output

#### REGISTER 14-3: LATA: PORTA DATA LATCH REGISTER

R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-1/1	R/W-x/u	R/W-x/u	R/W-x/u
LATA7	LATA6	LATA5	LATA4	LATA3	LATA2	LATA1	LATA0
bit 7	<i>5.</i>	5	·				bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 LATA<7:0>: RA<7:0> Output Latch Value bits(1)

Note 1: Writes to PORTA are actually written to corresponding LATA register. Reads from PORTA register returns actual I/O pin values.

# REGISTER 14-4: ANSELA: PORTA ANALOG SELECT REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| ANSA7   | ANSA6   | ANSA5   | ANSA4   | ANSA3   | ANSA2   | ANSA1   | ANSA0   |
| bit 7   |         |         |         |         |         | •       | bit (   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 ANSA<7:0>: Analog Select between Analog or Digital Function on pins RA<7:0>, respectively

1 = Analog input. Pin is assigned as analog input<sup>(1)</sup>. Digital input buffer disabled.

0 = Digital I/O. Pin is assigned to port or digital special function.

Note 1: When setting a pin to an analog input, the corresponding TRIS bit must be set to Input mode to allow external control of the voltage on the pin.

# REGISTER 14-5: WPUA: WEAK PULL-UP PORTA REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| WPUA7   | WPUA6   | WPUA5   | WPUA4   | WPUA3   | WPUA2   | WPUA1   | WPUA0   |
| bit 7   | 91B     |         | 100     | -       |         | 1       | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 WPUA<7:0>: Weak Pull-up Register bits

1 = Pull-up enabled 0 = Pull-up disabled

Note 1: The weak pull-up device is automatically disabled if the pin is configured as an output.

# REGISTER 14-6: ODCONA: PORTA OPEN-DRAIN CONTROL REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| ODCA7   | ODCA6   | ODCA5   | ODCA4   | ODCA3   | ODCA2   | ODCA1   | ODCA0   |
| bit 7   | •       |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 ODCA<7:0>: PORTA Open-Drain Enable bits

For RA<7:0> pins, respectively

1 = Port pin operates as open-drain drive (sink current only)

0 = Port pin operates as standard push-pull drive (source and sink current)

# REGISTER 14-7: SLRCONA: PORTA SLEW RATE CONTROL REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| SLRA7   | SLRA6   | SLRA5   | SLRA4   | SLRA3   | SLRA2   | SLRA1   | SLRA0   |
| bit 7   |         |         |         |         |         | •       | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 SLRA<7:0>: PORTA Slew Rate Enable bits

For RA<7:0> pins, respectively 1 = Port pin slew rate is limited 0 = Port pin slews at maximum rate

#### REGISTER 14-8: INLVLA: PORTA INPUT LEVEL CONTROL REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| INLVLA7 | INLVLA6 | INLVLA5 | INLVLA4 | INLVLA3 | INLVLA2 | INLVLA1 | INLVLA0 |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 INLVLA<7:0>: PORTA Input Level Select bits

For RA<7:0> pins, respectively

1 = ST input used for PORT reads and interrupt-on-change

0 = TTL input used for PORT reads and interrupt-on-change

TABLE 14-2: SUMMARY OF REGISTERS ASSOCIATED WITH PORTA

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
PORTA	RA7	RA6	RA5	RA4	RA3	RA2	RA1	RA0	175
TRISA	TRISA7	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	175
LATA	LATA7	LATA6	LATA5	LATA4	LATA3	LATA2	LATA1	LATA0	176
ANSELA	ANSA7	ANSA6	ANSA5	ANSA4	ANSA3	ANSA2	ANSA1	ANSA0	176
WPUA	WPUA7	WPUA6	WPUA5	WPUA4	WPUA3	WPUA2	WPUA1	WPUA0	177
ODCONA	ODCA7	ODCA6	ODCA5	ODCA4	ODCA3	ODCA2	ODCA1	ODCA0	177
SLRCONA	SLRA7	SLRA6	SLRA5	SLRA4	SLRA3	SLRA2	SLRA1	SLRA0	178
INLVLA	INLVLA7	INLVLA6	INLVLA5	INLVLA4	INLVLA3	INLVLA2	INLVLA1	INLVLA0	178

**Legend:** x = unknown, u = unchanged, – = unimplemented locations read as '0'. Shaded cells are not used by PORTA.

## 14.4 PORTB Registers

#### 14.4.1 DATA REGISTER

PORTB is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISB (Register 14-10). Setting a TRISB bit (= 1) will make the corresponding PORTB pin an input (i.e., disable the output driver). Clearing a TRISB bit (= 0) will make the corresponding PORTB pin an output (i.e., enables output driver and puts the contents of the output latch on the selected pin). Figure 14-1 shows how to initialize PORTB.

Reading the PORTB register (Register 14-9) reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified and then written to the PORT data latch (LATB).

The PORT data latch LATB (Register 14-11) holds the output port data, and contains the latest value of a LATB or PORTB write.

#### 14.4.2 DIRECTION CONTROL

The TRISB register (Register 14-10) controls the PORTB pin output drivers, even when they are being used as analog inputs. The user must ensure the bits in the TRISB register are maintained set when using them as analog inputs. I/O pins configured as analog inputs always read '0'.

## 14.4.3 OPEN-DRAIN CONTROL

The ODCONB register (Register 14-14) controls the open-drain feature of the port. Open-drain operation is independently selected for each pin. When an ODCONB bit is set, the corresponding port output becomes an open-drain driver capable of sinking current only. When an ODCONB bit is cleared, the corresponding port output pin is the standard push-pull drive capable of sourcing and sinking current.

Note: It is not necessary to set open-drain control when using the pin for I<sup>2</sup>C; the I<sup>2</sup>C module controls the pin and makes the pin open-drain.

## 14.4.4 SLEW RATE CONTROL

The SLRCONB register (Register 14-15) controls the slew rate option for each port pin. Slew rate control is independently selectable for each port pin. When an SLRCONB bit is set, the corresponding port pin drive is slew rate limited. When an SLRCONB bit is cleared, The corresponding port pin drive slews at the maximum rate possible.

#### 14.4.5 INPUT THRESHOLD CONTROL

The INLVLB register (Register 14-8) controls the input voltage threshold for each of the available PORTB input pins. A selection between the Schmitt Trigger CMOS or the TTL Compatible thresholds is available. The input threshold is important in determining the value of a read of the PORTB register and also the level at which an interrupt-on-change occurs, if that feature is enabled. See Table 37-4 for more information on threshold levels.

Note: Changing the input threshold selection may be performed while all peripheral modules are disabled. Changing the threshold level during the time a module is active may inadvertently generate a transition associated with an input pin, regardless of the actual voltage level on that pin.

## 14.4.6 ANALOG CONTROL

The ANSELB register (Register 14-12) is used to configure the Input mode of an I/O pin to analog. Setting the appropriate ANSELA bit high will cause all digital reads on the pin to be read as '0' and allow analog functions on the pin to operate correctly.

The state of the ANSELB bits has no effect on digital output functions. A pin with its TRIS bit clear and its ANSEL bit set will still operate as a digital output, but the Input mode will be analog. This can cause unexpected behavior when executing read-modify-write instructions on the affected port.

Note: The ANSELB bits default to the Analog mode after Reset. To use any pins as digital general purpose or peripheral inputs, the corresponding ANSEL bits must be initialized to '0' by user software.

#### 14.4.7 WEAK PULL-UP CONTROL

The WPUB register (Register 14-5) controls the individual weak pull-ups for each PORT pin.

## 14.4.8 PORTB FUNCTIONS AND OUTPUT PRIORITIES

Each PORTB pin is multiplexed with other functions.

Each pin defaults to the PORT latch data after Reset. Other output functions are selected with the peripheral pin select logic or by enabling an analog output, such as the DAC. See Section 15.0 "Peripheral Pin Select (PPS) Module" for more information.

Analog input functions, such as ADC and comparator inputs are not shown in the peripheral pin select lists. Digital output functions may continue to control the pin when it is in Analog mode.

## 14.5 Register Definitions: PORTB

#### REGISTER 14-9: PORTB: PORTB REGISTER

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| RB7     | RB6     | RB5     | RB4     | RB3     | RB2     | RB1     | RB0     |
| bit 7   |         |         |         |         | -       | _       | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 RB<7:0>: PORTB I/O Value bits<sup>(1)</sup>

1 = Port pin is  $\ge$  VIH 0 = Port pin is  $\le$  VIL

Note 1: Writes to PORTB are actually written to corresponding LATB register. The actual I/O pin values are read from the PORTB register.

## REGISTER 14-10: TRISB: PORTB TRI-STATE REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| TRISB7  | TRISB6  | TRISB5  | TRISB4  | TRISB3  | TRISB2  | TRISB1  | TRISB0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 TRISB<7:0>: PORTB Tri-State Control bit

1 = PORTB pin configured as an input (tri-stated)

0 = PORTB pin configured as an output

#### REGISTER 14-11: LATB: PORTB DATA LATCH REGISTER

R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
LATB7	LATB6	LATB5	LATB4	LATB3	LATB2	LATB1	LATB0
bit 7	<i>5.</i>	5-	·				bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 LATB<7:0>: RB<7:0> Output Latch Value bits(1)

Note 1: Writes to PORTB are actually written to corresponding LATB register. Reads from PORTB register returns actual I/O pin values.

## REGISTER 14-12: ANSELB: PORTB ANALOG SELECT REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| ANSB7   | ANSB6   | ANSB5   | ANSB4   | ANSB3   | ANSB2   | ANSB1   | ANSB0   |
| bit 7   | •       | •       |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 ANSB<7:0>: Analog Select between Analog or Digital Function on pins RB<7:0>, respectively

1 = Analog input. Pin is assigned as analog input<sup>(1)</sup>. Digital input buffer disabled.

0 = Digital I/O. Pin is assigned to port or digital special function.

Note 1: When setting a pin to an analog input, the corresponding TRIS bit must be set to Input mode to allow external control of the voltage on the pin.

#### REGISTER 14-13: WPUB: WEAK PULL-UP PORTB REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| WPUB7   | WPUB6   | WPUB5   | WPUB4   | WPUB3   | WPUB2   | WPUB1   | WPUB0   |
| bit 7   |         | 39      | 100     | 100     |         | •••     | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 WPUB<7:0>: Weak Pull-up Register bits

1 = Pull-up enabled 0 = Pull-up disabled

#### REGISTER 14-14: ODCONB: PORTB OPEN-DRAIN CONTROL REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| ODCB7   | ODCB6   | ODCB5   | ODCB4   | ODCB3   | ODCB2   | ODCB1   | ODCB0   |
| bit 7   | •       |         | _       |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 ODCB<7:0>: PORTB Open-Drain Enable bits

For RB<7:0> pins, respectively

1 = Port pin operates as open-drain drive (sink current only)

0 = Port pin operates as standard push-pull drive (source and sink current)

## REGISTER 14-15: SLRCONB: PORTB SLEW RATE CONTROL REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| SLRB7   | SLRB6   | SLRB5   | SLRB4   | SLRB3   | SLRB2   | SLRB1   | SLRB0   |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 SLRB<7:0>: PORTB Slew Rate Enable bits

For RB<7:0> pins, respectively 1 = Port pin slew rate is limited 0 = Port pin slews at maximum rate

#### REGISTER 14-16: INLVLB: PORTB INPUT LEVEL CONTROL REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| INLVLB7 | INLVLB6 | INLVLB5 | INLVLB4 | INLVLB3 | INLVLB2 | INLVLB1 | INLVLB0 |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 INLVLB<7:0>: PORTB Input Level Select bits

For RB<7:0> pins, respectively

1 = ST input used for PORT reads and interrupt-on-change

0 = TTL input used for PORT reads and interrupt-on-change

## TABLE 14-3: SUMMARY OF REGISTERS ASSOCIATED WITH PORTB

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
PORTB	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0	181
TRISB	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	181
LATB	LATB7	LATB6	LATB5	LATB4	LATB3	LATB2	LATB1	LATB0	182
ANSELB	ANSB7	ANSB6	ANSB5	ANSB4	ANSB3	ANSB2	ANSB1	ANSB0	182
WPUB	WPUB7	WPUB6	WPUB5	WPUB4	WPUB3	WPUB2	WPUB1	WPUB0	183
ODCONB	ODCB7	ODCB6	ODCB5	ODCB4	ODCB3	ODCB2	ODCB1	ODCB0	183
SLRCONB	SLRB7	SLRB6	SLRB5	SLRB4	SLRB3	SLRB2	SLRB1	SLRB0	184
INLVLB	INLVLB7	INLVLB6	INLVLB5	INLVLB4	INLVLB3	INLVLB2	INLVLB1	INLVLB0	184

**Legend:** x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by PORTB.

## 14.6 PORTC Registers

#### 14.6.1 DATA REGISTER

PORTC is an 8-bit wide bidirectional port. The corresponding data direction register is TRISC (Register 14-18). Setting a TRISC bit (= 1) will make the corresponding PORTC pin an input (i.e., put the corresponding output driver in a High-Impedance mode). Clearing a TRISC bit (= 0) will make the corresponding PORTC pin an output (i.e., enable the output driver and put the contents of the output latch on the selected pin). Figure 14-1 shows how to initialize an I/O port.

Reading the PORTC register (Register 14-17) reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified and then written to the PORT data latch (LATC).

The PORT data latch LATC (Register 14-19) holds the output port data, and contains the latest value of a LATC or PORTC write.

#### 14.6.2 DIRECTION CONTROL

The TRISC register (Register 14-18) controls the PORTC pin output drivers, even when they are being used as analog inputs. The user must ensure the bits in the TRISC register are maintained set when using them as analog inputs. I/O pins configured as analog inputs always read '0'.

## 14.6.3 OPEN-DRAIN CONTROL

The ODCONC register (Register 14-22) controls the open-drain feature of the port. Open-drain operation is independently selected for each pin. When an ODCONC bit is set, the corresponding port output becomes an open-drain driver capable of sinking current only. When an ODCONC bit is cleared, the corresponding port output pin is the standard push-pull drive capable of sourcing and sinking current.

Note: It is not necessary to set open-drain control when using the pin for I<sup>2</sup>C; the I<sup>2</sup>C module controls the pin and makes the pin open-drain.

## 14.6.4 SLEW RATE CONTROL

The SLRCONC register (Register 14-23) controls the slew rate option for each port pin. Slew rate control is independently selectable for each port pin. When an SLRCONC bit is set, the corresponding port pin drive is slew rate limited. When an SLRCONC bit is cleared, The corresponding port pin drive slews at the maximum rate possible.

#### 14.6.5 INPUT THRESHOLD CONTROL

The INLVLC register (Register 14-24) controls the input voltage threshold for each of the available PORTC input pins. A selection between the Schmitt Trigger CMOS or the TTL Compatible thresholds is available. The input threshold is important in determining the value of a read of the PORTC register and also the level at which an interrupt-on-change occurs, if that feature is enabled. See Table 37-4 for more information on threshold levels.

Note: Changing the input threshold selection may be performed while all peripheral modules are disabled. Changing the threshold level during the time a module is active may inadvertently generate a transition associated with an input pin, regardless of the actual voltage level on that pin.

## 14.6.6 ANALOG CONTROL

The ANSELC register (Register 14-20) is used to configure the Input mode of an I/O pin to analog. Setting the appropriate ANSELC bit high will cause all digital reads on the pin to be read as '0' and allow analog functions on the pin to operate correctly.

The state of the ANSELC bits has no effect on digital output functions. A pin with TRIS clear and ANSELC set will still operate as a digital output, but the Input mode will be analog. This can cause unexpected behavior when executing read-modify-write instructions on the affected port.

Note: The ANSELC bits default to the Analog mode after Reset. To use any pins as digital general purpose or peripheral inputs, the corresponding ANSEL bits must be initialized to '0' by user software.

#### 14.6.7 WEAK PULL-UP CONTROL

The WPUC register (Register 14-21) controls the individual weak pull-ups for each port pin.

## 14.6.8 PORTC FUNCTIONS AND OUTPUT PRIORITIES

Each pin defaults to the PORT latch data after Reset. Other output functions are selected with the peripheral pin select logic. See Section 15.0 "Peripheral Pin Select (PPS) Module" for more information.

Analog input functions, such as ADC and comparator inputs, are not shown in the peripheral pin select lists. Digital output functions may continue to control the pin when it is in Analog mode.

## 14.7 Register Definitions: PORTC

#### REGISTER 14-17: PORTC: PORTC REGISTER

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| RC7     | RC6     | RC5     | RC4     | RC3     | RC2     | RC1     | RC0     |
| bit 7   |         |         |         |         |         |         | bit     |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 RC<7:0>: PORTC General Purpose I/O Pin bits<sup>(1)</sup>

1 = Port pin is  $\geq$  VIH 0 = Port pin is  $\leq$  VIL

Note 1: Writes to PORTC are actually written to corresponding LATC register. The actual I/O pin values are read from the PORTC register.

#### REGISTER 14-18: TRISC: PORTC TRI-STATE REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| TRISC7  | TRISC6  | TRISC5  | TRISC4  | TRISC3  | TRISC2  | TRISC1  | TRISC0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 TRISC<7:0>: PORTC Tri-State Control bits

1 = PORTC pin configured as an input (tri-stated)

0 = PORTC pin configured as an output

## REGISTER 14-19: LATC: PORTC DATA LATCH REGISTER

R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
LATC7	LATC6	LATC5	LATC4	LATC3	LATC2	LATC1	LATC0
bit 7	· · · · · · · · · · · · · · · · · · ·	•				90	bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 LATC<7:0>: PORTC Output Latch Value bits<sup>(1)</sup>

Note 1: Writes to PORTC are actually written to corresponding LATC register. Reads from PORTC register returns actual I/O pin values.

## REGISTER 14-20: ANSELC: PORTC ANALOG SELECT REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| ANSC7   | ANSC6   | ANSC5   | ANSC4   | ANSC3   | ANSC2   | ANSC1   | ANSC0   |
| bit 7   | ANOOO   | 7,1000  | ANOOT   | ANOUS   | ANOUZ   | ANOCI   | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown
'1' = Bit is set '0' = Bit is cleared

U = Unimplemented bit, read as '0'

-n/n = Value at POR and BOR/Value at all other Resets

bit 7-0 ANSC<7:0>: Analog Select between Analog or Digital Function on Pins RC<7:0>, respectively(1)

1 = Analog input. Pin is assigned as analog input<sup>(1)</sup>. Digital input buffer disabled.

0 = Digital I/O. Pin is assigned to port or digital special function.

Note 1: When setting a pin to an analog input, the corresponding TRIS bit must be set to Input mode to allow external control of the voltage on the pin.

#### REGISTER 14-21: WPUC: WEAK PULL-UP PORTC REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| WPUC7   | WPUC6   | WPUC5   | WPUC4   | WPUC3   | WPUC2   | WPUC1   | WPUC0   |
| bit 7   |         |         |         |         |         | •       | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 WPUC<7:0>: Weak Pull-up Register bits

1 = Pull-up enabled 0 = Pull-up disabled

## REGISTER 14-22: ODCONC: PORTC OPEN-DRAIN CONTROL REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| ODCC7   | ODCC6   | ODCC5   | ODCC4   | ODCC3   | ODCC2   | ODCC1   | ODCC0   |
| bit 7   |         |         | _       |         |         | -       | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 ODCC<7:0>: PORTC Open-Drain Enable bits

For RC<7:0> pins, respectively

1 = Port pin operates as open-drain drive (sink current only)

0 = Port pin operates as standard push-pull drive (source and sink current)

## REGISTER 14-23: SLRCONC: PORTC SLEW RATE CONTROL REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| SLRC7   | SLRC6   | SLRC5   | SLRC4   | SLRC3   | SLRC2   | SLRC1   | SLRC0   |
| bit 7   | - \$    | Š.      | 0       |         |         | _       | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 SLRC<7:0>: PORTC Slew Rate Enable bits

For RC<7:0> pins, respectively
1 = Port pin slew rate is limited
0 = Port pin slews at maximum rate

#### REGISTER 14-24: INLVLC: PORTC INPUT LEVEL CONTROL REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| INLVLC7 | INLVLC6 | INLVLC5 | INLVLC4 | INLVLC3 | INLVLC2 | INLVLC1 | INLVLC0 |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 INLVLC<7:0>: PORTC Input Level Select bits

For RC<7:0> pins, respectively

1 = ST input used for PORT reads and interrupt-on-change 0 = TTL input used for PORT reads and interrupt-on-change

TABLE 14-4: SUMMARY OF REGISTERS ASSOCIATED WITH PORTC

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
PORTC	RC7	RC6	RC5	RC4	RC3	RC2	RC1	RC0	186
TRISC	TRISC7	TRISC6	TRISC5	TRISC4	TRISC3	TRISC2	TRISC1	TRISC0	186
LATC	LATC7	LATC6	LATC5	LATC4	LATC3	LATC2	LATC1	LATC0	186
ANSELC	ANSC7	ANSC6	ANSC5	ANSC4	ANSC3	ANSC2	ANSC1	ANSC0	187
WPUC	WPUC7	WPUC6	WPUC5	WPUC4	WPUC3	WPUC2	WPUC1	WPUC0	187
ODCONC	ODCC7	ODCC6	ODCC5	ODCC4	ODCC3	ODCC2	ODCC1	ODCC0	188
SLRCONC	SLRC7	SLRC6	SLRC5	SLRC4	SLRC3	SLRC2	SLRC1	SLRC0	188
INLVLC	INLVLC7	INLVLC6	INLVLC5	INLVLC4	INLVLC3	INLVLC2	INLVLC1	INLVLC0	188

**Legend:** -= unimplemented locations read as '0'. Shaded cells are not used by PORTC.

## 14.8 PORTE Registers

#### 14.8.1 DATA REGISTER

PORTE is a single bit-bit wide port. The corresponding data direction register is TRISE (Register 14-25). Setting a TRISE bit (= 1) will make the corresponding PORTE pin an input (i.e., disable the output driver). Clearing a TRISE bit (= 0) will make the corresponding PORTE pin an output (i.e., enables output driver and puts the contents of the output latch on the selected pin). Figure 14-1 shows how to initialize PORTE.

Reading the PORTE register (Register 14-25) reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified and then written to the PORT data latch (LATE).

#### 14.8.2 DIRECTION CONTROL

The TRISE register (Register 14-26) controls the PORTE pin output drivers, even when they are being used as analog inputs. The user must ensure the bits in the TRISE register are maintained set when using them as analog inputs. I/O pins configured as analog inputs always read '0'.

Note: The TRISE3 bit is a read-only bit and it always reads a '1'.

## 14.8.3 INPUT THRESHOLD CONTROL

The INLVLE register (Register 14-28) controls the input voltage threshold for each of the available PORTE input pins. A selection between the Schmitt Trigger CMOS or the TTL Compatible thresholds is available. The input threshold is important in determining the value of a read of the PORTE register and also the level at which an interrupt-on-change occurs, if that feature is enabled. See Table 37-4 for more information on threshold levels.

Note: Changing the input threshold selection may be performed while all peripheral modules are disabled. Changing the threshold level during the time a module is active may inadvertently generate a transition associated with an input pin, regardless of the actual voltage level on that pin.

#### 14.8.4 WEAK PULL-UP CONTROL

The WPUE register (Register 14-27) controls the individual weak pull-ups for each port pin.

## 14.8.5 PORTE FUNCTIONS AND OUTPUT PRIORITIES

Each pin defaults to the PORT latch data after Reset. Other output functions are selected with the peripheral pin select logic. See Section 15.0 "Peripheral Pin Select (PPS) Module" for more information.

Analog input functions, such as ADC and comparator inputs, are not shown in the peripheral pin select lists. Digital output functions may continue to control the pin when it is in Analog mode.

## 14.9 Register Definitions: PORTE

#### REGISTER 14-25: PORTE: PORTE REGISTER

U-0	U-0	U-0	U-0	R-x/u	U-0	U-0	U-0
-	:	_	.—	RE3	_	-	( <del></del> 0
bit 7	*	5		38		20.	bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-4 Unimplemented: Read as '0' bit 3 RE<3>: PORTE Input Pin bit

1 = Port pin is > VIH 0 = Port pin is < VIL

bit 2-0 Unimplemented: Read as '0'

## REGISTER 14-26: TRISE: PORTE TRI-STATE REGISTER

U-0	U-0	U-0	U-0	U-1	U-0	U-0	U-0
	_	-	_	_(1)	5 <u></u> 5	: <u></u>	_
bit 7			_				bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-4 Unimplemented: Read as '0' bit 3 Unimplemented: Read as '1' bit 2-0 Unimplemented: Read as '0'

Note 1: Unimplemented, read as '1'.

## REGISTER 14-27: WPUE: WEAK PULL-UP PORTE REGISTER

U-0	U-0	U-0	U-0	R/W-1/1	U-0	U-0	U-0
<del></del> .	(s <del></del> ):	_	-	WPUE3 <sup>(1)</sup>	9 <del>1 - 1</del> 2		<del>-</del> .
bit 7						•	bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-4 Unimplemented: Read as '0'

bit 3 WPUE3: Weak Pull-up Register bit<sup>(1)</sup>

1 = Pull-up enabled 0 = Pull-up disabled

bit 2-0 Unimplemented: Read as '0'

Note 1: If MCLRE = 1, the weak pull-up in RE3 is always enabled; bit WPUE3 is not affected.

2: The weak pull-up device is automatically disabled if the pin is configured as an output.

#### REGISTER 14-28: INLVLE: PORTE INPUT LEVEL CONTROL REGISTER

U-0	U-0	U-0	U-0	R/W-1/1	U-0	U-0	U-0
<del></del> :	33	-	_	INLVLE3	<del>-</del> -	_	1 <del></del> 2
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-4 Unimplemented: Read as '0'

bit 3 INLVLE3: PORTE Input Level Select bits

For RE3 pin,

1 = ST input used for PORT reads and interrupt-on-change 0 = TTL input used for PORT reads and interrupt-on-change

bit 2-0 Unimplemented: Read as '0'

TABLE 14-5: SUMMARY OF REGISTERS ASSOCIATED WITH PORTE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
PORTE	-	-	=	-	RE3	_	_	_	191
TRISE	_	_	_	_	(1)	<del>-</del> -	_	_	191
WPUE	<u></u>	_	_		WPUE3	-		<u></u> -	192
INLVLE	×	<del>4</del> 1	_		INLVLE3	::	17—8	_	192

Legend: x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by PORTE.

Note 1: Unimplemented, read as '1'

## TABLE 14-6: SUMMARY OF CONFIGURATION WORD WITH PORTE

Name	Bits	Bit -/7	Bit -/6	Bit 13/5	Bit 12/4	Bit 11/3	Bit 10/2	Bit 9/1	Bit 8/0	Register on Page
CONFICE	13:8	===	5_3	DEBUG	STVREN	PPS1WAY	ZCDDIS	BORV	_	77
CONFIG2	7:0	BOREN	N <1:0>	LPBOREN	-		-	PWRTE	MCLRE	11


Legend: — = unimplemented location, read as '0'. Shaded cells are not used by PORTE.

# 15.0 PERIPHERAL PIN SELECT (PPS) MODULE

The Peripheral Pin Select (PPS) module connects peripheral inputs and outputs to the device I/O pins. Only digital signals are included in the selections.

All analog inputs and outputs remain fixed to their assigned pins. Input and output selections are independent as shown in the simplified block diagram Figure 15-1.

#### FIGURE 15-1: SIMPLIFIED PPS BLOCK DIAGRAM



## 15.1 PPS Inputs

Each peripheral has a PPS register with which the inputs to the peripheral are selected. Inputs include the device pins.

Although every peripheral has its own PPS input selection register, the selections are identical for every peripheral as shown in Register 15-1.

Note: The notation "xxx" in the register name is a place holder for the peripheral identifier. For example, CLC1PPS.

## 15.2 PPS Outputs

Each I/O pin has a PPS register with which the pin output source is selected. With few exceptions, the port TRIS control associated with that pin retains control over the pin output driver. Peripherals that control the pin output driver as part of the peripheral operation will override the TRIS control as needed. These peripherals are (See Section 15.3 "Bidirectional Pins"):

- EUSART (synchronous operation)
- MSSP (I<sup>2</sup>C)

Although every pin has its own PPS peripheral selection register, the selections are identical for every pin as shown in Register 15-2.

Note: The notation "Rxy" is a place holder for the pin port and bit identifiers. For example, x and y for PORTA bit 0 would be A and 0, respectively, resulting in the pin PPS output selection register RA0PPS.

TABLE 15-1: PPS INPUT SIGNAL ROUTING OPTIONS (PIC16(L)F15354/55)

INDUT CICNAL	Innut Dogistor	Default	DesetVolus	Remappable to Pins of PORTx				
INPUT SIGNAL NAME	Input Register Name	Location at	Reset Value (xxxPPS<5:0>)	PI	C16(L)F15354/	55		
	Traino.	POR	(****)	PORTA	PORTB	PORTC		
INT	INTPPS	RB0	01000	•	•			
T0CKI	T0CKIPPS	RA4	00100	•	•			
T1CKI	T1CKIPSS	RC0	10000	•		•		
T1G	T1GPPS	RB5	01101		•	•		
T2IN	T2INPPS	RC3	10011	•		•		
CCP1	CCP1PPS	RC2	10010		•	•		
CCP2	CCP2PPS	RC1	10001		•	•		
CWG1IN	CWG1PPS	RB0	01000		•	•		
CLCIN0	CLCIN0PPS	RA0	00000	•		•		
CLCIN1	CLCIN1PPS	RA1	00001	•		•		
CLCIN2	CLCIN2PPS	RB6	01110		•	•		
CLCIN3	CLCIN3PPS	RB7	01111		•	•		
ADACT	ADACTPPS	RB4	01100		•	•		
SCK1/SCL1	SSP1CLKPPS	RC3	10011		•	•		
SDI1/SDA1	SSP1DATPPS	RC4	10100		•	•		
SS1	SSP1SS1PPS	RA5	00101	•		•		
SCK2/SCL2	SSP2CLKPPS	RB1	01001		•	•		
SDI2/SDA2	SSP2DATPPS	RB2	01010		•	•		
SS2	SSP2SSPPS	RB0	01000		•	•		
RX1/DT1	RX1DTPPS	RC7	10111		•	•		
CK1	TX1CKPPS	RC6	10110		•	•		
RX2/DT2	RX2DTPPS	RB7	01111		•	•		
CK2	TX2CKPPS	RB6	01110		•	•		

TABLE 15-2: PPS INPUT REGISTER VALUES

Desired Input Pin	Value to Write to Register
RA0	0x00
RA1	0x01
RA2	0x02
RA3	0x03
RA4	0x04
RA5	0x05
RA6	0x06
RA7	0x07
RB0	0x08
RB1	0x09
RB2	0x0A
RB3	0x0B
RB4	0x0C
RB5	0x0D
RB6	0x0E
RB7	0x0F
RC0	0x10
RC1	0x11
RC2	0x12
RC3	0x13
RC4	0x14
RC5	0x15
RC6	0x16
RC7	0x17

Note 1: Only a few of the values in this column are valid for any given signal. For example, since the INT signal can only be mapped to PORTA or PORTB pins, only the register values 0x00-0x0F (corresponding to RA<7:0> and RB<7:0>) are valid values to write to the INTPPS register.

#### 15.3 Bidirectional Pins

PPS selections for peripherals with bidirectional signals on a single pin must be made so that the PPS input and PPS output select the same pin. Peripherals that have bidirectional signals include:

- EUSART (synchronous operation)
- MSSP (I<sup>2</sup>C)

Note: The I<sup>2</sup>C SCLx and SDAx functions can be remapped through PPS. However, only the RB1, RB2, RC3 and RC4 pins have the I<sup>2</sup>C and SMBus specific input buffers implemented (I<sup>2</sup>C mode disables INLVL and sets thresholds that are specific for I<sup>2</sup>C). If the SCLx or SDAx functions are mapped to some other pin (other than RB1, RB2, RC3 or RC4), the general purpose TTL or ST input buffers (as configured based on INLVL register setting) will be used instead. In most applications, it is therefore recommended only to map the SCLx and SDAx pin functions to the RB1, RB2, RC3 or RC4 pins.

## 15.4 PPS Lock

The PPS includes a mode in which all input and output selections can be locked to prevent inadvertent changes. PPS selections are locked by setting the PPSLOCKED bit of the PPSLOCK register. Setting and clearing this bit requires a special sequence as an extra precaution against inadvertent changes. Examples of setting and clearing the PPSLOCKED bit are shown in Example 15-1.

## EXAMPLE 15-1: PPS LOCK/UNLOCK SEQUENCE

```
; suspend interrupts
   BCF
          INTCON, GIE
   BANKSEL PPSLOCK
                     ; set bank
; required sequence, next 5 instructions
   MOVLW 0x55
   MOVWF
          PPSLOCK
   MOVLW
          0xAA
   MOVWF
           PPSLOCK
; Set PPSLOCKED bit to disable writes or
; Clear PPSLOCKED bit to enable writes
   BSF
           PPSLOCK, PPSLOCKED
; restore interrupts
   BSF
           INTCON, GIE
```

## 15.5 PPS Permanent Lock

The PPS can be permanently locked by setting the PPS1WAY Configuration bit. When this bit is set, the PPSLOCKED bit can only be cleared and set one time after a device Reset. This allows for clearing the PPSLOCKED bit so that the input and output selections can be made during initialization. When the PPSLOCKED bit is set after all selections have been made, it will remain set and cannot be cleared until after the next device Reset event.

## 15.6 Operation During Sleep

PPS input and output selections are unaffected by Sleep.

## 15.7 Effects of a Reset

A device Power-on-Reset (POR) clears all PPS input and output selections to their default values (Permanent Lock Removed). All other Resets leave the selections unchanged. Default input selections are shown in Table 15-1.

TABLE 15-3: PPS OUTPUT SIGNAL ROUTING OPTIONS (PIC16(L)F15354/55)

Output	RxyPPS	Rema	ppable to PORTx	Pins of	
Signal Name	Register Value	PIC	16(L)F1535	5354/55	
		PORTA	PORTB	PORTC	
CLKR	0x1B		•	• :	
NCO1OUT	0x1A	•		•	
TMR0	0x19		•	• ::	
SDO2/SDA2	0x18		•	•	
SCK2/SCL2	0x17		•	•	
SDO1/SDA1	0x16		•	•	
SCK1/SCL1	0x15		•	•	
C2OUT	0x14	•		•	
C1OUT	0x13	•		•	
DT2	0x12		•	•	
TX2/CK2	0x11		•	•	
DT1	0x10		•	•	
TX1/CK1	0x0F		•	•	
PWM6OUT	0x0E	•		•	
PWM5OUT	0x0D	•		•	
PWM4OUT	0x0C		•	•	
PWM3OUT	0x0B		•	•	
CCP2	0x0A		•	•	
CCP1	0x09		•	•	
CWG1D	0x08		•	•	
CWG1C	0x07		•	•	
CWG1B	0x06		•	•	
CWG1A	0x05		•	•	
CLC4OUT	0x04		•	•	
CLC3OUT	0x03		•	•	
CLC2OUT	0x02	•		•	
CLC10UT	0x01	•	8	•	

## 15.8 Register Definitions: PPS Input Selection

## REGISTER 15-1: xxxPPS: PERIPHERAL xxx INPUT SELECTION(1)

U-0	U-0	R/W-q/u	R/W-q/u	R/W/q/u	R/W-q/u	R/W-q/u	R/W-q/u		
-	—		xxxPPS<5:0>						
bit 7		7					bit 0		

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = value depends on peripheral

bit 7-6 Unimplemented: Read as '0'

bit 5-0 xxxPPS<5:0>: Peripheral xxx Input Selection bits

See Table 15-1.

Note 1: The "xxx" in the register name "xxxPPS" represents the input signal function name, such as "INT", "T0CKI", "RX", etc. This register summary shown here is only a prototype of the array of actual registers, as each input function has its own dedicated SFR (ex: INTPPS, T0CKIPPS, RXPPS, etc.).

2: Each specific input signal may only be mapped to a subset of these I/O pins, as shown in Table 15-1. Attempting to map an input signal to a non-supported I/O pin will result in undefined behavior. For example, the "INT" signal map be mapped to any PORTA or PORTB pin. Therefore, the INTPPS register may be written with values from 0x00-0x0F (corresponding to RA0-RB7). Attempting to write 0x10 or higher to the INTPPS register is not supported and will result in undefined behavior.

## REGISTER 15-2: RxyPPS: PIN Rxy OUTPUT SOURCE SELECTION REGISTER

U-0	U-0	U-0	R/W-0/u	R/W-0/u	R/W-0/u	R/W-0/u	R/W-0/u
_	·—·	<u> </u>			RxyPPS<4:0>	1	
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-5 Unimplemented: Read as '0'

bit 4-0 RxyPPS<4:0>: Pin Rxy Output Source Selection bits

See Table 15-3.

## REGISTER 15-3: PPSLOCK: PPS LOCK REGISTER

U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-0/0
<u></u>	* <u></u>	* <u></u> *	1 <del></del> 1	<del></del>	<u></u>	==	PPSLOCKED
bit 7				73	N. 15.1		bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-1 Unimplemented: Read as '0' bit 0 PPSLOCKED: PPS Locked bit

1= PPS is locked. PPS selections can not be changed. 0= PPS is not locked. PPS selections can be changed.

TABLE 15-4: SUMMARY OF REGISTERS ASSOCIATED WITH THE PPS MODULE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on page		
PPSLOCK	_	:::		_	_	===		PPSLOCKED	200		
INTPPS		(1 <del></del> )			INT	PPS<5:0>		•	199		
T0CKIPPS	_			_	TOCK	(IPPS<5:0>			199		
T1CKIPPS					T1Ck	(IPPS<5:0>			199		
T1GPPS	_			T1GPPS<5:0>							
T2INPPS				T2INPPS<5:0>							
CCP1PPS		-			CCP	1PPS<5:0>			199		
CCP2PPS	_				CCP	2PPS<5:0>			199		
CWG1PPS	_				CWG	1PPS<5:0>			199		
SSP1CLKPPS		·			SSP10	CLKPPS<5:0	>		199		
SSP1DATPPS	_	· <del></del> :			SSP1D	ATPPS<5:0	>		199		
SSP1SSPPS	_	:: <u></u> ::			SSP19	SSPPS<5:0>	•		199		
SSP2CLKPPS	_	0-0			SSP2C	CLKPPS<5:0	>		199		
SSP2DATPPS	<del>_</del>	_		_	SSP2D	ATPPS<5:0	>		199		
SSP2SSPPS		:=::			SSP29	SSPPS<5:0>	• 7		199		
RX1DTPPS					RX1D	)TPPS<5:0>			199		
TX1CKPPS		_			TX1C	KPPS<5:0>			199		
CLCIN0PPS	_	1—			CLCIN	N0PPS<5:0>			199		
CLCIN1PPS	-	_			CLCIN	N1PPS<5:0>			199		
CLCIN2PPS	_	_	i.	CLCIN2PPS<5:0>							
CLCIN3PPS	1-3	( )			CLCIN	N3PPS<5:0>			199 199		
RX2DTPPS	_	_	-		RX2D	)TPPS<5:0>			199		
TX2CKPPS		_			TX2C	KPPS<5:0>			199		
ADACTPPS		7.—3			ADAC	CTPPS<5:0>			199		
RA0PPS	_		_			RA0PPS<	4:0>		200		
RA1PPS	_					RA1PPS<	4:0>		200		
RA2PPS	—	11	_			RA2PPS<	4:0>		200		
RA3PPS	_		_			RA3PPS<	4:0>		200		
RA4PPS	_	:: <u></u> ::		_		RA4PPS<	4:0>		200		
RA5PPS		n—.	_			RA5PPS<	4:0>		200		
RA6PPS	—,	_	_	_		RA6PPS<			200		
RA7PPS	13—33	-	_	_		RA7PPS<	4:0>		200		
RB0PPS		(1 <del></del> )	_			RB0PPS<	4:0>		200		
RB1PPS	—	_	_	_		RB1PPS<	4:0>		200		
RB2PPS		-	_			RB2PPS<	4:0>		200		
RB3PPS	_		_			RB3PPS<	4:0>		200		
RB4PPS	_	-				RB4PPS<	4:0>		200		
RB5PPS	_	_	_	RB5PPS<4:0>							
RB6PPS	_		_								
RB7PPS	_					RB7PPS<	4:0>		200		
RC0PPS	——»		_	— RC0PPS<4:0>							
RC1PPS			_	<u> </u>		RC1PPS<	4:0>		200		
Lamandi -	unimplement			- RCIFF3-4.07							

**Legend:** — = unimplemented, read as '0'. Shaded cells are unused by the PPS module.

TABLE 15-4: SUMMARY OF REGISTERS ASSOCIATED WITH THE PPS MODULE (CONTINUED)

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on page		
RC2PPS		·—	_		RC2PPS<4:0>						
RC3PPS	—		-		RC3PPS<4:0>						
RC4PPS	_	_	_			RC4PPS<	4:0>		200		
RC5PPS		0	-			RC5PPS<	4:0>		200		
RC6PPS	<del>-</del>	, <del>-</del> ,	-	RC6PPS<4:0>					200		
RC7PPS	1—33	_	1		200						

Legend: — = unimplemented, read as '0'. Shaded cells are unused by the PPS module.

# 16.0 PERIPHERAL MODULE DISABLE

The PIC16(L)F15354/55 provides the ability to disable selected modules, placing them into the lowest possible Power mode.

For legacy reasons, all modules are ON by default following any Reset.

## 16.1 Disabling a Module

Disabling a module has the following effects:

- All clock and control inputs to the module are suspended; there are no logic transitions, and the module will not function.
- · The module is held in Reset:
  - Writing to SFRs is disabled
  - Reads return 00h

## 16.2 Enabling a module

When the register bit is cleared, the module is reenabled and will be in its Reset state; SFR data will reflect the POR Reset values.

Depending on the module, it may take up to one full instruction cycle for the module to become active. There must be no interaction with the module (e.g., writing to registers) for at least one instruction after it has been re-enabled.

## 16.3 Disabling a Module

When a module is disabled, all the associated PPS selection registers (Register 15-1, 15-2 and 15-3), are also disabled.

## 16.4 System Clock Disable

Setting SYSCMD (PMD0, Register 16-1) disables the system clock (FOSC) distribution network to the peripherals. Not all peripherals make use of SYSCLK, so not all peripherals are affected. Refer to the specific peripheral description to see if it will be affected by this bit.

## 16.5 Register Definitions: Peripheral Module Disable Control

## REGISTER 16-1: PMD0: PMD CONTROL REGISTER 0

R/W-0/0	R/W-0/0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0
SYSCMD	FVRMD	-	_	8 <del></del> 8	NVMMD	CLKRMD	IOCMD
7	80	7		30			0

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is clearedq = Value depends on condition

bit 7 SYSCMD: Disable Peripheral System Clock Network bit

See description in Section 16.4 "System Clock Disable".

1 = System clock network disabled (a.k.a. Fosc)

0 = System clock network enabled

bit 6 FVRMD: Disable Fixed Voltage Reference (FVR) bit

1 = FVR module disabled 0 = FVR module enabled

bit 5-3 Unimplemented: Read as '0'

bit 2 NVMMD: NVM Module Disable bit(1)

1 = User memory reading and writing is disabled; NVMCON registers cannot be written; FSR access

to these locations returns zero.

0 = NVM module enabled

bit 1 CLKRMD: Disable Clock Reference CLKR bit

1 = CLKR module disabled0 = CLKR module enabled

bit 0 IOCMD: Disable Interrupt-on-Change bit, All Ports

1 = IOC module(s) disabled 0 = IOC module(s) enabled

Note 1: When enabling NVM, a delay of up to 1 µs may be required before accessing data.

## REGISTER 16-2: PMD1: PMD CONTROL REGISTER 1

R/W-0/0	U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0
NCO1MD	.—»	s <del></del> 2	-	_	TMR2MD	TMR1MD	TMR0MD
bit 7	_	_					bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7 NCO1MD: Disable Numerically Control Oscillator bit 1 = NCO1 module disabled 0 = NCO1 module enabled bit 6-3 Unimplemented: Read as '0' bit 2 TMR2MD: Disable Timer TMR2 bit 1 = Timer2 module disabled 0 = Timer2 module enabled bit 1 TMR1MD: Disable Timer TMR1 bit 1 = Timer1 module disabled 0 = Timer1 module enabled bit 0 TMR0MD: Disable Timer TMR0 bit 1 = Timer0 module disabled 0 = Timer0 module enabled

## REGISTER 16-3: PMD2: PMD CONTROL REGISTER 2

U-0	R/W-0/0	R/W-0/0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0
_	DAC1MD	ADCMD	-	<del>-</del>	CMP2MD	CMP1MD	ZCDMD
bit 7			_				bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7	Unimplemented: Read as '0'
bit 6	DAC1MD: Disable DAC1 bit 1 = DAC module disabled 0 = DAC module enabled
bit 5	ADCMD: Disable ADC bit 1 = ADC module disabled 0 = ADC module enabled
bit 4-3	Unimplemented: Read as '0'
bit 2	<b>CMP2MD:</b> Disable Comparator C2 bit 1 = C2 module disabled 0 = C2 module enabled
bit 1	<b>CMP1MD:</b> Disable Comparator C1 bit 1 = C1 module disabled 0 = C1 module enabled
bit 0	<b>ZCDMD:</b> Disable ZCD bit 1 = ZCD module disabled 0 = ZCD module enabled

## REGISTER 16-4: PMD3: PMD CONTROL REGISTER 3

U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
<del></del>	-	PWM6MD	PWM5MD	PWM4MD	PWM3MD	CCP2MD	CCP1MD
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7-6	Unimplemented: Read as '0'
bit 5	<b>PWM6MD:</b> Disable Pulse-Width Modulator PWM6 bit 1 = PWM6 module disabled 0 = PWM6 module enabled
bit 4	<b>PWM5MD:</b> Disable Pulse-Width Modulator PWM5 bit 1 = PWM5 module disabled 0 = PWM5 module enabled
bit 3	<b>PWM4MD:</b> Disable Pulse-Width Modulator PWM4 bit 1 = PWM4 module disabled 0 = PWM4 module enabled
bit 2	<b>PWM3MD:</b> Disable Pulse-Width Modulator PWM3 bit 1 = PWM3 module disabled 0 = PWM3 module enabled
bit 1	CCP2MD: Disable CCP2 bit  1 = CCP2 module disabled  0 = CCP2 module enabled
bit 0	CCP1MD: Disable CCP1 bit  1 = CCP1 module disabled  0 = CCP1 module enabled

## REGISTER 16-5: PMD4: PMD CONTROL REGISTER 4

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	U-0	U-0	U-0	R/W-0/0
UART2MD	UART1MD	MSSP2MD	MSSP1MD	5		.—:	CWG1MD
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7	UART2MD: Disable EUSART2 bit 1 = EUSART2 module disabled 0 = EUSART2 module enabled
bit 6	UART1MD: Disable EUSART1 bit 1 = EUSART1 module disabled 0 = EUSART1 module enabled
bit 5	MSSP2MD: Disable MSSP2 bit 1 = MSSP2 module disabled 0 = MSSP2 module enabled
bit 4	MSSP1MD: Disable MSSP1 bit 1 = MSSP1 module disabled 0 = MSSP1 module enabled
bit 3-1	Unimplemented: Read as '0'
bit 0	CWG1MD: Disable CWG1 bit 1 = CWG1 module disabled 0 = CWG1 module enabled

## REGISTER 16-6: PMD5 - PMD CONTROL REGISTER 5

U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	U-0
_	_	s <del></del> z	CLC4MD	CLC3MD	CLC2MD	CLC1MD	, <del></del>
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7-5	Unimplemented: Read as '0'
bit 4	CLC4MD: Disable CLC4 bit
	<ul><li>1 = CLC4 module disabled</li><li>0 = CLC4 module enabled</li></ul>
bit 3	CLC3MD: Disable CLC3 bit
	1 = CLC3 module disabled 0 = CLC3 module enabled
bit 2	CLC2MD: Disable CLC2 bit
	1 = CLC2 module disabled 0 = CLC2 module enabled
bit 1	CLC1MD: Disable CLC1 bit
	1 = CLC1 module disabled 0 = CLC1 module enabled
bit 0	Unimplemented: Read as '0'

TABLE 16-1: SUMMARY OF REGISTERS ASSOCIATED WITH THE PMD MODULE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on page
PMD0	SYSCMD	FVRMD	_	÷	=	NVMMD	CLKRMD	IOCMD	204
PMD1	NCO1MD		<del>1</del>		_	TMR2MD	TMR1MD	TMR0MD	205
PMD2	_	DAC1MD	ADCMD	_	_	CMP2MD	CMP1MD	ZCDMD	206
PMD3	-	1-	PWM6MD	PWM5MD	PWM4MD	PWM3MD	CCP2MD	CCP1MD	207
PMD4	UART2MD	UART1MD	MSSP2MD	MSSP1MD	_	_	_	CWG1MD	208
PMD5	-	<del>-</del>	-	CLC4MD	CLC3MD	CLC2MD	CLC1MD	-	209

**Legend:** — = unimplemented, read as '0'. Shaded cells are unused by the PMD module.

## 17.0 INTERRUPT-ON-CHANGE

All pins on ports A, B and C and lower four bits of PORTE can be configured to operate as Interrupt-on-Change (IOC) pins. An interrupt can be generated by detecting a signal that has either a rising edge or a falling edge. Any individual pin, or combination of pins, can be configured to generate an interrupt. The interrupt-on-change module has the following features:

- Interrupt-on-Change enable (Host Switch)
- Individual pin configuration
- · Rising and falling edge detection
- · Individual pin interrupt flags

Figure 17-1 is a block diagram of the IOC module.

## 17.1 Enabling the Module

To allow individual pins to generate an interrupt, the IOCIE bit of the PIE0 register must be set. If the IOCIE bit is disabled, the edge detection on the pin will still occur, but an interrupt will not be generated.

## 17.2 Individual Pin Configuration

For each pin, a rising edge detector and a falling edge detector are present. To enable a pin to detect a rising edge, the associated bit of the IOCxP register is set. To enable a pin to detect a falling edge, the associated bit of the IOCxN register is set.

A pin can be configured to detect rising and falling edges simultaneously by setting the associated bits in both of the IOCxP and IOCxN registers.

## 17.3 Interrupt Flags

The bits located in the IOCxF registers are status flags that correspond to the interrupt-on-change pins of each port. If an expected edge is detected on an appropriately enabled pin, then the status flag for that pin will be set, and an interrupt will be generated if the IOCIE bit is set. The IOCIF bit of the PIR0 register reflects the status of all IOCxF bits.

#### 17.3.1 CLEARING INTERRUPT FLAGS

The individual status flags (IOCxF register bits) can be cleared by resetting them to zero. If another edge is detected during this clearing operation, the associated status flag will be set at the end of the sequence, regardless of the value actually being written.

To ensure that no detected edge is lost while clearing flags, only AND operations masking out known changed bits may be performed. The following sequence is an example of what may be performed.


# EXAMPLE 17-1: CLEARING INTERRUPT FLAGS (PORTA EXAMPLE)

MOVLW0xff XORWFIOCAF, W ANDWFIOCAF, F

## 17.4 Operation in Sleep

The interrupt-on-change interrupt event will wake the device from Sleep mode, if the IOCIE bit is set.

**FIGURE 17-1:** INTERRUPT-ON-CHANGE BLOCK DIAGRAM (PORTB EXAMPLE)



## 17.5 Register Definitions: Interrupt-on-Change Control

#### REGISTER 17-1: IOCAP: INTERRUPT-ON-CHANGE PORTA POSITIVE EDGE REGISTER

bit 7				š		1%	bit 0
IOCAP7	IOCAP6	IOCAP5	IOCAP4	IOCAP3	IOCAP2	IOCAP1	IOCAP0
R/W-0/0							

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 IOCAP<7:0>: Interrupt-on-Change PORTA Positive Edge Enable bits

- 1 = Interrupt-on-Change enabled on the pin for a positive-going edge. IOCAFx bit and IOCIF flag will be set upon detecting an edge.
- 0 = Interrupt-on-Change disabled for the associated pin.

#### REGISTER 17-2: IOCAN: INTERRUPT-ON-CHANGE PORTA NEGATIVE EDGE REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| IOCAN7  | IOCAN6  | IOCAN5  | IOCAN4  | IOCAN3  | IOCAN2  | IOCAN1  | IOCAN0  |
| bit 7   | •       |         |         |         |         | •       | bit 0   |

Legend:		=
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

## bit 7-0 IOCAN<7:0>: Interrupt-on-Change PORTA Negative Edge Enable bits

- 1 = Interrupt-on-Change enabled on the pin for a negative-going edge. IOCAFx bit and IOCIF flag will be set upon detecting an edge.
- 0 = Interrupt-on-Change disabled for the associated pin.

## REGISTER 17-3: IOCAF: INTERRUPT-ON-CHANGE PORTA FLAG REGISTER

| R/W/HS-0/0 |
|------------|------------|------------|------------|------------|------------|------------|------------|
| IOCAF7     | IOCAF6     | IOCAF5     | IOCAF4     | IOCAF3     | IOCAF2     | IOCAF1     | IOCAF0     |
| bit 7      |            |            |            |            |            |            | bit 0      |

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HS - Bit is set in hardware

## bit 7-0 IOCAF<7:0>: Interrupt-on-Change PORTA Flag bits

- 1 = An enabled change was detected on the associated pin. Set when IOCAPx = 1 and a rising edge was detected on RAx, or when IOCANx = 1 and a falling edge was detected on RAx.
- 0 = No change was detected, or the user cleared the detected change.

#### REGISTER 17-4: IOCBP: INTERRUPT-ON-CHANGE PORTB POSITIVE EDGE REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| IOCBP7  | IOCBP6  | IOCBP5  | IOCBP4  | IOCBP3  | IOCBP2  | IOCBP1  | IOCBP0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 IOCBP<7:0>: Interrupt-on-Change PORTB Positive Edge Enable bits

1 = Interrupt-on-Change enabled on the pin for a positive-going edge. IOCBFx bit and IOCIF flag will be set upon detecting an edge.

0 = Interrupt-on-Change disabled for the associated pin.

#### REGISTER 17-5: IOCBN: INTERRUPT-ON-CHANGE PORTB NEGATIVE EDGE REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| IOCBN7  | IOCBN6  | IOCBN5  | IOCBN4  | IOCBN3  | IOCBN2  | IOCBN1  | IOCBN0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 IOCBN<7:0>: Interrupt-on-Change PORTB Negative Edge Enable bits

1 = Interrupt-on-Change enabled on the pin for a negative-going edge. IOCBFx bit and IOCIF flag will be set upon detecting an edge.

0 = Interrupt-on-Change disabled for the associated pin.

## REGISTER 17-6: IOCBF: INTERRUPT-ON-CHANGE PORTB FLAG REGISTER

R/W/HS-0/0	R/W/HS-0/0 R/W/HS-0/0		R/W/HS-0/0	R/W/HS-0/0	R/W/HS-0/0	R/W/HS-0/0	
IOCBF7	IOCBF7 IOCBF6		IOCBF4	IOCBF3	IOCBF2	IOCBF1	IOCBF0
bit 7						•	bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HS - Bit is set in hardware

## bit 7-0 IOCBF<7:0>: Interrupt-on-Change PORTB Flag bits

- 1 = An enabled change was detected on the associated pin. Set when IOCBPx = 1 and a rising edge was detected on RBx, or when IOCBNx = 1 and a falling edge was detected on RBx.
- 0 = No change was detected, or the user cleared the detected change.

#### REGISTER 17-7: IOCCP: INTERRUPT-ON-CHANGE PORTC POSITIVE EDGE REGISTER

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
IOCCP7	IOCCP7 IOCCP6		IOCCP4	IOCCP3	IOCCP2	IOCCP1	IOCCP0
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set '0' = Bit is cleared

bit 7-0 IOCCP<7:0>: Interrupt-on-Change PORTC Positive Edge Enable bits

1 = Interrupt-on-Change enabled on the pin for a positive-going edge. IOCCFx bit and IOCIF flag will be set upon detecting an edge.

0 = Interrupt-on-Change disabled for the associated pin

## REGISTER 17-8: IOCCN: INTERRUPT-ON-CHANGE PORTC NEGATIVE EDGE REGISTER

R/W-0/0								
IOCCN7	IOCCN6	IOCCN5	IOCCN4	IOCCN3	IOCCN2	IOCCN1	IOCCN0	
bit 7								

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 IOCCN<7:0>: Interrupt-on-Change PORTC Negative Edge Enable bits

1 = Interrupt-on-Change enabled on the pin for a negative-going edge. IOCCFx bit and IOCIF flag will be set upon detecting an edge.

0 = Interrupt-on-Change disabled for the associated pin

## REGISTER 17-9: IOCCF: INTERRUPT-ON-CHANGE PORTC FLAG REGISTER

| R/W/HS-0/0 |
|------------|------------|------------|------------|------------|------------|------------|------------|
| IOCCF7     | IOCCF6     | IOCCF5     | IOCCF4     | IOCCF3     | IOCCF2     | IOCCF1     | IOCCF0     |
| bit 7      |            |            |            |            |            |            | bit 0      |

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set '0' = Bit is cleared HS - Bit is set in hardware

bit 7-0 IOCCF<7:0>: Interrupt-on-Change PORTC Flag bits

1 = An enabled change was detected on the associated pin Set when IOCCPx = 1 and a rising edge was detected on RCx, or when IOCCNx = 1 and a falling edge was detected on RCx.

0 = No change was detected, or the user cleared the detected change

#### REGISTER 17-10: IOCEP: INTERRUPT-ON-CHANGE PORTE POSITIVE EDGE REGISTER

U-0	U-0	U-0	U-0	R/W/HS-0/0	U-0	U-0	U-0
<del></del> -	10-		12	IOCEP3	-	-	<del>-</del>
bit 7	•						bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HS - Bit is set in hardware

bit 7-4 Unimplemented: Read as '0'

bit 3 IOCEP3: Interrupt-on-Change PORTE Positive Edge Enable bit

1 = Interrupt-on-Change enabled on the pin for a positive-going edge. IOCCFx bit and IOCIF flag will be set upon detecting an edge.

0 = Interrupt-on-Change disabled for the associated pin

bit 2-0 Unimplemented: Read as '0'

## REGISTER 17-11: IOCEN: INTERRUPT-ON-CHANGE PORTE NEGATIVE EDGE REGISTER

U-0	U-0	U-0	U-0	R/W/HS-0/0	U-0	U-0	U-0
_	·—·	<u></u>	_	IOCEN3	8 <u></u> 8)	<u></u>	( <del>)</del> ()
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HS - Bit is set in hardware

bit 7-4 Unimplemented: Read as '0'

bit 3 IOCEN3: Interrupt-on-Change PORTE Negative Edge Enable bit

1 = Interrupt-on-Change enabled on the pin for a negative-going edge. IOCCFx bit and IOCIF flag will

be set upon detecting an edge.

0 = Interrupt-on-Change disabled for the associated pin

bit 2-0 Unimplemented: Read as '0'

## REGISTER 17-12: IOCEF: INTERRUPT-ON-CHANGE PORTE FLAG REGISTER

U-0	U-0	U-0	U-0	R/W/HS-0/0	U-0	U-0	U-0
<del></del> :	-	<del>11 1</del> 2	-	IOCEF3	0 <del></del> 0	<del></del>	(
bit 7						-	bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HS - Bit is set in hardware

bit 7-4 Unimplemented: Read as '0'

bit 3 IOCEF3: Interrupt-on-Change PORTE Flag bit

1 = An enabled change was detected on the associated pin

Set when IOCCPx = 1 and a rising edge was detected on RCx, or when IOCCNx = 1 and a falling

edge was detected on RCx.

0 = No change was detected, or the user cleared the detected change

bit 2-0 Unimplemented: Read as '0'

TABLE 17-1: SUMMARY OF REGISTERS ASSOCIATED WITH INTERRUPT-ON-CHANGE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
INTCON	GIE	PEIE	_		_	_		INTEDG	121
PIE0	-	7	TMR0IE	IOCIE	-		-	INTE	122
IOCAP	IOCAP7	IOCAP6	IOCAP5	IOCAP4	IOCAP3	IOCAP2	IOCAP1	IOCAP0	213
IOCAN	IOCAN7	IOCAN6	IOCAN5	IOCAN4	IOCAN3	IOCAN2	IOCAN1	IOCAN0	213
IOCAF	IOCAF7	IOCAF6	IOCAF5	IOCAF4	IOCAF3	IOCAF2	IOCAF1	IOCAF0	214
IOCBP	IOCBP7	IOCBP6	IOCBP5	IOCBP4	IOCBP3	IOCBP2	IOCBP1	IOCBP0	215
IOCBN	IOCBN7	IOCBN6	IOCBN5	IOCBN4	IOCBN3	IOCBN2	IOCBN1	IOCBN0	215
IOCBF	IOCBF7	IOCBF6	IOCBF5	IOCBF4	IOCBF3	IOCBF2	IOCBF1	IOCBF0	216
IOCCP	IOCCP7	IOCCP6	IOCCP5	IOCCP4	IOCCP3	IOCCP2	IOCCP1	IOCCP0	217
IOCCN	IOCCN7	IOCCN6	IOCCN5	IOCCN4	IOCCN3	IOCCN2	IOCCN1	IOCCN0	217
IOCCF	IOCCF7	IOCCF6	IOCCF5	IOCCF4	IOCCF3	IOCCF2	IOCCF1	IOCCF0	218
IOCEP	-	_	_	_	IOCEP3	_	-	(5-2)	218
IOCEN	-	= [	-	=	IOCEN3	_	-		219
IOCEF	_	_		_	IOCEF3	-	× <del></del>	::	219

Legend: — = unimplemented location, read as '0'. Shaded cells are not used by interrupt-on-change.

## 18.0 FIXED VOLTAGE REFERENCE (FVR)

The Fixed Voltage Reference, or FVR, is a stable voltage reference, independent of VDD, with 1.024V, 2.048V or 4.096V selectable output levels. The output of the FVR can be configured to supply a reference voltage to the following:

- ADC input channel
- ADC positive reference
- · Comparator positive and negative input
- · Digital-to-Analog Converter (DAC)

The FVR can be enabled by setting the FVREN bit of the FVRCON register.

Note: Fixed Voltage Reference output cannot exceed VDD.

## 18.1 Independent Gain Amplifiers

The output of the FVR, which is connected to the ADC, comparators, and DAC, is routed through two independent programmable gain amplifiers. Each amplifier can be programmed for a gain of 1x, 2x or 4x, to produce the three possible voltage levels.

The ADFVR<1:0> bits of the FVRCON register are used to enable and configure the gain amplifier settings for the reference supplied to the ADC module. Reference Section 20.0 "Analog-to-Digital Converter (ADC) Module" for additional information.


The CDAFVR<1:0> bits of the FVRCON register are used to enable and configure the gain amplifier settings for the reference supplied to the DAC and comparator module. Reference Section 21.0 "5-Bit Digital-to-Analog Converter (DAC1) Module" and Section 23.0 "Comparator Module" for additional information.

### 18.2 FVR Stabilization Period

When the Fixed Voltage Reference module is enabled, it requires time for the reference and amplifier circuits to stabilize.

FVRRDY is an indicator of the reference being ready. In the case of an LF device, or a device on which the BOR is enabled in the Configuration Word settings, then the FVRRDY bit will be high prior to setting FVREN as those module require the reference voltage.

FIGURE 18-1: VOLTAGE REFERENCE BLOCK DIAGRAM



## 18.3 Register Definitions: FVR Control

## REGISTER 18-1: FVRCON: FIXED VOLTAGE REFERENCE CONTROL REGISTER

R/W-0/0	R-q/q	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
FVREN	FVRRDY <sup>(1)</sup>	TSEN(3)	TSRNG <sup>(3)</sup>	CDAF\	/R<1:0>	ADFV	R<1:0>
bit 7							bit 0

Legend:		-
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7	FVREN: Fixed Voltage Reference Enable bit  1 = Fixed Voltage Reference is enabled  0 = Fixed Voltage Reference is disabled
bit 6	<b>FVRRDY:</b> Fixed Voltage Reference Ready Flag bit <sup>(1)</sup> 1 = Fixed Voltage Reference output is ready for use  0 = Fixed Voltage Reference output is not ready or not enabled
bit 5	TSEN: Temperature Indicator Enable bit <sup>(3)</sup> 1 = Temperature Indicator is enabled  0 = Temperature Indicator is disabled
bit 4	TSRNG: Temperature Indicator Range Selection bit <sup>(3)</sup> 1 = Temperature in High Range Vout = 3VT  0 = Temperature in Low Range Vout = 2VT
bit 3-2	CDAFVR<1:0>: Comparator FVR Buffer Gain Selection bits  11 =Comparator FVR Buffer Gain is 4x, (4.096V) <sup>(2)</sup> 10 =Comparator FVR Buffer Gain is 2x, (2.048V) <sup>(2)</sup> 01 =Comparator FVR Buffer Gain is 1x, (1.024V)  00 =Comparator FVR Buffer is off
bit 1-0	ADFVR<1:0>: ADC FVR Buffer Gain Selection bit 11 =ADC FVR Buffer Gain is 4x, (4.096V) <sup>(2)</sup> 10 =ADC FVR Buffer Gain is 2x, (2.048V) <sup>(2)</sup> 01 =ADC FVR Buffer Gain is 1x, (1.024V) 00 =ADC FVR Buffer is off

Note 1: FVRRDY is always '1'.

2: Fixed Voltage Reference output cannot exceed VDD.

3: See Section 19.0 "Temperature Indicator Module" for additional information.

TABLE 18-1: SUMMARY OF REGISTERS ASSOCIATED WITH FIXED VOLTAGE REFERENCE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on page
FVRCON	FVREN	FVRRDY	TSEN	TSEN TSRNG CDAFVR<1:0>				ADFVR<1:0>	
ADCON0			CHS<	5:0>			GO/DONE	ADON	234
ADCON1	ADFM	V	ADCS<2:0>			_	ADPRE	F<1:0>	235
DAC1CON0	DAC1EN	:	— DAC10E1 DAC10E2			SS<1:0>	_	DAC1NSS	243

Legend: -= unimplemented locations read as '0'. Shaded cells are not used with the Fixed Voltage Reference.

## 19.0 TEMPERATURE INDICATOR MODULE

This family of devices is equipped with a temperature circuit designed to measure the operating temperature of the silicon die.


The circuit's range of operating temperature falls between -40°C and +125°C. A one-point calibration allows the circuit to indicate a temperature closely surrounding that point. A two-point calibration allows the circuit to sense the entire range of temperature more accurately.

## 19.1 Module Operation

The temperature indicator module consists of a temperature-sensing circuit that provides a voltage to the device ADC. The analog voltage output, VMEAS, varies inversely to the device temperature. The output of the temperature indicator is referred to as VMEAS.

Figure 19-1 shows a simplified block diagram of the temperature indicator module.

FIGURE 19-1: TEMPERATURE INDICATOR MODULE BLOCK DIAGRAM



The output of the circuit is measured using the internal Analog-to-Digital Converter. A channel is reserved for the temperature circuit output. Refer to Section 20.0 "Analog-to-Digital Converter (ADC) Module" for detailed information.

The ON/OFF bit for the module is located in the FVRCON register. See Section 18.0 "Fixed Voltage Reference (FVR)" for more information. The circuit is enabled by setting the TSEN bit of the FVRCON register. When the module is disabled, the circuit draws no current.

The circuit operates in either High or Low range. Refer to Section 19.1.1 "Temperature Indicator Range" for more details on the range settings.

## 19.1.1 TEMPERATURE INDICATOR RANGE

The temperature indicator circuit operates in either high or low range. The high range, selected by setting the TSRNG bit of the FVRCON register, provides a wider output voltage. This provides more resolution over the temperature range. High range requires a higher-bias voltage to operate and thus, a higher VDD is needed. The low range is selected by clearing the TSRNG bit of the FVRCON register. The low range generates a lower sensor voltage and thus, a lower VDD voltage is needed to operate the circuit.

The output voltage of the sensor is the highest value at -40°C and the lowest value at +125°C.

- High Range: The High range is used in applications with the reference for the ADC,
   VREF = 2.048V. This range may not be suitable for battery-powered applications. The ADC reading (in counts) at 90°C for the high range setting is stored in the DIA Table (Table 6-1) as parameter TSHR2.
- Low Range: This mode is useful in applications in which the VDD is too low for high-range operation. The VDD in this mode can be as low as 1.8V. VDD must, however, be at least 0.5V higher than the maximum sensor voltage depending on the expected low operating temperature. The ADC reading (in counts) at 90°C for the Low range setting is stored in the DIA Table (Table 6-1) as parameter TSLR2.

## 19.1.2 MINIMUM OPERATING VDD

When the temperature circuit is operated in low range, the device may be operated at any operating voltage that is within specifications. When the temperature circuit is operated in high range, the device operating voltage, VDD, must be high enough to ensure that the temperature circuit is correctly biased.

Table 19-1 shows the recommended minimum VDD vs. Range setting.

TABLE 19-1: RECOMMENDED VDD vs. RANGE

Min.V <sub>DD</sub> , TSRNG = 1	Min. VDD, TSRNG = 0
(High Range)	(Low Range)
≥ 2.5	≥ 1.8

## 19.2 Temperature Calculation

This section describes the steps involved in calculating the die temperature, TMEAS:

- Obtain the ADC count value of the measured analog voltage: The analog output voltage, VMEAS is converted to a digital count value by the Analog-to-Digital Converter (ADC) and is referred to as ADCMEAS.
- Obtain the ADC count value, ADCDIA at 90 degrees, in the DIA table (Table 6-1). This parameter is TSLR2 for the low range setting or TSHR2 for the high range setting of the temperature indicator module.
- Obtain the output analog voltage (in mV) value of the Fixed Reference Voltage (FVR) for 2x setting, from the DIA Table. This parameter is FVRA2X in the DIA table (Table 6-1).
- Obtain the value of the temperature indicator voltage sensitivity, parameter Mv, from Table 37-26 for the corresponding range setting.

Equation 19-1 provides an estimate for the die temperature based on the above parameters.

### **EQUATION 19-1: SENSOR TEMPERATURE**

$T_{MEAS} = 90 +$	$(ADC_{MEAS} - ADC_{DIA}) \times FVRA2X$
MEAS - 90	$(2^N-1)\times MV$

Where:

ADCMEAS = ADC reading at temperature being estimated

ADCDIA = ADC reading stored in the DIA

FVRA2X = FVR value stored in the DIA for 2x setting

N = Resolution of the ADC

Mv = Temperature Indicator voltage sensitivity (mV/°C)

## Note 1: It is recommended to take the average of ten measurements of ADCmeas to reduce noise and improve accuracy.

 Refer to Section 37.0, Electrical Specifications for FVR reference voltage accuracy.

#### 19.2.1 CALIBRATION

## 19.2.1.1 Higher-Order Calibration

If the application requires more precise temperature measurement, additional calibrations steps will be necessary. For these applications, two-point or three-point calibration is recommended.

## 19.3 ADC Acquisition Time

To ensure accurate temperature measurements, the user must wait a certain minimum acquisition time (parameter TS01 in Table 37-26) for the ADC value to settle, after the ADC input multiplexer is connected to the temperature indicator output, before the conversion is performed.

## TABLE 19-2: SUMMARY OF REGISTERS ASSOCIATED WITH THE TEMPERATURE INDICATOR<sup>(1)</sup>

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on page
FVRCON	EN	RDY	TSEN	TSRNG	CDAFV	'R<1:0>	ADFVI	R<1:0>	222

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are unused by the temperature indicator module.

Note 1: It is recommended to take the average of ten measurements of ADCMEAS to reduce noise and improve accuracy.


# 20.0 ANALOG-TO-DIGITAL CONVERTER (ADC) MODULE

The Analog-to-Digital Converter (ADC) allows conversion of an analog input signal to a 10-bit binary representation of that signal. This device uses analog inputs, which are multiplexed into a single sample and hold circuit. The output of the sample and hold is connected to the input of the converter. The converter generates a 10-bit binary result via successive approximation and stores the conversion result into the ADC result registers (ADRESH:ADRESL register pair). Figure 20-1 shows the block diagram of the ADC.

The ADC voltage reference is software selectable to be either internally generated or externally supplied.

The ADC can generate an interrupt upon completion of a conversion. This interrupt can be used to wake-up the device from Sleep.

FIGURE 20-1: ADC BLOCK DIAGRAM



## 20.1 ADC Configuration

When configuring and using the ADC the following functions must be considered:

- Port configuration
- · Channel selection
- · ADC voltage reference selection
- · ADC conversion clock source
- Interrupt control
- Result formatting

## 20.1.1 PORT CONFIGURATION

The ADC can be used to convert both analog and digital signals. When converting analog signals, the I/O pin will be configured for analog by setting the associated TRIS and ANSEL bits. Refer to Section 14.0 "I/O Ports" for more information.

Note: Analog voltages on any pin that is defined as a digital input may cause the input buffer to conduct excess current.

## 20.1.2 CHANNEL SELECTION

There are several channel selections available:

- · Seven Port A channels
- Seven Port B channels
- Seven Port C channels
- · Temperature Indicator
- DAC output
- Fixed Voltage Reference (FVR)
- AVSS (Ground)

The CHS<5:0> bits of the ADCON0 register (Register 20-1) determine which channel is connected to the sample and hold circuit.

When changing channels, a delay is required before starting the next conversion. Refer to **Section 20.2** "ADC Operation" for more information.

Note: It is recommended that when switching from an ADC channel of a higher voltage to a channel of a lower voltage, that the user selects the Vss channel before connecting to the channel with the lower voltage. If the ADC does not have a dedicated Vss input channel, the Vss selection (DAC1R<4:0> = b'00000') through the DAC output channel can be used. If the DAC is in use, a free input channel can be connected to Vss, and can be used in place of the DAC.

#### 20.1.3 ADC VOLTAGE REFERENCE

The ADPREF<1:0> bits of the ADCON1 register provides control of the positive voltage reference. The positive voltage reference can be:

- VREF+ pin
- VDD
- FVR 2.048V
- FVR 4.096V (Not available on LF devices)

The ADPREF bit of the ADCON1 register provides control of the negative voltage reference. The negative voltage reference can be:

- VREF- pin
- Vss

See Section 18.0 "Fixed Voltage Reference (FVR)" for more details on the Fixed Voltage Reference.

#### 20.1.4 CONVERSION CLOCK

The source of the conversion clock is software selectable via the ADCS<2:0> bits of the ADCON1 register. There are seven possible clock options:

- Fosc/2
- Fosc/4
- Fosc/8
- Fosc/16
- Fosc/32
- Fosc/64
- FRC (dedicated RC oscillator)

The time to complete one bit conversion is defined as TAD. One full 10-bit conversion requires 11.5 TAD periods as shown in Figure 20-2.

For correct conversion, the appropriate TAD specification must be met. Refer to Table 37-13 for more information. Table 20-1 gives examples of appropriate ADC clock selections.

Note: Unless using the FRC, any changes in the system clock frequency will change the ADC clock frequency, which may adversely affect the ADC result.

TABLE 20-1: ADC CLOCK PERIOD (TAD) Vs. DEVICE OPERATING FREQUENCIES


ADC Clock Period (TAD)		Device Frequency (Fosc)						
ADC Clock Source	ADCS<2:0>	32 MHz	20 MHz	16 MHz	8 MHz	4 MHz	1 MHz	
Fosc/2	000	62.5ns <sup>(2)</sup>	100 ns <sup>(2)</sup>	125 ns <sup>(2)</sup>	250 ns <sup>(2)</sup>	500 ns <sup>(2)</sup>	2.0 μs	
Fosc/4	100	125 ns <sup>(2)</sup>	200 ns <sup>(2)</sup>	250 ns <sup>(2)</sup>	500 ns <sup>(2)</sup>	1.0 μs	4.0 μs	
Fosc/8	001	0.5 μs <sup>(2)</sup>	400 ns <sup>(2)</sup>	0.5 μs <sup>(2)</sup>	1.0 μs	2.0 μs	8.0 μs <sup>(3)</sup>	
Fosc/16	101	800 ns	800 ns	1.0 μs	2.0 μs	4.0 μs	16.0 μs <sup>(3)</sup>	
Fosc/32	010	1.0 μs	1.6 μs	2.0 μs	4.0 μs	8.0 μs <sup>(3)</sup>	32.0 μs <sup>(2)</sup>	
Fosc/64	110	2.0 μs	3.2 μs	4.0 μs	8.0 μs <sup>(3)</sup>	16.0 μs <sup>(2)</sup>	64.0 μs <sup>(2)</sup>	
FRC	x11	1.0-6.0 μs <sup>(1,4)</sup>						

Legend: Shaded cells are outside of recommended range.

Note 1: See TAD parameter for FRC source typical TAD value.

- 2: These values violate the required TAD time.
- 3: Outside the recommended TAD time.
- 4: The ADC clock period (TAD) and total ADC conversion time can be minimized when the ADC clock is derived from the system clock Fosc. However, the FRC oscillator source must be used when conversions are to be performed with the device in Sleep mode.

FIGURE 20-2: ANALOG-TO-DIGITAL CONVERSION TAD CYCLES



#### 20.1.5 INTERRUPTS

The ADC module allows for the ability to generate an interrupt upon completion of an Analog-to-Digital conversion. The ADC Interrupt Flag is the ADIF bit in the PIR1 register. The ADC Interrupt Enable is the ADIE bit in the PIE1 register. The ADIF bit must be cleared in software.

- Note 1: The ADIF bit is set at the completion of every conversion, regardless of whether or not the ADC interrupt is enabled.
  - 2: The ADC operates during Sleep only when the FRC oscillator is selected.


This interrupt can be generated while the device is operating or while in Sleep. If the device is in Sleep, the interrupt will wake-up the device. Upon waking from Sleep, the next instruction following the SLEEP instruction is always executed. If the user is attempting to wake-up from Sleep and resume in-line code execution, the ADIE bit of the PIE1 register and the PEIE bit of the INTCON register must both be set and the GIE bit of the INTCON register must be cleared. If all three of these bits are set, the execution will switch to the Interrupt Service Routine (ISR).

#### 20.1.6 RESULT FORMATTING

The 10-bit ADC conversion result can be supplied in two formats, left justified or right justified. The ADFM bit of the ADCON1 register controls the output format.

Figure 20-3 shows the two output formats.

FIGURE 20-3: 10-BIT ADC CONVERSION RESULT FORMAT



## 20.2 ADC Operation

#### 20.2.1 STARTING A CONVERSION

To enable the ADC module, the ADON bit of the ADCON0 register must be set to a '1'. Setting the GO/DONE bit of the ADCON0 register to a '1' will start the Analog-to-Digital conversion.

Note: The GO/DONE bit will not be set in the same instruction that turns on the ADC. Refer to Section 20.2.5 "ADC Conversion Procedure".

## 20.2.2 COMPLETION OF A CONVERSION

When the conversion is complete, the ADC module will:

- · Clear the GO/DONE bit
- · Set the ADIF Interrupt Flag bit
- Update the ADRESH and ADRESL registers with new conversion result

Note: A device Reset forces all registers to their Reset state. Thus, the ADC module is turned off and any pending conversion is terminated.

## 20.2.3 ADC OPERATION DURING SLEEP

The ADC module can operate during Sleep. This requires the ADC clock source to be set to the FRC option. When the FRC oscillator source is selected, the ADC waits one additional instruction before starting the conversion. This allows the SLEEP instruction to be executed, which can reduce system noise during the conversion. If the ADC interrupt is enabled, the device will wake-up from Sleep when the conversion completes. If the ADC interrupt is disabled, the ADC module is turned off after the conversion completes, although the ADON bit remains set.

When the ADC clock source is something other than FRC, a SLEEP instruction causes the present conversion to be aborted and the ADC module is turned off, although the ADON bit remains set.

## 20.2.4 AUTO-CONVERSION TRIGGER

The Auto-conversion Trigger allows periodic ADC measurements without software intervention. When a rising edge of the selected source occurs, the GO/ DONE bit is set by hardware.

The Auto-conversion Trigger source is selected with the ADACT<4:0> bits of the ADACT register.

Using the Auto-conversion Trigger does not assure proper ADC timing. It is the user's responsibility to ensure that the ADC timing requirements are met.

See Table 20-2 for auto-conversion sources.

Note: The Auto-conversion feature is not available while the device is in Sleep mode.

TABLE 20-2: ADC AUTO-CONVERSION TABLE

ADACT VALUE	SOURCE/ PERIPHERAL	DESCRIPTION
0x00	Disabled	External Trigger Disabled
0x01	ADACTPPS	Pin Selected by ADACTPPS
0x02	TMR0	Timer0 overflow condition
0x03	TMR1	Timer1 overflow condition
0x04	TMR2	Match between Timer2 postscaled value and PR2
0x05	CCP1	CCP1 output
0x06	CCP2	CCP2 output
0x07	PWM3	PWM3 output
0x08	PWM4	PWM4 output
0x09	PWM5	PWM5 output
0x0A	PWM6	PWM6 output
0x0B	NCO1	NCO1 output
0x0C	C1OUT	Comparator C1 output
0x0D	C2OUT	Comparator C2 output
0x0E	IOCIF	Interrupt-on change flag trigger
0x0F	CLC1	CLC1 output
0x10	CLC2	CLC2 output
0x11	CLC3	CLC3 output
0x12	CLC4	CLC4 output
0x13-0xFF	Reserved	Reserved, do not use

#### 20.2.5 ADC CONVERSION PROCEDURE

This is an example procedure for using the ADC to perform an Analog-to-Digital conversion:

- Configure Port:
  - Disable pin output driver (Refer to the TRIS register)
  - Configure pin as analog (Refer to the ANSEL register)
- 2. Configure the ADC module:
  - · Select ADC conversion clock
  - · Select voltage reference
  - · Select ADC input channel
  - · Turn on ADC module
- 3. Configure ADC interrupt (optional):
  - · Clear ADC interrupt flag
  - · Enable ADC interrupt
  - Enable peripheral interrupt
  - Enable global interrupt<sup>(1)</sup>
- 4. Wait the required acquisition time<sup>(2)</sup>.
- 5. Start conversion by setting the GO/DONE bit.
- Wait for ADC conversion to complete by one of the following:
  - · Polling the GO/DONE bit
  - · Waiting for the ADC interrupt
- 7. Read ADC Result.
- Clear the ADC interrupt flag (required if interrupt is enabled).
  - Note 1: The global interrupt can be disabled if the user is attempting to wake-up from Sleep and resume in-line code execution.
    - Refer to Section 20.3 "ADC Acquisition Requirements".

## **EXAMPLE 20-1: ADC CONVERSION**

```
; This code block configures the ADC
; for polling, Vdd and Vss references, FRC
;oscillator and ANO input.
; Conversion start & polling for completion ;
are included.
BANKSELADCON1:
MOVLWB'11110000'; Right justify, FRC
        ; oscillator
MOVWFADCON1; Vdd and Vss Vref
BANKSELTRISA;
BSF TRISA, 0; Set RAO to input
BANKSELANSELA:
BSF ANSELA, 0; Set RAO to analog
BANKSELADCONO:
MOVLWB'00000001'; Select channel ANO
MOVWFADCON0; Turn ADC On
CALLSampleTime; Acquisiton delay
BSF ADCON0, ADGO; Start conversion
BTFSCADCON0, ADGO; Is conversion done?
GOTO$-1 ; No, test again
BANKSELADRESH;
MOVFADRESH, W; Read upper 2 bits
MOVWFRESULTHI; store in GPR space
BANKSELADRESL;
MOVFADRESL, W; Read lower 8 bits
MOVWFRESULTLO; Store in GPR space
```

## 20.3 ADC Acquisition Requirements

For the ADC to meet its specified accuracy, the charge holding capacitor (CHOLD) must be allowed to fully charge to the input channel voltage level. The Analog Input model is shown in Figure 20-4. The source impedance (Rs) and the internal sampling switch (Rss) impedance directly affect the time required to charge the capacitor CHOLD. The sampling switch (Rss) impedance varies over the device voltage (VDD), refer to Figure 20-4. The maximum recommended impedance for analog sources is 10 kΩ. As the

source impedance is decreased, the acquisition time may be decreased. After the analog input channel is selected (or changed), an ADC acquisition must be done before the conversion can be started. To calculate the minimum acquisition time, Equation 20-1 may be used. This equation assumes that 1/2 LSb error is used (1024 steps for the ADC). The 1/2 LSb error is the maximum error allowed for the ADC to meet its specified resolution.

#### **EQUATION 20-1: ACQUISITION TIME EXAMPLE**

Assumptions: Temperature =  $50^{\circ}$ C and external impedance of  $10k\Omega$  5.0V VDD

$$TACQ = Amplifier Settling Time + Hold Capacitor Charging Time + Temperature Coefficient$$
  
=  $TAMP + TC + TCOFF$   
=  $2\mu s + TC + [(Temperature - 25°C)(0.05\mu s/°C)]$ 

The value for Tc can be approximated with the following equations:

$$V_{APPLIED}\left(1-\frac{1}{(2^{n+1})-1}\right) = V_{CHOLD}$$
 ;[1]  $V_{CHOLD}$  charged to within 1/2 lsb

$$V_{APPLIED} \left(1 - e^{\frac{-Tc}{RC}}\right) = V_{CHOLD}$$
 ;[2]  $V_{CHOLD}$  charge response to  $V_{APPLIED}$ 

$$V_{APPLIED}\left(1-e^{\frac{-Tc}{RC}}\right) = V_{APPLIED}\left(1-\frac{1}{(2^{n+1})-1}\right)$$
 ; combining [1] and [2]

*Note:* Where n = number of bits of the ADC.

Solving for TC:

$$TC = -C_{HOLD}(RIC + RSS + RS) \ln(1/2047)$$

$$= -10pF(1k\Omega + 7k\Omega + 10k\Omega) \ln(0.0004885)$$


$$= 1.37\mu s$$

Therefore:


$$TACQ = 2\mu s + 1.37 + [(50^{\circ}C - 25^{\circ}C)(0.05\mu s/^{\circ}C)]$$
  
= 4.62\mu s

- Note 1: The VAPPLIED has no effect on the equation, since it cancels itself out.
  - 2: The charge holding capacitor (CHOLD) is not discharged after each conversion.
  - 3: The maximum recommended impedance for analog sources is 10 kΩ. This is required to meet the pin leakage specification.

FIGURE 20-4: ANALOG INPUT MODEL



## FIGURE 20-5: ADC TRANSFER FUNCTION



## 20.4 Register Definitions: ADC Control

## REGISTER 20-1: ADCON0: ADC CONTROL REGISTER 0

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
CHS<5:0>						GO/DONE	ADON
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown n/n - Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-2 CHS<5:0>: Analog Channel Select bits 111111 =FVR Buffer 2 reference voltage(2) 111110 =FVR 1Buffer 1 reference voltage(2) 111101 =DAC1 output voltage(1) 111100 =Temperature sensor output(3) 111011 = AVSS (Analog Ground) 111010-011000 = Reserved. No channel connected 010111 = RC7010110 = RC6 010101 = RC5 010100 = RC4 010011 = RC3 010010 = RC2010001 = RC1 010000 = RC0 001111 = RB7 001110 = RB6 001101 = RB5 001100 = RB4 001011 = RB3 001010 = RB2 001001 = RB1 001000 = RB0  $001011 = RA7^{(4)}$ 000110 = RA6000101 = RA5 000100 = RA4 000011 = RA3 000010 = RA2 000001 = RA1 000000 = RA0

bit 1 GO/DONE: ADC Conversion Status bit

1 = ADC conversion cycle in progress. Setting this bit starts an ADC conversion cycle.
 This bit is automatically cleared by hardware when the ADC conversion has completed.
 ADC conversion completed/not in progress.

0 = ADC conversion completed/not in progress

bit 0 ADON: ADC Enable bit

1 = ADC is enabled

0 = ADC is disabled and consumes no operating current

Note 1: See Section 21.0 "5-Bit Digital-to-Analog Converter (DAC1) Module" for more information.

2: See Section 18.0 "Fixed Voltage Reference (FVR)" for more information.

3: See Section 19.0 "Temperature Indicator Module" for more information.

The analog channel functionality on these pins is disabled when the system clock source is selected is external.

## REGISTER 20-2: ADCON1: ADC CONTROL REGISTER 1

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	U-0	U-0	R/W-0/0	R/W-0/0
ADFM	ADCS<2:0>				-	ADPRE	F<1:0>
bit 7	\$6:			X222	3	-80	bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7 ADFM: ADC Result Format Select bit

1 = Right justified. Six Most Significant bits of ADRESH are set to '0' when the conversion result is loaded.

0 = Left justified. Six Least Significant bits of ADRESL are set to '0' when the conversion result is loaded.

bit 6-4 ADCS<2:0>: ADC Conversion Clock Select bits

111 = FRC (dedicated RC oscillator)

110 = Fosc/64

101 = Fosc/16

100 = Fosc/4

011 = FRC (dedicated RC oscillator)

010 = Fosc/32

001 = Fosc/8

000 = Fosc/2

bit 3-2 Unimplemented: Read as '0'

bit 1-0 ADPREF<1:0>: ADC Positive Voltage Reference Configuration bits

11 = VREF+ is connected to internal Fixed Voltage Reference (FVR) module(1)

10 = VREF+ is connected to external VREF+ pin(1)

01 = Reserved

00 = VREF+ is connected to VDD

Note 1: When selecting the VREF+ pin as the source of the positive reference, be aware that a minimum voltage specification exists. See Table 37-14 for details.

## REGISTER 20-3: ADACT: A/D AUTO-CONVERSION TRIGGER

U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
_		-		:	ADACT<4:0>		
bit 7	90	80					bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-5 Unimplemented: Read as '0'

bit 4-0 ADACT<4:0>: Auto-Conversion Trigger Selection bits<sup>(1)</sup> (see Table 20-2)

Note 1: This is a rising edge sensitive input for all sources.

## REGISTER 20-4: ADRESH: ADC RESULT REGISTER HIGH (ADRESH) ADFM = 0

R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	
			ADRES	6<9:2>				
bit 7	bit 7 bit 0							

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown
'1' = Bit is set '0' = Bit is cleared

U = Unimplemented bit, read as '0'

-n/n = Value at POR and BOR/Value at all other Resets

bit 7-0 ADRES<9:2>: ADC Result Register bits
Upper eight bits of 10-bit conversion result

## REGISTER 20-5: ADRESL: ADC RESULT REGISTER LOW (ADRESL) ADFM = 0

R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
ADRES	S<1:0>	( <del></del> 1)		-	( <del></del> (	-	_
bit 7		-				,,,	bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-6 ADRES<1:0>: ADC Result Register bits

Lower two bits of 10-bit conversion result

bit 5-0 Reserved: Do not use.

## REGISTER 20-6: ADRESH: ADC RESULT REGISTER HIGH (ADRESH) ADFM = 1

R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
	,	( <del></del> )		() <del>2</del>		ADRES	S<9:8>
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-2 Reserved: Do not use.

bit 1-0 ADRES<9:8>: ADC Result Register bits
Upper two bits of 10-bit conversion result

## REGISTER 20-7: ADRESL: ADC RESULT REGISTER LOW (ADRESL) ADFM = 1

R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
			ADRES	6<7:0>			
bit 7 bit 0							

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown
'1' = Bit is set '0' = Bit is cleared

U = Unimplemented bit, read as '0'

-n/n = Value at POR and BOR/Value at all other Resets

bit 7-0 ADRES<7:0>: ADC Result Register bits
Lower eight bits of 10-bit conversion result

TABLE 20-3: SUMMARY OF REGISTERS ASSOCIATED WITH ADC

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
INTCON	GIE	PEIE				<u> </u>	·—	INTEDG	121
PIE1	OSFIE	CSWIE		:	-	-	_	ADIE	123
PIR1	OSFIF	CSWIF	-	_	_	_	×—×	ADIF	131
TRISA	TRISA7	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	175
TRISB	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	181
TRISC	TRISC7	TRISC6	TRISC5	TRISC4	TRISC3	TRISC2	TRISC1	TRISC0	186
ANSELA	ANSA7	ANSA6	ANSA5	ANSA4	ANSA3	ANSA2	ANSA1	ANSA0	176
ANSELB	ANSB7	ANSB6	ANSB5	ANSB4	ANSB3	ANSB2	ANSB1	ANSB0	182
ANSELC	ANSC7	ANSC6	ANSC5	ANSC4	ANSC3	ANSC2	ANSC1	ANSC0	187
ADCON0			CHS<	5:0>			GO/DONE	ADON	234
ADCON1	ADFM		ADCS<2:0>	13	-	-	ADPREF	235	
ADACT	<del></del> .	<del></del> .	s <del></del>		7 St	ADACT<4	:0>		236
ADRESH		•		ADRE	SH<7:0>				237
ADRESL		ADRESL<7:0>						237	
FVRCON	FVREN	FVRRDY	TSEN	TSRNG CDAFVR<1:0> ADFVR<1:0>					222
DAC1CON1		— — DAC1R<4:0>							243
OSCSTAT1	EXTOR	HFOR	MFOR	LFOR	SOR	ADOR	.—.	PLLR	112

**Legend:** — = unimplemented read as '0'. Shaded cells are not used for the ADC module.

# 21.0 5-BIT DIGITAL-TO-ANALOG CONVERTER (DAC1) MODULE

The Digital-to-Analog Converter supplies a variable voltage reference, ratiometric with the input source, with 32 selectable output levels.

The input of the DAC can be connected to:

- External VREF pins
- VDD supply voltage
- FVR (Fixed Voltage Reference)

The output of the DAC can be configured to supply a reference voltage to the following:

- · Comparator positive input
- · ADC input channel
- DAC1OUT pin

The Digital-to-Analog Converter (DAC) is enabled by setting the DAC1EN bit of the DAC1CON0 register.

## 21.1 Output Voltage Selection

The DAC has 32 voltage level ranges. The 32 levels are set with the DAC1R<4:0> bits of the DAC1CON1 register.

The DAC output voltage is determined by Equation 21-1:

## **EQUATION 21-1: DAC OUTPUT VOLTAGE**

$$\begin{split} v_{OUT} &= \left\{ (v_{SOURCE+} - v_{SOURCE-}) \right\} \frac{DAC1R\langle 4:0 \rangle}{2^5} + (v_{SOURCE-}) \\ v_{SOURCE+} &= v_{DD} \ or \ v_{REF+} \ or \ FVR \\ v_{SOURCE-} &= v_{SS} \ or \ v_{REF-} \end{split}$$

## 21.2 Ratiometric Output Level

The DAC output value is derived using a resistor ladder with each end of the ladder tied to a positive and negative voltage reference input source. If the voltage of either input source fluctuates, a similar fluctuation will result in the DAC output value.

The value of the individual resistors within the ladder can be found in Table 37-15.

## 21.3 DAC Voltage Reference Output

The DAC voltage can be output to the DAC1OUT1/2 pins by setting the DAC1OE1/2 bits of the DAC1CON0 register, respectively. Selecting the DAC reference voltage for output on the DAC1OUT1/2 pins automatically overrides the digital output buffer and digital input threshold detector functions, disables the weak pull-up, and disables the current-controlled drive function of that pin. Reading the DAC1OUT1/2 pin when it has been configured for DAC reference voltage output will always return a '0'.

Due to the limited current drive capability, a buffer must be used on the DAC voltage reference output for external connections to the DAC10UT1/2 pins. Figure 21-2 shows an example buffering technique.

FIGURE 21-1: DIGITAL-TO-ANALOG CONVERTER BLOCK DIAGRAM





FIGURE 21-2: VOLTAGE REFERENCE OUTPUT BUFFER EXAMPLE



## 21.4 Operation During Sleep

The DAC continues to function during Sleep. When the device wakes up from Sleep through an interrupt or a Watchdog Timer time-out, the contents of the DAC1CON0 register are not affected.

## 21.5 Effects of a Reset

A device Reset affects the following:

- · DAC is disabled.
- DAC output voltage is removed from the DAC10UT1/2 pins.
- The DAC1R<4:0> range select bits are cleared.

## 21.6 Register Definitions: DAC Control

### REGISTER 21-1: DAC1CON0: VOLTAGE REFERENCE CONTROL REGISTER 0

R/W-0/0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	U-0	R/W-0/0
DAC1EN	· <del></del> :	DAC10E1	DAC10E2	DAC1P	SS<1:0>	-	DAC1NSS
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 DAC1EN: DAC1 Enable bit 1 = DAC is enabled 0 = DAC is disabled bit 6 Unimplemented: Read as '0' bit 5 DAC10E1: DAC1 Voltage Output 1 Enable bit 1 = DAC voltage level is an output on the DAC10UT1 pin 0 = DAC voltage level is disconnected from the DAC10UT1 pin bit 4 DAC10E2: DAC1 Voltage Output 2 Enable bit 1 = DAC voltage level is an output on the DAC10UT2 pin 0 = DAC voltage level is disconnected from the DAC1OUT2 pin DAC1PSS<1:0>: DAC1 Positive Source Select bits bit 3-2 11 =Reserved, do not use 10 =FVR output 01 =VREF+ pin 00 = VDD bit 1 Unimplemented: Read as '0' DAC1NSS: Read as '0' bit 0

## REGISTER 21-2: DAC1CON1: VOLTAGE REFERENCE CONTROL REGISTER 1

U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
<del>-</del>	_	-			DAC1R<4:0>	į	
bit 7							bit 0

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is cleared

bit 7-5 Unimplemented: Read as '0'

bit 4-0 DAC1R<4:0>: DAC1 Voltage Output Select bits

Vout = (Vsrc+ - Vsrc-)\*(DAC1R<4:0>/32) + Vsrc

TABLE 21-1: SUMMARY OF REGISTERS ASSOCIATED WITH THE DAC1 MODULE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on page
DAC1CON0	DAC1EN	Ţ	DAC10E1	DAC10E2	DAC1PS	SS<1:0>	<del></del> -	DAC1NSS	243
DAC1CON1	_	_				DAC1R<4:	0>		243
CM1PSEL	_	1-2	_	_	-		PCH<2:0>		263
CM2PSEL	_	::	_	_			PCH<2:0>		263

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are not used with the DAC module.


# 22.0 NUMERICALLY CONTROLLED OSCILLATOR (NCO) MODULE

The Numerically Controlled Oscillator (NCO) module is a timer that uses overflow from the addition of an increment value to divide the input frequency. The advantage of the addition method over simple counter driven timer is that the output frequency resolution does not vary with the divider value. The NCO is most useful for application that requires frequency accuracy and fine resolution at a fixed duty cycle.

Features of the NCO include:

- · 20-bit Increment Function
- · Fixed Duty Cycle mode (FDC) mode
- · Pulse Frequency (PF) mode
- · Output Pulse Width Control
- Multiple Clock Input Sources
- · Output Polarity Control
- Interrupt Capability

Figure 22-1 is a simplified block diagram of the NCO module.



#### 22.1 NCO OPERATION

The NCO operates by repeatedly adding a fixed value to an accumulator. Additions occur at the input clock rate. The accumulator will overflow with a carry periodically, which is the raw NCO output (NCO\_overflow). This effectively reduces the input clock by the ratio of the addition value to the maximum accumulator value. See Equation 22-1.

The NCO output can be further modified by stretching the pulse or toggling a flip-flop. The modified NCO output is then distributed internally to other peripherals and can be optionally output to a pin. The accumulator overflow also generates an interrupt (NCO\_overflow).

The NCO period changes in discrete steps to create an average frequency.

#### EQUATION 22-1: NCO OVERFLOW FREQUENCY

Foverflow= 
$$\frac{NCO\ Clock\ Frequency \times Increment\ Value}{2^{20}}$$

#### 22.1.1 NCO CLOCK SOURCES

Clock sources available to the NCO include:

- HFINTOSC
- Fosc
- · LC1 out
- LC2\_out
- · LC3 out
- LC4 out
- MFINTOSC (500 kHz)
- MFINTOSC (32 kHz)
- · sosc
- CLKR

The NCO clock source is selected by configuring the N1CKS<2:0> bits in the NCO1CLK register.

#### 22.1.2 ACCUMULATOR

The accumulator is a 20-bit register. Read and write access to the accumulator is available through three registers:

- NCO1ACCL
- NCO1ACCH
- NCO1ACCU

## 22.1.3 ADDER

The NCO Adder is a full adder, which operates synchronously from the source clock. The addition of the previous result and the increment value replaces the accumulator value on the rising edge of each input clock.

#### 22.1.4 INCREMENT REGISTERS

The increment value is stored in three registers making up a 20-bit incrementer. In order of LSB to MSB they are:

- NCO1INCL
- NCO1INCH
- NCO1INCU

When the NCO module is enabled, the NCO1INCU and NCO1INCH registers must be written first, then the NCO1INCL register. Writing to the NCO1INCL register initiates the increment buffer registers to be loaded simultaneously on the second rising edge of the NCO\_clk signal.

The registers are readable and writable. The increment registers are double-buffered to allow value changes to be made without first disabling the NCO module.

When the NCO module is disabled, the increment buffers are loaded immediately after a write to the increment registers.

Note: The increment buffer registers are not useraccessible.

## 22.2 FIXED DUTY CYCLE MODE

In Fixed Duty Cycle (FDC) mode, every time the accumulator overflows (NCO\_overflow), the output is toggled at a frequency rate half of the FOVERFLOW. This provides a 50% duty cycle, provided that the increment value remains constant. For more information, see Figure 22-2.

The FDC mode is selected by clearing the N1PFM bit in the NCO1CON register.

## 22.3 PULSE FREQUENCY MODE

In Pulse Frequency (PF) mode, every time the Accumulator overflows, the output becomes active for one or more clock periods. Once the clock period expires, the output returns to an inactive state. This provides a pulsed output. The output becomes active on the rising clock edge immediately following the overflow event. For more information, see Figure 22-2.

The value of the active and inactive states depends on the polarity bit, N1POL in the NCO1CON register.

The PF mode is selected by setting the N1PFM bit in the NCO1CON register.

#### 22.3.1 OUTPUT PULSE WIDTH CONTROL

When operating in PF mode, the active state of the output can vary in width by multiple clock periods. Various pulse widths are selected with the N1PWS<2:0> bits in the NCO1CLK register.

When the selected pulse width is greater than the Accumulator overflow time frame, then NCO1 output does not toggle.

### 22.4 OUTPUT POLARITY CONTROL

The last stage in the NCO module is the output polarity. The N1POL bit in the NCO1CON register selects the output polarity. Changing the polarity while the interrupts are enabled will cause an interrupt for the resulting output transition.

The NCO output signal (NCO1\_out) is available to the following peripherals:

- · CLC
- CWG
- Timer1
- Timer2
- CLKR

## 22.5 Interrupts

When the accumulator overflows (NCO\_overflow), the NCO Interrupt Flag bit, NCO1IF, of the PIR7 register is set. To enable the interrupt event (NCO\_interrupt), the following bits must be set:

- N1EN bit of the NCO1CON register
- NCO1IE bit of the PIE7 register
- · PEIE bit of the INTCON register
- · GIE bit of the INTCON register

The interrupt must be cleared by software by clearing the NCO1IF bit in the Interrupt Service Routine.

## 22.6 Effects of a Reset

All of the NCO registers are cleared to zero as the result of a Reset.

## 22.7 Operation in Sleep


The NCO module operates independently from the system clock and will continue to run during Sleep, provided that the clock source selected remains active.

The HFINTOSC remains active during Sleep when the NCO module is enabled and the HFINTOSC is selected as the clock source, regardless of the system clock source selected.

In other words, if the HFINTOSC is simultaneously selected as the system clock and the NCO clock source, when the NCO is enabled, the CPU will go Idle during Sleep, but the NCO will continue to operate and the HFINTOSC will remain active.

This will have a direct effect on the Sleep mode current.





## 22.8 NCO Control Registers

## REGISTER 22-1: NCO1CON: NCO CONTROL REGISTER

R/W-0/0	U-0	R-0/0	R/W-0/0	U-0	U-0	U-0	R/W-0/0
N1EN	.—	N1OUT	N1POL	-	. =	2 <del></del>	N1PFM
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	N1EN: NCO1 Enable bit  1 = NCO1 module is enabled  0 = NCO1 module is disabled
bit 6	Unimplemented: Read as '0'
bit 5	N10UT: NCO1 Output bit Displays the current output value of the NCO1 module.
bit 4	N1POL: NCO1 Polarity bit  1 = NCO1 output signal is inverted  0 = NCO1 output signal is not inverted
bit 3-1	Unimplemented: Read as '0'
bit 0	N1PFM: NCO1 Pulse Frequency Mode bit 1 = NCO1 operates in Pulse Frequency mode 0 = NCO1 operates in Fixed Duty Cycle mode, divide by 2

# REGISTER 22-2: NCO1CLK: NCO1 INPUT CLOCK CONTROL REGISTER

R/W-0/0	R/W-0/0	R/W-0/0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
N	N1PWS<2:0> <sup>(1,2)</sup>			N1CKS<3:0>			
bit 7			•			bit 0	

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

N1PWS<2:0>: NCO1 Output Pulse Width Select bits(1)					
111 = NCO1 output is active for 128 input clock periods					
110 = NCO1 output is active for 64 input clock periods					
101 = NCO1 output is active for 32 input clock periods					
100 = NCO1 output is active for 16 input clock periods					
011 = NCO1 output is active for 8 input clock periods					
010 = NCO1 output is active for 4 input clock periods					
001 = NCO1 output is active for 2 input clock periods					
000 = NCO1 output is active for 1 input clock period					
Unimplemented: Read as '0'					
N1CKS<3:0>: NCO1 Clock Source Select bits					
1011-1111 = Reserved					
1010 = LC4 out					
1001 = LC3 out					
1000 = LC2_out					
0111 = LC1 out					
0110 = CLKR					
0101 = SOSC					
0100 = MFINTOSC (32 kHz)					
0011 = MFINTOSC (500 kHz)					
0010 = LFINTOSC					
0001 = HFINTOSC					
0000 = Fosc					

Note 1: N1PWS applies only when operating in Pulse Frequency mode.

## REGISTER 22-3: NCO1ACCL: NCO1 ACCUMULATOR REGISTER - LOW BYTE

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0		
	NCO1ACC<7:0>								
bit 7 bit 0									

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-0 NCO1ACC<7:0>: NCO1 Accumulator, Low Byte

## REGISTER 22-4: NC01ACCH: NC01 ACCUMULATOR REGISTER - HIGH BYTE

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
NCO1ACC<15:8>							
bit 7 bit 0							

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-0 NOC1ACC<15:8>: NCO1 Accumulator, High Byte

# REGISTER 22-5: NCO1ACCU: NCO1 ACCUMULATOR REGISTER - UPPER BYTE(1)

U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	
-	-	_	-	NCO1ACC<19:16>				
bit 7		•	•	_			bit 0	

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-4 Unimplemented: Read as '0'

bit 3-0 NCO1ACC<19:16>: NCO1 Accumulator, Upper Byte

Note 1: The accumulator spans registers NCO1ACCU:NCO1ACCH: NCO1ACCL. The 24 bits are reserved but not all are used. This register updates in real-time, asynchronously to the CPU; there is no provision to guarantee atomic access to this 24-bit space using an 8-bit bus. Writing to this register while the module is operating will produce undefined results.

# REGISTER 22-6: NCO1INCL: NCO1 INCREMENT REGISTER - LOW BYTE<sup>(1,2)</sup>

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-1/1	
NCO1INC<7:0>								
bit 7	bit 7 bit 0							

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-0 NCO1INC<7:0>: NCO1 Increment, Low Byte

Note 1: The logical increment spans NCO1INCU:NCO1INCH:NCO1INCL.

2: NCO1INC is double-buffered as INCBUF; INCBUF is updated on the next falling edge of NCOCLK after writing to NCO1INCL; NCO1INCU and NCO1INCH must be written prior to writing NCO1INCL.

# REGISTER 22-7: NCO1INCH: NCO1 INCREMENT REGISTER - HIGH BYTE(1)

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
NCO1INC<15:8>							
bit 7 bit 0							

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-0 NCO1INC<15:8>: NCO1 Increment, High Byte

Note 1: The logical increment spans NCO1INCU:NCO1INCH:NCO1INCL.

## REGISTER 22-8: NCO1INCU: NCO1 INCREMENT REGISTER - UPPER BYTE<sup>(1)</sup>

U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
<del></del>	·—·	: <del></del> :	<del>-</del>		NCO1IN	C<19:16>	
bit 7	e:	2		- 34			bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-4 Unimplemented: Read as '0'

bit 3-0 NCO1INC<19:16>: NCO1 Increment, Upper Byte

Note 1: The logical increment spans NCO1INCU:NCO1INCH:NCO1INCL.

TABLE 22-1: SUMMARY OF REGISTERS ASSOCIATED WITH NCO

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
INTCON	GIE	PEIE	_		-		_	INTEDG	121
PIR7	_	_	NVMIF	NCO1IF	_	_	<u></u>	CWG1IF	137
PIE7	_	-	NVMIE	NCO1IE	_		_	CWG1IE	129
NCO1CON	N1EN	-	N1OUT	N1POL	-	-	_	N1PFM	250
NCO1CLK		N1PWS<2:0	)>	_	- N1CKS<3:0>				
NCO1ACCL				NCO1ACC	·7:0>				252
NCO1ACCH				NCO1ACC<	15:8>				252
NCO1ACCU	_	-	=	-		NCO1ACC	<19:16>		252
NCO1INCL	3			NCO1INC<	7:0>				253
NCO1INCH				NCO1INC<	15:8>				253
NCO1INCU	-	_	_			NCO1AINO	C<19:16>		253
RxyPPS	-	-	_		R	xyPPS<4:0>			200

**Legend:** – = unimplemented read as '0'. Shaded cells are not used for NCO module.

## 23.0 COMPARATOR MODULE

Comparators are used to interface analog circuits to a digital circuit by comparing two analog voltages and providing a digital indication of their relative magnitudes. Comparators are very useful mixed signal building blocks because they provide analog functionality independent of program execution. The analog comparator module includes the following features:

- · Programmable input selection
- · Selectable voltage reference
- · Programmable output polarity
- · Rising/falling output edge interrupts
- CWG1 Auto-shutdown source


# 23.1 Comparator Overview

A single comparator is shown in Figure 23-1 along with the relationship between the analog input levels and the digital output. When the analog voltage at VIN+ is less than the analog voltage at VIN-, the output of the comparator is a digital low level. When the analog voltage at VIN+ is greater than the analog voltage at VIN-, the output of the comparator is a digital high level.


The comparators available are shown in Table 23-1.

TABLE 23-1: AVAILABLE COMPARATORS

Device	C1	C2
PIC16(L)F15354/55	•	•



# FIGURE 23-2: COMPARATOR MODULE SIMPLIFIED BLOCK DIAGRAM



## 23.2 Comparator Control

Each comparator has two control registers: CMxCON0 and CMxCON1.

The CMxCON0 register (see Register 23-1) contains Control and Status bits for the following:

- Enable
- Output
- · Output polarity
- Hysteresis enable
- · Timer1 output synchronization

The CMxCON1 register (see Register 23-2) contains Control bits for the following:

· Interrupt on positive/negative edge enables

### 23.2.1 COMPARATOR ENABLE

Setting the CxON bit of the CMxCON0 register enables the comparator for operation. Clearing the CxON bit disables the comparator resulting in minimum current consumption.

## 23.2.2 COMPARATOR OUTPUT

The output of the comparator can be monitored by reading either the CxOUT bit of the CMxCON0 register or the MCxOUT bit of the CMOUT register.

The comparator output can also be routed to an external pin through the RxyPPS register (Register 15-2). The corresponding TRIS bit must be clear to enable the pin as an output.

Note 1: The internal output of the comparator is latched with each instruction cycle. Unless otherwise specified, external outputs are not latched.

#### 23.2.3 COMPARATOR OUTPUT POLARITY

Inverting the output of the comparator is functionally equivalent to swapping the comparator inputs. The polarity of the comparator output can be inverted by setting the CxPOL bit of the CMxCON0 register. Clearing the CxPOL bit results in a noninverted output.

Table 23-2 shows the output state versus input conditions, including polarity control.

TABLE 23-2: COMPARATOR OUTPUT STATE VS. INPUT CONDITIONS

Input Condition	CxPOL	CXOUT
CxVn > CxVp	0	0
CxVn < CxVP	0	1
CxVn > CxVp	1	1
CxVn < CxVP	1	0

## 23.3 Comparator Hysteresis

A selectable amount of separation voltage can be added to the input pins of each comparator to provide a hysteresis function to the overall operation. Hysteresis is enabled by setting the CxHYS bit of the CMxCON0 register.

See Comparator Specifications in Table 37-14 for more information.

## 23.4 Timer1 Gate Operation

The output resulting from a comparator operation can be used as a source for gate control of Timer1. See Section 26.7 "Timer Gate" for more information. This feature is useful for timing the duration or interval of an analog event.

It is recommended that the comparator output be synchronized to Timer1. This ensures that Timer1 does not increment while a change in the comparator is occurring.

# 23.4.1 COMPARATOR OUTPUT SYNCHRONIZATION

The output from a comparator can be synchronized with Timer1 by setting the CxSYNC bit of the CMxCON0 register.

Once enabled, the comparator output is latched on the falling edge of the Timer1 source clock. If a prescaler is used with Timer1, the comparator output is latched after the prescaling function. To prevent a race condition, the comparator output is latched on the falling edge of the Timer1 clock source and Timer1 increments on the rising edge of its clock source. See the Comparator Block Diagram (Figure 23-2) and the Timer1 Block Diagram (Figure 26-1) for more information.

## 23.5 Comparator Interrupt

An interrupt can be generated upon a change in the output value of the comparator for each comparator, a rising edge detector and a falling edge detector are present.

When either edge detector is triggered and its associated enable bit is set (CxINTP and/or CxINTN bits of the CMxCON1 register), the Corresponding Interrupt Flag bit (CxIF bit of the PIR2 register) will be set.

To enable the interrupt, the user must set the following bits:

- CxON, CxPOL and CxSP bits of the CMxCON0 register
- · CxIE bit of the PIE2 register
- CxINTP bit of the CMxCON1 register (for a rising edge detection)
- CxINTN bit of the CMxCON1 register (for a falling edge detection)
- PEIE and GIE bits of the INTCON register

The associated interrupt flag bit, CxIF bit of the PIR2 register, must be cleared in software. If another edge is detected while this flag is being cleared, the flag will still be set at the end of the sequence.

Note:

Although a comparator is disabled, an interrupt can be generated by changing the output polarity with the CxPOL bit of the CMxCON0 register, or by switching the comparator on or off with the CxON bit of the CMxCON0 register.

# 23.6 Comparator Positive Input Selection

Configuring the CxPCH<2:0> bits of the CMxPSEL register directs an internal voltage reference or an analog pin to the noninverting input of the comparator:

- CxIN0+ analog pin
- DAC output
- FVR (Fixed Voltage Reference)
- Vss (Ground)

See Section 18.0 "Fixed Voltage Reference (FVR)" for more information on the Fixed Voltage Reference module

See Section 21.0 "5-Bit Digital-to-Analog Converter (DAC1) Module" for more information on the DAC input signal.

Any time the comparator is disabled (CxON = 0), all comparator inputs are disabled.

# 23.7 Comparator Negative Input Selection

The CxNCH<2:0> bits of the CMxNSEL register direct an analog input pin and internal reference voltage or analog ground to the inverting input of the comparator:

- CxINy pin
- FVR (Fixed Voltage Reference)
- Analog Ground

Note:

To use CxINy+ and CxINy- pins as analog input, the appropriate bits must be set in the ANSEL register and the corresponding TRIS bits must also be set to disable the output drivers.

## 23.8 Comparator Response Time

The comparator output is indeterminate for a period of time after the change of an input source or the selection of a new reference voltage. This period is referred to as the response time. The response time of the comparator differs from the settling time of the voltage reference. Therefore, both of these times must be considered when determining the total response time to a comparator input change. See the Comparator and Voltage Reference Specifications in Table 37-14 for more details.


# 23.9 Analog Input Connection Considerations

A simplified circuit for an analog input is shown in Figure 23-3. Since the analog input pins share their connection with a digital input, they have reverse biased ESD protection diodes to VDD and VSS. The analog input, therefore, must be between VSS and VDD. If the input voltage deviates from this range by more than 0.6V in either direction, one of the diodes is forward biased and a latch-up may occur.

A maximum source impedance of 10 k $\Omega$  is recommended for the analog sources. Also, any external component connected to an analog input pin, such as a capacitor or a Zener diode, must have very little leakage current to minimize inaccuracies introduced.

- Note 1: When reading a PORT register, all pins configured as analog inputs will read as a '0'. Pins configured as digital inputs will convert as an analog input, according to the input specification.
  - Analog levels on any pin defined as a digital input, may cause the input buffer to consume more current than is specified.

FIGURE 23-3: ANALOG INPUT MODEL



## 23.10 CWG1 Auto-shutdown Source

The output of the comparator module can be used as an auto-shutdown source for the CWG1 module. When the output of the comparator is active and the corresponding ASxE is enabled, the CWG operation will be suspended immediately (see Section 30.10 "Auto-Shutdown").

## 23.11 Operation in Sleep Mode

The comparator module can operate during Sleep. The comparator clock source is based on the Timer1 clock source. If the Timer1 clock source is either the system clock (Fosc) or the instruction clock (Fosc/4), Timer1 will not operate during Sleep, and synchronized comparator outputs will not operate.

A comparator interrupt will wake the device from Sleep. The CxIE bits of the PIE2 register must be set to enable comparator interrupts.

## 23.12 Register Definitions: Comparator Control

## REGISTER 23-1: CMxCON0: COMPARATOR Cx CONTROL REGISTER 0

R/W-0/0	R-0/0	U-0	R/W-0/0	U-0	U-0	R/W-0/0	R/W-0/0
ON	OUT	_	POL	-	) <del>_</del>	HYS	SYNC
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 ON: Comparator Enable bit

1 = Comparator is enabled

0 = Comparator is disabled and consumes no active power

bit 6 OUT: Comparator Output bit

If CxPOL = 1 (inverted polarity):

1 = CxVP < CxVN 0 = CxVP > CxVN

If CxPOL = 0 (noninverted polarity):

1 = CxVP > CxVN 0 = CxVP < CxVN

bit 5 Unimplemented: Read as '0'

bit 4 POL: Comparator Output Polarity Select bit

1 = Comparator output is inverted 0 = Comparator output is not inverted

bit 3-2 Unimplemented: Read as '0'

bit 1 HYS: Comparator Hysteresis Enable bit

1 = Comparator hysteresis enabled0 = Comparator hysteresis disabled

bit 0 SYNC: Comparator Output Synchronous Mode bit

1 = Comparator output to Timer1 and I/O pin is synchronous to changes on Timer1 clock source.

Output updated on the falling edge of Timer1 clock source.

0 = Comparator output to Timer1 and I/O pin is asynchronous

## REGISTER 23-2: CMxCON1: COMPARATOR Cx CONTROL REGISTER 1

U-0	U-0	U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0
<del>-</del>		( <del></del> )	-	( <del></del>		INTP	INTN
bit 7				•			bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-2 Unimplemented: Read as '0'

bit 1 INTP: Comparator Interrupt on Positive-Going Edge Enable bits

1 = The CxIF interrupt flag will be set upon a positive-going edge of the CxOUT bit

0 = No interrupt flag will be set on a positive-going edge of the CxOUT bit

bit 0 INTN: Comparator Interrupt on Negative-Going Edge Enable bits

1 = The CxIF interrupt flag will be set upon a negative-going edge of the CxOUT bit

0 = No interrupt flag will be set on a negative-going edge of the CxOUT bit

## REGISTER 23-3: CMxNSEL: COMPARATOR Cx NEGATIVE INPUT SELECT REGISTER

U-0	U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	
1	<del></del>	-		(a <del></del>	NCH<2:0>			
bit 7				•	•		bit 0	

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-3 Unimplemented: Read as '0'

bit 2-0 NCH<2:0>: Comparator Negative Input Channel Select bits

111 =CxVN connects to AVss

110 =CxVN connects to FVR Buffer 2

101 =CxVN unconnected

100 =CxVN unconnected

011 =CxVN connects to CxIN3- pin

010 =CxVN connects to CxIN2- pin

001 =CxVN connects to CxIN1- pin

000 =CxVN connects to CxIN0- pin

## REGISTER 23-4: CMxPSEL: COMPARATOR Cx POSITIVE INPUT SELECT REGISTER

U-0	U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0
·	-	<del></del> )	-	_		PCH<2:0>	
bit 7	-						bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-3 Unimplemented: Read as '0'

bit 2-0 PCH<2:0>: Comparator Positive Input Channel Select bits

111 =CxVP connects to AVss

110 =CxVP connects to FVR Buffer 2

101 =CxVP connects to DAC output

100 =CxVP unconnected

011 =CxVP unconnected

010 =CxVP unconnected

001 =CxVP connects to CxIN1+ pin

000 =CxVP connects to CxIN0+ pin

## REGISTER 23-5: CMOUT: COMPARATOR OUTPUT REGISTER

U-0	U-0	U-0	U-0	U-0	U-0	R-0/0	R-0/0
	v <del>. v.</del>	<del>-</del>	: <del></del> :	(2 <del></del> 2	) <del></del> -	MC2OUT	MC10UT
bit 7	•			•	•	_	bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-2 Unimplemented: Read as '0'
bit 1 MC2OUT: Mirror Copy of C2OUT bit
bit 0 MC1OUT: Mirror Copy of C1OUT bit

## TABLE 23-3: SUMMARY OF REGISTERS ASSOCIATED WITH COMPARATOR MODULE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
CMxCON0	ON	OUT	3-V	POL		-	HYS	SYNC	261
CMxCON1	-		<u></u>	=	_	8	INTP	INTN	262
CMOUT	-		-	-	-	-	MC2OUT	MC1OUT	264
FVRCON	FVREN	FVRRDY	TSEN	TSRNG CDAFVR<1:0> ADFVR<1:0>				222	
DAC1CON0	DAC1EN	_	DAC10E1	DAC10E2	DAC1PS	SS<1:0>	-	DAC1NSS	243
DAC1CON1	-	-	_			DAC1R<4:0>		•	243
INTCON	GIE	PEIE						INTEDG	121
PIE2	( <del></del>	ZCDIE	-	_	<del>-</del>	ş	C2IE	C1IE	124
PIR2		ZCDIF	-	-	_		C2IF	C1IF	132
RxyPPS	-	_	_	RxyPPS<4:0>					200
CLCINxPPS	3 <u></u>	_		CLCIN0PPS<5:0>					199
T1GPPS	_	_			T1GPPS<5:0>				

Legend: — = unimplemented location, read as '0'. Shaded cells are unused by the comparator module.

# 24.0 ZERO-CROSS DETECTION (ZCD) MODULE

The ZCD module detects when an A/C signal crosses through the ground potential. The actual zero crossing threshold is the zero crossing reference voltage, VCPINV, which is typically 0.75V above ground.

The connection to the signal to be detected is through a series current limiting resistor. The module applies a current source or sink to the ZCD pin to maintain a constant voltage on the pin, thereby preventing the pin voltage from forward biasing the ESD protection diodes. When the applied voltage is greater than the reference voltage, the module sinks current. When the applied voltage is less than the reference voltage, the module sources current. The current source and sink action keeps the pin voltage constant over the full range of the applied voltage. The ZCD module is shown in the simplified block diagram Figure 24-2.

The ZCD module is useful when monitoring an A/C waveform for, but not limited to, the following purposes:

- · A/C period measurement
- Accurate long term time measurement
- · Dimmer phase delayed drive
- Low EMI cycle switching

## 24.1 External Resistor Selection

The ZCD module requires a current limiting resistor in series with the external voltage source. The impedance and rating of this resistor depends on the external source peak voltage. Select a resistor value that will drop all of the peak voltage when the current through the resistor is nominally 300  $\mu\text{A}$ . Refer to Equation 24-1 and Figure 24-1. Make sure that the ZCD I/O pin internal weak pull-up is disabled so it does not interfere with the current source and sink.

# **EQUATION 24-1: EXTERNAL RESISTOR**

$$RSERIES = \frac{VPEAK}{3 \times 10^{-4}}$$

#### FIGURE 24-1: EXTERNAL VOLTAGE




FIGURE 24-2: SIMPLIFIED ZCD BLOCK DIAGRAM **VPULLUP** optional RPULLUP **ZCDxIN** RSERIES External **RPULLDOWN** Zcpinv voltage source optional ZCD Output for other modules POL Interrupt det Set **ZCDxINTP** ZCDxIF **ZCDxINTN** flag Interrupt det

## 24.2 ZCD Logic Output

The ZCD module includes a Status bit, which can be read to determine whether the current source or sink is active. The OUT bit of the ZCDxCON register is set when the current sink is active, and cleared when the current source is active. The OUT bit is affected by the polarity even if the module is disabled.

## 24.3 ZCD Logic Polarity

The POL bit of the ZCDxCON register inverts the ZCDxOUT bit relative to the current source and sink output. When the POL bit is set, a logic '1' on the OUT bit indicates that the current source is active, and a logic '0' on the OUT bit indicates that the current sink is active. When the POL bit is clear, a logic '1' on the OUT bit indicates that the current sink is active, and a logic '0' on the OUT bit indicates that the current source is active

The POL bit affects the ZCD interrupts. See Section 24.4 "ZCD Interrupts".

## 24.4 ZCD Interrupts

An interrupt will be generated upon a change in the ZCD logic output when the appropriate interrupt enables are set. A rising edge detector and a falling edge detector are present in the ZCD for this purpose.

The ZCDIF bit of the PIR2 register will be set when either edge detector is triggered and its associated enable bit is set. The INTP enables rising edge interrupts and the INTN bit enables falling edge interrupts. Both are located in the ZCDxCON register.

To fully enable the interrupt, the following bits must be set:

- · ZCDIE bit of the PIE2 register
- INTP bit of the ZCDxCON register (for a rising edge detection)
- INTN bit of the ZCDxCON register (for a falling edge detection)
- PEIE and GIE bits of the INTCON register

Changing the POL bit can cause an interrupt, regardless of the level of the EN bit.

The ZCDIF bit of the PIR2 register must be cleared in software as part of the interrupt service. If another edge is detected while this flag is being cleared, the flag will still be set at the end of the sequence.

## 24.5 Correcting for VCPINV offset

The actual voltage at which the ZCD switches is the reference voltage at the noninverting input of the ZCD op amp. For external voltage source waveforms other than square waves, this voltage offset from zero causes the zero-cross event to occur either too early or too late.

## 24.5.1 CORRECTION BY AC COUPLING

When the external voltage source is sinusoidal then the effects of the VCPINV offset can be eliminated by isolating the external voltage source from the ZCD pin with a capacitor in addition to the voltage reducing resistor. The capacitor will cause a phase shift resulting in the ZCD output switch in advance of the actual zero crossing event. The phase shift will be the same for both rising and falling zero crossings, which can be compensated for by either delaying the CPU response to the ZCD switch by a timer or other means, or selecting a capacitor value large enough that the phase shift is negligible.

To determine the series resistor and capacitor values for this configuration, start by computing the impedance, Z, to obtain a peak current of 300  $\mu$ A. Next, arbitrarily select a suitably large non-polar capacitor and compute its reactance, Xc, at the external voltage source frequency. Finally, compute the series resistor, capacitor peak voltage, and phase shift by the formulas shown in Equation 24-2.

## **EQUATION 24-2: R-C CALCULATIONS**

VPEAK = external voltage source peak voltage

f = external voltage source frequency

C = series capacitor

R = series resistor

Vc = Peak capacitor voltage

 $\Phi$  = Capacitor induced zero crossing phase advance in radians

 $T_{\Phi}$  = Time ZC event occurs before actual zero crossing

 $Z = VPEAK/3x10^{-4}$ 

 $Xc = 1/(2\pi fC)$ 

 $R = \sqrt{(Z^2 - Xc^2)}$ 

 $Vc = Xc(3x10^{-4})$ 

 $\Phi = \text{Tan}^{-1}(Xc/R)$ 

 $T_{\Phi} = \Phi/(2\Pi f)$ 

#### **EXAMPLE 24-1:**

VRMS = 120

VPEAK = VRMS\*  $\sqrt{2}$  = 169.7

f = 60 Hz

 $C = 0.1 \, \mu F$ 

 $Z = VPEAK/3x10^{-4} = 169.7/(3x10^{-4}) = 565.7 k\Omega$ 

 $Xc = 1/(2\Pi fC) = 1/(2\Pi *60*1*10^{-7}) = 26.53 \text{ k}\Omega$ 

R =  $\sqrt{(Z^2 - Xc^2)}$  = 565.1 kΩ (computed)

 $R = 560 k\Omega \text{ (used)}$ 

 $ZR = \sqrt{(R^2 + Xc^2)} = 560.6 \text{ k}\Omega$  (using actual resistor)

IPEAK = VPEAK/ ZR = 302.7\*10<sup>-6</sup>

VC = Xc\* IPEAK = 8.0 V

 $\Phi = \text{Tan}^{-1}(Xc/R) = 0.047 \text{ radians}$ 

 $T_{\Phi} = \Phi/(2\Pi f) = 125.6 \text{ us}$ 

# 24.5.2 CORRECTION BY OFFSET CURRENT

When the waveform is varying relative to Vss, then the zero cross is detected too early as the waveform falls and too late as the waveform rises. When the waveform is varying relative to VDD, then the zero cross is detected too late as the waveform rises and too early as the waveform falls. The actual offset time can be determined for sinusoidal waveforms with the corresponding equations shown in Equation 24-3.

## **EQUATION 24-3: ZCD EVENT OFFSET**

When External Voltage Source is relative to Vss:

$$Toffset = \frac{asin\left(\frac{Vcpinv}{VPEAK}\right)}{2\pi \bullet Freq}$$

When External Voltage Source is relative to VDD:

$$Toffset = \frac{asin\left(\frac{V_{DD} - V_{cpinv}}{V_{PEAK}}\right)}{2\pi \bullet F_{req}}$$

This offset time can be compensated for by adding a pull-up or pull-down biasing resistor to the ZCD pin. A pull-up resistor is used when the external voltage source is varying relative to VSS. A pull-down resistor is used when the voltage is varying relative to VDD. The resistor adds a bias to the ZCD pin so that the target external voltage source must go to zero to pull the pin voltage to the VCPINV switching voltage. The pull-up or pull-down value can be determined with the equation shown in Equation 24-4.

## **EQUATION 24-4: ZCD PULL-UP/DOWN**

When External Signal is relative to Vss:

$$RPULLUP = \frac{RSERIES(VPULLUP - Vcpinv)}{Vcpinv}$$

When External Signal is relative to VDD:

$$\left(RPULLDOWN = \frac{RSERIES \times (Vcpinv)}{(VDD - Vcpinv)}\right)$$

# 24.6 Handling VPEAK variations

If the peak amplitude of the external voltage is expected to vary, the series resistor must be selected to keep the ZCD current source and sink below the design maximum range of  $\pm\,600~\mu\text{A}$  and above a reasonable minimum range. A general rule of thumb is that the maximum peak voltage can be no more than six times the minimum peak voltage. To ensure that the maximum current does not exceed  $\pm\,600~\mu\text{A}$  and the minimum is at least  $\pm\,100~\mu\text{A}$ , compute the series resistance as shown in Equation 24-5. The compensating pull-up for this series resistance can be determined with Equation 24-4 because the pull-up value is not dependent from the peak voltage.

## EQUATION 24-5: SERIES R FOR V RANGE

$$RSERIES = \frac{V_{MAXPEAK} + V_{MINPEAK}}{7 \times 10^{-4}}$$

# 24.7 Operation During Sleep

The ZCD current sources and interrupts are unaffected by Sleep.

## 24.8 Effects of a Reset

The ZCD circuit can be configured to default to the active or inactive state on Power-on-Reset (POR). When the ZCDDIS Configuration bit is cleared, the ZCD circuit will be active at POR. When the ZCD Configuration bit is set, the EN bit of the ZCDxCON register must be set to enable the ZCD module.

## 24.9 Register Definitions: ZCD Control

## REGISTER 24-1: ZCDCON: ZERO-CROSS DETECTION CONTROL REGISTER

R/W-q/q	U-0	R-x/x	R/W-0/0	U-0	U-0	R/W-0/0	R/W-0/0
SEN	a <del></del> -0	OUT	POL	_	: <del></del> :	INTP	INTN
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared q = value depends on Configuration bits

bit 7 SEN: Zero-Cross Detection Enable bit

1 = Zero-Cross Detect is enabled. ZCD pin is forced to output to source and sink current.

0 = Zero-Cross Detect is disabled. ZCD pin operates according to PPS and TRIS controls.

bit 6 Unimplemented: Read as '0'

bit 5 OUT: Zero-Cross Detection Logic Level bit

POL bit = 1:

1 = ZCD pin is sourcing current 0 = ZCD pin is sinking current

POL bit = 0:

1 = ZCD pin is sinking current 0 = ZCD pin is sourcing current

bit 4 POL: Zero-Cross Detection Logic Output Polarity bit

1 = ZCD logic output is inverted0 = ZCD logic output is not inverted

bit 3-2 Unimplemented: Read as '0'

bit 1 INTP: Zero-Cross Positive Edge Interrupt Enable bit

1 = ZCDIF bit is set on low-to-high ZCDx\_output transition

0 = ZCDIF bit is unaffected by low-to-high ZCDx\_output transition

bit 0 INTN: Zero-Cross Negative Edge Interrupt Enable bit

1 = ZCDIF bit is set on high-to-low ZCDx output transition

0 = ZCDIF bit is unaffected by high-to-low ZCDx\_output transition

### TABLE 24-1: SUMMARY OF REGISTERS ASSOCIATED WITH THE ZCD MODULE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on page
PIE2		ZCDIE	1	_	_		C2IE	C1IE	124
PIR2	-	ZCDIF	<u> </u>	_			C2IF	C1IF	132
ZCDxCON	EN	::	OUT	POL	-	-	INTP	INTN	270

**Legend:** — = unimplemented, read as '0'. Shaded cells are unused by the ZCD module.

## TABLE 24-2: SUMMARY OF CONFIGURATION WORD WITH THE ZCD MODULE

Name	Bits	Bit -/7	Bit -/6	Bit 13/5	Bit 12/4	Bit 11/3	Bit 10/2	Bit 9/1	Bit 8/0	Register on Page
CONFICE	13:8	-		DEBUG	STVREN	PPS1WAY	ZCDDIS	BORV	9 <del></del>	77
CONFIG2	7:0	BOREN	V <1:0>	LPBOREN	::	_	-	PWRTE	MCLRE	//

Legend: — = unimplemented location, read as '0'. Shaded cells are not used by the ZCD module.

## 25.0 TIMERO MODULE

The Timer0 module is an 8/16-bit timer/counter with the following features:

- 16-bit timer/counter
- 8-bit timer/counter with programmable period
- Synchronous or asynchronous operation
- Selectable clock sources
- Programmable prescaler (independent of Watchdog Timer)
- Programmable postscaler
- · Operation during Sleep mode
- · Interrupt on match or overflow
- · Output on I/O pin (via PPS) or to other peripherals

## 25.1 Timer0 Operation

Timer0 can operate as either an 8-bit timer/counter or a 16-bit timer/counter. The mode is selected with the T016BIT bit of the T0CON register.

#### 25.1.1 16-BIT MODE

In normal operation, TMR0 increments on the rising edge of the clock source. A 15-bit prescaler on the clock input gives several prescale options (see prescaler control bits, T0CKPS<3:0> in the T0CON1 register).

# 25.1.1.1 Timer0 Reads and Writes in 16-Bit Mode

TMR0H is not the actual high byte of Timer0 in 16-bit mode. It is actually a buffered version of the real high byte of Timer0, which is neither directly readable nor writable (see Figure 25-1). TMR0H is updated with the contents of the high byte of Timer0 during a read of TMR0L. This provides the ability to read all 16 bits of Timer0 without having to verify that the read of the high and low byte was valid, due to a rollover between successive reads of the high and low byte.

Similarly, a write to the high byte of Timer0 must also take place through the TMR0H Buffer register. The high byte is updated with the contents of TMR0H when a write occurs to TMR0L. This allows all 16 bits of Timer0 to be updated at once.

#### 25.1.2 8-BIT MODE

In normal operation, TMR0 increments on the rising edge of the clock source. A 15-bit prescaler on the clock input gives several prescale options (see prescaler control bits, T0CKPS<3:0> in the T0CON1 register).

The value of TMR0L is compared to that of the Period buffer, a copy of TMR0H, on each clock cycle. When the two values match, the following events happen:

- TMR0\_out goes high for one prescaled clock period
- TMR0L is reset
- The contents of TMR0H are copied to the period buffer

In 8-bit mode, the TMR0L and TMR0H registers are both directly readable and writable. The TMR0L register is cleared on any device Reset, while the TMR0H register initializes at FFh.

Both the prescaler and postscaler counters are cleared on the following events:

- · A write to the TMR0L register
- A write to either the T0CON0 or T0CON1 registers
- Any device Reset Power-on Reset (POR), MCLR Reset, Watchdog Timer Reset (WDTR) or Brown-out Reset (BOR)

#### 25.1.3 COUNTER MODE

In Counter mode, the prescaler is normally disabled by setting the T0CKPS bits of the T0CON1 register to '0000'. Each rising edge of the clock input (or the output of the prescaler if the prescaler is used) increments the counter by '1'.

## 25.1.4 TIMER MODE

In Timer mode, the Timer0 module will increment every instruction cycle as long as there is a valid clock signal and the T0CKPS bits of the T0CON1 register (Register 25-2) are set to '0000'. When a prescaler is added, the timer will increment at the rate based on the prescaler value.

## 25.1.5 ASYNCHRONOUS MODE

When the T0ASYNC bit of the T0CON1 register is set (T0ASYNC = 1), the counter increments with each rising edge of the input source (or output of the prescaler, if used). Asynchronous mode allows the counter to continue operation during Sleep mode provided that the clock also continues to operate during Sleep.

## 25.1.6 SYNCHRONOUS MODE

When the T0ASYNC bit of the T0CON1 register is clear (T0ASYNC = 0), the counter clock is synchronized to the system oscillator (FoSc/4). When operating in Synchronous mode, the counter clock frequency cannot exceed FoSc/4.

## 25.2 Clock Source Selection

The T0CS<2:0> bits of the T0CON1 register are used to select the clock source for Timer0. Register 25-2 displays the clock source selections.

#### 25.2.1 INTERNAL CLOCK SOURCE

When the internal clock source is selected, Timer0 operates as a timer and will increment on multiples of the clock source, as determined by the Timer0 prescaler.

#### 25.2.2 EXTERNAL CLOCK SOURCE

When an external clock source is selected, Timer0 can operate as either a timer or a counter. Timer0 will increment on multiples of the rising edge of the external clock source, as determined by the Timer0 prescaler.

## 25.3 Programmable Prescaler

A software programmable prescaler is available for exclusive use with Timer0. There are 16 prescaler options for Timer0 ranging in powers of two from 1:1 to 1:32768. The prescaler values are selected using the T0CKPS<3:0> bits of the T0CON1 register.

The prescaler is not directly readable or writable. Clearing the prescaler register can be done by writing to the TMR0L register or the T0CON1 register.

## 25.4 Programmable Postscaler

A software programmable postscaler (output divider) is available for exclusive use with Timer0. There are 16 postscaler options for Timer0 ranging from 1:1 to 1:16. The postscaler values are selected using the T0OUTPS<3:0> bits of the T0CON0 register.

The postscaler is not directly readable or writable. Clearing the postscaler register can be done by writing to the TMR0L register or the T0CON0 register.

In the 16-bit mode, if the postscaler option is selected to a ratio other than 1:1, the reload of the TMR0H and TMR0L registers is not possible inside the Interrupt Service Routine. The timer period must be calculated with the prescaler and postscaler factors selected.

## 25.5 Operation during Sleep

When operating synchronously, Timer0 will halt. When operating asynchronously, Timer0 will continue to increment and wake the device from Sleep (if Timer0 interrupts are enabled) provided that the input clock source is active.

## 25.6 Timer0 Interrupts

The Timer0 interrupt flag (TMR0IF) bit is set when either of the following conditions occur:

- 8-bit TMR0L matches the TMR0H value
- 16-bit TMR0 rolls over from 'FFFFh'

When the postscaler bits (T0OUTPS<3:0>) are set to 1:1 operation (no division), the T0IF flag bit will be set with every TMR0 match or rollover. In general, the TMR0IF flag bit will be set every T0OUTPS +1 matches or rollovers.


If Timer0 interrupts are enabled (the TMR0IE bit of the PIE0 register = 1), the CPU will be interrupted and the device may wake from Sleep (see Section 25.2 "Clock Source Selection" for more details).

## 25.7 Timer0 Output

The Timer0 output can be routed to any I/O pin via the RxyPPS output selection register (see Section 15.0 "Peripheral Pin Select (PPS) Module" for additional information). The Timer0 output can also be used by other peripherals, such as the Auto-conversion Trigger of the Analog-to-Digital Converter. Finally, the Timer0 output can be monitored through software via the Timer0 output (T0OUT) bit of the T0CON0 register (Register 25-1).

TMR0\_out will be one postscaled clock period when a match occurs between TMR0L and TMR0H in 8-bit mode, or when TMR0 rolls over in 16-bit mode. The Timer0 output is a 50% duty cycle that toggles on each TMR0 out rising clock edge.

FIGURE 25-1: BLOCK DIAGRAM OF TIMER0



# 25.8 Register Definitions: Timer0 Control

# REGISTER 25-1: T0CON0: TIMER0 CONTROL REGISTER 0

R/W-0/0	U-0	R-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
T0EN	· <del></del>	TOOUT	T016BIT		TOOUT	PS<3:0>	
bit 7		38					bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	<b>T0EN:</b> Timer0 Enable bit  1 = The module is enabled and operating  0 = The module is disabled and in the lowest Power mode
bit 6	Unimplemented: Read as '0'
bit 5	<b>T0OUT:</b> Timer0 Output bit (read-only) Timer0 output bit
bit 4	T016BIT: Timer0 Operating as 16-bit Timer Select bit  1 = Timer0 is a 16-bit timer  0 = Timer0 is an 8-bit timer
bit 3-0	T0OUTPS<3:0>: Timer0 output postscaler (divider) select bits 1111 = 1:16 Postscaler 1110 = 1:15 Postscaler 1101 = 1:14 Postscaler 1100 = 1:13 Postscaler 1011 = 1:12 Postscaler 1010 = 1:11 Postscaler 1000 = 1:10 Postscaler 1000 = 1:9 Postscaler 1010 = 1:7 Postscaler 0111 = 1:8 Postscaler 0110 = 1:7 Postscaler 0101 = 1:6 Postscaler 0101 = 1:5 Postscaler 0101 = 1:4 Postscaler 0011 = 1:3 Postscaler 0010 = 1:3 Postscaler 0010 = 1:1 Postscaler

## REGISTER 25-2: T0CON1: TIMER0 CONTROL REGISTER 1

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
	T0CS<2:0>		T0ASYNC		T0CKP	S<3:0>	
bit 7	bit 7						bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-5 T0CS<2:0>: Timer0 Clock Source select bits

111 = LC1\_out

110 = SOSC

101 = MFINTOSC (500 kHz)

100 = LFINTOSC

011 = HFINTOSC

010 = Fosc/4

001 = T0CKIPPS (Inverted)

000 = T0CKIPPS (True)

bit 4 T0ASYNC: TMR0 Input Asynchronization Enable bit

1 = The input to the TMR0 counter is not synchronized to system clocks

0 = The input to the TMR0 counter is synchronized to Fosc/4

bit 3-0 T0CKPS<3:0>: Prescaler Rate Select bit

1111 = 1:32768

1110 = 1:16384

1101 = 1:8192

1100 = 1:4096

1011 = 1:2048

1010 = 1:1024

1001 = 1:512

1000 = 1:256

0111 = 1:128

0110 = 1:64

0101 = 1:32

0100 = 1:16

0011 = 1:8

0010 = 1:4

0001 = 1:2

0000 = 1:1

TABLE 25-1: SUMMARY OF REGISTERS ASSOCIATED WITH TIMERO

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
TMR0L	Holding Regi	ster for the Le	east Significa	nt Byte of the 1	I 16-bit TMR0 Regis	ter			271*
TMR0H	Holding Regi	ster for the M	ost Significar	nt Byte of the 1	6-bit TMR0 Regist	er			271*
T0CON0	T0EN	_	T0OUT	T016BIT		T00UTPS	<3:0>		274
T0CON1	T0CS<2:0>			T0ASYNC			275		
T0CKIPPS	-	-			T0CKIPPS	<5:0>			199
TMR0PPS	_	_			TMR0PPS	<5:0>			199
T1GCON	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL	_	_	287
INTCON	GIE	PEIE	_	_		-	<del></del> );	INTEDG	121
PIR0	_	=	TMR0IF	IOCIF		-	-	INTF	130
PIE0	_	_	TMR0IE	IOCIE	<u></u>	Y	_	INTE	122

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are not used by the Timer0 module.

Page with Register information.

# 26.0 TIMER1 MODULE WITH GATE CONTROL

The Timer1 module is 16-bit timer/counters with the following features:


- 16-bit timer/counter register pair (TMR1H:TMR1L)
- · Programmable internal or external clock source
- · 2-bit prescaler
- Clock source for optional comparator synchronization
- · Multiple Timer1 gate (count enable) sources
- · Interrupt on overflow

- Wake-up on overflow (external clock, Asynchronous mode only)
- · Time base for the Capture/Compare function
- · Auto-conversion Trigger (with CCP)
- · Selectable Gate Source Polarity
- · Gate Toggle mode
- · Gate Single-Pulse mode
- · Gate Value Status
- Gate Event Interrupt

Figure 26-1 is a block diagram of the Timer1 module.

This device has one instance of Timer1 type modules.

## FIGURE 26-1: TIMER1 BLOCK DIAGRAM



## 26.1 Timer1 Operation

The Timer1 modules are 16-bit incrementing counters which are accessed through the TMR1H:TMR1L register pairs. Writes to TMR1H or TMR1L directly update the counter.

When used with an internal clock source, the module is a timer and increments on every instruction cycle. When used with an external clock source, the module can be used as either a timer or counter and increments on every selected edge of the external source.

The timer is enabled by configuring the TMR1ON and GE bits in the T1CON and T1GCON registers, respectively. Table 26-1 displays the Timer1 enable selections.

TABLE 26-1: TIMER1 ENABLE SELECTIONS

TMR10N	TMR1GE	Timer1 Operation
1	1	Count Enabled
1	0	Always On
0	1	Off
0	0	Off

## 26.2 Clock Source Selection

The T1CLK register is used to select the clock source for the timer. Register 26-3 shows the possible clock sources that may be selected to make the timer increment.

#### 26.2.1 INTERNAL CLOCK SOURCE

When the internal clock source FOSC is selected, the TMR1H:TMR1L register pair will increment on multiples of FOSC as determined by the respective Timer1 prescaler.

When the Fosc internal clock source is selected, the timer register value will increment by four counts every instruction clock cycle. Due to this condition, a 2 LSB error in resolution will occur when reading the TMR1H:TMR1L value. To utilize the full resolution of the timer in this mode, an asynchronous input signal must be used to gate the timer clock input.

Out of the total timer gate signal sources, the following subset of sources can be asynchronous and may be useful for this purpose:

- CLC4 output
- CLC3 output
- CLC2 output
- CLC1 output
- · Zero-Cross Detect output
- · Comparator2 output
- · Comparator1 output
- · TxG PPS remappable input pin

## 26.2.2 EXTERNAL CLOCK SOURCE

When the timer is enabled and the external clock input source (ex: T1CKI PPS remappable input) is selected as the clock source, the timer will increment on the rising edge of the external clock input.

When using an external clock source, the timer can be configured to run synchronously or asynchronously, as described in Section 26.6 "Timer Operation in Asynchronous Mode".

When used as a timer with a clock oscillator, an external 32.768 kHz crystal can be used connected to the SOSCI/SOSCO pins.

Note: When using Timer1 to count events, a falling edge must be registered by the counter prior to the first incrementing rising edge after any one or more of the following conditions:

- The timer is first enabled after POR
- •Firmware writes to TMR1H or TMR1L
- The timer is disabled
- The timer is re-enabled (e.g., TMR1ON-->1) when the T1CKI signal is currently logic low.

## 26.3 Timer Prescaler

Timer1 has four prescaler options allowing 1, 2, 4 or 8 divisions of the clock input. The CKPS bits of the T1CON register control the prescale counter. The prescale counter is not directly readable or writable; however, the prescaler counter is cleared upon a write to TMR1H or TMR1L.

### 26.4 Timer1 16-Bit Read/Write Mode

Timer1 can be configured for 16-bit reads and writes. When the RD16 control bit (T1CON<1>) is set, the address for TMR1H is mapped to a buffer register for the high byte of Timer1. A read from TMR1L loads the contents of the high byte of Timer1 into the Timer1 High Byte Buffer register. This provides the user with the


ability to accurately read all 16 bits of Timer1 without having to determine whether a read of the high byte, followed by a read of the low byte, has become invalid due to a rollover between reads.

A write to the high byte of Timer1 must also take place through the TMR1H Buffer register. The Timer1 high byte is updated with the contents of TMR1H when a write occurs to TMR1L. This allows a user to write all 16 bits at once to

both the high and low bytes of Timer1. The high byte of Timer1 is not directly readable or writable in this mode. All reads and writes must take place through the Timer1 High Byte Buffer register. Writes to TMR1H do not clear

the Timer1 prescaler. The prescaler is only cleared on writes to TMR1L.

FIGURE 26-2: TIMER1 16-BIT READ/WRITE MODE BLOCK DIAGRAM



## 26.5 Secondary Oscillator

A dedicated low-power 32.768 kHz oscillator circuit is built-in between pins SOSCI (input) and SOSCO (amplifier output). This internal circuit is designed to be used in conjunction with an external 32.768 kHz crystal.

The oscillator circuit is enabled by setting the SOSCEN bit of the OSCEN register. The oscillator will continue to run during Sleep.

Note:

The oscillator requires a start-up and stabilization time before use. Thus, SOSCEN must be set and a suitable delay observed prior to using Timer1 with the SOSC source. A suitable delay similar to the OST delay can be implemented in software by clearing the TMR1IF bit then presetting the TMR1H:TMR1L register pair to FC00h. The TMR1IF flag will be set when 1024 clock cycles have elapsed, thereby indicating that the oscillator is running and reasonably stable.

# 26.6 Timer Operation in Asynchronous Mode

If the control bit SYNC of the T1CON register is set, the external clock input is not synchronized. The timer increments asynchronously to the internal phase clocks. If the external clock source is selected then the timer will continue to run during Sleep and can generate an interrupt on overflow, which will wake-up the processor. However, special precautions in software are needed to read/write the timer (see Section 26.6.1 "Reading and Writing Timer1 in Asynchronous Mode").

Note:

When switching from synchronous to asynchronous operation, it is possible to skip an increment. When switching from asynchronous to synchronous operation, it is possible to produce an additional increment.

## 26.6.1 READING AND WRITING TIMER1 IN ASYNCHRONOUS MODE

Reading TMR1H or TMR1L while the timer is running from an external asynchronous clock will ensure a valid read (taken care of in hardware). However, the user has to keep in mind that reading the 16-bit timer in two 8-bit values itself, poses certain problems, since the timer may overflow between the reads.

For writes, it is recommended that the user simply stop the timer and write the desired values. A write contention may occur by writing to the timer registers, while the register is incrementing. This may produce an unpredictable value in the TMR1H:TMR1L register pair.

## 26.7 Timer Gate

Timer1 can be configured to count freely or the count can be enabled and disabled using the time gate circuitry. This is also referred to as Timer Gate Enable.

The timer gate can also be driven by multiple selectable sources.

#### 26.7.1 TIMER GATE ENABLE

The Timer Gate Enable mode is enabled by setting the GE bit of the T1GCON register. The polarity of the Timer Gate Enable mode is configured using the GPOL bit of the T1GCON register.

When Timer Gate Enable signal is enabled, the timer will increment on the rising edge of the Timer1 clock source. When Timer Gate Enable signal is disabled, the timer always increments, regardless of the GE bit. See Figure 26-4 for timing details.

TABLE 26-2: TIMER GATE ENABLE SELECTIONS

T1CLK	T1GPOL	T1G	Timer Operation
1	1	1	Counts
1	1	0	Holds Count
1	0	1	Holds Count
1	0	0	Counts

#### 26.7.2 TIMER GATE SOURCE SELECTION

One of the several different external or internal signal sources may be chosen to gate the timer and allow the timer to increment. The gate input signal source can be selected based on the T1GATE register setting. See the T1GATE register (Register 26-4) description for a complete list of the available gate sources. The polarity for each available source is also selectable. Polarity selection is controlled by the GPOL bit of the T1GCON register.

## 26.7.2.1 T1G Pin Gate Operation

The T1G pin is one source for the timer gate control. It can be used to supply an external source to the time gate circuitry.

## 26.7.2.2 Timer0 Overflow Gate Operation

When Timer0 overflows, or a period register match condition occurs (in 8-bit mode), a low-to-high pulse will automatically be generated and internally supplied to the Timer1 gate circuitry.

## 26.7.2.3 Comparator C1 Gate Operation

The output resulting from a Comparator 1 operation can be selected as a source for the timer gate control. The Comparator 1 output can be synchronized to the timer clock or left asynchronous. For more information see Section 23.4.1 "Comparator Output Synchronization".

## 26.7.2.4 Comparator C2 Gate Operation

The output resulting from a Comparator 2 operation can be selected as a source for the timer gate control. The Comparator 2 output can be synchronized to the timer clock or left asynchronous. For more information see Section 23.4.1 "Comparator Output Synchronization".

#### 26.7.3 TIMER1 GATE TOGGLE MODE

When Timer1 Gate Toggle mode is enabled, it is possible to measure the full-cycle length of a timer gate signal, as opposed to the duration of a single level pulse.

The timer gate source is routed through a flip-flop that changes state on every incrementing edge of the signal. See Figure 26-5 for timing details.

Timer1 Gate Toggle mode is enabled by setting the GTM bit of the T1GCON register. When the GTM bit is cleared, the flip-flop is cleared and held clear. This is necessary to control which edge is measured.

Note: Enabling Toggle mode at the same time as changing the gate polarity may result in indeterminate operation.

# 26.7.4 TIMER1 GATE SINGLE-PULSE MODE

When Timer1 Gate Single-Pulse mode is enabled, it is possible to capture a single-pulse gate event. Timer1 Gate Single-Pulse mode is first enabled by setting the GSPM bit in the T1GCON register. Next, the GGO/DONE bit in the T1GCON register must be set. The timer will be fully enabled on the next incrementing edge. On the next trailing edge of the pulse, the GGO/DONE bit will automatically be cleared. No other gate events will be allowed to increment the timer until the GGO/DONE bit is once again set in software. See Figure 26-6 for timing details.

If the Single-Pulse Gate mode is disabled by clearing the GSPM bit in the T1GCON register, the GGO/DONE bit must also be cleared.

Enabling the Toggle mode and the Single-Pulse mode simultaneously will permit both sections to work together. This allows the cycle times on the timer gate source to be measured. See Figure 26-7 for timing details.

## 26.7.5 TIMER1 GATE VALUE STATUS

When Timer1 Gate Value Status is utilized, it is possible to read the most current level of the gate control value. The value is stored in the GVAL bit in the T1GCON register. The GVAL bit is valid even when the timer gate is not enabled (GE bit is cleared).

#### 26.7.6 TIMER1 GATE EVENT INTERRUPT

When Timer1 Gate Event Interrupt is enabled, it is possible to generate an interrupt upon the completion of a gate event. When the falling edge of GVAL occurs, the TMR1GIF flag bit in the PIR5 register will be set. If the TMR1GIE bit in the PIE5 register is set, then an interrupt will be recognized.

The TMR1GIF flag bit operates even when the timer gate is not enabled (TMR1GE bit is cleared).

## 26.8 Timer1 Interrupts

The timer register pair (TMR1H:TMR1L) increments to FFFFh and rolls over to 0000h. When the timer rolls over, the respective timer interrupt flag bit of the PIR5 register is set. To enable the interrupt on rollover, the user must set these bits:

- ON bit of the T1CON register
- · TMR1IE bit of the PIE4 register
- PEIE bit of the INTCON register
- GIE bit of the INTCON register

The interrupt is cleared by clearing the TMR1IF bit in the Interrupt Service Routine.

Note:

To avoid immediate interrupt vectoring, the TMR1H:TMR1L register pair must be preloaded with a value that is not imminently about to rollover, and the TMR1IF flag must be cleared prior to enabling the timer interrupts.

## 26.9 Timer1 Operation During Sleep

Timer1 can only operate during Sleep when setup in Asynchronous Counter mode. In this mode, an external crystal or clock source can be used to increment the counter. To set up the timer to wake the device:

- · ON bit of the T1CON register must be set
- TMR1IE bit of the PIE4 register must be set
- · PEIE bit of the INTCON register must be set
- SYNC bit of the T1CON register must be set
- · CS bits of the T1CLK register must be configured
- The timer clock source must be enabled and continue operation during Sleep. When the SOSC is used for this purpose, the SOSCEN bit of the OSCEN register must be set.

The device will wake-up on an overflow and execute the next instructions. If the GIE bit of the INTCON register is set, the device will call the Interrupt Service Routine.

Secondary oscillator will continue to operate in Sleep regardless of the SYNC bit setting.

## 26.10 CCP Capture/Compare Time Base

The CCP modules use the TMR1H:TMR1L register pair as the time base when operating in Capture or Compare mode.

In Capture mode, the value in the TMR1H:TMR1L register pair is copied into the CCPRxH:CCPRxL register pair on a configured event.

In Compare mode, an event is triggered when the value CCPRxH:CCPRxL register pair matches the value in the TMR1H:TMR1L register pair. This event can be an Auto-conversion Trigger.

For more information, see Section 28.0 "Capture/ Compare/PWM Modules".

## 26.11 CCP Auto-Conversion Trigger


When any of the CCP's are configured to trigger an auto-conversion, the trigger will clear the TMR1H:TMR1L register pair. This auto-conversion does not cause a timer interrupt. The CCP module may still be configured to generate a CCP interrupt.

In this mode of operation, the CCPRxH:CCPRxL register pair becomes the period register for Timer1.


The timer must be synchronized and Fosc/4 must be selected as the clock source to utilize the Auto-conversion Trigger. Asynchronous operation of the timer can cause an Auto-conversion Trigger to be missed.


In the event that a write to TMR1H or TMR1L coincides with an Auto-conversion Trigger from the CCP, the write will take precedence.

For more information, see Section 28.2.4 "Compare During Sleep".

















# 26.12 Register Definitions: Timer1 Control

## REGISTER 26-1: T1CON: TIMER1 CONTROL REGISTER

U-0	U-0	R/W-0/u	R/W-0/u	U-0	R/W-0/u	R/W-0/u	R/W-0/u
	· · ·	CKPS	<1:0>	_	SYNC	RD16	ON
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-6 Unimplemented: Read as '0'

bit 5-4 CKPS<1:0>: Timer1 Input Clock Prescale Select bits

11 =1:8 Prescale value 10 =1:4 Prescale value 01 =1:2 Prescale value 00 =1:1 Prescale value

bit 3 Unimplemented: Read as '0'

bit 2 SYNC: Timer1 Synchronization Control bit

When TMR1CLK = Fosc or Fosc/4

This bit is ignored. The timer uses the internal clock and no additional synchronization is performed.

**ELSE** 

0 = Synchronize external clock input with system clock

1 = Do not synchronize external clock input

bit 1 RD16: 16-bit Read/Write Mode Enable bit

0 = Enables register read/write of Timer1 in two 8-bit operation
 1 = Enables register read/write of Timer1 in one 16-bit operation

bit 0 ON: Timer1 On bit

1 = Enables Timer1

0 = Stops Timer1 and clears Timer1 gate flip-flop

#### REGISTER 26-2: T1GCON: TIMER1 GATE CONTROL REGISTER

R/W-0/u	R/W-0/u	R/W-0/u	R/W-0/u	R/W/HC-0/u	R-x/x	U-0	U-0
GE	GPOL	GTM	GSPM	GGO/DONE	GVAL	_	_
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HC = Bit is cleared by hardware

GE: Timer1 Gate Enable bit bit 7 If ON = 0: This bit is ignored If ON = 1: 1 = Timer1 counting is controlled by the Timer1 gate function 0 = Timer1 is always counting bit 6 GPOL: Timer1 Gate Polarity bit 1 = Timer1 gate is active-high (Timer1 counts when gate is high) 0 = Timer1 gate is active-low (Timer1 counts when gate is low) bit 5 GTM: Timer1 Gate Toggle Mode bit 1 = Timer1 Gate Toggle mode is enabled 0 = Timer1 Gate Toggle mode is disabled and toggle flip-flop is cleared Timer1 gate flip-flop toggles on every rising edge bit 4 GSPM: Timer1 Gate Single-Pulse Mode bit 1 = Timer1 Gate Single-Pulse mode is enabled 0 = Timer1 Gate Single-Pulse mode is disabled bit 3 GGO/DONE: Timer1 Gate Single-Pulse Acquisition Status bit 1 = Timer1 gate single-pulse acquisition is ready, waiting for an edge 0 = Timer1 gate single-pulse acquisition has completed or has not been started This bit is automatically cleared when GSPM is cleared bit 2 GVAL: Timer1 Gate Value Status bit Indicates the current state of the Timer1 gate that can be provided to TMR1H:TMR1L Unaffected by Timer1 Gate Enable (GE) bit 1-0 Unimplemented: Read as '0'

#### REGISTER 26-3: T1CLK TIMER1 CLOCK SELECT REGISTER

U-0	U-0	U-0	U-0	R/W-0/u	R/W-0/u	R/W-0/u	R/W-0/u
2 <del></del> 2	_	_	<del>-</del>		CS<	:3:0>	
bit 7	Fix.	řiv.	di-				bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HC = Bit is cleared by hardware

bit 7-4 Unimplemented: Read as '0'

bit 3-0 CS<3:0>: Timer1 Clock Select bits

1111 = Reserved

1110 = Reserved

1101 = LC4 out

1100 = LC3 out

1011 = LC2\_out

1010 = LC1\_out

1001 = Timer0 overflow output

1000 = CLKR output

0111 = SOSC

0110 = MFINTOSC (32 kHz)

0101 = MFINTOSC (500 kHz)

0100 = LFINTOSC

0011 = HFINTOSC

0010 = Fosc

0001 = Fosc/4

0000 = T1CKIPPS

#### REGISTER 26-4: T1GATE TIMER1 GATE SELECT REGISTER

U-0	U-0	U-0	R/W-0/u	R/W-0/u	R/W-0/u	R/W-0/u	R/W-0/u
? <del></del> ?	_	·—·			GSS<4:0>		
bit 7	ş.:	e i					bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HC = Bit is cleared by hardware

bit 7-5 Unimplemented: Read as '0'

bit 4-0 GSS<4:0>: Timer1 Gate Select bits

11111-10001 = Reserved

10000 = LC4\_out

01111 = LC3\_out

01110 = LC2\_out

01101 = LC1\_out

00100 = ZCD1\_output

01011 = C2OUT\_sync

01010 = C1OUT\_sync

01001 = NCO1\_out

01000 = PWM6\_out

00111 = PWM5\_out

00110 = PWM4\_out

00101 = PWM3\_out

00100 = CCP2\_out 00011 = CCP1 out

00010 = TMR2 postscaled

00001 = Timer0 overflow output

00000 = T1GPPS

TABLE 26-3: SUMMARY OF REGISTERS ASSOCIATED WITH TIMER1

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
INTCON	GIE	PEIE	-		-			INTEDG	121
PIE4	<u> </u>	<u>2</u>		_		1 <u>2</u>	TMR2IE	TMR1IE	126
PIR4	-	-	×—×	_	_	_	TMR2IF	TMR1IF	134
T1CON	-		CKPS	<1:0>	-	SYNC	RD16	ON	286
T1GCON	GE	GPOL	GTM	GSPM	GGO/DONE	CVAL	-	<del>v=</del> 8	287
T1GATE	-	ST-0	, <del>_</del>	GSS<4:0>				289	
T1CLK		<u>2-1</u> 2	_			CS<	3:0>		288
TMR1L	Holding Reg	ister for the L	east Significa	nt Byte of the	16-bit TMR1 Re	egister			277*
TMR1H	Holding Reg	ister for the N	Nost Significa	nt Byte of the	16-bit TMR1 Re	egister			277*
T1CKIPPS	-	-			T1CKIPP	S<5:0>			199
T1GPPS		<u>2—</u> 3		T1GPPS<5:0>					199
CCPxCON	CCPxEN	CCPxOE	CCPxOUT	CCPxOUT CCPxFMT CCPxMODE<3:0>				319	
CLCxSELy	_	_	-	— LCxDyS<4:0>					364
ADACT	-	-	_		А	DACT<4:0>			236

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are not used with the Timer1 modules.

<sup>\*</sup> Page with register information.

# 27.0 TIMER2 MODULE WITH HARDWARE LIMIT TIMER (HLT)


The Timer2 module is an 8-bit timer that can operate as free-running period counters or in conjunction with external signals that control start, run, freeze, and Reset operation in One Shot and Monostable modes of operation. Sophisticated waveform control such as pulse density modulation are possible by combining the operation of this timer with other internal peripherals such as the comparators and CCP modules. Features of the timer include:

- 8-bit timer register
- · 8-bit period register


- Selectable external hardware timer Resets
- Programmable prescaler (1:1 to 1:128)
- Programmable postscaler (1:1 to 1:16)
- · Selectable synchronous/asynchronous operation
- · Alternate clock sources
- · Interrupt-on-period
- · Three modes of operation:
  - Free Running Period
  - One Shot
  - Monostable

See Figure 27-1 for a block diagram of Timer2. See Figure 27-2 for the clock source block diagram.

#### FIGURE 27-1: TIMER2 BLOCK DIAGRAM



### FIGURE 27-2: TIMER2 CLOCK SOURCE BLOCK DIAGRAM



#### 27.1 Timer2 Operation

Timer2 operates in three major modes:

- Free Running Period
- One Shot
- Monostable

Within each mode there are several options for starting, stopping, and Reset. Table 27-1 lists the options.

In all modes, the TMR2 count register is incremented on the rising edge of the clock signal from the programmable prescaler. When TMR2 equals PR2, a high level is output to the postscaler counter. TMR2 is cleared on the next clock input.

An external signal from hardware can also be configured to gate the timer operation or force a TMR2 count Reset. In Gate modes the counter stops when the gate is disabled and resumes when the gate is enabled. In Reset modes the TMR2 count is reset on either the level or edge from the external source.

The TMR2 and PR2 registers are both directly readable and writable. The TMR2 register is cleared and the PR2 register initializes to FFh on any device Reset. Both the prescaler and postscaler counters are cleared on the following events:

- · a write to the TMR2 register
- a write to the T2CON register
- any device Reset
- External Reset Source event that resets the timer.

Note: TMR2 is not cleared when T2CON is written.

#### 27.1.1 FREE RUNNING PERIOD MODE

The value of TMR2 is compared to that of the Period register, PR2, on each TMR2\_clk cycle. When the two values match, the comparator resets the value of TMR2 to 00h on the next rising TMR2\_clk edge and increments

the output postscaler counter. When the postscaler count equals the value in the OUTPS<4:0> bits of the TMR2CON1 register, a one TMR2\_clk period wide pulse occurs on the TMR2\_postscaled output, and the postscaler count is cleared.

#### 27.1.2 ONE SHOT MODE

The One Shot mode is identical to the Free Running Period mode except that the ON bit is cleared and the timer is stopped when TMR2 matches PR2 and will not restart until the T2ON bit is cycled off and on. Postscaler OUTPS<4:0> values other than 0 are meaningless in this mode because the timer is stopped at the first period event and the postscaler is reset when the timer is restarted.

#### 27.1.3 MONOSTABLE MODE

Monostable modes are similar to One Shot modes except that the ON bit is not cleared and the timer can be restarted by an external Reset event.

#### 27.2 Timer2 Output

The Timer2 module's primary output is TMR2\_posts-caled, which pulses for a single TMR2\_clk period when the postscaler counter matches the value in the OUTPS bits of the TMR2CON register. The PR2 post-scaler is incremented each time the TMR2 value matches the PR2 value. This signal can be selected as an input to several other input modules:

- · The ADC module, as an Auto-conversion Trigger
- · COG, as an auto-shutdown source

In addition, the Timer2 is also used by the CCP module for pulse generation in PWM mode. Both the actual TMR2 value as well as other internal signals are sent to the CCP module to properly clock both the period and pulse width of the PWM signal. See Section 28.0 "Capture/Compare/PWM Modules" for more details on setting up Timer2 for use with the CCP, as well as the timing diagrams in Section 27.5 "Operation Examples" for examples of how the varying Timer2 modes affect CCP PWM output.

#### 27.3 External Reset Sources

In addition to the clock source, the Timer2 also takes in an external Reset source. This external Reset source is selected for Timer2 with the T2RST register. This source can control starting and stopping of the timer, as well as resetting the timer, depending on which mode the timer is in. The mode of the timer is controlled by the MODE<4:0> bits of the TMR2HLT register. Edge-Triggered modes require six Timer clock periods between external triggers. Level-Triggered modes require the triggering level to be at least three Timer clock periods long. External triggers are ignored while in Debug Freeze mode.

TABLE 27-1: TIMER2 OPERATING MODES

Mada	MODE	<4:0>	Output	0		Timer Control	
Mode	<4:3>	<2:0>	Operation	Operation	Start	Reset	Stop
		000	9	Software gate (Figure 27-4)	ON = 1	¥-3	ON = 0
		001	Period Pulse	Hardware gate, active-high (Figure 27-5)	ON = 1 and TMRx_ers = 1		ON = 0 or TMRx_ers = 0
		010	i uise	Hardware gate, active-low	ON = 1 and TMRx_ers = 0		ON = 0 or TMRx_ers = 1
Free	00	011	9	Rising or falling edge Reset		TMRx_ers ‡	i.
Running Period	00	100	Period	Rising edge Reset (Figure 27-6)	Ī	TMRx_ers ↑	ON = 0
		101	Pulse	Falling edge Reset		TMRx_ers↓	1
		110	with Hardware	Low level Reset	ON = 1	TMRx_ers = 0	ON = 0 or TMRx_ers = 0
		111	Reset	High level Reset (Figure 27-7)		TMRx_ers = 1	ON = 0 or TMRx_ers = 1
	100	000	One-shot	Software start (Figure 27-8)	ON = 1	8. <u>65—5</u> 71	
		001	Edge	Rising edge start (Figure 27-9)	ON = 1 and TMRx_ers↑	_	
		010	triggered start	Falling edge start	ON = 1 and TMRx_ers↓	4	
		011	(Note 1)	Any edge start	ON = 1 and TMRx_ers ‡	4	ON = 0 or Next clock
One Shot	e Shot 01		Edge	Rising edge start and Rising edge Reset (Figure 27-10)	ON = 1 and TMRx_ers↑	TMRx_ers ↑	after TMRx = PRx
			triggered start and	Falling edge start and Falling edge Reset	ON = 1 and TMRx_ers↓	TMRx_ers↓	(Note 2)
		110	hardware Reset	Rising edge start and Low level Reset (Figure 27-11)	ON = 1 and TMRx_ers ↑	TMRx_ers = 0	
		111	(Note 1)	Falling edge start and High level Reset	ON = 1 and TMRx_ers↓	TMRx_ers = 1	
		000		Rese	rved		_
		001	Edge	Rising edge start (Figure 27-12)	ON = 1 and TMRx_ers ↑		ON = 0 or
Monostable		010	triggered start	Falling edge start	ON = 1 and TMRx_ers↓	<del></del>	Next clock after
	0	011	(Note 1)	Any edge start	ON = 1 and TMRx_ers ‡	<del>53.5</del> 43	TMRx = PRx (Note 3)
Reserved	10	100		Rese	rved		
Reserved		101	13 10	Rese	rved	-99	2
		110	Level triggered	High level start and Low level Reset (Figure 27-13)	ON = 1 and TMRx_ers = 1	TMRx_ers = 0	ON = 0 or
One Shot	start		and hardware	Low level start and High level Reset	ON = 1 and TMRx_ers = 0 TMRx_ers = 1		Held in Reset (Note 2)
Reserved	11	xxx	8	Rese	rved		

Note 1: If ON = 0 then an edge is required to restart the timer after ON = 1.


2: When TMRx = PRx then the next clock clears ON and stops TMRx at 00h.

3: When TMRx = PRx then the next clock stops TMRx at 00h but does not clear ON.

#### 27.4 Timer2 Interrupt

Timer2 can also generate a device interrupt. The interrupt is generated when the postscaler counter matches one of 16 postscale options (from 1:1 through 1:16), which are selected with the postscaler control bits, OUTPS<3:0> of the T2CON register. The interrupt is enabled by setting the TMR2IE interrupt enable bit of the PIE4 register. Interrupt timing is illustrated in Figure 27-3.

FIGURE 27-3: TIMER2 PRESCALER, POSTSCALER, AND INTERRUPT TIMING DIAGRAM



### PIC16(L)F15354/55


#### 27.5 Operation Examples

Unless otherwise specified, the following notes apply to the following timing diagrams:

- Both the prescaler and postscaler are set to 1:1 (both the CKPS and OUTPS bits in the T2CON register are cleared).
- The diagrams illustrate any clock except Fosc/4 and show clock-sync delays of at least two full cycles for both ON and Timer2\_ers. When using Fosc/4, the clocksync delay is at least one instruction period for Timer2\_ers; ON applies in the next instruction period.
- The PWM Duty Cycle and PWM output are illustrated assuming that the timer is used for the PWM function of the CCP module as described in Section 28.0 "Capture/Compare/PWM Modules". The signals are not a part of the Timer2 module.

#### 27.5.1 SOFTWARE GATE MODE

This mode corresponds to legacy Timer2 operation. The timer increments with each clock input when ON=1 and does not increment when ON=0. When the TMR2 count equals the PR2 period count the timer resets on the next clock and continues counting from 0. Operation with the ON bit software controlled is illustrated in Figure 27-4. With PR2=5, the counter advances until TMR2=5, and goes to zero with the next clock.



## PIC16(L)F15354/55


#### 27.5.2 HARDWARE GATE MODE

The Hardware Gate modes operate the same as the Software Gate mode except the TMR2\_ers external signal gates the timer. When used with the CCP the gating extends the PWM period. If the timer is stopped when the PWM output is high then the duty cycle is also extended.

When MODE<4:0> = 00001 then the timer is stopped when the external signal is high. When MODE<4:0> = 00010 then the timer is stopped when the external signal is low.

Figure 27-5 illustrates the Hardware Gating mode for MODE<4:0> = 00001 in which a high input level starts the counter.

FIGURE 27-5: HARDWARE GATE MODE TIMING DIAGRAM (MODE = 00001)




### 27.5.3 EDGE-TRIGGERED HARDWARE LIMIT MODE

In Hardware Limit mode, the timer can be reset by the TMR2\_ers external signal before the timer reaches the period count. Three types of Resets are possible:

- Reset on rising or falling edge (MODE<4:0>= 00011)
- Reset on rising edge (MODE<4:0> = 00100)
- Reset on falling edge (MODE<4:0> = 00101)

When the timer is used in conjunction with the CCP in PWM mode then an early Reset shortens the period and restarts the PWM pulse after a two clock delay. Refer to Figure 27-6.

# FIGURE 27-6: EDGE-TRIGGERED HARDWARE LIMIT MODE TIMING DIAGRAM (MODE = 00100)




### 27.5.4 LEVEL-TRIGGERED HARDWARE LIMIT MODE

In the Level-Triggered Hardware Limit Timer modes, the counter is reset by high or low levels of the external signal TMR2\_ers, as shown in Figure 27-7. Selecting MODE<4:0> = 00110 will cause the timer to reset on a low level external signal. Selecting MODE<4:0> = 00111 will cause the timer to reset on a high level external signal. In the example, the counter is reset while TMR2\_ers = 1. ON is controlled by BSF and BCF instructions. When ON = 0 the external signal is ignored.

When the CCP uses the timer as the PWM time base then the PWM output will be set high when the timer starts counting and then set low only when the timer count matches the CCPRx value. The timer is reset when either the timer count matches the PR2 value or two clock periods after the external Reset signal goes true and stays true.

The timer starts counting, and the PWM output is set high, on either the clock following the PR2 match or two clocks after the external Reset signal relinquishes the Reset. The PWM output will remain high until the timer counts up to match the CCPRx pulse width value. If the external Reset signal goes true while the PWM output is high then the PWM output will remain high until the Reset signal is released allowing the timer to count up to match the CCPRx value.

FIGURE 27-7: LEVEL-TRIGGERED HARDWARE LIMIT MODE TIMING DIAGRAM (MODE = 00111)




### 27.5.5 SOFTWARE START ONE SHOT MODE

In One Shot mode, the timer resets and the ON bit is cleared when the timer value matches the PR2 period value. The ON bit must be set by software to start another timer cycle. Setting MODE<4:0> = 01000 selects One Shot mode which is illustrated in Figure 27-8. In the example, ON is controlled by BSF and BCF instructions. In the first case, a BSF instruction sets ON and the counter runs to completion and clears ON. In the second case, a BSF instruction starts the cycle, BCF/BSF instructions turn the counter off and on during the cycle, and then it runs to completion.

When One Shot mode is used in conjunction with the CCP PWM operation the PWM pulse drive starts concurrent with setting the ON bit. Clearing the ON bit while the PWM drive is active will extend the PWM drive. The PWM drive will terminate when the timer value matches the CCPRx pulse width value. The PWM drive will remain off until software sets the ON bit to start another cycle. If software clears the ON bit after the CCPRx match but before the PR2 match then the PWM drive will be extended by the length of time the ON bit remains cleared. Another timing cycle can only be initiated by setting the ON bit after it has been cleared by a PR2 period count match.

FIGURE 27-8: SOFTWARE START ONE SHOT MODE TIMING DIAGRAM (MODE = 01000)



### PIC16(L)F15354/55

### 27.5.6 EDGE-TRIGGERED ONE SHOT MODE


The Edge-Triggered One Shot modes start the timer on an edge from the external signal input, after the ON bit is set, and clear the ON bit when the timer matches the PR2 period value. The following edges will start the timer:

- Rising edge (MODE<4:0> = 01001)
- Falling edge (MODE<4:0> = 01010)
- Rising or Falling edge (MODE<4:0> = 01011)

If the timer is halted by clearing the ON bit then another TMR2\_ers edge is required after the ON bit is set to resume counting. Figure 27-9 illustrates operation in the rising edge One Shot mode.

When Edge-Triggered One Shot mode is used in conjunction with the CCP then the edge-trigger will activate the PWM drive and the PWM drive will deactivate when the timer matches the CCPRx pulse width value and stay deactivated when the timer halts at the PR2 period count match.

FIGURE 27-9: EDGE-TRIGGERED ONE SHOT MODE TIMING DIAGRAM (MODE = 01001)



### 27.5.7 EDGE-TRIGGERED HARDWARE LIMIT ONE SHOT MODE

In Edge-Triggered Hardware Limit One Shot modes, the timer starts on the first external signal edge after the ON bit is set and resets on all subsequent edges. Only the first edge after the ON bit is set is needed to start the timer. The counter will resume counting automatically two clocks after all subsequent external Reset edges. Edge triggers are as follows:


- Rising edge start and Reset (MODE<4:0> = 01100)
- Falling edge start and Reset (MODE<4:0> = 01101)

The timer resets and clears the ON bit when the timer value matches the PR2 period value. External signal edges will have no effect until after software sets the ON bit. Figure 27-10 illustrates the rising edge hardware limit one-shot operation.

When this mode is used in conjunction with the CCP then the first starting edge trigger, and all subsequent Reset edges, will activate the PWM drive. The PWM drive will deactivate when the timer matches the CCPRx pulse-width value and stay deactivated until the timer halts at the PR2 period match unless an external signal edge resets the timer before the match occurs.

PIC16(L)F15354/55





### 27.5.8 LEVEL RESET, EDGE-TRIGGERED HARDWARE LIMIT ONE SHOT MODES

In Level-Triggered One Shot mode, the timer count is reset on the external signal level and starts counting on the rising/falling edge of the transition from Reset level to the active level while the ON bit is set. Reset levels are selected as follows:


- Low Reset level (MODE<4:0> = 01110)
- High Reset level (MODE<4:0> = 01111)

When the timer count matches the PR2 period count, the timer is reset and the ON bit is cleared. When the ON bit is cleared by either a PR2 match or by software control a new external signal edge is required after the ON bit is set to start the counter.

When Level-Triggered Reset One Shot mode is used in conjunction with the CCP PWM operation the PWM drive goes active with the external signal edge that starts the timer. The PWM drive goes inactive when the timer count equals the CCPRx pulse width count. The PWM drive does not go active when the timer count clears at the PR2 period count match.

PIC16(L)F15354/55

FIGURE 27-11: LOW LEVEL RESET, EDGE-TRIGGERED HARDWARE LIMIT ONE SHOT MODE TIMING DIAGRAM (MODE = 01110)



#### 27.5.9 EDGE-TRIGGERED MONOSTABLE MODES


The Edge-Triggered Monostable modes start the timer on an edge from the external Reset signal input, after the ON bit is set, and stop incrementing the timer when the timer matches the PR2 period value. The following edges will start the timer:

When an Edge-Triggered Monostable mode is used in conjunction with the CCP PWM operation the PWM drive goes active with the external Reset signal edge that starts the timer, but will not go active when the timer matches the PR2 value. While the timer is incrementing, additional edges on the external Reset signal will not affect the CCP PWM.

PIC16(L)F15354/55

- Rising edge (MODE<4:0> = 10001)
- Falling edge (MODE<4:0> = 10010)
- Rising or Falling edge (MODE<4:0> = 10011)

FIGURE 27-12: RISING EDGE-TRIGGERED MONOSTABLE MODE TIMING DIAGRAM (MODE = 10001)



### 27.5.10 LEVEL-TRIGGERED HARDWARE LIMIT ONE SHOT MODES

The Level-Triggered Hardware Limit One Shot modes hold the timer in Reset on an external Reset level and start counting when both the ON bit is set and the external signal is not at the Reset level. If one of either the external signal is not in Reset or the ON bit is set then the other signal being set/made active will start the timer. Reset levels are selected as follows:


- Low Reset level (MODE<4:0> = 10110)
- High Reset level (MODE<4:0> = 10111)

When the timer count matches the PR2 period count, the timer is reset and the ON bit is cleared. When the ON bit is cleared by either a PR2 match or by software control the timer will stay in Reset until both the ON bit is set and the external signal is not at the Reset level.

When Level-Triggered Hardware Limit One Shot modes are used in conjunction with the CCP PWM operation the PWM drive goes active with either the external signal edge or the setting of the ON bit, whichever of the two starts the timer.

PIC16(L)F15354/55





#### 27.6 Timer2 Operation During Sleep

When PSYNC = 1, Timer2 cannot be operated while the processor is in Sleep mode. The contents of the TMR2 and PR2 registers will remain unchanged while processor is in Sleep mode.

When PSYNC = 0, Timer2 will operate in Sleep as long as the clock source selected is also still running. Selecting the LFINTOSC, MFINTOSC, or HFINTOSC oscillator as the timer clock source will keep the selected oscillator running during Sleep.

#### 27.7 Register Definitions: Timer2 Control

#### REGISTER 27-1: T2CLKCON: TIMER2 CLOCK SELECTION REGISTER

U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
,	_	·—:	-		CS<	3:0>	8
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-4 Unimplemented: Read as '0' bit 3-0 CS<3:0>: Timer2 Clock Select bits 1111 = Reserved 1110 = LC4 out 1101 = LC3\_out 1100 = LC2\_out 1011 = LC1\_out 1010 = ZCD1\_output 1001 = NCO1 out 1000 = CLKR 0111 = SOSC 0110 = MFINTOSC (31.25 kHz) 0101 = MFINTOSC (500 kHz) 0100 = LFINTOSC 0011 = HFINTOSC (32 MHz) 0010 = Fosc 0001 = Fosc/40000 = T2CKIPPS

#### REGISTER 27-2: T2CON: TIMER2 CONTROL REGISTER

R/W/HC-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
ON <sup>(1)</sup>		CKPS<2:0>			OUTP	S<3:0>	
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	HC = Bit is cleared by hardware

```
bit 7
              ON: Timer2 On bit
              1 = Timer2 is on
              0 = Timer2 is off: all counters and state machines are reset
bit 6-4
              CKPS<2:0>: Timer2-type Clock Prescale Select bits
              111 =1:128 Prescaler
              110 =1:64 Prescaler
              101 =1:32 Prescaler
              100 =1:16 Prescaler
              011 =1:8 Prescaler
              010 =1:4 Prescaler
              001 =1:2 Prescaler
              000 =1:1 Prescaler
bit 3-0
              OUTPS<3:0>: Timer2 Output Postscaler Select bits
              1111 =1:16 Postscaler
              1110 =1:15 Postscaler
              1101 =1:14 Postscaler
              1100 =1:13 Postscaler
              1011 =1:12 Postscaler
              1010 =1:11 Postscaler
              1001 =1:10 Postscaler
              1000 =1:9 Postscaler
              0111 =1:8 Postscaler
              0110 =1:7 Postscaler
              0101 =1:6 Postscaler
              0100 =1:5 Postscaler
              0011 =1:4 Postscaler
              0010 =1:3 Postscaler
              0001 =1:2 Postscaler
              0000 =1:1 Postscaler
```

Note 1: In certain modes, the ON bit will be auto-cleared by hardware. See Section 27.5 "Operation Examples".

#### REGISTER 27-3: T2HLT: TIMER2 HARDWARE LIMIT CONTROL REGISTER

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
PSYNC <sup>(1, 2)</sup>	CKPOL <sup>(3)</sup>	CKSYNC <sup>(4, 5)</sup>		- 1)	MODE<4:0>(6, 7)		
bit 7	38	3) 3)					bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	PSYNC: Timer2 Prescaler Synchronization Enable bit (1, 2)
	1 = TMR2 Prescaler Output is synchronized to Fosc/4
	0 = TMR2 Prescaler Output is not synchronized to Fosc/4
bit 6	CKPOL: Timer2 Clock Polarity Selection bit (3)
	1 = Falling edge of input clock clocks timer/prescaler
	0 = Rising edge of input clock clocks timer/prescaler
bit 5	CKSYNC: Timer2 Clock Synchronization Enable bit (4, 5)
	1 = ON register bit is synchronized to TMR2_clk input
	0 = ON register bit is not synchronized to TMR2_clk input
bit 4-0	MODE<4:0>: Timer2 Control Mode Selection bits <sup>(6, 7)</sup>
	See Table 27-1.

Note 1: Setting this bit ensures that reading TM2x will return a valid value.

- 2: When this bit is '1', Timer2 cannot operate in Sleep mode.
- 3: CKPOL may not be changed while ON = 1.
- 4: Setting this bit ensures glitch-free operation when the ON is enabled or disabled.
- 5: When this bit is set then the timer operation will be delayed by two TMR2 input clocks after the ON bit is set.
- 6: Unless otherwise indicated, all modes start upon ON = 1 and stop upon ON = 0 (stops occur without affecting the value of TMR2).
- 7: When TMR2 = PR2, the next clock clears TMR2, regardless of the operating mode.

#### REGISTER 27-4: T2RST: TIMER2 EXTERNAL RESET SIGNAL SELECTION REGISTER

U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
\ <del>-</del>	-		-	RSEL<3:0>			
bit 7			_	-			bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-4 Unimplemented: Read as '0'

bit 3-0 RSEL<3:0>: Timer2 External Reset Signal Source Selection bits

1111 = Reserved

1101 = LC4\_out

1100 = LC3\_out

1011 = LC2\_out

1010 = LC1\_out

1001 = ZCD1\_output

1000 = C2OUT\_sync

0111 = C1OUT\_sync

0110 = PWM6\_out

0101 = PWM5\_out

0100 = PWM4\_out

0011 = PWM3\_out

0010 = CCP2\_out

0001 = CCP1\_out

0000 = T2INPPS

TABLE 27-2: SUMMARY OF REGISTERS ASSOCIATED WITH TIMER2

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
CCP1CON	EN	-	OUT	FMT		MODI	E<3:0>	29	319
CCP2CON	EN	_	OUT	FMT		MODI	E<3:0>		319
INTCON	GIE	PEIE	-		_	, s <del></del> ,	_	INTEDG	121
PIE4	_		-	_	::	-	TMR2IE	TMR1IE	126
PIR4	_	_	_		_	-	TMR2IF	TMR1IF	134
PR2	Timer2 Mod	ule Period Re	gister		•	10	2	As:	291*
TMR2	Holding Reg	ister for the 8	bit TMR2 Re	gister	_				292*
T2CON	ON		CKPS<2:0>			OUTP	S<3:0>		308
T2CLKCON	-	_	( <del>-</del> )	_	_ CS<3:0>				
T2RST	-	-		-	— RSEL<3:0>				
T2HLT	PSYNC	CKPOL	CKSYNC			MODE<4:0>	8		309

Legend: — = unimplemented location, read as '0'. Shaded cells are not used for Timer2 module.

Page provides register information.

# 28.0 CAPTURE/COMPARE/PWM MODULES

The Capture/Compare/PWM module is a peripheral that allows the user to time and control different events, and to generate Pulse-Width Modulation (PWM) signals. In Capture mode, the peripheral allows the timing of the duration of an event. The Compare mode allows the user to trigger an external event when a predetermined amount of time has expired. The PWM mode can generate Pulse-Width Modulated signals of varying frequency and duty cycle.

The Capture/Compare/PWM modules available are shown in Table 28-1.

TABLE 28-1: AVAILABLE CCP MODULES

Device	CCP1	CCP2
PIC16(L)F15354/55		•

The Capture and Compare functions are identical for all CCP modules.

- Note 1: In devices with more than one CCP module, it is very important to pay close attention to the register names used. A number placed after the module acronym is used to distinguish between separate modules. For example, the CCP1CON and CCP2CON control the same operational aspects of two completely different CCP modules.
  - 2: Throughout this section, generic references to a CCP module in any of its operating modes may be interpreted as being equally applicable to CCPx module. Register names, module signals, I/O pins, and bit names may use the generic designator 'x' to indicate the use of a numeral to distinguish a particular module, when required.

#### 28.1 Capture Mode

Capture mode makes use of the 16-bit Timer1 resource. When an event occurs on the capture source, the 16-bit CCPRxH:CCPRxL register pair captures and stores the 16-bit value of the TMR1H:TMR1L register pair, respectively. An event is defined as one of the following and is configured by the CCPxMODE<3:0> bits of the CCPxCON register:

- Every falling edge
- Every rising edge
- · Every 4th rising edge
- · Every 16th rising edge

When a capture is made, the Interrupt Request Flag bit CCPxIF of the PIR6 register is set. The interrupt flag must be cleared in software. If another capture occurs before the value in the CCPRxH, CCPRxL register pair is read, the old captured value is overwritten by the new captured value.

Figure 28-1 shows a simplified diagram of the capture operation.

#### 28.1.1 CAPTURE SOURCES


In Capture mode, the CCPx pin may be configured as an input by setting the associated TRIS control bit.

Note: If the CCPx pin is configured as an output, a write to the port can cause a capture condition.

The capture source is selected by configuring the CCPxCTS<2:0> bits of the CCPxCAP register. The following sources can be selected:

- CCPxPPS input
- C1OUT sync
- C2OUT\_sync
- IOC\_interrupt
- LC1\_out
- LC2 out
- LC3\_out
- LC4\_out

FIGURE 28-1: CAPTURE MODE OPERATION BLOCK DIAGRAM



#### 28.1.2 TIMER1 MODE RESOURCE

Timer1 must be running in Timer mode or Synchronized Counter mode for the CCP module to use the capture feature. In Asynchronous Counter mode, the capture operation may not work.

See Section 26.0 "Timer1 Module with Gate Control" for more information on configuring Timer1.

#### 28.1.3 SOFTWARE INTERRUPT MODE

When the Capture mode is changed, a false capture interrupt may be generated. The user must keep the CCPxIE interrupt enable bit of the PIE6 register clear to avoid false interrupts. Additionally, the user must clear the CCPxIF interrupt flag bit of the PIR6 register following any change in Operating mode.

Note: Clocking Timer1 from the system clock (Fosc) may not be used in Capture mode. In order for Capture mode to recognize the trigger event on the CCPx pin, Timer1 must be clocked from the instruction clock (Fosc/4).

#### 28.1.4 CCP PRESCALER

There are four prescaler settings specified by the CCPxMODE<3:0> bits of the CCPxCON register. Whenever the CCP module is turned off, or the CCP module is not in Capture mode, the prescaler counter is cleared. Any Reset will clear the prescaler counter.

Switching from one capture prescaler to another does not clear the prescaler and may generate a false interrupt. To avoid this unexpected operation, turn the module off by clearing the CCPxCON register before changing the prescaler. Example 28-1 demonstrates the code to perform this function.

### EXAMPLE 28-1: CHANGING BETWEEN CAPTURE PRESCALERS

BANKSE	L CCPxCON	;Set Bank bits to point
		;to CCPxCON
CLRF	CCPxCON	;Turn CCP module off
MOVLW	NEW CAPT	PS;Load the W reg with
	<i>7</i> . (3)	;the new prescaler
		; move value and CCP ON
MOVWF	CCPxCON	;Load CCPxCON with this
		;value

#### 28.1.5 CAPTURE DURING SLEEP

Capture mode depends upon the Timer1 module for proper operation. There are two options for driving the Timer1 module in Capture mode. It can be driven by the instruction clock (FOSC/4), or by an external clock source.

When Timer1 is clocked by Fosc/4, Timer1 will not increment during Sleep. When the device wakes from Sleep, Timer1 will continue from its previous state.

Capture mode will operate during Sleep when Timer1 is clocked by an external clock source.

#### 28.2 Compare Mode

Compare mode makes use of the 16-bit Timer1 resource. The 16-bit value of the CCPRxH:CCPRxL register pair is constantly compared against the 16-bit value of the TMR1H:TMR1L register pair. When a match occurs, one of the following events can occur:


- Toggle the CCPx output
- · Set the CCPx output
- · Clear the CCPx output
- · Generate an Auto-conversion Trigger
- · Generate a Software Interrupt

The action on the pin is based on the value of the CCPxMODE<3:0> control bits of the CCPxCON register. At the same time, the interrupt flag CCPxIF bit is set, and an ADC conversion can be triggered, if selected.

All Compare modes can generate an interrupt and trigger and ADC conversion.

Figure 28-2 shows a simplified diagram of the compare operation.

# FIGURE 28-2: COMPARE MODE OPERATION BLOCK DIAGRAM



#### 28.2.1 CCPX PIN CONFIGURATION

The software must configure the CCPx pin as an output by clearing the associated TRIS bit and defining the appropriate output pin through the RxyPPS registers. See Section 15.0 "Peripheral Pin Select (PPS) Module" for more details.

The CCP output can also be used as an input for other peripherals.

Note: Clearing the CCPxCON register will force the CCPx compare output latch to the default low level. This is not the PORT I/O data latch.

#### 28.2.2 TIMER1 MODE RESOURCE

In Compare mode, Timer1 must be running in either Timer mode or Synchronized Counter mode. The compare operation may not work in Asynchronous Counter mode.

See Section 26.0 "Timer1 Module with Gate Control" for more information on configuring Timer1.

Note: Clocking Timer1 from the system clock (FOSC) may not be used in Compare mode. In order for Compare mode to recognize the trigger event on the CCPx pin, Tlmer1 must be clocked from the instruction clock (FOSC/4) or from an external clock source.

#### 28.2.3 AUTO-CONVERSION TRIGGER

All CCPx modes set the CCP interrupt flag (CCPxIF). When this flag is set and a match occurs, an Auto-conversion Trigger can take place if the CCP module is selected as the conversion trigger source.

Refer to Section 20.2.4 "Auto-Conversion Trigger" for more information.

Note: Removing the match condition by changing the contents of the CCPRxH and CCPRxL register pair, between the clock edge that generates the Autoconversion Trigger and the clock edge that generates the Timer1 Reset, will preclude the Reset from occurring

#### 28.2.4 COMPARE DURING SLEEP

Since Fosc is shut down during Sleep mode, the Compare mode will not function properly during Sleep, unless the timer is running. The device will wake on interrupt (if enabled).

#### 28.3 PWM Overview

Pulse-Width Modulation (PWM) is a scheme that provides power to a load by switching quickly between fully on and fully off states. The PWM signal resembles a square wave where the high portion of the signal is considered the on state and the low portion of the signal is considered the off state. The high portion, also known as the pulse width, can vary in time and is defined in steps. A larger number of steps applied, which lengthens the pulse width, also supplies more power to the load. Lowering the number of steps applied, which shortens the pulse width, supplies less power. The PWM period is defined as the duration of one complete cycle or the total amount of on and off time combined.

PWM resolution defines the maximum number of steps that can be present in a single PWM period. A higher resolution allows for more precise control of the pulse width time and in turn the power that is applied to the load

The term duty cycle describes the proportion of the on time to the off time and is expressed in percentages, where 0% is fully off and 100% is fully on. A lower duty cycle corresponds to less power applied and a higher duty cycle corresponds to more power applied.

Figure 28-3 shows a typical waveform of the PWM signal.

#### 28.3.1 STANDARD PWM OPERATION


The standard PWM mode generates a Pulse-Width Modulation (PWM) signal on the CCPx pin with up to ten bits of resolution. The period, duty cycle, and resolution are controlled by the following registers:

- PR2 registers
- T2CON registers
- CCPRxL registers
- CCPxCON registers

Figure 28-4 shows a simplified block diagram of PWM operation.

Note: The corresponding TRIS bit must be cleared to enable the PWM output on the CCPx pin.

#### FIGURE 28-3: CCP PWM OUTPUT SIGNAL



**FIGURE 28-4:** SIMPLIFIED PWM BLOCK DIAGRAM Rev. 10-000 157C 9/5/201 4 Duty cycle registers CCPRxH CCPRxL CCPx out To Peripherals set CCPIF 10-bit Latch(2) (Not accessible by user) Comparator R CCPx **RxyPPS** TRIS Control TMR2 Module TMR2 (1) **ERS** logic CCP<sub>x</sub> pset Comparator PR<sub>2</sub>

#### 28.3.2 SETUP FOR PWM OPERATION

The following steps must be taken when configuring the CCP module for standard PWM operation:

- Use the desired output pin RxyPPS control to select CCPx as the source and disable the CCPx pin output driver by setting the associated TRIS bit.
- Load the PR2 register with the PWM period value.
- Configure the CCP module for the PWM mode by loading the CCPxCON register with the appropriate values.
- Load the CCPRxL register, and the CCPRxH register with the PWM duty cycle value and configure the CCPxFMT bit of the CCPxCON register to set the proper register alignment.
- 5. Configure and start Timer2:
  - Clear the TMR2IF interrupt flag bit of the PIR4 register. See Note below.
  - Configure the CKPS bits of the T2CON register with the Timer prescale value.
  - Enable the Timer by setting the Timer2 ON bit of the T2CON register.

- 6. Enable PWM output pin:
  - Wait until the Timer overflows and the TMR2IF bit of the PIR4 register is set. See the Note below
  - Enable the CCPx pin output driver by clearing the associated TRIS bit

Note: To send a complete duty cycle and period on the first PWM output, the above steps must be included in the setup sequence. If it is not critical to start with a complete PWM signal on the first output, then step 6 may be ignored.

#### 28.3.3 CCP/PWM CLOCK SELECTION

The PIC16(L)F15354/55 allows each individual CCP and PWM module to select the timer source that controls the module. Each module has an independent selection.

#### 28.3.4 TIMER2 TIMER RESOURCE

This device has a newer version of the Timer2 module that has many new modes, which allow for greater customization and control of the PWM signals than on older parts. Refer to Section 27.5 "Operation Examples" for examples of PWM signal generation using the different modes of Timer2. The CCP operation requires that the timer used as the PWM time base has the FOSC/4 clock source selected

#### 28.3.5 PWM PERIOD

The PWM period is specified by the PR2 register of Timer2. The PWM period can be calculated using the formula of Equation 28-1.

#### **EQUATION 28-1: PWM PERIOD**

$$PWM \ Period = [(PR2) + 1] \bullet 4 \bullet Tosc \bullet$$

$$(TMR2 \ Prescale \ Value)$$

Note 1: Tosc = 1/Fosc

When TMR2 is equal to PR2, the following three events occur on the next increment cycle:

- TMR2 is cleared
- The CCPx pin is set. (Exception: If the PWM duty cycle = 0%, the pin will not be set.)
- The PWM duty cycle is transferred from the CCPRxL/H register pair into a 10-bit buffer.

Note: The Timer postscaler (see Section 27.4 "Timer2 Interrupt") is not used in the determination of the PWM frequency.


#### 28.3.6 PWM DUTY CYCLE

The PWM duty cycle is specified by writing a 10-bit value to the CCPRxH:CCPRxL register pair. The alignment of the 10-bit value is determined by the CCPRxFMT bit of the CCPxCON register (see Figure 28-5). The CCPRxH:CCPRxL register pair can be written to at any time; however the duty cycle value is not latched into the 10-bit buffer until after a match between PR2 and TMR2.

Equation 28-2 is used to calculate the PWM pulse width.

Equation 28-3 is used to calculate the PWM duty cycle ratio.

#### FIGURE 28-5: PWM 10-BIT ALIGNMENT



#### **EQUATION 28-2: PULSE WIDTH**

Pulse Width = (CCPRxH:CCPRxL register pair) •

Tosc • (TMR2 Prescale Value)

#### **EQUATION 28-3: DUTY CYCLE RATIO**

Duty Cycle Ratio = 
$$\frac{(CCPRxH:CCPRxL\ register\ pair)}{4(PR2+1)}$$

CCPRxH:CCPRxL register pair are used to double buffer the PWM duty cycle. This double buffering provides for glitchless PWM operation.

The 8-bit timer TMR2 register is concatenated with either the 2-bit internal system clock (FOSC), or two bits of the prescaler, to create the 10-bit time base. The system clock is used if the Timer2 prescaler is set to 1:1.

When the 10-bit time base matches the CCPRxH:CCPRxL register pair, then the CCPx pin is cleared (see Figure 28-4).

#### 28.3.7 PWM RESOLUTION

The resolution determines the number of available duty cycles for a given period. For example, a 10-bit resolution will result in 1024 discrete duty cycles, whereas an 8-bit resolution will result in 256 discrete duty cycles.

The maximum PWM resolution is ten bits when PR2 is 255. The resolution is a function of the PR2 register value as shown by Equation 28-4.

#### **EQUATION 28-4: PWM RESOLUTION**

Resolution = 
$$\frac{log[4(PR2+1)]}{log(2)}$$
 bits

Note: If the pulse width value is greater than the period the assigned PWM pin(s) will remain unchanged.

#### TABLE 28-2: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS (Fosc = 20 MHz)

PWM Frequency	1.22 kHz	4.88 kHz	19.53 kHz	78.12 kHz	156.3 kHz	208.3 kHz
Timer Prescale	16	4	1	1	1	1
PR2 Value	0xFF	0xFF	0xFF	0x3F	0x1F	0x17
Maximum Resolution (bits)	10	10	10	8	7	6.6

#### TABLE 28-3: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS (Fosc = 8 MHz)

PWM Frequency	1.22 kHz	4.90 kHz	19.61 kHz	76.92 kHz	153.85 kHz	200.0 kHz
Timer Prescale	16	4	1	1	1	1
PR2 Value	0x65	0x65	0x65	0x19	0x0C	0x09
Maximum Resolution (bits)	8	8	8	6	5	5

#### 28.3.8 OPERATION IN SLEEP MODE

In Sleep mode, the TMR2 register will not increment and the state of the module will not change. If the CCPx pin is driving a value, it will continue to drive that value. When the device wakes up, TMR2 will continue from its previous state.

### 28.3.9 CHANGES IN SYSTEM CLOCK FREQUENCY

The PWM frequency is derived from the system clock frequency. Any changes in the system clock frequency will result in changes to the PWM frequency. See Section 9.0 "Oscillator Module (with Fail-Safe Clock Monitor)" for additional details.

#### 28.3.10 EFFECTS OF RESET

Any Reset will force all ports to Input mode and the CCP registers to their Reset states.

#### 28.4 Register Definitions: CCP Control

Long bit name prefixes for the CCP peripherals are shown in Section 1.1 "Register and Bit Naming Conventions".

TABLE 28-4: LONG BIT NAMES PREFIXES FOR CCP PERIPHERALS

Peripheral	Bit Name Prefix		
CCP1	CCP1		
CCP2	CCP2		

#### REGISTER 28-1: CCPxCON: CCPx CONTROL REGISTER

R/W-0/0	U-0	R-x	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
EN	1	OUT	FMT	MODE<3:0>			
bit 7	-	-					bit 0

Legend:		<del></del>
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Reset
'1' = Bit is set	'0' = Bit is cleared	

bit 7	EN: CCPx Module Enable bit 1 = CCPx is enabled 0 = CCPx is disabled
bit 6	Unimplemented: Read as '0'
bit 5	OUT: CCPx Output Data bit (read-only)
bit 4	FMT: CCPW (Pulse Width) Alignment bit MODE = Capture mode Unused MODE = Compare mode Unused MODE = PWM mode 1 = Left-aligned format 0 = Right-aligned format
bit 3-0	MODE<3:0>: CCPx Mode Select bits <sup>(1)</sup> 1111 - 1100 = PWM mode (Timer2 as the timer source) 1110 = Reserved 1101 = Reserved 1100 = Reserved
	1011 =Compare mode: output will pulse 0-1-0; Clears TMR1 1010 =Compare mode: output will pulse 0-1-0 1001 =Compare mode: clear output on compare match 1000 =Compare mode: set output on compare match
	0111 =Capture mode: every 16th rising edge of CCPx input 0110 =Capture mode: every 4th rising edge of CCPx input 0101 =Capture mode: every rising edge of CCPx input 0100 =Capture mode: every falling edge of CCPx input
	0011 =Capture mode: every edge of CCPx input 0010 =Compare mode: toggle output on match 0001 =Compare mode: toggle output on match; clear TMR1 0000 =Capture/Compare/PWM off (resets CCPx module)

Note 1: All modes will set the CCPxIF bit, and will trigger an ADC conversion if CCPx is selected as the ADC trigger source.

#### REGISTER 28-2: CCPxCAP: CAPTURE INPUT SELECTION REGISTER

U-0	U-0	U-0	U-0	U-0	R/W-0/x	R/W-0/x	R/W-0/x
_	_	1 <del></del> 2	<del>-</del>	— —		CTS<2:0>	
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Reset

'1' = Bit is set '0' = Bit is cleared

bit 7-3 Unimplemented: Read as '0'

bit 2-0 CTS<2:0>: Capture Trigger Input Selection bits

CTS	CCP1.capture	CCP2.capture				
111	LC4_out					
110	LC3_out					
101	LC2_out					
100	LC1_out					
011	IOC_interrupt					
010	C2OUT					
001	C1OUT					
000	CCP1PPS	CCP2PPS				

#### REGISTER 28-3: CCPRxL REGISTER: CCPx REGISTER LOW BYTE

R/W-x/x	R/W-x/x	R/W-x/x	R/W-x/x	R/W-x/x	R/W-x/x	R/W-x/x	R/W-x/x		
CCPRx<7:0>									
bit 7							bit 0		

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Reset

'1' = Bit is set '0' = Bit is cleared

bit 7-0 CCPxMODE = Capture mode

CCPRxL<7:0>: Capture value of TMR1L

CCPxMODE = Compare mode

CCPRxL<7:0>: LS Byte compared to TMR1L
CCPxMODE = PWM modes when CCPxFMT = 0:
CCPRxL<7:0>: Pulse-width Least Significant eight bits
CCPxMODE = PWM modes when CCPxFMT = 1:
CCPRxL<7:6>: Pulse-width Least Significant two bits

CCPRxL<5:0>: Not used.

#### REGISTER 28-4: CCPRxH REGISTER: CCPx REGISTER HIGH BYTE

| R/W-x/x |
|---------|---------|---------|---------|---------|---------|---------|---------|
|         |         |         | CCPRx   | <15:8>  |         |         | j       |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Reset

'1' = Bit is set '0' = Bit is cleared

bit 7-0 CCPxMODE = Capture mode

CCPRxH<7:0>: Captured value of TMR1H

CCPxMODE = Compare mode

**CCPRxH<7:0>:** MS Byte compared to TMR1H <u>CCPxMODE = PWM modes when CCPxFMT = 0</u>:

CCPRxH<7:2>: Not used

CCPRxH<1:0>: Pulse-width Most Significant two bits CCPxMODE = PWM modes when CCPxFMT = 1: CCPRxH<7:0>: Pulse-width Most Significant eight bits

TABLE 28-5: SUMMARY OF REGISTERS ASSOCIATED WITH CCPx

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
INTCON	GIE	PEIE	-	-	s <del></del> s	-	1	INTEDG	121
PIR6	1 <del></del>	_	_	-		-	CCP2IF	CCP1IF	136
PIE6	1-3	:			::	: <u></u> -	CCP2IE	CCP1IE	128
CCP1CON	EN	8—X	OUT	OUT FMT MODE<3:0>					
CCP1CAP	-		-	CTS<2:0>					
CCPR1L	Capture/Compare/PWM Register 1 (LSB)							320	
CCPR1H	Capture/Compare/PWM Register 1 (MSB)							321	
CCP2CON	EN		OUT	FMT	FMT MODE<3:0>				
CCP2CAP	` <del>-</del> `	-	*	11_2	CTS<2:0>				
CCPR2L	Capture/Compare/PWM Register 1 (LSB)								320
CCPR2H	Capture/Compare/PWM Register 1 (MSB)								320
CCP1PPS	-	_	CCP1PPS<5:0>						
CCP2PPS	-		CCP2PPS<5:0>						
RxyPPS		,—,	-	- RxyPPS<4:0>					
ADACT	-	_	_	— ADACT<4:0>					
CLCxSELy	_	_	LCxDyS<4:0>						364
CWG1DAT	_	_		DAT<3:0>					

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are not used by the CCP module.

# 29.0 PULSE-WIDTH MODULATION (PWM)

The PWMx modules generate Pulse-Width Modulated (PWM) signals of varying frequency and duty cycle.

In addition to the CCP modules, the PIC16(L)F15354/55 devices contain four 10-bit PWM modules (PWM3, PWM4, PWM5 and PWM6). The PWM modules reproduce the PWM capability of the CCP modules.


Note: PWM3/4/5/6 modules four instances of the same PWM module design. Throughout this section, the lower case 'x' in register and bit names is a generic reference to the PWM module number (which may be substituted with 3, or 4, or, 5, or 6 during code development). For example, the control register is generically described in this chapter as PWMxCON, but the actual device registers are PWM3CON, PWM4CON, PWM5CON and PWM6CON. Similarly, the PWMxEN bit represents PWM3EN, PWM4EN, PWM5EN and PWM6EN bits.

Pulse-Width Modulation (PWM) is a scheme that provides power to a load by switching quickly between fully on and fully off states. The PWM signal resembles a square wave where the high portion of the signal is considered the 'on' state (pulse width), and the low portion of the signal is considered the 'off' state. The term duty cycle describes the proportion of the 'on' time to the 'off' time and is expressed in percentages, where 0% is fully off and 100% is fully on. A lower duty cycle corresponds to less power applied and a higher duty cycle corresponds to more power applied. The PWM period is defined as the duration of one complete cycle or the total amount of on and off time combined.

PWM resolution defines the maximum number of steps that can be present in a single PWM period. A higher resolution allows for more precise control of the pulse width time and, in turn, the power that is applied to the load.

Figure 29-1 shows a typical waveform of the PWM signal.

## FIGURE 29-1: PWM OUTPUT



### 29.1 Standard PWM Mode

The standard PWM mode generates a Pulse-Width Modulation (PWM) signal on the PWMx pin with up to ten bits of resolution. The period, duty cycle, and resolution are controlled by the following registers:

- TMR2 register
- PR2 register
- PWMxCON registers
- PWMxDCH registers
- PWMxDCL registers


Figure 29-2 shows a simplified block diagram of PWM operation.

If PWMPOL = 0, the default state of the output is '0'. If PWMPOL = 1, the default state is '1'. If PWMEN = 0, the output will be the default state.

Note: The corresponding TRIS bit must be cleared to enable the PWM output on the

PWMx pin

#### FIGURE 29-2: SIMPLIFIED PWM BLOCK DIAGRAM



create 10-bit time-base.

#### 29.1.1 PWM CLOCK SELECTION

The PIC16(L)F15354/55 allows each individual CCP and PWM module to select the timer source that controls the module. Each module has an independent selection.

## 29.1.2 USING THE TMR2 WITH THE PWM MODULE

This device has a newer version of the TMR2 module that has many new modes, which allow for greater customization and control of the PWM signals than on older parts. Refer to Section 27.5 "Operation Examples" for examples of PWM signal generation using the different modes of Timer2.

Note: PWM operation requires that the timer used as the PWM time base has the FOSC/4 clock source selected.

### 29.1.3 PWM PERIOD

Referring to Figure 29-1, the PWM output has a period and a pulse width. The frequency of the PWM is the inverse of the period (1/period).

The PWM period is specified by writing to the PR2 register. The PWM period can be calculated using the following formula:

## **EQUATION 29-1: PWM PERIOD**

 $PWM \ Period = \ [(PR2) + 1] \cdot 4 \cdot TOSC$  $\cdot (TMR2 \ Prescale \ Value)$ 

Note 1: Tosc = 1/Fosc

When TMR2 is equal to PR2, the following three events occur on the next increment cycle:

- TMR2 is cleared
- The PWMx pin is set (Exception: If the PWM duty cycle = 0%, the pin will not be set.)
- . The PWM pulse width is latched from PWMxDC.

Note: If the pulse width value is greater than the period the assigned PWM pin(s) will remain unchanged.

## 29.1.4 PWM DUTY CYCLE

The PWM duty cycle is specified by writing a 10-bit value to the PWMxDC register. The PWMxDCH contains the eight MSbs and the PWMxDCL<7:6> bits contain the two LSbs.

The PWMDC register is double-buffered and can be updated at any time. This double buffering is essential for glitch-free PWM operation. New values take effect when TMR2 = PR2. Note that PWMDC is left-justified.

The 8-bit timer TMR2 register is concatenated with either the 2-bit internal system clock (FOSC), or two bits of the prescaler, to create the 10-bit time base. The system clock is used if the Timer2 prescaler is set to 1.1

Equation 29-2 is used to calculate the PWM pulse width.

Equation 29-3 is used to calculate the PWM duty cycle ratio

### **EQUATION 29-2: PULSE WIDTH**

Pulse Width =  $(PWMxDC) \cdot TOSC \cdot (TMR2 Prescale Value)$ 

### **EQUATION 29-3: DUTY CYCLE RATIO**

Duty Cycle Ratio = 
$$\frac{(PWMxDC)}{4(PR2+1)}$$

## 29.1.5 PWM RESOLUTION

The resolution determines the number of available duty cycles for a given period. For example, a 10-bit resolution will result in 1024 discrete duty cycles, whereas an 8-bit resolution will result in 256 discrete duty cycles.

The maximum PWM resolution is ten bits when PR2 is 255. The resolution is a function of the PR2 register value as shown by Equation 29-4.

## **EQUATION 29-4: PWM RESOLUTION**

$$Resolution = \frac{\log[4(PR2+1)]}{\log(2)} bits$$

#### 29.1.6 OPERATION IN SLEEP MODE

In Sleep mode, the TMR2 register will not increment and the state of the module will not change. If the PWMx pin is driving a value, it will continue to drive that value. When the device wakes up, TMR2 will continue from its previous state.

## 29.1.7 CHANGES IN SYSTEM CLOCK FREQUENCY

The PWM frequency is derived from the system clock frequency. Any changes in the system clock frequency will result in changes to the PWM frequency. See Section 9.0 "Oscillator Module (with Fail-Safe Clock Monitor)" for additional details.

#### 29.1.8 EFFECTS OF RESET

Any Reset will force all ports to Input mode and the PWMx registers to their Reset states.

TABLE 29-1: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS (Fosc = 20 MHz)

PWM Frequency	1.22 kHz	4.88 kHz	19.53 kHz	78.12 kHz	156.3 kHz	208.3 kHz
Timer Prescale	16	4	1	1	1	1
PR2 Value	0xFF	0xFF	0xFF	0x3F	0x1F	0x17
Maximum Resolution (bits)	10	10	10	8	7	6.6

TABLE 29-2: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS (Fosc = 8 MHz)

PWM Frequency	1.22 kHz	4.90 kHz	19.61 kHz	76.92 kHz	153.85 kHz	200.0 kHz
Timer Prescale	16	4	1	1	1	1
PR2 Value	0x65	0x65	0x65	0x19	0x0C	0x09
Maximum Resolution (bits)	8	8	8	6	5	5

#### 29.1.9 SETUP FOR PWM OPERATION

The following steps must be taken when configuring the module for using the PWMx outputs:

- Disable the PWMx pin output driver(s) by setting the associated TRIS bit(s).
- Configure the PWM output polarity by configuring the PWMxPOL bit of the PWMxCON register.
- Load the PR2 register with the PWM period value, as determined by Equation 29-1.
- Load the PWMxDCH register and bits <7:6> of the PWMxDCL register with the PWM duty cycle value, as determined by Equation 29-2.
- Configure and start Timer2:
- Clear the TMR2IF interrupt flag bit of the PIR4 register
- Select the Timer2 prescale value by configuring the CKPS<2:0> bits of the T2CON register
- Enable Timer2 by setting the Timer2 ON bit of the T2CON register

- 6. Wait until the TMR2IF is set.
- 7. When the TMR2IF flag bit is set:
- Clear the associated TRIS bit(s) to enable the output driver
- Route the signal to the desired pin by configuring the RxyPPS register
- Enable the PWMx module by setting the PWMxEN bit of the PWMxCON register

To send a complete duty cycle and period on the first PWM output, the above steps must be followed in the order given. If it is not critical to start with a complete PWM signal, then the PWM module can be enabled during Step 2 by setting the PWMxEN bit of the PWMxCON register.

## 29.2 Register Definitions: PWM Control

## REGISTER 29-1: PWMxCON: PWM CONTROL REGISTER

R/W-0/0	U-0	R-0	R/W-0/0	U-0	U-0	U-0	U-0
PWMxEN	-	PWMxOUT	PWMxPOL	·—	-	<del></del>	_
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	PWMxEN: PWM Module Enable bit
	<ul><li>1 = PWM module is enabled</li><li>0 = PWM module is disabled</li></ul>
bit 6	Unimplemented: Read as '0'
bit 5	PWMxOUT: PWM Module Output Level when Bit is Read
bit 4	PWMxPOL: PWMx Output Polarity Select bit
	<ul><li>1 = PWM output is active-low</li><li>0 = PWM output is active-high</li></ul>
bit 3-0	Unimplemented: Read as '0'

### REGISTER 29-2: PWMxDCH: PWM DUTY CYCLE HIGH BITS

R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u		
	PWMxDC<9:2>								
bit 7 bit									

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown

'1' = Bit is set '0' = Bit is cleared

U = Unimplemented bit, read as '0'

-n/n = Value at POR and BOR/Value at all other Resets

bit 7-0 PWMxDC<9:2>: PWM Duty Cycle Most Significant bits

These bits are the MSbs of the PWM duty cycle. The two LSbs are found in PWMxDCL Register.

#### REGISTER 29-3: PWMxDCL: PWM DUTY CYCLE LOW BITS

R/W-x/u	R/W-x/u	U-0	U-0	U-0	U-0	U-0	U-0
PWMxDC<1:0>		( <del>1</del> 1)		_	( <del></del>	_	_
bit 7	bit 7						bit 0

 Legend:
 R = Readable bit
 W = Writable bit
 U = Unimplemented bit, read as '0'

 u = Bit is unchanged
 x = Bit is unknown
 -n/n = Value at POR and BOR/Value at all other Resets

 '1' = Bit is set
 '0' = Bit is cleared

bit 7-6 PWMxDC<1:0>: PWM Duty Cycle Least Significant bits

These bits are the LSbs of the PWM duty cycle. The MSbs are found in PWMxDCH Register.

bit 5-0 Unimplemented: Read as '0'

## TABLE 29-3: SUMMARY OF REGISTERS ASSOCIATED WITH PWMx

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
T2CON	ON	ON CKPS<2:0> OUTPS<3:0>							
T2TMR	Holding Regi	Holding Register for the 8-bit TMR2 Register							
T2PR	TMR2 Period	TMR2 Period Register							291*
RxyPPS		<u></u> 5		— RxyPPS<4:0>					200
CWG1DAT	· <del></del>	-	-	_		DAT<	3:0>		353
CLCxSELy		_	LCxDyS<5:0>						364

Legend: -= Unimplemented locations, read as '0'. Shaded cells are not used by the PWMx module.

<sup>\*</sup> Page with Register information.

# 30.0 COMPLEMENTARY WAVEFORM GENERATOR (CWG) MODULE

The Complementary Waveform Generator (CWG) produces half-bridge, full-bridge, and steering of PWM waveforms. It is backwards compatible with previous ECCP functions.

The CWG has the following features:

- Six operating modes:
  - Synchronous Steering mode
  - Asynchronous Steering mode
  - Full-Bridge mode, Forward
  - Full-Bridge mode, Reverse
  - Half-Bridge mode
  - Push-Pull mode
- · Output polarity control
- Output steering
  - Synchronized to rising event
  - Immediate effect
- Independent 6-bit rising and falling event deadband timers
  - Clocked dead band
  - Independent rising and falling dead-band enables
- · Auto-shutdown control with:
  - Selectable shutdown sources
  - Auto-restart enable
  - Auto-shutdown pin override control

The CWG modules available are shown in Table 30-1.

### TABLE 30-1: AVAILABLE CWG MODULES

Device	CWG1
PIC16(L)F15354/55	•

### 30.1 Fundamental Operation

The CWG module can operate in six different modes, as specified by MODE of the CWG1CON0 register:


- Half-Bridge mode (Figure 30-9)
- Push-Pull mode (Figure 30-2)
  - Full-Bridge mode, Forward (Figure 30-3)
  - Full-Bridge mode, Reverse (Figure 30-3)
- Steering mode (Figure 30-10)
- · Synchronous Steering mode (Figure 30-11)

It may be necessary to guard against the possibility of circuit faults or a feedback event arriving too late or not at all. In this case, the active drive must be terminated before the Fault condition causes damage. Thus, all output modes support auto-shutdown, which is covered in 30.10 "Auto-Shutdown".

#### 30.1.1 HALF-BRIDGE MODE

In Half-Bridge mode, two output signals are generated as true and inverted versions of the input as illustrated in Figure 30-9. A nonoverlap (dead-band) time is inserted between the two outputs as described in Section 30.5 "Dead-Band Control".

The unused outputs CWG1C and CWG1D drive similar signals, with polarity independently controlled by the POLC and POLD bits of the CWG1CON1 register, respectively.



PIC16(L)F15354/55

## 30.1.2 PUSH-PULL MODE

In Push-Pull mode, two output signals are generated, alternating copies of the input as illustrated in Figure 30-2. This alternation creates the push-pull effect required for driving some transformer-based power supply designs.


The push-pull sequencer is reset whenever EN = 0 or if an auto-shutdown event occurs. The sequencer is clocked by the first input pulse, and the first output appears on CWG1A.

The unused outputs CWG1C and CWG1D drive copies of CWG1A and CWG1B, respectively, but with polarity controlled by the POLC and POLD bits of the CWG1CON1 register, respectively.

#### 30.1.3 FULL-BRIDGE MODES


In Forward and Reverse Full-Bridge modes, three outputs drive static values while the fourth is modulated by the input data signal. In Forward Full-Bridge mode, CWG1A is driven to its active state, CWG1B and CWG1C are driven to their inactive state, and CWG1D is modulated by the input signal. In Reverse Full-Bridge mode, CWG1C is driven to its active state, CWG1A and CWG1D are driven to their inactive states, and CWG1B is modulated by the input signal. In Full-Bridge mode, the dead-band period is used when there is a switch from forward to reverse or vice-versa. This dead-band control is described in Section 30.5 "Dead-Band Control", with additional details in Section 30.6 "Rising Edge and Reverse Dead Band" and Section 30.7 "Falling Edge and Forward Dead Band".

The mode selection may be toggled between forward and reverse toggling the MODE<0> bit of the CWG1CON0 while keeping MODE<2:1> static, without disabling the CWG module.



PIC16(L)F15354/55

DS40001853D-page 334




### 30.1.4 STEERING MODES

In Steering modes, the data input can be steered to any or all of the four CWG output pins. In Synchronous Steering mode, changes to steering selection registers take effect on the next rising input.

In Nonsynchronous mode, steering takes effect on the next instruction cycle. Additional details are provided in Section 30.9 "CWG Steering Mode".

FIGURE 30-4: SIMPLIFIED CWG BLOCK DIAGRAM (OUTPUT STEERING MODES)



## 30.2 Clock Source

The CWG module allows the following clock sources to be selected:

- · Fosc (system clock)
- HFINTOSC (16 MHz only)

The clock sources are selected using the CS bit of the CWG1CLKCON register.

## 30.3 Selectable Input Sources

The CWG generates the output waveforms from the input sources in Table 30-2.

TABLE 30-2: SELECTABLE INPUT SOURCES

Source Peripheral	Signal Name
CWG input PPS pin	CWG1PPS
CCP1	CCP1_out
CCP2	CCP2_out
PWM3	PWM3_out
PWM4	PWM4_out
PWM5	PWM5_out
PWM6	PWM6_out
NCO	NCO1_out
Comparator C1	C1OUT_sync
Comparator C2	C2OUT_sync
CLC1	LC1_out
CLC2	LC2_out
CLC3	LC3_out
CLC4	LC4_out

The input sources are selected using the CWG1DAT register.

## 30.4 Output Control

### 30.4.1 POLARITY CONTROL

The polarity of each CWG output can be selected independently. When the output polarity bit is set, the corresponding output is active-high. Clearing the output polarity bit configures the corresponding output as active-low. However, polarity does not affect the override levels. Output polarity is selected with the POLx bits of the CWG1CON1. Auto-shutdown and steering options are unaffected by polarity.

FIGURE 30-5: **CWG OUTPUT BLOCK DIAGRAM** LSAC<1:0> **RxyPPS** '1' 11 TRIS Control '0' 10 CWG\_dataA High Z 01 **PPS** CWGxA POLA 00 **OVRA** 0 STRA(1) LSBD<1:0> **RxyPPS** 1' 11 TRIS Control '0' 10 1 CWG\_dataB High Z 01 **PPS** POLB 00 **OVRB** 0 STRB(1) LSAC<1:0> **RxyPPS** 11 11 TRIS Control '0' -10 CWG\_dataC High Z 01 PPS CWGxC 0 POLC 00 **OVRC** 0 STRC(1) LSBD<1:0> -**RxyPPS** 11'-11 TRIS Control '0' -10 CWG\_dataD CWGxD PPS High Z 01 1 0 POLD 00 OVRD STRD(1) CWG\_shutdown Note 1: STRx is held to 1 in all modes other than Output Steering Mode.

#### 30.5 Dead-Band Control

The dead-band control provides nonoverlapping PWM signals to prevent shoot-through current in PWM switches. Dead-band operation is employed for Half-Bridge and Full-Bridge modes. The CWG contains two 6-bit dead-band counters. One is used for the rising edge of the input source control in Half-Bridge mode or for reverse dead-band Full-Bridge mode. The other is used for the falling edge of the input source control in Half-Bridge mode or for forward dead band in Full-Bridge mode.

Dead band is timed by counting CWG clock periods from zero up to the value in the rising or falling deadband counter registers. See CWG1DBR and CWG1DBF registers, respectively.

## 30.5.1 DEAD-BAND FUNCTIONALITY IN HALF-BRIDGE MODE

In Half-Bridge mode, the dead-band counters dictate the delay between the falling edge of the normal output and the rising edge of the inverted output. This can be seen in Figure 30-9.

## 30.5.2 DEAD-BAND FUNCTIONALITY IN FULL-BRIDGE MODE

In Full-Bridge mode, the dead-band counters are used when undergoing a direction change. The MODE<0> bit of the CWG1CON0 register can be set or cleared while the CWG is running, allowing for changes from Forward to Reverse mode. The CWG1A and CWG1C signals will change upon the first rising input edge following a direction change, but the modulated signals (CWG1B or CWG1D, depending on the direction of the change) will experience a delay dictated by the dead-band counters. This is demonstrated in Figure 30-3.


## 30.6 Rising Edge and Reverse Dead Band


CWG1DBR controls the rising edge dead-band time at the leading edge of CWG1A (Half-Bridge mode) or the leading edge of CWG1B (Full-Bridge mode). The CWG1DBR value is double-buffered. When EN = 0, the CWG1DBR register is loaded immediately when CWG1DBR is written. When EN = 1, then software must set the LD bit of the CWG1CON0 register, and the buffer will be loaded at the next falling edge of the CWG input signal. If the input source signal is not present for enough time for the count to be completed, no output will be seen on the respective output.

## 30.7 Falling Edge and Forward Dead Band

CWG1DBF controls the dead-band time at the leading edge of CWG1B (Half-Bridge mode) or the leading edge of CWG1D (Full-Bridge mode). The CWG1DBF value is double-buffered. When EN = 0, the CWG1DBF register is loaded immediately when CWG1DBF is written. When EN = 1 then software must set the LD bit of the CWG1CON0 register, and the buffer will be loaded at the next falling edge of the CWG input signal. If the input source signal is not present for enough time for the count to be completed, no output will be seen on the respective output.

Refer to Figure 30-6 and Figure 30-7 for examples.





PIC16(L)F15354/55

## 30.8 Dead-Band Uncertainty

When the rising and falling edges of the input source are asynchronous to the CWG clock, it creates uncertainty in the dead-band time delay. The maximum uncertainty is equal to one CWG clock period. Refer to Equation 30-1 for more details.

## EQUATION 30-1: DEAD-BAND UNCERTAINTY

$$TDEADBAND\_UNCERTAINTY = \frac{1}{Fcwg\ clock}$$


Example:

Therefore:

$$TDEADBAND\_UNCERTAINTY = \frac{1}{Fcwg\_clock}$$
$$= \frac{1}{16MHz}$$


= 62.5 ns

## FIGURE 30-8: EXAMPLE OF PWM DIRECTION CHANGE



- Note 1: WGPOL{ABCD} = 0
  - 2: The direction bit MODE<0> (Register 30-1) can be written any time during the PWM cycle, and takes effect at the next rising CWG1 data.
  - 3: When changing directions, CWG1A and CWG1C switch at rising CWG1\_data; modulated CWG1B and CWG1D are held inactive for the dead band duration shown; dead band affects only the first pulse after the direction change.

## FIGURE 30-9: CWG HALF-BRIDGE MODE OPERATION



## 30.9 CWG Steering Mode

In Steering mode (MODE = 00x), the CWG allows any combination of the CWG1x pins to be the modulated signal. The same signal can be simultaneously available on multiple pins, or a fixed-value output can be presented.

When the respective STRx bit of CWG10CON0 is '0', the corresponding pin is held at the level defined. When the respective STRx bit of CWG10CON0 is '1', the pin is driven by the input data signal. The user can assign the input data signal to one, two, three, or all four output pins.

The POLx bits of the CWG1CON1 register control the signal polarity only when STRx = 1.

The CWG auto-shutdown operation also applies in Steering modes as described in Section 30.10 "Auto-Shutdown". An auto-shutdown event will only affect pins that have STRx = 1.

#### 30.9.1 STEERING SYNCHRONIZATION

Changing the MODE bits allows for two modes of steering, synchronous and asynchronous.

When MODE = 000, the steering event is asynchronous and will happen at the end of the instruction that writes to STRx (that is, immediately). In this case, the output signal at the output pin may be an incomplete waveform. This can be useful for immediately removing a signal from the pin.

When MODE = 001, the steering update is synchronous and occurs at the beginning of the next rising edge of the input data signal. In this case, steering the output on/off will always produce a complete waveform.

Figure 30-10 and Figure 30-11 illustrate the timing of asynchronous and synchronous steering, respectively.

FIGURE 30-10: EXAMPLE OF ASYNCHRONOUS STEERING EVENT (MODE<2:0> = 000)





FIGURE 30-11: EXAMPLE OF STEERING EVENT (MODE<2:0> = 001)



### 30.10 Auto-Shutdown

Auto-shutdown is a method to immediately override the CWG output levels with specific overrides that allow for safe shutdown of the circuit. The shutdown state can be either cleared automatically or held until cleared by software. The auto-shutdown circuit is illustrated in Figure 30-12.

#### 30.10.1 SHUTDOWN

The shutdown state can be entered by either of the following two methods:

- Software generated
- External Input

## 30.10.1.1 Software Generated Shutdown

Setting the SHUTDOWN bit of the CWG1AS0 register will force the CWG into the shutdown state.

When the auto-restart is disabled, the shutdown state will persist as long as the SHUTDOWN bit is set.

When auto-restart is enabled, the SHUTDOWN bit will clear automatically and resume operation on the next rising edge event.

#### 30.10.2 EXTERNAL INPUT SOURCE

External shutdown inputs provide the fastest way to safely suspend CWG operation in the event of a Fault condition. When any of the selected shutdown inputs goes active, the CWG outputs will immediately go to the selected override levels without software delay. Several input sources can be selected to cause a shutdown condition. All input sources are active-low. The sources are:

- Comparator C1OUT\_sync
- Comparator C2OUT sync
- Timer2 TMR2\_postscaled
- CWG1IN input pin

Shutdown inputs are selected using the CWG1AS1 register (Register 30-6).

Note:

Shutdown inputs are level sensitive, not edge sensitive. The shutdown state cannot be cleared, except by disabling auto-shutdown, as long as the shutdown input level persists.


## 30.11 Operation During Sleep

The CWG module operates independently from the system clock and will continue to run during Sleep, provided that the clock and input sources selected remain active.

The HFINTOSC remains active during Sleep when all the following conditions are met:

- · CWG module is enabled
- · Input source is active
- HFINTOSC is selected as the clock source, regardless of the system clock source selected.

In other words, if the HFINTOSC is simultaneously selected as the system clock and the CWG clock source, when the CWG is enabled and the input source is active, then the CPU will go Idle during Sleep, but the HFINTOSC will remain active and the CWG will continue to operate. This will have a direct effect on the Sleep mode current.



## 30.12 Configuring the CWG

The following steps illustrate how to properly configure the CWG.

- Ensure that the TRIS control bits corresponding to the desired CWG pins for the application are set so that the pins are configured as inputs.
- 2. Clear the EN bit, if not already cleared.
- Set desired mode of operation with the MODE bits.
- Set desired dead-band times, if applicable to mode, with the CWG1DBR and CWG1DBF registers.
- Setup the following controls in the CWG1AS0 and CWG1AS1 registers.
  - a. Select the desired shutdown source.
  - Select both output overrides to the desired levels (this is necessary even if not using autoshutdown because start-up will be from a shutdown state).
  - Set which pins will be affected by auto-shutdown with the CWG1AS1 register.
  - d. Set the SHUTDOWN bit and clear the REN bit.
- Select the desired input source using the CWG1DAT register.
- Configure the following controls.
  - Select desired clock source using the CWG1CLKCON register.
  - Select the desired output polarities using the CWG1CON1 register.
  - c. Set the output enables for the desired outputs.
- 8. Set the EN bit.
- Clear TRIS control bits corresponding to the desired output pins to configure these pins as outputs.
- If auto-restart is to be used, set the REN bit and the SHUTDOWN bit will be cleared automatically. Otherwise, clear the SHUTDOWN bit to start the CWG.

#### 30.12.1 PIN OVERRIDE LEVELS

The levels driven to the output pins, while the shutdown input is true, are controlled by the LSBD and LSAC bits of the CWG1AS0 register. LSBD<1:0> controls the CWG1B and D override levels and LSAC<1:0> controls the CWG1A and C override levels. The control bit logic level corresponds to the output logic drive level while in the shutdown state. The polarity control does not affect the override level.

#### 30.12.2 AUTO-SHUTDOWN RESTART

After an auto-shutdown event has occurred, there are two ways to resume operation:

- Software controlled
- Auto-restart

The restart method is selected with the REN bit of the CWG1CON2 register. Waveforms of software controlled and automatic restarts are shown in Figure 30-13 and Figure 30-14.


#### 30.12.2.1 Software Controlled Restart


When the REN bit of the CWG1AS0 register is cleared, the CWG must be restarted after an auto-shutdown event by software. Clearing the shutdown state requires all selected shutdown inputs to be low, otherwise the SHUTDOWN bit will remain set. The overrides will remain in effect until the first rising edge event after the SHUTDOWN bit is cleared. The CWG will then resume operation.

#### 30.12.2.2 Auto-Restart

When the REN bit of the CWG1CON2 register is set, the CWG will restart from the auto-shutdown state automatically. The SHUTDOWN bit will clear automatically when all shutdown sources go low. The overrides will remain in effect until the first rising edge event after the SHUTDOWN bit is cleared. The CWG will then resume operation.







## 30.13 Register Definitions: CWG Control

Long bit name prefixes for the CWG peripherals are shown in Section 1.1 "Register and Bit Naming Conventions".

## REGISTER 30-1: CWG1CON0: CWG1 CONTROL REGISTER 0

R/W-0/0	R/W/HC-0/0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0
EN	LD <sup>(1)</sup>	-	-	<del></del>		MODE<2:0>	
bit 7							bit 0

Legend:		
HC = Bit is cleared by ha	rdware	HS = Bit is set by hardware
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7	EN: CWG1 Enable bit
	1 = Module is enabled
	0 = Module is disabled
bit 6	LD: CWG1 Load Buffer bits <sup>(1)</sup>
	<ul><li>1 = Buffers to be loaded on the next rising/falling event</li><li>0 = Buffers not loaded</li></ul>
bit 5-3	Unimplemented: Read as '0'
bit 2-0	MODE<2:0>: CWG1 Mode bits 111 = Reserved
	110 = Reserved 101 = CWG outputs operate in Push-Pull mode
	100 = CWG outputs operate in Half-Bridge mode
	011 = CWG outputs operate in Reverse Full-Bridge mode
	010 = CWG outputs operate in Forward Full-Bridge mode
	001 = CWG outputs operate in Synchronous Steering mode
	000 = CWG outputs operate in Steering mode

Note 1: This bit can only be set after EN = 1 and cannot be set in the same instruction that EN is set.

## REGISTER 30-2: CWG1CON1: CWG1 CONTROL REGISTER 1

U-0	U-0	R-x	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
<del></del> .	:	IN	:	POLD	POLC	POLB	POLA
bit 7 bit 0							

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7-6	Unimplemented: Read as '0'
bit 5	IN: CWG Input Value bit
bit 4	Unimplemented: Read as '0'
bit 3	POLD: CWG1D Output Polarity bit
	<ul><li>1 = Signal output is inverted polarity</li><li>0 = Signal output is normal polarity</li></ul>
bit 2	POLC: CWG1C Output Polarity bit
	<ul><li>1 = Signal output is inverted polarity</li><li>0 = Signal output is normal polarity</li></ul>
bit 1	POLB: CWG1B Output Polarity bit
	<ul><li>1 = Signal output is inverted polarity</li><li>0 = Signal output is normal polarity</li></ul>
bit 0	POLA: CWG1A Output Polarity bit
	<ul><li>1 = Signal output is inverted polarity</li><li>0 = Signal output is normal polarity</li></ul>

## REGISTER 30-3: CWG1DBR: CWG1 RISING DEAD-BAND COUNTER REGISTER

U-0	U-0	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
<u></u>		DBR<5:0>					
bit 7							bit 0

Legend:

'1' = Bit is set

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared q = Value depends on condition

bit 7-6 Unimplemented: Read as '0'

bit 5-0 DBR<5:0>: Rising Event Dead-Band Value for Counter bits

## REGISTER 30-4: CWG1DBF: CWG1 FALLING DEAD-BAND COUNTER REGISTER

U-0	U-0	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
-	_			DBF	<5:0>		
bit 7	20	- A					bit 0

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets

q = Value depends on condition

bit 7-6 Unimplemented: Read as '0'

bit 5-0 DBF<5:0>: Falling Event Dead-Band Value for Counter bits

'0' = Bit is cleared

#### REGISTER 30-5: CWG1AS0: CWG1 AUTO-SHUTDOWN CONTROL REGISTER 0

R/W/HS-0/0	R/W-0/0	R/W-0/0	R/W-1/1	R/W-0/0	R/W-1/1	U-0	U-0
SHUTDOWN <sup>(1, 2)</sup>	REN	LSBD<1:0>		LSAC<1:0>		<u></u>	
bit 7					,	-	bit 0

Legend:

HC = Bit is cleared by hardware

R = Readable bit

U = Unimplemented bit, read as '0'

u = Bit is unchanged

x = Bit is unknown

'1' = Bit is set

'0' = Bit is cleared

y = Value depends on condition

bit 7 SHUTDOWN: Auto-Shutdown Event Status bit (1, 2)

1 = An Auto-Shutdown state is in effect0 = No Auto-shutdown event has occurred

bit 6 REN: Auto-Restart Enable bit

1 = Auto-restart enabled 0 = Auto-restart disabled

bit 5-4 LSBD<1:0>: CWG1B and CWG1D Auto-Shutdown State Control bits

11 =A logic '1' is placed on CWG1B/D when an auto-shutdown event is present 10 =A logic '0' is placed on CWG1B/D when an auto-shutdown event is present 01 =Pin is tri-stated on CWG1B/D when an auto-shutdown event is present

00 =The inactive state of the pin, including polarity, is placed on CWG1B/D after the required deadband interval

bit 3-2 LSAC<1:0>: CWG1A and CWG1C Auto-Shutdown State Control bits

11 =A logic '1' is placed on CWG1A/C when an auto-shutdown event is present 10 =A logic '0' is placed on CWG1A/C when an auto-shutdown event is present 01 =Pin is tri-stated on CWG1A/C when an auto-shutdown event is present

00 =The inactive state of the pin, including polarity, is placed on CWG1A/C after the required deadband interval

bit 1-0 Unimplemented: Read as '0'

Note 1: This bit may be written while EN = 0 (CWG1CON0 register) to place the outputs into the shutdown configuration.

The outputs will remain in auto-shutdown state until the next rising edge of the input signal after this bit is cleared.

## REGISTER 30-6: CWG1AS1: CWG1 AUTO-SHUTDOWN CONTROL REGISTER 1

U-1	U-1	U-1	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
<del></del> -		-	AS4E	AS3E	AS2E	AS1E	AS0E
bit 7 bit 0							

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7-5	Unimplemented: Read as '0'
bit 4	AS4E: CLC2 Output bit
	<ul><li>1 = LC2_out shut-down is enabled</li><li>0 = LC2_out shut-down is disabled</li></ul>
bit 3	AS3E: Comparator C2 Output bit
	<ul><li>1 = C2 output shut-down is enabled</li><li>0 = C2 output shut-down is disabled</li></ul>
bit 2	AS2E: Comparator C1 Output bit
	<ul><li>1 = C1 output shut-down is enabled</li><li>0 = C1 output shut-down is disabled</li></ul>
bit 2	AS1E: TMR2 Postscale Output bit
	<ul><li>1 = TMR2 Postscale shut-down is enabled</li><li>0 = TMR2 Postscale shut-down is disabled</li></ul>
bit 0	AS0E: CWG1 Input Pin bit
	<ul><li>1 = Input pin selected by CWG1PPS shut-down is enabled</li><li>0 = Input pin selected by CWG1PPS shut-down is disabled</li></ul>

## REGISTER 30-7: CWG1STR: CWG1 STEERING CONTROL REGISTER<sup>(1)</sup>

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
OVRD	OVRC	OVRB	OVRA	STRD <sup>(2)</sup>	STRC <sup>(2)</sup>	STRB <sup>(2)</sup>	STRA <sup>(2)</sup>
bit 7						bit 0	

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	q = Value depends on condition

bit 7	OVRD: Steering Data D bit
bit 6	OVRC: Steering Data C bit
bit 5	OVRB: Steering Data B bit
bit 4	OVRA: Steering Data A bit
bit 3	STRD: Steering Enable D bit <sup>(2)</sup>
	<ul><li>1 = CWG1D output has the CWG1_data waveform with polarity control from POLD bit</li><li>0 = CWG1D output is assigned the value of OVRD bit</li></ul>
bit 2	STRC: Steering Enable C bit <sup>(2)</sup>
	<ul><li>1 = CWG1C output has the CWG1_data waveform with polarity control from POLC bit</li><li>0 = CWG1C output is assigned the value of OVRC bit</li></ul>
bit 1	STRB: Steering Enable B bit <sup>(2)</sup>
	<ul><li>1 = CWG1B output has the CWG1_data waveform with polarity control from POLB bit</li><li>0 = CWG1B output is assigned the value of OVRB bit</li></ul>
bit 0	STRA: Steering Enable A bit <sup>(2)</sup>
	<ul><li>1 = CWG1A output has the CWG1_data waveform with polarity control from POLA bit</li><li>0 = CWG1A output is assigned the value of OVRA bit</li></ul>

Note 1: The bits in this register apply only when MODE<2:0> = 00x.

2: This bit is effectively double-buffered when MODE<2:0> = 001.

#### REGISTER 30-8: CWG1CLK: CWG1 CLOCK SELECTION REGISTER

U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-0/0
<del></del> -			0 <del></del> )		<del></del>	_	CS
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared q = Value depends on condition

bit 7-1 Unimplemented: Read as '0'

bit 0 CS: CWG1 Clock Selection bit

1 = HFINTOSC 16 MHz is selected

0 = Fosc is selected

#### REGISTER 30-9: CWG1DAT: CWG1 INPUT SELECTION REGISTER

U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
<del></del>	5 <del></del> 2	19. <del></del>	2:21		DAT	<3:0>	
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared q = Value depends on condition

bit 7-4 Unimplemented: Read as '0'

bit 3-0 DAT<3:0>: CWG1 Input Selection bits

1111 =Reserved. No channel connected.

1111 -Reserved. No charmer connected

1110 =Reserved. No channel connected.

1101 =LC4\_out

1100 =LC3\_out

1011 =LC2\_out

1010 =LC1\_out

1001 =Comparator C2 out

1000 =Comparator C1 out

0111 =NCO1 output

0110 =PWM6 out

0101 =PWM5\_out

0100 - 5100

0100 =PWM4\_out

0011 =PWM3\_out

0010 =CCP2\_out

0001 =CCP1\_out 0000 =CWG11CLK

TABLE 30-3: SUMMARY OF REGISTERS ASSOCIATED WITH CWG

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
CWG1CLKCON	_	_	_	_		-	N-4	CS	353
CWG1DAT	* 2 <u>4</u> 31	-	_	_		DAT	<3:0>		353
CWG1DBR	<u>-</u>	_			DBF	< <u>5:0</u> >			349
CWG1DBF	_	_			DBF	<5:0>			349
CWG1CON0	EN	LD	-	-	-		MODE<2:0>		352
CWG1CON1	_	_	IN	_	POLD	POLC	POLB	POLA	348
CWG1AS0	SHUTDOWN	REN	LSBD	<1:0>	LSAC	<1:0>	-	_	350
CWG1AS1	: <del></del> :	-	·—	AS4E	AS3E	AS2E	AS1E	AS0E	351
CWG1STR	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA	352

Legend: -= unimplemented locations read as '0'. Shaded cells are not used by CWG.

# 31.0 CONFIGURABLE LOGIC CELL (CLC)

The Configurable Logic Cell (CLCx) module provides programmable logic that operates outside the speed limitations of software execution. The logic cell selects from 40 input signals and, through the use of configurable gates, reduces the inputs to four logic lines that drive one of eight selectable single-output logic functions.

Input sources are a combination of the following:

- I/O pins
- · Internal clocks
- Peripherals
- Register bits

The output can be directed internally to peripherals and to an output pin.

The CLC modules available are shown in Table 31-1.

#### TABLE 31-1: AVAILABLE CLC MODULES

Device	CLC1	CLC2	CLC3	CLC4
PIC16(L)F15354/55	•	•	•	•


Note: The CLC1, CLC2, CLC3 and CLC4 are four separate module instances of the same CLC module design. Throughout this section, the lower case 'x' in register and bit names is a generic reference to the CLC number (which may be substituted with 1, 2, 3, or 4 during code development). For example, the control register is generically described in this chapter as CLCxCON, but the actual device registers are CLC1CON, CLC2CON, CLC3CON and CLC4CON. Similarly, the LCxEN bit represents the LC1EN, LC2EN, LC3EN and LC4EN bits.

Refer to Figure 31-1 for a simplified diagram showing signal flow through the CLCx.

Possible configurations include:

- Combinatorial Logic
  - AND
  - NAND
  - AND-OR
  - AND-OR-INVERT
  - OR-XOR
  - OR-XNOR
- Latches
  - S-R
  - Clocked D with Set and Reset
  - Transparent D with Set and Reset
  - Clocked J-K with Reset

FIGURE 31-1: CLCx SIMPLIFIED BLOCK DIAGRAM



## 31.1 CLCx Setup

Programming the CLCx module is performed by configuring the four stages in the logic signal flow. The four stages are:

- Data selection
- Data gating
- · Logic function selection
- · Output polarity

Each stage is setup at run time by writing to the corresponding CLCx Special Function Registers. This has the added advantage of permitting logic reconfiguration on-the-fly during program execution.

#### 31.1.1 DATA SELECTION

There are 40 signals available as inputs to the configurable logic. Four 40-input multiplexers are used to select the inputs to pass on to the next stage.

Data selection is through four multiplexers as indicated on the left side of Figure 31-2. Data inputs in the figure are identified by a generic numbered input name.

Table 31-2 correlates the generic input name to the actual signal for each CLC module. The column labeled 'LCxDyS<5:0> Value' indicates the MUX selection code for the selected data input. LCxDyS is an abbreviation to identify specific multiplexers: LCxD1S<5:0> through LCxD4S<5:0>.

Data inputs are selected with CLCxSEL0 through CLCxSEL3 registers (Register 31-3 through Register 31-6).

TABLE 31-2: CLCx DATA INPUT SELECTION

LCxDyS<5:0> Value	CLCx Input Source
101000 to 111111 [40+]	Reserved
100111 [39]	CWG1B output
100110 [38]	CWG1A output
100101 [37]	MSSP2 SCK output
100100 [36]	MSSP2 SDO output
100011 [35]	MSSP1 SCK output
100010 [34]	MSSP1 SDO output
100001 [33]	EUSART2 (TX/CK) output
100000 [32]	EUSART2 (DT) output
011111 [31]	EUSART1 (TX/CK) output
011110 [30]	EUSART1 (DT) output
011101 [29]	CLC4 output
011100 [28]	CLC3 output
011011 [27]	CLC2 output
011010 [26]	CLC1 output
011001 [25]	IOCIF
011000 [24]	ZCD output
010111 [23]	C2OUT
010110 [22]	C1OUT
010101 [21]	NCO1 output
010100 [20]	PWM6 output
010011 [19]	PWM5 output
010010 [18]	PWM4 output
010001 [17]	PWM3 output
010000 [16]	CCP2 output
001111 [15]	CCP1 output
001110 [14]	Timer2 overflow
001101 [13]	Timer1 overflow
001100 [12]	Timer0 overflow
001011 [11]	CLKR
001010 [10]	FRC
001001 [9]	SOSC
001000 [8]	MFINTOSC (32 kHz)
000111 [7]	MFINTOSC (500 kHz)
000110 [6]	LFINTOSC
000101 [5]	HFINTOSC
000100 [4]	Fosc
000011 [3]	CLCIN3PPS
000010 [2]	CLCIN2PPS
000001 [1]	CLCIN1PPS
000000 [0]	CLCIN0PPS

#### 31.1.2 DATA GATING

Outputs from the input multiplexers are directed to the desired logic function input through the data gating stage. Each data gate can direct any combination of the four selected inputs.

Note: Data gating is undefined at power-up.

The gate stage is more than just signal direction. The gate can be configured to direct each input signal as inverted or noninverted data. The output of each gate can be inverted before going on to the logic function stage.

The gating is in essence a 1-to-4 input AND/NAND/OR/NOR gate. When every input is inverted and the output is inverted, the gate is an OR of all enabled data inputs. When the inputs and output are not inverted, the gate is an AND or all enabled inputs.

Table 31-3 summarizes the basic logic that can be obtained in gate 1 by using the gate logic select bits. The table shows the logic of four input variables, but each gate can be configured to use less than four. If no inputs are selected, the output will be zero or one, depending on the gate output polarity bit.

TABLE 31-3: DATA GATING LOGIC

CLCxGLSy	LCxGyPOL	Gate Logic
0x55	1	4-input AND
0x55	0	4-input NAND
0xAA	1	4-input NOR
0xAA	0	4-input OR
0x00	0	Logic 0
0x00	1	Logic 1

It is possible (but not recommended) to select both the true and negated values of an input. When this is done, the gate output is zero, regardless of the other inputs, but may emit logic glitches (transient-induced pulses). If the output of the channel must be zero or one, the recommended method is to set all gate bits to zero and use the gate polarity bit to set the desired level.

Data gating is configured with the logic gate select registers as follows:

- Gate 1: CLCxGLS0 (Register 31-7)
- Gate 2: CLCxGLS1 (Register 31-8)
- Gate 3: CLCxGLS2 (Register 31-9)
- Gate 4: CLCxGLS3 (Register 31-10)

Register number suffixes are different than the gate numbers because other variations of this module have multiple gate selections in the same register.

Data gating is indicated in the right side of Figure 31-2. Only one gate is shown in detail. The remaining three gates are configured identically with the exception that the data enables correspond to the enables for that gate.

#### 31.1.3 LOGIC FUNCTION

There are eight available logic functions including:

- AND-OR
- OR-XOR
- AND
- S-R Latch
- . D Flip-Flop with Set and Reset
- · D Flip-Flop with Reset
- · J-K Flip-Flop with Reset
- · Transparent Latch with Set and Reset

Logic functions are shown in Figure 31-2. Each logic function has four inputs and one output. The four inputs are the four data gate outputs of the previous stage. The output is fed to the inversion stage and from there to other peripherals, an output pin, and back to the CLCx itself.

#### 31.1.4 OUTPUT POLARITY

The last stage in the Configurable Logic Cell is the output polarity. Setting the LCxPOL bit of the CLCxPOL register inverts the output signal from the logic stage. Changing the polarity while the interrupts are enabled will cause an interrupt for the resulting output transition.

# 31.2 CLCx Interrupts

An interrupt will be generated upon a change in the output value of the CLCx when the appropriate interrupt enables are set. A rising edge detector and a falling edge detector are present in each CLC for this purpose.

The CLCxIF bit of the associated PIR5 register will be set when either edge detector is triggered and its associated enable bit is set. The LCxINTP enables rising edge interrupts and the LCxINTN bit enables falling edge interrupts. Both are located in the CLCxCON register.

To fully enable the interrupt, set the following bits:

- CLCxIE bit of the PIE5 register
- LCxINTP bit of the CLCxCON register (for a rising edge detection)
- LCxINTN bit of the CLCxCON register (for a falling edge detection)
- PEIE and GIE bits of the INTCON register

The CLCxIF bit of the PIR5 register, must be cleared in software as part of the interrupt service. If another edge is detected while this flag is being cleared, the flag will still be set at the end of the sequence.

## 31.3 Output Mirror Copies

Mirror copies of all LCxCON output bits are contained in the CLCxDATA register. Reading this register reads the outputs of all CLCs simultaneously. This prevents any reading skew introduced by testing or reading the LCxOUT bits in the individual CLCxCON registers.

# 31.4 Effects of a Reset

The CLCxCON register is cleared to zero as the result of a Reset. All other selection and gating values remain unchanged.

# 31.5 Operation During Sleep

The CLC module operates independently from the system clock and will continue to run during Sleep, provided that the input sources selected remain active.

The HFINTOSC remains active during Sleep when the CLC module is enabled and the HFINTOSC is selected as an input source, regardless of the system clock source selected.

In other words, if the HFINTOSC is simultaneously selected as the system clock and as a CLC input source, when the CLC is enabled, the CPU will go Idle during Sleep, but the CLC will continue to operate and the HFINTOSC will remain active.

This will have a direct effect on the Sleep mode current.

## 31.6 CLCx Setup Steps

Follow these steps when setting up the CLCx:

- · Disable CLCx by clearing the LCxEN bit.
- Select desired inputs using CLCxSEL0 through CLCxSEL3 registers (See Table 31-2).
- Clear any associated ANSEL bits.
- Enable the chosen inputs through the four gates using CLCxGLS0, CLCxGLS1, CLCxGLS2, and CLCxGLS3 registers.
- Select the gate output polarities with the LCxGyPOL bits of the CLCxPOL register.
- Select the desired logic function with the LCxMODE<2:0> bits of the CLCxCON register.
- Select the desired polarity of the logic output with the LCxPOL bit of the CLCxPOL register. (This step may be combined with the previous gate output polarity step).
- If driving a device pin, set the desired pin PPS control register and also clear the TRIS bit corresponding to that output.
- If interrupts are desired, configure the following hits:
  - Set the LCxINTP bit in the CLCxCON register for rising event.
  - Set the LCxINTN bit in the CLCxCON register for falling event.
  - Set the CLCxIE bit of the PIE5 register.
  - Set the GIE and PEIE bits of the INTCON register.
- Enable the CLCx by setting the LCxEN bit of the CLCxCON register.





FIGURE 31-3: PROGRAMMABLE LOGIC FUNCTIONS



# 31.7 Register Definitions: CLC Control

# REGISTER 31-1: CLCxCON: CONFIGURABLE LOGIC CELL CONTROL REGISTER

R/W-0/0	U-0	R-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
LCxEN	:	LCxOUT	LCxINTP	LCxINTN	L	CxMODE<2:0>	>
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	LCxEN: Configurable Logic Cell Enable bit
	<ul><li>1 = Configurable logic cell is enabled and mixing input signals</li><li>0 = Configurable logic cell is disabled and has logic zero output</li></ul>
bit 6	Unimplemented: Read as '0'
bit 5	LCxOUT: Configurable Logic Cell Data Output bit
	Read-only: logic cell output data, after LCPOL; sampled from CLCxOUT
bit 4	LCxINTP: Configurable Logic Cell Positive Edge Going Interrupt Enable bit
	<ul><li>1 = CLCxIF will be set when a rising edge occurs on CLCxOUT</li><li>0 = CLCxIF will not be set</li></ul>
bit 3	LCxINTN: Configurable Logic Cell Negative Edge Going Interrupt Enable bit
	<ul><li>1 = CLCxIF will be set when a falling edge occurs on CLCxOUT</li><li>0 = CLCxIF will not be set</li></ul>
bit 2-0	LCxMODE<2:0>: Configurable Logic Cell Functional Mode bits
	111 =Cell is 1-input transparent latch with S and R
	110 =Cell is J-K flip-flop with R
	101 =Cell is 2-input D flip-flop with R
	100 =Cell is 1-input D flip-flop with S and R
	011 =Cell is S-R latch
	010 =Cell is 4-input AND
	001 =Cell is OR-XOR
	000 =Cell is AND-OR

# REGISTER 31-2: CLCxPOL: SIGNAL POLARITY CONTROL REGISTER

R/W-0/0	U-0	U-0	U-0	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
LCxPOL	—	=	_	LCxG4POL	LCxG3POL	LCxG2POL	LCxG1POL
bit 7		_					bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	LCxPOL: CLCxOUT Output Polarity Control bit
	1 = The output of the logic cell is inverted
	0 = The output of the logic cell is not inverted
bit 6-4	Unimplemented: Read as '0'
bit 3	LCxG4POL: Gate 3 Output Polarity Control bit
	<ul><li>1 = The output of gate 3 is inverted when applied to the logic cell</li><li>0 = The output of gate 3 is not inverted</li></ul>
bit 2	LCxG3POL: Gate 2 Output Polarity Control bit
	<ul><li>1 = The output of gate 2 is inverted when applied to the logic cell</li><li>0 = The output of gate 2 is not inverted</li></ul>
bit 1	LCxG2POL: Gate 1 Output Polarity Control bit
	<ul><li>1 = The output of gate 1 is inverted when applied to the logic cell</li><li>0 = The output of gate 1 is not inverted</li></ul>
bit 0	LCxG1POL: Gate 0 Output Polarity Control bit
	<ul><li>1 = The output of gate 0 is inverted when applied to the logic cell</li><li>0 = The output of gate 0 is not inverted</li></ul>

### REGISTER 31-3: CLCxSEL0: GENERIC CLCx DATA 0 SELECT REGISTER

U-0	U-0	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
<del>-</del>	-			LCxD:	1S<5:0>		
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-6 Unimplemented: Read as '0'

bit 5-0 LCxD1S<5:0>: CLCx Data1 Input Selection bits

See Table 31-2.

#### REGISTER 31-4: CLCxSEL1: GENERIC CLCx DATA 1 SELECT REGISTER

U-0	U-0	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
<del>-</del>	<del></del>			LCxD:	2S<5:0>		
bit 7		131					bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-6 Unimplemented: Read as '0'

bit 5-0 LCxD2S<5:0>: CLCx Data 2 Input Selection bits

See Table 31-2.

### REGISTER 31-5: CLCxSEL2: GENERIC CLCx DATA 2 SELECT REGISTER

U-0	U-0	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
_				LCxD	3S<5:0>		
bit 7	*	Č.					bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-6 Unimplemented: Read as '0'

bit 5-0 LCxD3S<5:0>: CLCx Data 3 Input Selection bits

See Table 31-2.

#### REGISTER 31-6: CLCxSEL3: GENERIC CLCx DATA 3 SELECT REGISTER

U-0	U-0	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u	R/W-x/u
_	_			LCxD	4S<5:0>		
bit 7				_	_		bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-6 Unimplemented: Read as '0'

bit 5-0 LCxD4S<5:0>: CLCx Data 4 Input Selection bits

See Table 31-2.

# REGISTER 31-7: CLCxGLS0: GATE 0 LOGIC SELECT REGISTER

| R/W-x/u  |
|----------|----------|----------|----------|----------|----------|----------|----------|
| LCxG1D4T | LCxG1D4N | LCxG1D3T | LCxG1D3N | LCxG1D2T | LCxG1D2N | LCxG1D1T | LCxG1D1N |
| bit 7    |          | _        |          |          |          |          | bit 0    |

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	LCxG1D4T: Gate 0 Data 4 True (noninverted) bit
	1 = CLCIN3 (true) is gated into CLCx Gate 0
	0 = CLCIN3 (true) is not gated into CLCx Gate 0
bit 6	LCxG1D4N: Gate 0 Data 4 Negated (inverted) bit
	1 = CLCIN3 (inverted) is gated into CLCx Gate 0
	0 = CLCIN3 (inverted) is not gated into CLCx Gate 0
bit 5	LCxG1D3T: Gate 0 Data 3 True (noninverted) bit
	1 = CLCIN2 (true) is gated into CLCx Gate 0
	0 = CLCIN2 (true) is not gated into CLCx Gate 0
bit 4	LCxG1D3N: Gate 0 Data 3 Negated (inverted) bit
	1 = CLCIN2 (inverted) is gated into CLCx Gate 0
	0 = CLCIN2 (inverted) is not gated into CLCx Gate 0
bit 3	LCxG1D2T: Gate 0 Data 2 True (noninverted) bit
	1 = CLCIN1 (true) is gated into CLCx Gate 0
	0 = CLCIN1 (true) is not gated into I CLCx Gate 0
bit 2	LCxG1D2N: Gate 0 Data 2 Negated (inverted) bit
	1 = CLCIN1 (inverted) is gated into CLCx Gate 0
	0 = CLCIN1 (inverted) is not gated into CLCx Gate 0
bit 1	LCxG1D1T: Gate 0 Data 1 True (noninverted) bit
	1 = CLCIN0 (true) is gated into CLCx Gate 0
	0 = CLCIN0 (true) is not gated into CLCx Gate 0
bit 0	LCxG1D1N: Gate 0 Data 1 Negated (inverted) bit
	1 = CLCIN0 (inverted) is gated into CLCx Gate 0
	0 = CLCIN0 (inverted) is not gated into CLCx Gate 0

# REGISTER 31-8: CLCxGLS1: GATE 1 LOGIC SELECT REGISTER

| R/W-x/u  |
|----------|----------|----------|----------|----------|----------|----------|----------|
| LCxG2D4T | LCxG2D4N | LCxG2D3T | LCxG2D3N | LCxG2D2T | LCxG2D2N | LCxG2D1T | LCxG2D1N |
| bit 7    |          |          |          |          |          |          | bit 0    |

Legend:		===
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	LCxG2D4T: Gate 1 Data 4 True (noninverted) bit
	1 = CLCIN3 (true) is gated into CLCx Gate 1
	0 = CLCIN3 (true) is not gated into CLCx Gate 1
bit 6	LCxG2D4N: Gate 1 Data 4 Negated (inverted) bit
	1 = CLCIN3 (inverted) is gated into CLCx Gate 1
	0 = CLCIN3 (inverted) is not gated into CLCx Gate 1
bit 5	LCxG2D3T: Gate 1 Data 3 True (noninverted) bit
	1 = CLCIN2 (true) is gated into CLCx Gate 1
	0 = CLCIN2 (true) is not gated into CLCx Gate 1
bit 4	LCxG2D3N: Gate 1 Data 3 Negated (inverted) bit
	1 = CLCIN2 (inverted) is gated into CLCx Gate 1
	0 = CLCIN2 (inverted) is not gated into CLCx Gate 1
bit 3	LCxG2D2T: Gate 1 Data 2 True (noninverted) bit
	1 = CLCIN1 (true) is gated into CLCx Gate 1
	0 = CLCIN1 (true) is not gated into CLCx Gate 1
bit 2	LCxG2D2N: Gate 1 Data 2 Negated (inverted) bit
	1 = CLCIN1 (inverted) is gated into CLCx Gate 1
	0 = CLCIN1 (inverted) is not gated into CLCx Gate 1
bit 1	LCxG2D1T: Gate 1 Data 1 True (noninverted) bit
	1 = CLCIN0 (true) is gated into CLCx Gate 1
	0 = CLCIN0 (true) is not gated into CLCx Gate1
bit 0	LCxG2D1N: Gate 1 Data 1 Negated (inverted) bit
	1 = CLCIN0 (inverted) is gated into CLCx Gate 1
	0 = CLCIN0 (inverted) is not gated into CLCx Gate 1

# REGISTER 31-9: CLCxGLS2: GATE 2 LOGIC SELECT REGISTER

| R/W-x/u  |
|----------|----------|----------|----------|----------|----------|----------|----------|
| LCxG3D4T | LCxG3D4N | LCxG3D3T | LCxG3D3N | LCxG3D2T | LCxG3D2N | LCxG3D1T | LCxG3D1N |
| bit 7    |          |          |          |          |          |          | bit 0    |

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	LCxG3D4T: Gate 2 Data 4 True (noninverted) bit
	1 = CLCIN3 (true) is gated into CLCx Gate 2
	0 = CLCIN3 (true) is not gated into CLCx Gate 2
bit 6	LCxG3D4N: Gate 2 Data 4 Negated (inverted) bit
	1 = CLCIN3 (inverted) is gated into CLCx Gate 2
	0 = CLCIN3 (inverted) is not gated into CLCx Gate 2
bit 5	LCxG3D3T: Gate 2 Data 3 True (noninverted) bit
	1 = CLCIN2 (true) is gated into CLCx Gate 2
	0 = CLCIN2 (true) is not gated into CLCx Gate 2
bit 4	LCxG3D3N: Gate 2 Data 3 Negated (inverted) bit
	1 = CLCIN2 (inverted) is gated into CLCx Gate 2
	0 = CLCIN2 (inverted) is not gated into CLCx Gate 2
bit 3	LCxG3D2T: Gate 2 Data 2 True (noninverted) bit
	1 = CLCIN1 (true) is gated into CLCx Gate 2
	0 = CLCIN1 (true) is not gated into CLCx Gate 2
bit 2	LCxG3D2N: Gate 2 Data 2 Negated (inverted) bit
	1 = CLCIN1 (inverted) is gated into CLCx Gate 2
	0 = CLCIN1 (inverted) is not gated into CLCx Gate 2
bit 1	LCxG3D1T: Gate 2 Data 1 True (noninverted) bit
	1 = CLCIN0 (true) is gated into CLCx Gate 2
	0 = CLCIN0 (true) is not gated into CLCx Gate 2
bit 0	LCxG3D1N: Gate 2 Data 1 Negated (inverted) bit
	1 = CLCIN0 (inverted) is gated into CLCx Gate 2
	0 = CLCIN0 (inverted) is not gated into CLCx Gate 2

# REGISTER 31-10: CLCxGLS3: GATE 3 LOGIC SELECT REGISTER

| R/W-x/u  |
|----------|----------|----------|----------|----------|----------|----------|----------|
| LCxG4D4T | LCxG4D4N | LCxG4D3T | LCxG4D3N | LCxG4D2T | LCxG4D2N | LCxG4D1T | LCxG4D1N |
| bit 7    |          |          |          |          |          |          | bit 0    |

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	LCxG4D4T: Gate 3 Data 4 True (noninverted) bit
	1 = CLCIN3 (true) is gated into CLCx Gate 3
	0 = CLCIN3 (true) is not gated into CLCx Gate 3
bit 6	LCxG4D4N: Gate 3 Data 4 Negated (inverted) bit
	1 = CLCIN3 (inverted) is gated into CLCx Gate 3
	0 = CLCIN3 (inverted) is not gated into CLCx Gate 3
bit 5	LCxG4D3T: Gate 3 Data 3 True (noninverted) bit
	1 = CLCIN2 (true) is gated into CLCx Gate 3
	0 = CLCIN2 (true) is not gated into CLCx Gate 3
bit 4	LCxG4D3N: Gate 3 Data 3 Negated (inverted) bit
	1 = CLCIN2 (inverted) is gated into CLCx Gate 3
	0 = CLCIN2 (inverted) is not gated into CLCx Gate 3
bit 3	LCxG4D2T: Gate 3 Data 2 True (noninverted) bit
	1 = CLCIN1 (true) is gated into CLCx Gate 3
	0 = CLCIN1 (true) is not gated into CLCx Gate 3
bit 2	LCxG4D2N: Gate 3 Data 2 Negated (inverted) bit
	1 = CLCIN1 (inverted) is gated into CLCx Gate 3
	0 = CLCIN1 (inverted) is not gated into CLCx Gate 3
bit 1	LCxG4D1T: Gate 4 Data 1 True (noninverted) bit
	1 = CLCIN0 (true) is gated into CLCx Gate 3
	0 = CLCIN0 (true) is not gated into CLCx Gate 3
bit 0	LCxG4D1N: Gate 3 Data 1 Negated (inverted) bit
	1 = CLCIN0 (inverted) is gated into CLCx Gate 3
	0 = CLCIN0 (inverted) is not gated into CLCx Gate 3

# REGISTER 31-11: CLCDATA: CLC DATA OUTPUT

U-0	U-0	U-0	U-0	R-0	R-0	R-0	R-0
-		=	_	MLC4OUT	MLC3OUT	MLC2OUT	MLC1OUT
bit 7			_				bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-4	Unimplemented: Read as '0'
bit 3	MLC4OUT: Mirror copy of LC4OUT bit
bit 2	MLC3OUT: Mirror copy of LC3OUT bit
bit 1	MLC2OUT: Mirror copy of LC2OUT bit
bit 0	MLC1OUT: Mirror copy of LC1OUT bit

TABLE 31-4: SUMMARY OF REGISTERS ASSOCIATED WITH CLCx

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
INTCON	GIE	PEIE	_	_	_	==	<u></u> :	INTEDG	121
PIR5	CLC4IF	CLC3IF	CLC2IF	CLC1IF	_	_	_	TMR1GIF	135
PIE5	CLC4IE	CLC4IE	CLC2IE	CLC1IE	_	-	_	TMR1GIE	127
CLC1CON	LC1EN	-	LC10UT	LC1INTP	LC1INTN	[9]	LC1MODE<2:0	>	362
CLC1POL	LC1POL	W <u></u>	=	=	LC1G4POL	LC1G3POL	LC1G2POL	LC1G1POL	363
CLC1SEL0	222	_			LC1D	1S<5:0>			364
CLC1SEL1		-			LC1D	2S<5:0>			364
CLC1SEL2	-	-			LC1D	3S<5:0>			364
CLC1SEL3	-	-		D.A	LC1D	4S<5:0>			364
CLC1GLS0	LC1G1D4T	LC1G1D4N	LC1G1D3T	LC1G1D3N	LC1G1D2T	LC1G1D2N	LC1G1D1T	LC1G1D1N	365
CLC1GLS1	LC1G2D4T	LC1G2D4N	LC1G2D3T	LC1G2D3N	LC1G2D2T	LC1G2D2N	LC1G2D1T	LC1G2D1N	366
CLC1GLS2	LC1G3D4T	LC1G3D4N	LC1G3D3T	LC1G3D3N	LC1G3D2T	LC1G3D2N	LC1G3D1T	LC1G3D1N	367
CLC1GLS3	LC1G4D4T	LC1G4D4N	LC1G4D3T	LC1G4D3N	LC1G4D2T	LC1G4D2N	LC1G4D1T	LC1G4D1N	368
CLC2CON	LC2EN	72 <u>—1</u> 2	LC2OUT	LC2INTP	LC2INTN	LC2MODE<2:0>			362
CLC2POL	LC2POL	-	_	_	LC2G4POL	LC2G3POL	LC2G2POL	LC2G1POL	363
CLC2SEL0	-	-		LC2D1S<5:0>					
CLC2SEL1	-	-			LC2D	2S<5:0>			364
CLC2SEL2	_	» <del>—</del>		LC2D3S<5:0>					
CLC2SEL3	-	_			LC2D	4S<5:0>			364
CLC2GLS0	LC2G1D4T	LC2G1D4N	LC2G1D3T	LC2G1D3N	LC2G1D2T	LC2G1D2N	LC2G1D1T	LC2G1D1N	365
CLC2GLS1	LC2G2D4T	LC2G2D4N	LC2G2D3T	LC2G2D3N	LC2G2D2T	LC2G2D2N	LC2G2D1T	LC2G2D1N	366
CLC2GLS2	LC2G3D4T	LC2G3D4N	LC2G3D3T	LC2G3D3N	LC2G3D2T	LC2G3D2N	LC2G3D1T	LC2G3D1N	367
CLC2GLS3	LC2G4D4T	LC2G4D4N	LC2G4D3T	LC2G4D3N	LC2G4D2T	LC2G4D2N	LC2G4D1T	LC2G4D1N	368
CLC3CON	LC3EN	-	LC3OUT	LC3INTP	LC3INTN		LC3MODE<2:0	>	362
CLC3POL	LC3POL	-	_	-	LC3G4POL	LC3G3POL	LC3G2POL	LC3G1POL	363
CLC3SEL0	-	-	LC3D1S<5:0>						364
CLC3SEL1	_	· —	LC3D2S<5:0>						364
CLC3SEL2	=	_	LC3D3S<5:0>					364	
CLC3SEL3	-	_	LC3D4S<5:0>					364	
CLC3GLS0	LC3G1D4T	LC3G1D4N	LC3G1D3T	LC3G1D3N	LC3G1D2T	LC3G1D2N	LC3G1D1T	LC3G1D1N	365
CLC3GLS1	LC3G2D4T	LC3G2D4N	LC3G2D3T	LC3G2D3N	LC3G2D2T	LC3G2D2N	LC3G2D1T	LC3G2D1N	366
CLC3GLS2	LC3G3D4T	LC3G3D4N	LC3G3D3T	LC3G3D3N	LC3G3D2T	LC3G3D2N	LC3G3D1T	LC3G3D1N	367
CLC3GLS3	LC3G4D4T	LC3G4D4N	LC3G4D3T	LC3G4D3N	LC3G4D2T	LC3G4D2N	LC3G4D1T	LC3G4D1N	368
CLC4CON	LC4EN	-	LC4OUT	LC4INTP	LC4INTN		LC4MODE<2:0	>	362
CLC4POL	LC4POL	·	1 <del>1</del>	_	LC4G4POL	LC4G3POL	LC4G2POL	LC4G1POL	363
CLC4SEL0	-	_			LC4D	1S<5:0>		*	364
CLC4SEL1		_			LC4D	2S<5:0>		33	364
CLC4SEL2	-	_	LC4D3S<5:0>					364	
CLC4SEL3	-	-	LC4D4S<5:0>					364	
CLC4GLS0	LC4G1D4T	LC4G1D4N	LC4G1D3T	LC4G1D3N	LC4G1D2T	LC4G1D2N	LC4G1D1T	LC4G1D1N	365

Legend: — = unimplemented, read as '0'. Shaded cells are unused by the CLCx modules.

TABLE 31-4: SUMMARY OF REGISTERS ASSOCIATED WITH CLCx (continued)

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	
CLC4GLS1	LC4G2D4T	LC4G2D4N	LC4G2D3T	LC4G2D3N	LC4G2D2T	LC4G2D2N	LC4G2D1T	LC4G2D1N	366
CLC4GLS2	LC4G3D4T	LC4G3D4N	LC4G3D3T	LC4G3D3N	LC4G3D2T	LC4G3D2N	LC4G3D1T	LC4G3D1N	367
CLC4GLS3	LC4G4D4T	LC4G4D4N	LC4G4D3T	LC4G4D3N	LC4G4D2T	LC4G4D2N	LC4G4D1T	LC4G4D1N	368
CLCIN0PPS		7 <u></u> -	CLCIN0PPS<5:0>				199		
CLCIN1PPS		_	CLCIN1PPS<5:0>					199	
CLCIN2PPS	-	-	CLCIN2PPS<5:0>				199		
CLCIN3PPS	_	-	CLCIN3PPS<5:0>				199		

Legend: — = unimplemented, read as '0'. Shaded cells are unused by the CLCx modules.

# 32.0 HOST SYNCHRONOUS SERIAL PORT (MSSPx) MODULES

## 32.1 MSSP Module Overview

The Host Synchronous Serial Port (MSSP) module is a serial interface useful for communicating with other peripheral or microcontroller devices. These peripheral devices may be serial EEPROMs, shift registers, display drivers, A/D converters, etc. The MSSP module can operate in one of two modes:


- · Serial Peripheral Interface (SPI)
- Inter-Integrated Circuit (I<sup>2</sup>C)

The SPI interface supports the following modes and features:

- Host mode
- Client mode
- Clock Parity
- Client Select Synchronization (Client mode only)
- · Daisy-chain connection of client devices

Figure 32-1 is a block diagram of the SPI interface module.

FIGURE 32-1: MSSP BLOCK DIAGRAM (SPI MODE)




The I<sup>2</sup>C interface supports the following modes and features:

- · Host mode
- Client mode
- · Byte NACKing (Client mode)
- · Limited multi-host support
- 7-bit and 10-bit addressing
- · Start and Stop interrupts
- Interrupt masking
- · Clock stretching
- · Bus collision detection
- · General call address matching
- Address masking
- · Selectable SDA hold times


Figure 32-2 is a block diagram of the I<sup>2</sup>C interface module in Host mode. Figure 32-3 is a diagram of the I<sup>2</sup>C interface module in Client mode.

- Note 1: In devices with more than one MSSP module, it is very important to pay close attention to SSPxCONx register names. SSPxCON1 and SSPxCON2 registers control different operational aspects of the same module, while SSP1CON1 and SSP2CON1 control the same features for two different modules.
  - 2: Throughout this section, generic references to an MSSPx module in any of its operating modes may be interpreted as being equally applicable to MSSP1 or MSSP2. Register names, module I/O signals, and bit names may use the generic designator 'x' to indicate the use of a numeral to distinguish a particular module when required.

FIGURE 32-2: MSSP BLOCK DIAGRAM (I<sup>2</sup>C HOST MODE)



# FIGURE 32-3: MSSP BLOCK DIAGRAM (I<sup>2</sup>C CLIENT MODE)



#### 32.2 SPI Mode Overview

The Serial Peripheral Interface (SPI) bus is a synchronous serial data communication bus that operates in Full-Duplex mode. Devices communicate in a host/client environment where the host device initiates the communication. A client device is controlled through a Chip Select known as Client Select.

The SPI bus specifies four signal connections:

- Serial Clock (SCK)
- Serial Data Out (SDO)
- Serial Data In (SDI)
- Client Select (SS)

Figure 32-1 shows the block diagram of the MSSP module when operating in SPI mode.

The SPI bus operates with a single host device and one or more client devices. When multiple client devices are used, an independent Client Select connection can be used to address each client individually.

Figure 32-4 shows a typical connection between a host device and multiple client devices.

The host selects only one client at a time. Most client devices have tri-state outputs so their output signal appears disconnected from the bus when they are not selected.

Transmissions involve two shift registers, eight bits in size, one in the host and one in the client. Data is always shifted out one bit at a time, with the Most Significant bit (MSb) shifted out first. At the same time, a new Least Significant bit (LSb) is shifted into the same register.

Figure 32-5 shows a typical connection between two processors configured as host and client devices.

Data is shifted out of both shift registers on the programmed clock edge and latched on the opposite edge of the clock.

The host device transmits information out on its SDO output pin which is connected to, and received by, the client's SDI input pin. The client device transmits information out on its SDO output pin, which is connected to, and received by, the host's SDI input pin.

To begin communication, the host device first sends out the clock signal. Both the host and the client devices may be configured for the same clock polarity.

The host device starts a transmission by sending out the MSb from its shift register. The client device reads this bit from that same line and saves it into the LSb position of its shift register. During each SPI clock cycle, a full-duplex data transmission occurs. This means that while the host device is sending out the MSb from its shift register (on its SDO pin) and the client device is reading this bit and saving it as the LSb of its shift register, that the client device is also sending out the MSb from its shift register (on its SDO pin) and the host device is reading this bit and saving it as the LSb of its shift register.

After eight bits have been shifted out, the host and client have exchanged register values.

If there is more data to exchange, the shift registers are loaded with new data and the process repeats itself.

Whether the data is meaningful or not (dummy data), depends on the application software. This leads to three scenarios for data transmission:

- Host sends useful data and client sends dummy data
- Host sends useful data and client sends useful data
- Host sends dummy data and client sends useful data

Transmissions must be performed in multiples of eight clock pulses. When there is no more data to be transmitted, the host stops sending the clock signal and it deselects the client.

Every client device connected to the bus that has not been selected through its client select line must disregard the clock and transmission signals and must not transmit out any data of its own.

SCK SCK SPI Host SDO SDI SPI Client SDI #1 SDO General I/O SS General I/O General I/O SCK SDI SPI Client #2 SDO SS SCK SDI SPI Client #3 SDO SS

FIGURE 32-4: SPI HOST AND MULTIPLE CLIENT CONNECTION

## 32.2.1 SPI MODE REGISTERS

The MSSP module has five registers for SPI mode operation. These are:

- MSSP STATUS register (SSPxSTAT)
- MSSP Control register 1 (SSPxCON1)
- MSSP Control register 3 (SSPxCON3)
- MSSP Data Buffer register (SSPxBUF)
- MSSP Address register (SSPxADD)
- MSSP Shift register (SSPxSR) (Not directly accessible)

SSPxCON1 and SSPxSTAT are the control and status registers in SPI mode operation. The SSPxCON1 register is readable and writable. The lower six bits of the SSPxSTAT are read-only. The upper two bits of the SSPxSTAT are read/write.

In one SPI Host mode, SSPxADD can be loaded with a value used in the Baud Rate Generator. More information on the Baud Rate Generator is available in Section 32.7 "Baud Rate Generator".

SSPxSR is the shift register used for shifting data in and out. SSPxBUF provides indirect access to the SSPxSR register. SSPxBUF is the buffer register to which data bytes are written, and from which data bytes are read.

In receive operations, SSPxSR and SSPxBUF together create a buffered receiver. When SSPxSR receives a complete byte, it is transferred to SSPxBUF and the SSPxIF interrupt is set.

During transmission, the SSPxBUF is not buffered. A write to SSPxBUF will write to both SSPxBUF and SSPxSR.

#### 32.2.2 SPI MODE OPERATION

When initializing the SPI, several options need to be specified. This is done by programming the appropriate control bits (SSPxCON1<3:0> and SSPxSTAT<7:6>). These control bits allow the following to be specified:

- Host mode (SCK is the clock output)
- · Client mode (SCK is the clock input)
- · Clock Polarity (Idle state of SCK)
- Data Input Sample Phase (middle or end of data output time)
- Clock Edge (output data on rising/falling edge of SCK)
- Clock Rate (Host mode only)
- · Client Select mode (Client mode only)

To enable the serial port, SSP Enable bit, SSPEN of the SSPxCON1 register, must be set. To reset or reconfigure SPI mode, clear the SSPEN bit, re-initialize the SSPxCONx registers and then set the SSPEN bit. This configures the SDI, SDO, SCK and SS pins as serial port pins. For the pins to behave as the serial port function, some must have their data direction bits (in the TRISx register) appropriately programmed as follows:

- SDI must have corresponding TRIS bit set
- · SDO must have corresponding TRIS bit cleared
- SCK (Host mode) must have corresponding TRIS bit cleared
- SCK (Client mode) must have corresponding TRIS bit set
- SS must have corresponding TRIS bit set


Any serial port function that is not desired may be overridden by programming the corresponding data direction (TRIS) register to the opposite value.

The MSSP consists of a transmit/receive shift register (SSPxSR) and a buffer register (SSPxBUF). The SSPxSR shifts the data in and out of the device, MSb first. The SSPxBUF holds the data that was written to the SSPxSR until the received data is ready. Once the eight bits of data have been received, that byte is moved to the SSPxBUF register. Then, the Buffer Full Detect bit, BF of the SSPxSTAT register, and the interrupt flag bit, SSPxIF, are set. Any write to the SSPxBUF register during transmission/reception of data will be ignored and the write collision detect bit WCOL of the SSPxCON1 register, will be set. User software must clear the WCOL bit to allow the following write(s) to the SSPxBUF register to complete successfully.

When the application software is expecting to receive valid data, the SSPxBUF must be read before the next byte of data to transfer is written to the SSPxBUF. The Buffer Full bit, BF of the SSPxSTAT register, indicates when SSPxBUF has been loaded with the received data (transmission is complete). When the SSPxBUF is read, the BF bit is cleared. This data may be irrelevant if the SPI is only a transmitter. Generally, the MSSP interrupt is used to determine when the transmission/reception has completed. If the interrupt method is not going to be used, then software polling can be done to ensure that a write collision does not occur.

The SSPxSR is not directly readable or writable and can only be accessed by addressing the SSPxBUF register.





#### 32.2.3 SPI HOST MODE

The host can initiate the data transfer at any time because it controls the SCK line. The host determines when the client (Processor 2, Figure 32-5) is to broadcast data by the software protocol.

In Host mode, the data is transmitted/received as soon as the SSPxBUF register is written to. If the SPI is only going to receive, the SDO output can be disabled (programmed as an input). The SSPxSR register will continue to shift in the signal present on the SDI pin at the programmed clock rate. As each byte is received, it will be loaded into the SSPxBUF register as if a normal received byte (interrupts and Status bits appropriately set).


The clock polarity is selected by appropriately programming the CKP bit of the SSPxCON1 register and the CKE bit of the SSPxSTAT register. Then, this will give waveforms for SPI communication as shown in Figure 32-6, Figure 32-8, Figure 32-9 and Figure 32-10, where the MSB is transmitted first. In Host mode, the SPI clock rate (bit rate) is user programmable to be one of the following:

- Fosc/4 (or Tcy)
- Fosc/16 (or 4 \* Tcy)
- Fosc/64 (or 16 \* Tcy)
- Timer2 output/2
- Fosc/(4 \* (SSPxADD + 1))

Figure 32-6 shows the waveforms for Host mode.

When the CKE bit is set, the SDO data is valid before there is a clock edge on SCK. The change of the input sample is shown based on the state of the SMP bit. The time when the SSPxBUF is loaded with the received data is shown.





#### 32.2.4 SPI CLIENT MODE

In Client mode, the data is transmitted and received as external clock pulses appear on SCK. When the last bit is latched, the SSPxIF interrupt flag bit is set.

Before enabling the module in SPI Client mode, the clock line must match the proper Idle state. The clock line can be observed by reading the SCK pin. The Idle state is determined by the CKP bit of the SSPxCON1 register.

While in Client mode, the external clock is supplied by the external clock source on the SCK pin. This external clock must meet the minimum high and low times as specified in the electrical specifications.

While in Sleep mode, the client can transmit/receive data. The shift register is clocked from the SCK pin input and when a byte is received, the device will generate an interrupt. If enabled, the device will wake-up from Sleep.

#### 32.2.4.1 Daisy-Chain Configuration

The SPI bus can sometimes be connected in a daisy-chain configuration. The first client output is connected to the second client input, the second client output is connected to the third client input, and so on. The final client output is connected to the host input. Each client sends out, during a second group of clock pulses, an exact copy of what was received during the first group of clock pulses. The whole chain acts as one large communication shift register. The daisy-chain feature only requires a single Client Select line from the host device.

Figure 32-7 shows the block diagram of a typical daisy-chain connection when operating in SPI mode.

In a daisy-chain configuration, only the most recent byte on the bus is required by the client. Setting the BOEN bit of the SSPxCON3 register will enable writes to the SSPxBUF register, even if the previous byte has not been read. This allows the software to ignore data that may not apply to it.

# 32.2.5 CLIENT SELECT SYNCHRONIZATION

The Client Select can also be used to synchronize communication. The Client Select line is held high until the host device is ready to communicate. When the Client Select line is pulled low, the client knows that a new transmission is starting.

If the client fails to receive the communication properly, it will be reset at the end of the transmission, when the Client Select line returns to a high state. The client is then ready to receive a new transmission when the Client Select line is pulled low again. If the Client Select line is not used, there is a risk that the client will eventually become out of sync with the host. If the client misses a bit, it will always be one bit off in future transmissions. Use of the Client Select line allows the client and host to align themselves at the beginning of each transmission.

The  $\overline{SS}$  pin allows a Synchronous Client mode. The SPI must be in Client mode with  $\overline{SS}$  pin control enabled (SSPxCON1<3:0> = 0100).


When the SS pin is low, transmission and reception are enabled and the SDO pin is driven.

When the SS pin goes high, the SDO pin is no longer driven, even if in the middle of a transmitted byte and becomes a floating output. External pull-up/pull-down resistors may be desirable depending on the application.


- Note 1: When the SPI is in Client mode with SS pin control enabled (SSPxCON1<3:0> = 0100), the SPI module will reset if the SS pin is set to VDD.
  - When the SPI is used in Client mode with CKE set; the user must enable SS pin control
  - While operated in SPI Client mode the SMP bit of the SSPxSTAT register must remain clear.

When the SPI module resets, the bit counter is forced to '0'. This can be done by either forcing the SS pin to a high level or clearing the SSPEN bit.


FIGURE 32-7: SPI DAISY-CHAIN CONNECTION




# FIGURE 32-8: CLIENT SELECT SYNCHRONOUS WAVEFORM







## FIGURE 32-10: SPI MODE WAVEFORM (CLIENT MODE WITH CKE = 1)



#### 32.2.6 SPI OPERATION IN SLEEP MODE

In SPI Host mode, module clocks may be operating at a different speed than when in Full Power mode; in the case of the Sleep mode, all clocks are halted.

In SPI Host mode, when the Sleep mode is selected, all module clocks are halted and the transmission/ reception will remain in that state until the device wakes. After the device returns to Run mode, the module will resume transmitting and receiving data.

In SPI Client mode, the SPI Transmit/Receive Shift register operates asynchronously to the device. This allows the device to be placed in Sleep mode and data to be shifted into the SPI Transmit/Receive Shift register. When all eight bits have been received, the MSSP interrupt flag bit will be set and if enabled, will wake the device.

## 32.3 I<sup>2</sup>C MODE OVERVIEW

The Inter-Integrated Circuit (I<sup>2</sup>C) bus is a multi-host serial data communication bus. Devices communicate in a host/client environment where the host devices initiate the communication. A client device is controlled through addressing.

The I<sup>2</sup>C bus specifies two signal connections:

- Serial Clock (SCL)
- · Serial Data (SDA)

Figure 32-11 shows the block diagram of the MSSP module when operating in I<sup>2</sup>C mode.

Both the SCL and SDA connections are bidirectional open-drain lines, each requiring pull-up resistors for the supply voltage. Pulling the line to ground is considered a logical zero and letting the line float is considered a logical one.

Figure 32-11 shows a typical connection between two processors configured as host and client devices.

The I<sup>2</sup>C bus can operate with one or more host devices and one or more client devices.

There are four potential modes of operation for a given device:


- Host Transmit mode (host is transmitting data to a client)
- Host Receive mode (host is receiving data from a client)
- Client Transmit mode (client is transmitting data to a host)
- Client Receive mode (client is receiving data from the host)

To begin communication, the host device sends out a Start condition followed by the address byte of the client it intends to communicate with.

This is followed by a single Read/Write bit, which determines whether the host intends to transmit to or receive data from the client device.

If the requested client exists on the bus, it will respond with an Acknowledge bit, otherwise known as an ACK. The host then continues to either transmit or receive data from the client device.

FIGURE 32-11: I<sup>2</sup>C HOST/ CLIENT CONNECTION



The line is held high to indicate Start and Stop bits.

On the last byte of data communicated, the host device may end the transmission by sending a Stop bit. If the host device is in Receive mode, it sends the Stop bit in place of the last  $\overline{ACK}$  bit. A Stop bit is indicated by a low-to-high transition of the SDA line while the SCL line is held high.

In some cases, the host may want to maintain control of the bus and re-initiate another transmission. If so, the host device may send a Restart condition in place of the Stop condition or last  $\overline{\mathsf{ACK}}$  bit when it is in Receive mode.

The I<sup>2</sup>C bus specifies three message protocols:

- Single message where a host writes data to a client.
- Single message where a host reads data from a client.
- Combined message where a host initiates a minimum of two writes, or two reads, or a combination of writes and reads, to one or more clients.

#### 32.3.1 CLOCK STRETCHING

When a client device has not completed processing data, it can delay the transfer of more data through the process of clock stretching. An addressed client device may hold the SCL clock line low after receiving or sending a bit, indicating that it is not yet ready to continue. The host that is communicating with the client will attempt to raise the SCL line in order to transfer the next bit, but will detect that the clock line has not yet been released. Because the SCL connection is opendrain, the client has the ability to hold that line low until it is ready to continue communicating.

Clock stretching allows receivers that cannot keep up with a transmitter to control the flow of incoming data.

#### 32.3.2 ARBITRATION

Each host device must monitor the bus for Start and Stop bits. If the device detects that the bus is busy, it cannot begin a new message until the bus returns to an Idle state.

However, two host devices may try to initiate a transmission on or about the same time. When this occurs, the process of arbitration begins. Each transmitter checks the level of the SDA data line and compares it to the level that it expects to find. The first transmitter to observe that the two levels do not match, loses arbitration, and must stop transmitting on the SDA line.

For example, if one transmitter holds the SDA line to a logical one (lets it float) and a second transmitter holds it to a logical zero (pulls it low), the result is that the SDA line will be low. The first transmitter then observes that the level of the line is different than expected and concludes that another transmitter is communicating.

The first transmitter to notice this difference is the one that loses arbitration and must stop driving the SDA line. If this transmitter is also a host device, it also must stop driving the SCL line. It then can monitor the lines for a Stop condition before trying to reissue its transmission. In the meantime, the other device that has not noticed any difference between the expected and actual levels on the SDA line continues with its original transmission.

Client Transmit mode can also be arbitrated, when a host addresses multiple clients, but this is less common.

### 32.4 I2C MODE OPERATION

All MSSP I<sup>2</sup>C communication is byte oriented and shifted out MSb first. Six SFR registers and two interrupt flags interface the module with the PIC<sup>®</sup> microcontroller and user software. Two pins, SDA and SCL, are exercised by the module to communicate with other external I<sup>2</sup>C devices.

#### 32.4.1 BYTE FORMAT

All communication in  $I^2C$  is done in 9-bit segments. A byte is sent from a host to a client or vice-versa, followed by an Acknowledge bit sent back. After the eighth falling edge of the SCL line, the device outputting data on the SDA changes that pin to an input and reads in an acknowledge value on the next clock pulse.

The clock signal, SCL, is provided by the host. Data is valid to change while the SCL signal is low, and sampled on the rising edge of the clock. Changes on the SDA line while the SCL line is high define special conditions on the bus, explained below.

## 32.4.2 DEFINITION OF I<sup>2</sup>C TERMINOLOGY

There is language and terminology in the description of  $I^2C$  communication that have definitions specific to  $I^2C$ . That word usage is defined below and may be used in the rest of this document without explanation. This table was adapted from the Philips  $I^2C$  specification.

## 32.4.3 SDA AND SCL PINS

Selection of any I<sup>2</sup>C mode with the SSPEN bit set, forces the SCL and SDA pins to be open-drain. These pins may be set by the user to inputs by setting the appropriate TRIS bits.

Note 1: Any device pin can be selected for SDA and SCL functions with the PPS peripheral. These functions are bidirectional. The SDA input is selected with the SSPDATPPS registers. The SCL input is selected with the SSPCLKPPS registers. Outputs are selected with the RxyPPS registers. It is the user's responsibility to make the selections so that both the input and the output for each function is on the same pin.

#### 32.4.4 SDA HOLD TIME

The hold time of the SDA pin is selected by the SDAHT bit of the SSPxCON3 register. Hold time is the time SDA is held valid after the falling edge of SCL. Setting the SDAHT bit selects a longer 300 ns minimum hold time and may help on buses with large capacitance.

TABLE 32-1: I<sup>2</sup>C BUS TERMS

TERM	Description			
Transmitter	The device which shifts data out onto the bus.			
Receiver	The device which shifts data in from the bus.			
Host	The device that initiates a transfer, generates clock signals and terminates a transfer.			
Client	The device addressed by the host.			
Multi-host	A bus with more than one device that can initiate data transfers.			
Arbitration	Procedure to ensure that only one host at a time controls the bus. Winning arbitration ensures that the message is not corrupted.			
Synchronization	Procedure to synchronize the clocks of two or more devices on the bus.			
Idle	No host is controlling the bus, and both SDA and SCL lines are high.			
Active	Any time one or more host devices are controlling the bus.			
Addressed Cli- ent	Client device that has received a matching address and is actively being clocked by a host.			
Matching Address	Address byte that is clocked into a client that matches the value stored in SSPxADD.			
Write Request	Client receives a matching address with R/W bit clear, and is ready to clock in data.			
Read Request	Host sends an address byte with the R/W bit set, indicating that it wishes to clock data out of the Client. This data is the next and all following bytes until a Restart or Stop.			
Clock Stretching	When a device on the bus hold SCL low to stall communication.			
Bus Collision	Any time the SDA line is sampled low by the module while it is outputting and expected high state.			

#### 32.4.5 START CONDITION

The I<sup>2</sup>C specification defines a Start condition as a transition of SDA from a high to a low state while SCL line is high. A Start condition is always generated by the host and signifies the transition of the bus from an Idle to an active state. Figure 32-12 shows wave forms for Start and Stop conditions.

#### 32.4.6 STOP CONDITION

A Stop condition is a transition of the SDA line from low-to-high state while the SCL line is high.

Note: At least one SCL low time must appear before a Stop is valid, therefore, if the SDA line goes low then high again while the SCL line stays high, only the Start condition is detected.

#### 32.4.7 RESTART CONDITION

A Restart is valid any time that a Stop is valid. A host can issue a Restart if it wishes to hold the bus after terminating the current transfer. A Restart has the same effect on the client that a Start would, resetting all client logic and preparing it to clock in an address. The host may want to address the same or another client. Figure 32-13 shows the wave form for a Restart condition

In 10-bit Addressing Client mode a Restart is required for the host to clock data out of the addressed client. Once a client has been fully addressed, matching both high and low address bytes, the host can issue a Restart and the high address byte with the R/W bit set. The client logic will then hold the clock and prepare to clock out data.

# 32.4.8 START/STOP CONDITION INTERRUPT MASKING

The SCIE and PCIE bits of the SSPxCON3 register can enable the generation of an interrupt in Client modes that do not typically support this function. Client modes where interrupt on Start and Stop detect are already enabled, these bits will have no effect.

FIGURE 32-12: I<sup>2</sup>C START AND STOP CONDITIONS





FIGURE 32-13: I<sup>2</sup>C RESTART CONDITION



#### 32.4.9 ACKNOWLEDGE SEQUENCE

The 9th SCL pulse for any transferred byte in  $I^2C$  is dedicated as an Acknowledge. It allows receiving devices to respond back to the transmitter by pulling the SDA line low. The transmitter must release control of the line during this time to shift in the response. The Acknowledge  $(\overline{ACK})$  is an active-low signal, pulling the SDA line low indicates to the transmitter that the device has received the transmitted data and is ready to receive more.

The result of an ACK is placed in the ACKSTAT bit of the SSPxCON2 register.

Client software, when the AHEN and DHEN bits are set, allow the user to set the ACK value sent back to the transmitter. The ACKDT bit of the SSPxCON2 register is set/cleared to determine the response.

There are certain conditions where an ACK will not be sent by the client. If the BF bit of the SSPxSTAT register or the SSPOV bit of the SSPxCON1 register are set when a byte is received.

When the module is addressed, after the eighth falling edge of SCL on the bus, the ACKTIM bit of the SSPxCON3 register is set. The ACKTIM bit indicates the acknowledge time of the active bus. The ACKTIM Status bit is only active when the AHEN bit or DHEN bit is enabled.

## 32.5 I<sup>2</sup>C CLIENT MODE OPERATION

The MSSP Client mode operates in one of four modes selected by the SSPM bits of SSPxCON1 register. The modes can be divided into 7-bit and 10-bit Addressing mode. 10-bit Addressing modes operate the same as 7-bit with some additional overhead for handling the larger addresses.

Modes with Start and Stop bit interrupts operate the same as the other modes with SSPxIF additionally getting set upon detection of a Start, Restart, or Stop condition.

#### 32.5.1 CLIENT MODE ADDRESSES

The SSPxADD register (Register 32-6) contains the Client mode address. The first byte received after a Start or Restart condition is compared against the value stored in this register. If the byte matches, the value is loaded into the SSPxBUF register and an interrupt is generated. If the value does not match, the module goes Idle and no indication is given to the software that anything happened.

The SSP Mask register (Register 32-5) affects the address matching process. See Section 32.5.9 "SSP Mask Register" for more information.

## 32.5.1.1 I<sup>2</sup>C Client 7-bit Addressing Mode

In 7-bit Addressing mode, the LSb of the received data byte is ignored when determining if there is an address match.

#### 32.5.1.2 I<sup>2</sup>C Client 10-bit Addressing Mode

In 10-bit Addressing mode, the first received byte is compared to the binary value of '1 1 1 1 0 A9 A8 0'. A9 and A8 are the two MSb's of the 10-bit address and stored in bits 2 and 1 of the SSPxADD register.

After the acknowledge of the high byte the UA bit is set and SCL is held low until the user updates SSPxADD with the low address. The low address byte is clocked in and all eight bits are compared to the low address value in SSPxADD. Even if there is not an address match; SSPxIF and UA are set, and SCL is held low until SSPxADD is updated to receive a high byte again. When SSPxADD is updated the UA bit is cleared. This ensures the module is ready to receive the high address byte on the next communication.

A high and low address match as a write request is required at the start of all 10-bit addressing communication. A transmission can be initiated by issuing a Restart once the client is addressed, and clocking in the high address with the  $R\overline{W}$  bit set. The client hardware will then acknowledge the read request and prepare to clock out data. This is only valid for a client after it has received a complete high and low address byte match.

#### 32.5.2 CLIENT RECEPTION

When the R/W bit of a matching received address byte is clear, the R/W bit of the SSPxSTAT register is cleared. The received address is loaded into the SSPxBUF register and acknowledged.

When the overflow condition exists for a received address, then not Acknowledge is given. An overflow condition is defined as either bit BF of the SSPxSTAT register is set, or bit SSPOV of the SSPxCON1 register is set. The BOEN bit of the SSPxCON3 register modifies this operation. For more information see Register 32-4.

An MSSP interrupt is generated for each transferred data byte. Flag bit, SSPxIF, must be cleared by software.

When the SEN bit of the SSPxCON2 register is set, SCL will be held low (clock stretch) following each received byte. The clock must be released by setting the CKP bit of the SSPxCON1 register.

### 32.5.2.1 7-bit Addressing Reception

This section describes a standard sequence of events for the MSSP module configured as an I<sup>2</sup>C client in 7-bit Addressing mode. Figure 32-14 and Figure 32-15 is used as a visual reference for this description.

This is a step by step process of what typically must be done to accomplish I<sup>2</sup>C communication.

- Start bit detected.
- The S bit of SSPxSTAT is set; SSPxIF is set if interrupt on Start detect is enabled.
- 3. Matching address with R/W bit clear is received.
- The client pulls SDA low sending an ACK to the host, and sets SSPxIF bit.
- Software clears the SSPxIF bit.
- Software reads received address from SSPxBUF clearing the BF flag.
- If SEN = 1; Client software sets CKP bit to release the SCL line.
- 8. The host clocks out a data byte.
- Client drives SDA low sending an ACK to the host, and sets SSPxIF bit.
- 10. Software clears SSPxIF.
- 11. Software reads the received byte from SSPxBUF clearing BF.
- Steps 8-12 are repeated for all received bytes from the host.
- Host sends Stop condition, setting the P bit of SSPxSTAT, and the bus goes Idle.

#### 32.5.2.2 7-bit Reception with AHEN and DHEN


Client device reception with AHEN and DHEN set operate the same as without these options with extra interrupts and clock stretching added after the eighth falling edge of SCL. These additional interrupts allows time for the client software to decide whether it wants to  $\overline{ACK}$  the receive address or data byte.

This list describes the steps that need to be taken by client software to use these options for  $\rm I^2C$  communication. Figure 32-16 displays a module using both address and data holding. Figure 32-17 includes the operation with the SEN bit of the SSPxCON2 register set.


- The S bit of SSPxSTAT is set; SSPxIF is set if interrupt on Start detect is enabled.
- Matching address with R/W bit clear is clocked in. SSPxIF is set, and CKP is cleared in hardware after the eighth falling edge of SCL.
- Client clears the SSPxIF.
- Client can look at the ACKTIM bit of the SSPxCON3 register to determine if the SSPxIF was after or before the ACK.
- Client reads the address value from SSPxBUF, clearing the BF flag.
- Client sets ACK value clocked out to the host by setting ACKDT.
- Client releases the clock by setting CKP in software.
- SSPxIF is set after an ACK, not after a NACK.
- If SEN = 1 the client hardware will stretch the clock after the ACK.
- Client clears SSPxIF.


Note: SSPxIF is still set after the ninth falling edge of SCL even if there is no clock stretching and BF has been cleared. Only if NACK is sent to host is SSPxIF not set


- SSPxIF set, and CKP is cleared in hardware after eighth falling edge of SCL for a received data byte.
- Client looks at ACKTIM bit of SSPxCON3 to determine the source of the interrupt.
- Client reads the received data from SSPxBUF clearing BF.
- Steps 7-14 are the same for each received data byte.
- 15. Communication is ended by either the client sending an ACK = 1, or the host sending a Stop condition. If a Stop is sent and Interrupt on Stop Detect is disabled, the client will only know by polling the P bit of the SSPxSTAT register.











#### 32.5.3 CLIENT TRANSMISSION

When the R/W bit of the incoming address byte is set and an address match occurs, the R/W bit of the SSPxSTAT register is set. The received address is loaded into the SSPxBUF register, and an ACK pulse is sent by the client on the ninth bit.

Following the ACK, client hardware clears the CKP bit and the SCL pin is held low (see Section 32.5.6 "Clock Stretching" for more details). By stretching the clock, the host will be unable to assert another clock pulse until the client is done preparing the transmit data.

The transmit data must be loaded into the SSPxBUF register which also loads the SSPxSR register. Then the SCL pin may be released by setting the CKP bit of the SSPxCON1 register. The eight data bits are shifted out on the falling edge of the SCL input. This ensures that the SDA signal is valid during the SCL high time.

The  $\overline{ACK}$  pulse from the host-receiver is latched on the rising edge of the ninth SCL input pulse. This  $\overline{ACK}$  value is copied to the ACKSTAT bit of the SSPxCON2 register. If ACKSTAT is set (not  $\overline{ACK}$ ), then the data transfer is complete. In this case, when the not  $\overline{ACK}$  is latched by the client, the client goes Idle and waits for another occurrence of the Start bit. If the SDA line was low ( $\overline{ACK}$ ), the next transmit data must be loaded into the SSPxBUF register. Again, the SCL pin must be released by setting bit CKP.

An MSSP interrupt is generated for each data transfer byte. The SSPxIF bit must be cleared by software and the SSPxSTAT register is used to determine the status of the byte. The SSPxIF bit is set on the falling edge of the ninth clock pulse.

#### 32.5.3.1 Client Mode Bus Collision

A client receives a read request and begins shifting data out on the SDA line. If a bus collision is detected and the SBCDE bit of the SSPxCON3 register is set, the BCL1IF bit of the PIR3 register is set. Once a bus collision is detected, the client goes Idle and waits to be addressed again. User software can use the BCL1IF bit to handle a client bus collision.


#### 32.5.3.2 7-bit Transmission

A host device can transmit a read request to a client, and then clock data out of the client. The list below outlines what software for a client will need to do to accomplish a standard transmission. Figure 32-18 can be used as a reference to this list.

- 1. Host sends a Start condition on SDA and SCL.
- The S bit of SSPxSTAT is set; SSPxIF is set if interrupt on Start detect is enabled.
- Matching address with R/W bit set is received by the Client setting SSPxIF bit.
- Client hardware generates an ACK and sets SSPxIF.
- 5. SSPxIF bit is cleared by software.
- Software reads the received address from SSPxBUF, clearing BF.
- R/W is set so CKP was automatically cleared by hardware after the ACK.
- The client software loads the transmit data into SSPxBUF.
- CKP bit is set in software, releasing SCL, allowing the host to clock the data out of the client.
- SSPxIF is set after the ACK response from the host is loaded into the ACKSTAT bit.
- 11. SSPxIF bit is cleared.
- The client software checks the ACKSTAT bit to see if the host wants to clock out more data.

Note 1: If the host ACKs the clock will be stretched.

- ACKSTAT is the only bit updated on the rising edge of SCL (9th) rather than the falling.
- Steps 9-13 are repeated for each transmitted byte.
- If the host sends a not ACK; the clock is not held, but SSPxIF is still set.
- The host sends a Restart condition or a Stop.
- 16. The client is no longer addressed.



## 32.5.3.3 7-bit Transmission with Address Hold Enabled

Setting the AHEN bit of the SSPxCON3 register enables additional clock stretching and interrupt generation after the eighth falling edge of a received matching address. Once a matching address has been clocked in, CKP is cleared and the SSPxIF interrupt is set.


Figure 32-19 displays a standard waveform of a 7-bit address client transmission with AHEN enabled.

- Host sends Start condition; the S bit of SSPxSTAT is set; SSPxIF is set if interrupt on Start detect is enabled.
- Host sends matching address with R/W bit set.
   After the eighth falling edge of the SCL line the CKP bit is cleared by hardware and SSPxIF interrupt is generated.
- 3. Client software clears SSPxIF.
- Client software reads ACKTIM bit of SSPxCON3 register, and R/W and D/A of the SSPxSTAT register to determine the source of the interrupt.
- Client reads the address value from the SSPxBUF register clearing the BF bit.
- Client software decides from this information if it wishes to ACK or not ACK and sets the ACKDT bit of the SSPxCON2 register accordingly.
- 7. Client software sets the CKP bit releasing SCL.
- 8. Host clocks in the ACK value from the client.
- Client hardware automatically clears the CKP bit and sets SSPxIF after the ACK if the R/W bit is set.
- Client software clears SSPxIF.
- Client loads value to transmit to the host into SSPxBUF setting the BF bit.

Note: SSPxBUF cannot be loaded until after the ACK.

- Client sets the CKP bit releasing the clock.
- Host clocks out the data from the client and sends an ACK value on the ninth SCL pulse.
- Client hardware copies the ACK value into the ACKSTAT bit of the SSPxCON2 register.
- Steps 10-15 are repeated for each byte transmitted to the host from the client.
- If the host sends a not ACK the client releases the bus allowing the host to send a Stop and end the communication.

Note: Host must send a not ACK on the last byte to ensure that the client releases the SCL line to receive a Stop.



PIC16(L)F15354/55

# 32.5.4 CLIENT MODE 10-BIT ADDRESS RECEPTION

This section describes a standard sequence of events for the MSSP module configured as an I<sup>2</sup>C client in 10-bit Addressing mode.

Figure 32-20 is used as a visual reference for this description.

This is a step by step process of what must be done by client software to accomplish I<sup>2</sup>C communication.

- Host sends Start condition; S bit of SSPxSTAT is set; SSPxIF is set if interrupt on Start detect is enabled.
- Host sends matching high address with R/W bit clear; UA bit of the SSPxSTAT register is set.
- Client sends ACK and SSPxIF is set.
- 4. Software clears the SSPxIF bit.
- Software reads received address from SSPxBUF clearing the BF flag.
- Client loads low address into SSPxADD, releasing SCL.
- Host sends matching low address byte to the client; UA bit is set.

Note: Updates to the SSPxADD register are not allowed until after the ACK sequence.

Client sends ACK and SSPxIF is set.

Note: If the low address does not match, SSPxIF and UA are still set so that the client software can set SSPxADD back to the high address. BF is not set because there is no match. CKP is unaffected.

- Client clears SSPxIF.
- Client reads the received matching address from SSPxBUF clearing BF.
- 11. Client loads high address into SSPxADD.
- Host clocks a data byte to the client and clocks out the clients ACK on the ninth SCL pulse; SSPxIF is set.
- If SEN bit of SSPxCON2 is set, CKP is cleared by hardware and the clock is stretched.
- 14. Client clears SSPxIF.
- Client reads the received byte from SSPxBUF clearing BF.
- If SEN is set the client software sets CKP to release the SCL.
- Steps 13-17 repeat for each received byte.
- Host sends Stop to end the transmission.


# 32.5.5 10-BIT ADDRESSING WITH ADDRESS OR DATA HOLD

Reception using 10-bit addressing with AHEN or DHEN set is the same as with 7-bit modes. The only difference is the need to update the SSPxADD register using the UA bit. All functionality, specifically when the CKP bit is cleared and SCL line is held low are the same. Figure 32-21 can be used as a reference of a client in 10-bit addressing with AHEN set.


Figure 32-22 shows a standard waveform for a client transmitter in 10-bit Addressing mode.




PIC16(L)F15354/55









PIC16(L)F15354/55

### 32.5.6 CLOCK STRETCHING

Clock stretching occurs when a device on the bus holds the SCL line low, effectively pausing communication. The client may stretch the clock to allow more time to handle data or prepare a response for the host device. A host device is not concerned with stretching as anytime it is active on the bus and not transferring data it is stretching. Any stretching done by a client is invisible to the host software and handled by the hardware that generates SCL.

The CKP bit of the SSPxCON1 register is used to control stretching. Any time the CKP bit is cleared, the module will wait for the SCL line to go low and then hold it. Setting CKP will release SCL and allow more communication.

### 32.5.6.1 Normal Clock Stretching

Following an ACK if the R/W bit of SSPxSTAT is set, a read request, the client hardware will clear CKP. This allows the client time to update SSPxBUF with data to transfer to the host. If the SEN bit of SSPxCON2 is set, the client hardware will always stretch the clock after the ACK sequence. Once the client is ready; CKP is set by software and communication resumes.

### 32.5.6.2 10-bit Addressing Mode

In 10-bit Addressing mode, when the UA bit is set the clock is always stretched. This is the only time the SCL is stretched without CKP being cleared. SCL is released immediately after a write to SSPxADD.

### 32.5.6.3 Byte NACKing


When AHEN bit of SSPxCON3 is set; CKP is cleared by hardware after the eighth falling edge of SCL for a received matching address byte. When DHEN bit of SSPxCON3 is set; CKP is cleared after the eighth falling edge of SCL for received data.

Stretching after the eighth falling edge of SCL allows the client to look at the received address or data and decide if it wants to ACK the received data.

# 32.5.7 CLOCK SYNCHRONIZATION AND THE CKP BIT

Any time the CKP bit is cleared, the module will wait for the SCL line to go low and then hold it. However, clearing the CKP bit will not assert the SCL output low until the SCL output is already sampled low. Therefore, the CKP bit will not assert the SCL line until an external I<sup>2</sup>C host device has already asserted the SCL line. The SCL output will remain low until the CKP bit is set and all other devices on the I<sup>2</sup>C bus have released SCL. This ensures that a write to the CKP bit will not violate the minimum high time requirement for SCL (see Figure 32-23).





### 32.5.8 GENERAL CALL ADDRESS SUPPORT


The addressing procedure for the I<sup>2</sup>C bus is such that the first byte after the Start condition usually determines which device will be the client addressed by the host device. The exception is the general call address which can address all devices. When this address is used, all devices might, in theory, respond with an acknowledge.

The general call address is a reserved address in the  $I^2C$  protocol, defined as address  $0 \times 00$ . When the GCEN bit of the SSPxCON2 register is set, the client module will automatically ACK the reception of this address regardless of the value stored in SSPxADD. After the client clocks in an address of all zeros with the R/W bit clear, an interrupt is generated and client software can read SSPxBUF and respond. Figure 32-24 shows a general call reception sequence.

In 10-bit Address mode, the UA bit will not be set on the reception of the general call address. The client will prepare to receive the second byte as data, just as it would in 7-bit mode.

If the AHEN bit of the SSPxCON3 register is set, just as with any other address reception, the client hardware will stretch the clock after the eighth falling edge of SCL. The client must then set its ACKDT value and release the clock with communication progressing.





### 32.5.9 SSP MASK REGISTER

An SSP Mask (SSPxMSK) register (Register 32-5) is available in I<sup>2</sup>C Client mode as a mask for the value held in the SSPxSR register during an address comparison operation. A zero ('0') bit in the SSPxMSK register has the effect of making the corresponding bit of the received address a "don't care".

This register is reset to all '1's upon any Reset condition and, therefore, has no effect on standard SSP operation until written with a mask value.

The SSP Mask register is active during:

- 7-bit Address mode: address compare of A<7:1>.
- 10-bit Address mode: address compare of A<7:0>
   only. The SSP mask has no effect during the
   reception of the first (high) byte of the address.

### 32.6 I<sup>2</sup>C Host Mode

Host mode is enabled by setting and clearing the appropriate SSPM bits in the SSPxCON1 register and by setting the SSPEN bit. In Host mode, the SDA and SCK pins must be configured as inputs. The MSSP peripheral hardware will override the output driver TRIS controls when necessary to drive the pins low.

Host mode of operation is supported by interrupt generation on the detection of the Start and Stop conditions. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit is set, or the bus is Idle.

In Firmware Controlled Host mode, user code conducts all  $I^2C$  bus operations based on Start and Stop bit condition detection. Start and Stop condition detection is the only active circuitry in this mode. All other communication is done by the user software directly manipulating the SDA and SCL lines.

The following events will cause the SSP Interrupt Flag bit, SSPxIF, to be set (SSP interrupt, if enabled):

- · Start condition generated
- · Stop condition generated
- Data transfer byte transmitted/received
- Acknowledge transmitted/received
- Repeated Start generated
  - Note 1: The MSSP module, when configured in I<sup>2</sup>C
    Host mode, does not allow queuing of
    events. For instance, the user is not
    allowed to initiate a Start condition and
    immediately write the SSPxBUF register
    to initiate transmission before the Start
    condition is complete. In this case, the
    SSPxBUF will not be written to and the
    WCOL bit will be set, indicating that a
    write to the SSPxBUF did not occur.
    - 2: When in Host mode, Start/Stop detection is masked and an interrupt is generated when the SEN/PEN bit is cleared and the generation is complete.

### 32.6.1 I<sup>2</sup>C HOST MODE OPERATION

The host device generates all of the serial clock pulses and the Start and Stop conditions. A transfer is ended with a Stop condition or with a Repeated Start condition. Since the Repeated Start condition is also the beginning of the next serial transfer, the I<sup>2</sup>C bus will not be released.

In Host Transmitter mode, serial data is output through SDA, while SCL outputs the serial clock. The first byte transmitted contains the client <u>address of the receiving device (7 bits)</u> and the Read/Write (R/W) bit. In this case, the R/W bit will be logic '0'. Serial data is transmitted eight bits at a time. After each byte is transmitted, an Acknowledge bit is received. Start and Stop conditions are output to indicate the beginning and the end of a serial transfer.


In Host Receive mode, the first byte transmitted contains the client address of the transmitting device (7 bits) and the R/W bit. In this case, the R/W bit will be logic '1'. Thus, the first byte transmitted is a 7-bit client address followed by a '1' to indicate the receive bit. Serial data is received via SDA, while SCL outputs the serial clock. Serial data is received eight bits at a time. After each byte is received, an Acknowledge bit is transmitted. Start and Stop conditions indicate the beginning and end of transmission.

A Baud Rate Generator is used to set the clock frequency output on SCL. See Section 32.7 "Baud Rate Generator" for more details.

### 32.6.2 CLOCK ARBITRATION

Clock arbitration occurs when the host, during any receive, transmit or Repeated Start/Stop condition, releases the SCL pin (SCL allowed to float high). When the SCL pin is allowed to float high, the Baud Rate Generator (BRG) is suspended from counting until the SCL pin is actually sampled high. When the SCL pin is sampled high, the Baud Rate Generator is reloaded with the contents of SSPxADD<7:0> and begins counting. This ensures that the SCL high time will always be at least one BRG rollover count in the event that the clock is held low by an external device (Figure 32-25).

FIGURE 32-25: BAUD RATE GENERATOR TIMING WITH CLOCK ARBITRATION



### 32.6.3 WCOL STATUS FLAG

If the user writes the SSPxBUF when a Start, Restart, Stop, Receive or Transmit sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write does not occur). Any time the WCOL bit is set it indicates that an action on SSPxBUF was attempted while the module was not Idle.

Note: Because queuing of events is not allowed, writing to the lower five bits of SSPxCON2 is disabled until the Start condition is complete.

# PIC16(L)F15354/55


# 32.6.4 I<sup>2</sup>C HOST MODE START CONDITION TIMING

To initiate a Start condition (Figure 32-26), the user sets the Start Enable bit, SEN bit of the SSPxCON2 register. If the SDA and SCL pins are sampled high, the Baud Rate Generator is reloaded with the contents of SSPxADD<7:0> and starts its count. If SCL and SDA are both sampled high when the Baud Rate Generator times out (TBRG), the SDA pin is driven low. The action of the SDA being driven low while SCL is high is the Start condition and causes the S bit of the SSPxSTAT1 register to be set. Following this, the Baud Rate Generator is reloaded with the contents of SSPxADD<7:0> and resumes its count. When the Baud Rate Generator times out (TBRG), the SEN bit of the SSPxCON2 register will be automatically cleared

by hardware; the Baud Rate Generator is suspended, leaving the SDA line held low and the Start condition is complete.

- Note 1: If at the beginning of the Start condition, the SDA and SCL pins are already sampled low, or if during the Start condition, the SCL line is sampled low before the SDA line is driven low, a bus collision occurs, the Bus Collision Interrupt Flag, BCLIF, is set, the Start condition is aborted and the I<sup>2</sup>C module is reset into its Idle state.
  - 2: The Philips I<sup>2</sup>C specification states that a bus collision cannot occur on a Start.

FIGURE 32-26: FIRST START BIT TIMING




# 32.6.5 I<sup>2</sup>C HOST MODE REPEATED START CONDITION TIMING

A Repeated Start condition (Figure 32-27) occurs when the RSEN bit of the SSPxCON2 register is programmed high and the host state machine is no longer active. When the RSEN bit is set, the SCL pin is asserted low. When the SCL pin is sampled low, the Baud Rate Generator is loaded and begins counting. The SDA pin is released (brought high) for one Baud Rate Generator count (TBRG). When the Baud Rate Generator times out, if SDA is sampled high, the SCL pin will be deasserted (brought high). When SCL is sampled high, the Baud Rate Generator is reloaded and begins counting. SDA and SCL must be sampled high for one TBRG. This action is then followed by assertion of the SDA pin (SDA = 0) for one TBRG while SCL is high. SCL is asserted low. Following this, the RSEN bit of the SSPxCON2 register will be automatically cleared and the Baud Rate Generator will not be reloaded, leaving the SDA pin held low. As soon as a Start condition is detected on the SDA and SCL pins, the S bit of the SSPxSTAT register will be set. The SSPxIF bit will not be set until the Baud Rate Generator has timed out.

- Note 1: If RSEN is programmed while any other event is in progress, it will not take effect.
  - 2: A bus collision during the Repeated Start condition occurs if:
    - SDA is sampled low when SCL goes from low-to-high
    - SCL goes low before SDA is asserted low. This may indicate that another host is attempting to transmit a data '1'.

FIGURE 32-27: REPEATED START CONDITION WAVEFORM



# 32.6.6 I<sup>2</sup>C HOST MODE TRANSMISSION

Transmission of a data byte, a 7-bit address or the other half of a 10-bit address is accomplished by simply writing a value to the SSPxBUF register. This action will set the Buffer Full flag bit, BF, and allow the Baud Rate Generator to begin counting and start the next transmission. Each bit of address/data will be shifted out onto the SDA pin after the falling edge of SCL is asserted. SCL is held low for one Baud Rate Generator rollover count (TBRG). Data must be valid before SCL is released high. When the SCL pin is released high, it is held that way for TBRG. The data on the SDA pin must remain stable for that duration and some hold time after the next falling edge of SCL. After the eighth bit is shifted out (the falling edge of the eighth clock), the BF flag is cleared and the host releases SDA. This allows the client device being addressed to respond with an ACK bit during the ninth bit time if an address match occurred, or if data was received properly. The status of ACK is written into the ACKSTAT bit on the rising edge of the ninth clock. If the host receives an Acknowledge, the Acknowledge Status bit, ACKSTAT, is cleared. If not, the bit is set. After the ninth clock, the SSPxIF bit is set and the host clock (Baud Rate Generator) is suspended until the next data byte is loaded into the SSPxBUF, leaving SCL low and SDA unchanged (Figure 32-28).

After the write to the SSPxBUF, each bit of the address will be shifted out on the falling edge of SCL until all seven address bits and the R/W bit are completed. On the falling edge of the eighth clock, the host will release the SDA pin, allowing the client to respond with an Acknowledge. On the falling edge of the ninth clock, the host will sample the SDA pin to see if the address was recognized by a client. The status of the ACK bit is loaded into the ACKSTAT Status bit of the SSPxCON2 register. Following the falling edge of the ninth clock transmission of the address, the SSPxIF is set, the BF flag is cleared and the Baud Rate Generator is turned off until another write to the SSPxBUF takes place, holding SCL low and allowing SDA to float.

### 32.6.6.1 BF Status Flag

In Transmit mode, the BF bit of the SSPxSTAT register is set when the CPU writes to SSPxBUF and is cleared when all eight bits are shifted out.

### 32.6.6.2 WCOL Status Flag

If the user writes the SSPxBUF when a transmit is already in progress (i.e., SSPxSR is still shifting out a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).


WCOL must be cleared by software before the next transmission.

### 32.6.6.3 ACKSTAT Status Flag

In Transmit mode, the ACKSTAT bit of the SSPxCON2 register is cleared when the client has sent an Acknowledge (ACK = 0) and is set when the client does not Acknowledge (ACK = 1). A client sends an Acknowledge when it has recognized its address (including a general call), or when the client has properly received its data.

### 32.6.6.4 Typical Transmit Sequence:

- The user generates a Start condition by setting the SEN bit of the SSPxCON2 register.
- SSPxIF is set by hardware on completion of the Start.
- 3. SSPxIF is cleared by software.
- The MSSP module will wait the required start time before any other operation takes place.
- The user loads the SSPxBUF with the client address to transmit.
- Address is shifted out the SDA pin until all eight bits are transmitted. Transmission begins as soon as SSPxBUF is written to.
- The MSSP module shifts in the ACK bit from the client device and writes its value into the ACKSTAT bit of the SSPxCON2 register.
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPxIF bit.
- The user loads the SSPxBUF with eight bits of data.
- Data is shifted out the SDA pin until all eight bits are transmitted.
- The MSSP module shifts in the ACK bit from the client device and writes its value into the ACKSTAT bit of the SSPxCON2 register.
- Steps 8-11 are repeated for all transmitted data bytes.
- The user generates a Stop or Restart condition by setting the PEN or RSEN bits of the SSPx-CON2 register. Interrupt is generated once the Stop/Restart condition is complete.



PIC16(L)F15354/55

# 32.6.7 I<sup>2</sup>C HOST MODE RECEPTION

Host mode reception (Figure 32-29) is enabled by programming the Receive Enable bit, RCEN bit of the SSPxCON2 register.

Note: The MSSP module must be in an Idle state before the RCEN bit is set or the RCEN bit will be disregarded.

The Baud Rate Generator begins counting and on each rollover, the state of the SCL pin changes (high-to-low/low-to-high) and data is shifted into the SSPxSR. After the falling edge of the eighth clock, the receive enable flag is automatically cleared, the contents of the SSPxSR are loaded into the SSPxBUF, the BF flag bit is set, the SSPxIF flag bit is set and the Baud Rate Generator is suspended from counting, holding SCL low. The MSSP is now in Idle state awaiting the next command. When the buffer is read by the CPU, the BF flag bit is automatically cleared. The user can then send an Acknowledge bit at the end of reception by setting the Acknowledge Sequence Enable, ACKEN bit of the SSPxCON2 register.

### 32.6.7.1 BF Status Flag

In receive operation, the BF bit is set when an address or data byte is loaded into SSPxBUF from SSPxSR. It is cleared when the SSPxBUF register is read.

## 32.6.7.2 SSPOV Status Flag


In receive operation, the SSPOV bit is set when eight bits are received into the SSPxSR and the BF flag bit is already set from a previous reception.

### 32.6.7.3 WCOL Status Flag

If the user writes the SSPxBUF when a receive is already in progress (i.e., SSPxSR is still shifting in a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).

### 32.6.7.4 Typical Receive Sequence:

- The user generates a Start condition by setting the SEN bit of the SSPxCON2 register.
- SSPxIF is set by hardware on completion of the Start.
- 3. SSPxIF is cleared by software.
- User writes SSPxBUF with the client address to transmit and the R/W bit set.
- Address is shifted out the SDA pin until all eight bits are transmitted. Transmission begins as soon as SSPxBUF is written to.
- The MSSP module shifts in the ACK bit from the client device and writes its value into the ACKSTAT bit of the SSPxCON2 register.
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPxIF bit.
- User sets the RCEN bit of the SSPxCON2 register and the host clocks in a byte from the client.
- After the eighth falling edge of SCL, SSPxIF and BF are set.
- Host clears SSPxIF and reads the received byte from SSPxBUF, clears BF.
- Host sets ACK value sent to client in ACKDT bit of the SSPxCON2 register and initiates the ACK by setting the ACKEN bit.
- Host's ACK is clocked out to the client and SSPxIF is set.
- 13. User clears SSPxIF.
- Steps 8-13 are repeated for each received byte from the client.
- 15. Host sends a not ACK or Stop to end communication.



PIC16(L)F15354/55

# 32.6.8 ACKNOWLEDGE SEQUENCE TIMING

An Acknowledge sequence is enabled by setting the Acknowledge Sequence Enable bit, ACKEN bit of the SSPxCON2 register. When this bit is set, the SCL pin is pulled low and the contents of the Acknowledge data bit are presented on the SDA pin. If the user wishes to generate an Acknowledge, then the ACKDT bit may be cleared. If not, the user may set the ACKDT bit before starting an Acknowledge sequence. The Baud Rate Generator then counts for one rollover period (TBRG) and the SCL pin is deasserted (pulled high). When the SCL pin is sampled high (clock arbitration), the Baud Rate Generator counts for TBRG. The SCL pin is then pulled low. Following this, the ACKEN bit is automatically cleared, the Baud Rate Generator is turned off and the MSSP module then goes into Idle mode (Figure 32-30).

### 32.6.8.1 WCOL Status Flag

If the user writes the SSPxBUF when an Acknowledge sequence is in progress, then WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).


### 32.6.9 STOP CONDITION TIMING

A Stop bit is asserted on the SDA pin at the end of a receive/transmit by setting the Stop Sequence Enable bit, PEN bit of the SSPxCON2 register. At the end of a receive/transmit, the SCL line is held low after the falling edge of the ninth clock. When the PEN bit is set, the host will assert the SDA line low. When the SDA line is sampled low, the Baud Rate Generator is reloaded and counts down to '0'. When the Baud Rate Generator times out, the SCL pin will be brought high and one TBRG (Baud Rate Generator rollover count) later, the SDA pin will be deasserted. When the SDA pin is sampled high while SCL is high, the P bit of the SSPxSTAT register is set. A TBRG later, the PEN bit is cleared and the SSPxIF bit is set (Figure 32-31).


### 32.6.9.1 WCOL Status Flag

If the user writes the SSPxBUF when a Stop sequence is in progress, then the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).

FIGURE 32-30: ACKNOWLEDGE SEQUENCE WAVEFORM



## FIGURE 32-31: STOP CONDITION RECEIVE OR TRANSMIT MODE



## 32.6.10 SLEEP OPERATION

While in Sleep mode, the I<sup>2</sup>C client module can receive addresses or data and when an address match or complete byte transfer occurs, wake the processor from Sleep (if the MSSP interrupt is enabled).

### 32.6.11 EFFECTS OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

### 32.6.12 MULTI-HOST MODE

In Multi-Host mode, the interrupt generation on the detection of the Start and Stop conditions allows the determination of when the bus is free. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit of the SSPxSTAT register is set, or the bus is Idle, with both the S and P bits clear. When the bus is busy, enabling the SSP interrupt will generate the interrupt when the Stop condition occurs.

In multi-host operation, the SDA line must be monitored for arbitration to see if the signal level is the expected output level. This check is performed by hardware with the result placed in the BCL1IF bit.

The states where arbitration can be lost are:

- Address Transfer
- Data Transfer
- A Start Condition
- · A Repeated Start Condition
- An Acknowledge Condition

# 32.6.13 MULTI -HOST COMMUNICATION, BUS COLLISION AND BUS ARBITRATION

Multi-Host mode support is achieved by bus arbitration. When the host outputs address/data bits onto the SDA pin, arbitration takes place when the host outputs a '1' on SDA, by letting SDA float high and another host asserts a '0'. When the SCL pin floats high, data may be stable. If the expected data on SDA is a '1' and the data sampled on the SDA pin is '0', then a bus collision has taken place. The host will set the Bus Collision Interrupt Flag, BCL1IF and reset the I<sup>2</sup>C port to its Idle state (Figure 32-32).

If a transmit was in progress when the bus collision occurred, the transmission is halted, the BF flag is cleared, the SDA and SCL lines are deasserted and the SSPxBUF can be written to. When the user services the bus collision Interrupt Service Routine and if the I<sup>2</sup>C bus is free, the user can resume communication by asserting a Start condition.


If a Start, Repeated Start, Stop or Acknowledge condition was in progress when the bus collision occurred, the condition is aborted, the SDA and SCL lines are deasserted and the respective control bits in the SSPxCON2 register are cleared. When the user services the bus collision Interrupt Service Routine and if the I<sup>2</sup>C bus is free, the user can resume communication by asserting a Start condition.

The host will continue to monitor the SDA and SCL pins. If a Stop condition occurs, the SSPxIF bit will be set.

A write to the SSPxBUF will start the transmission of data at the first data bit, regardless of where the transmitter left off when the bus collision occurred.

In Multi-Host mode, the interrupt generation on the detection of Start and Stop conditions allows the determination of when the bus is free. Control of the I<sup>2</sup>C bus can be taken when the P bit is set in the SSPxSTAT register, or the bus is Idle and the S and P bits are cleared.





# 32.6.13.1 Bus Collision During a Start Condition

During a Start condition, a bus collision occurs if:

- a) SDA or SCL are sampled low at the beginning of the Start condition (Figure 32-33).
- SCL is sampled low before SDA is asserted low (Figure 32-34).

During a Start condition, both the SDA and the SCL pins are monitored.

If the SDA pin is already low, or the SCL pin is already low, then all of the following occur:

- · the Start condition is aborted,
- · the BCL1IF flag is set and
- the MSSP module is reset to its Idle state (Figure 32-33).


The Start condition begins with the SDA and SCL pins deasserted. When the SDA pin is sampled high, the Baud Rate Generator is loaded and counts down. If the SCL pin is sampled low while SDA is high, a bus collision occurs because it is assumed that another host is attempting to drive a data '1' during the Start condition.

If the SDA pin is sampled low during this count, the BRG is reset and the SDA line is asserted early (Figure 32-35). If, however, a '1' is sampled on the SDA pin, the SDA pin is asserted low at the end of the BRG count. The Baud Rate Generator is then reloaded and counts down to zero; if the SCL pin is sampled as '0' during this time, a bus collision does not occur. At the end of the BRG count, the SCL pin is asserted low.


Note:

The reason that bus collision is not a factor during a Start condition is that no two bus hosts can assert a Start condition at the exact same time. Therefore, one host will always assert SDA before the other. This condition does not cause a bus collision because the two hosts must be allowed to arbitrate the first address following the Start condition. If the address is the same, arbitration must be allowed to continue into the data portion, Repeated Start or Stop conditions.


FIGURE 32-33: BUS COLLISION DURING START CONDITION (SDA ONLY)







# FIGURE 32-35: BRG RESET DUE TO SDA ARBITRATION DURING START CONDITION



# 32.6.13.2 Bus Collision During a Repeated Start Condition

During a Repeated Start condition, a bus collision occurs if:

- A low level is sampled on SDA when SCL goes from low level to high level (Case 1).
- SCL goes low before SDA is asserted low, indicating that another host is attempting to transmit a data '1' (Case 2).

When the user releases SDA and the pin is allowed to float high, the BRG is loaded with SSPxADD and counts down to zero. The SCL pin is then deasserted and when sampled high, the SDA pin is sampled.


If SDA is low, a bus collision has occurred (i.e., another host is attempting to transmit a data '0', Figure 32-36). If SDA is sampled high, the BRG is reloaded and begins

counting. If SDA goes from high-to-low before the BRG times out, no bus collision occurs because no two hosts can assert SDA at exactly the same time.


If SCL goes from high-to-low before the BRG times out and SDA has not already been asserted, a bus collision occurs. In this case, another host is attempting to transmit a data '1' during the Repeated Start condition, see Figure 32-37.

If, at the end of the BRG time-out, both SCL and SDA are still high, the SDA pin is driven low and the BRG is reloaded and begins counting. At the end of the count, regardless of the status of the SCL pin, the SCL pin is driven low and the Repeated Start condition is complete.





## FIGURE 32-37: BUS COLLISION DURING REPEATED START CONDITION (CASE 2)



# 32.6.13.3 Bus Collision During a Stop Condition

Bus collision occurs during a Stop condition if:

- After the SDA pin has been deasserted and allowed to float high, SDA is sampled low after the BRG has timed out (Case 1).
- After the SCL pin is deasserted, SCL is sampled low before SDA goes high (Case 2).

The Stop condition begins with SDA asserted low. When SDA is sampled low, the SCL pin is allowed to float. When the pin is sampled high (clock arbitration), the Baud Rate Generator is loaded with SSPxADD and counts down to zero. After the BRG times out, SDA is sampled. If SDA is sampled low, a bus collision has occurred. This is due to another host attempting to drive a data '0' (Figure 32-38). If the SCL pin is sampled low before SDA is allowed to float high, a bus collision occurs. This is another case of another host attempting to drive a data '0' (Figure 32-39).

FIGURE 32-38: BUS COLLISION DURING A STOP CONDITION (CASE 1)





FIGURE 32-39: BUS COLLISION DURING A STOP CONDITION (CASE 2)



### 32.7 BAUD RATE GENERATOR

The MSSP module has a Baud Rate Generator available for clock generation in both I<sup>2</sup>C and SPI Host modes. The Baud Rate Generator (BRG) reload value is placed in the SSPxADD register (Register 32-6). When a write occurs to SSPxBUF, the Baud Rate Generator will automatically begin counting down.

Once the given operation is complete, the internal clock will automatically stop counting and the clock pin will remain in its last state.

An internal signal "Reload" in Figure 32-40 triggers the value from SSPxADD to be loaded into the BRG counter. This occurs twice for each oscillation of the


module clock line. The logic dictating when the reload signal is asserted depends on the mode the MSSP is being operated in.

Table 32-4 demonstrates clock rates based on instruction cycles and the BRG value loaded into SSPxADD.

### **EQUATION 32-1:**

$$FCLOCK = \frac{FOSC}{(SSP1ADD + 1)(4)}$$

FIGURE 32-40: BAUD RATE GENERATOR BLOCK DIAGRAM



Note: Values of 0x00, 0x01 and 0x02 are not valid for SSPxADD when used as a Baud Rate Generator for I<sup>2</sup>C. This is an implementation limitation.

TABLE 32-2: MSSP CLOCK RATE W/BRG

Fosc	FcY	BRG Value	FCLOCK (2 Rollovers of BRG)	
32 MHz	8 MHz	13h	400 kHz	
32 MHz	8 MHz	19h	308 kHz	
32 MHz	8 MHz	4Fh	100 kHz	
16 MHz	4 MHz	09h	400 kHz	
16 MHz	4 MHz	0Ch	308 kHz	
16 MHz	16 MHz 4 MHz		100 kHz	
4 MHz	1 MHz	09h	100 kHz	

Note: Refer to the I/O port electrical specifications in Table 37-4 to ensure the system is designed to support IoL requirements.

#### 32.8 Register Definitions: MSSPx Control

#### REGISTER 32-1: SSPxSTAT: SSPx STATUS REGISTER

R/W-0/0	R/W-0/0	R/HS/HC-0	R/HS/HC-0	R/HS/HC-0	R/HS/HC-0	R/HS/HC-0	R/HS/HC-0
SMP	CKE <sup>(1)</sup>	D/Ā	P(2)	S(2)	R/W	UA	BF
bit 7						_	bit 0

Legend: W = Writable bit R = Readable bit U = Unimplemented bit, read as '0' u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets HS/HC = Hardware set/clear '1' = Bit is set '0' = Bit is cleared

bit 7 SMP: SPI Data Input Sample bit

SPI Host mode:

1 = Input data sampled at end of data output time 0 = Input data sampled at middle of data output time

<u>SPI Client mode:</u> SMP must be cleared when SPI is used in Client mode

 $ln l^2C$  Host or Client mode: 1 = Slew rate control disabled for Standard Speed mode (100 kHz and 1 MHz)

0 = Slew rate control enabled for High-Speed mode (400 kHz)

CKE: SPI Clock Edge Select bit (SPI mode only)(1)

In SPI Host or Client mode:

1 = Transmit occurs on transition from active to Idle clock state 0 = Transmit occurs on transition from Idle to active clock state

In I<sup>2</sup>C mode only: 1 = Enable input logic so that thresholds are compliant with SMBus specification

0 = Disable SMBus specific inputs

bit 5 D/A: Data/Address bit (I<sup>2</sup>C mode only)

1 = Indicates that the last byte received or transmitted was data 0 = Indicates that the last byte received or transmitted was address

P: Stop bit(2) bit 4

bit 6

(I<sup>2</sup>C mode only. This bit is cleared when the MSSP module is disabled, SSPEN is cleared.)

1 = Indicates that a Stop bit has been detected last (this bit is '0' on Reset)

0 = Stop bit was not detected last

S: Start bit (2) bit 3

(I<sup>2</sup>C mode only. This bit is cleared when the MSSP module is disabled, SSPEN is cleared.)

1 = Indicates that a Start bit has been detected last (this bit is '0' on Reset)

0 = Start bit was not detected last

R/W: Read/Write bit information (I<sup>2</sup>C mode only) bit 2

This bit holds the  $R\overline{M}$  bit information following the last address match. This bit is only valid from the address match to the

next Start bit, Stop bit, or not ACK bit.

In I<sup>2</sup>C Client mode: 1 = Read

0 = Write

In I<sup>2</sup>C Host mode:

Transmit is in progress

0 = Transmit is not in progress

ORing this bit with SEN, RSEN, PEN, RCEN or ACKEN will indicate if the MSSP is in Idle mode.

**UA:** Update Address bit (10-bit I<sup>2</sup>C mode only) bit 1

1 = Indicates that the user needs to update the address in the SSPxADD register

0 = Address does not need to be updated

bit 0 BF: Buffer Full Status bit

Receive (SPI and I<sup>2</sup>C modes): 1 = Receive complete, SSPxBUF is full 0 = Receive not complete, SSPxBUF is empty

Transmit (I<sup>2</sup>C mode only):

1 = Data transmit in progress (does not include the ACK and Stop bits), SSPxBUF is full

0 = Data transmit complete (does not include the ACK and Stop bits), SSPxBUF is empty

Polarity of clock state is set by the CKP bit of the SSPxCON register. Note 1:

This bit is cleared on Reset and when SSPEN is cleared. 2:

#### REGISTER 32-2: SSPxCON1: SSPx CONTROL REGISTER 1

R/C/HS-0/0	R/C/HS-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	
WCOL	SSPOV <sup>(1)</sup>	SSPEN	CKP	SSPM<3:0>				
bit 7							bit 0	

Legend: R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets HS = Bit is set by hardware '1' = Bit is set '0' = Bit is cleared C = User cleared

bit 7 WCOL: Write Collision Detect bit (Transmit mode only)

1 = The SSPxBUF register is written while it is still transmitting the previous word (must be cleared in software)

0 = No collision

SSPOV: Receive Overflow Indicator bit(1) bit 6

In SPI mode

A new byte is received while the SSPxBUF register is still holding the previous data. In case of overflow, the data in SSPxSR is lost. Overflow can only occur in Client mode. In Client mode, the user must read the SSPxBUF, even if only transmitting data, to avoid setting overflow. In Host mode, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPxBUF register (must be cleared in software).

No overflow

In 1<sup>2</sup>C mode: 1 = A byte is received while the SSPxBUF register is still holding the previous byte. SSPOV is a "don't care" in Transmit mode (must be cleared in software).

0 = No overflow

bit 5 SSPEN: Synchronous Serial Port Enable bit

In both modes, when enabled, the following pins must be properly configured as input or output

1 = Enables serial port and configures SCK, SDO, SDI and SS as the source of the serial port pins (2) 0 = Disables serial port and configures these pins as I/O port pine

Disables serial port and configures these pins as I/O port pins

 $\frac{\ln 1^2 \text{C mode:}}{1 = \text{Enables the serial port and configures the SDA and SCL pins as the source of the serial port pins<sup>(3)</sup>}$ 

0 = Disables serial port and configures these pins as I/O port pins

bit 4 CKP: Clock Polarity Select bit

In SPI mode: 1 = Idle state for clock is a high level 0 = Idle state for clock is a low level

In I<sup>2</sup>C Client mode: SCL release control

1 = Enable clock 0 = Holds clock low (clock stretch). (Used to ensure data setup time.)

In I<sup>2</sup>C Host mode: Unused in this mode

bit 3-0 SSPM<3:0>: Synchronous Serial Port Mode Select bits

1111 = I<sup>2</sup>C Client mode, 10-bit address with Start and Stop bit interrupts enabled

1110 = I<sup>2</sup>C Client mode, 7-bit address with Start and Stop bit interrupts enabled

1101 = Reserved

1100 = Reserved

1011 = I2C firmware controlled Host mode (client Idle)

1010 = SPI Host mode, clock = Fosc/(4 \* (SSPxADD+1))(5)

1001 = Reserved

 $1000 = I^2C$  Host mode, clock = Fosc /  $(4 * (SSPxADD+1))^{(4)}$ 

0111 = I<sup>2</sup>C Client mode, 10-bit address

0110 = I2C Client mode, 7-bit address 0101 = SPI Client mode, clock = SCK pin, SS pin control disabled, SS can be used as I/O pin 0100 = SPI Client mode, clock = SCK pin, SS pin control enabled

0011 = SPI Host mode, clock = T2 match/2

0010 = SPI Host mode, clock = Fosc/64

0001 = SPI Host mode, clock = Fosc/16

0000 = SPI Host mode, clock = Fosc/4

In Host mode, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPxBUF register. Note

When enabled, these pins must be properly configured as input or output. Use SSPxSSPPS, SSPxCLKPPS, SSPxDATPPS, and 2: RxyPPS to select the pins.

- 3: When enabled, the SDA and SCL pins must be configured as inputs. Use SSPxCLKPPS, SSPxDATPPS, and RxyPPS to select the pins.
- 4: SSPxADD values of 0, 1 or 2 are not supported for I<sup>2</sup>C mode.
- 5: SSPxADD value of '0' is not supported. Use SSPM = 0000 instead.

# REGISTER 32-3: SSPxCON2: SSPx CONTROL REGISTER 2 (I<sup>2</sup>C MODE ONLY)(1)

R/W-0/0	R/HS/HC-0	R/W-0/0	R/S/HC-0/0	R/S/HC-0/0	R/S/HC-0/0	R/S/HC-0/0	R/S/HC-0/0
GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HC = Cleared by hardware S = User set

bit 7 GCEN: General Call Enable bit (in I<sup>2</sup>C Client mode only)

1 = Enable interrupt when a general call address (0x00 or 00h) is received in the SSPxSR

0 = General call address disabled

bit 6 ACKSTAT: Acknowledge Status bit (in I<sup>2</sup>C mode only)

1 = Acknowledge was not received 0 = Acknowledge was received

bit 5 ACKDT: Acknowledge Data bit (in I<sup>2</sup>C mode only)

In Receive mode:

Value transmitted when the user initiates an Acknowledge sequence at the end of a receive

1 = Not Acknowledge 0 = Acknowledge

bit 4 ACKEN: Acknowledge Sequence Enable bit (in I<sup>2</sup>C Host mode only)

In Host Receive mode:

1 = Initiate Acknowledge sequence on SDA and SCL pins, and transmit ACKDT data bit. Automatically cleared by hardware.

0 = Acknowledge sequence idle

bit 3 RCEN: Receive Enable bit (in I<sup>2</sup>C Host mode only)

1 = Enables Receive mode for I2C

0 = Receive idle

bit 2 **PEN:** Stop Condition Enable bit (in I<sup>2</sup>C Host mode only)

SCKMSSP Release Control:

1 = Initiate Stop condition on SDA and SCL pins. Automatically cleared by hardware.

0 = Stop condition Idle

bit 1 RSEN: Repeated Start Condition Enable bit (in I<sup>2</sup>C Host mode only)

1 = Initiate Repeated Start condition on SDA and SCL pins. Automatically cleared by hardware.

0 = Repeated Start condition Idle

bit 0 SEN: Start Condition Enable/Stretch Enable bit

In Host mode:

1 = Initiate Start condition on SDA and SCL pins. Automatically cleared by hardware.

0 = Start condition Idle

In Client mode:

1 = Clock stretching is enabled for both client transmit and client receive (stretch enabled)

0 = Clock stretching is disabled

Note 1: For bits ACKEN, RCEN, PEN, RSEN, SEN: If the I<sup>2</sup>C module is not in the Idle mode, this bit may not be set (no spooling) and the SSPxBUF may not be written (or writes to the SSPxBUF are disabled).

### REGISTER 32-4: SSPxCON3: SSPx CONTROL REGISTER 3

R-0/0	R/W-0/0									
ACKTIM <sup>(3)</sup>	PCIE	SCIE	BOEN	SDAHT	SBCDE	AHEN	DHEN			
bit 7 bit (										

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 ACKTIM: Acknowledge Time Status bit (I<sup>2</sup>C mode only)<sup>(3)</sup>

1 = Indicates the I<sup>2</sup>C bus is in an Acknowledge sequence, set on 8<sup>th</sup> falling edge of SCL clock

0 = Not an Acknowledge sequence, cleared on 9<sup>TH</sup> rising edge of SCL clock

bit 6 PCIE: Stop Condition Interrupt Enable bit (I<sup>2</sup>C mode only)

1 = Enable interrupt on detection of Stop condition

0 = Stop detection interrupts are disabled(2)

bit 5 SCIE: Start Condition Interrupt Enable bit (I<sup>2</sup>C mode only)

1 = Enable interrupt on detection of Start or Restart conditions

0 = Start detection interrupts are disabled(2)

bit 4 BOEN: Buffer Overwrite Enable bit

In SPI Client mode: (1)

1 = SSPxBUF updates every time that a new data byte is shifted in ignoring the BF bit

0 = If new byte is received with BF bit of the SSPxSTAT register already set, SSPOV bit of the SSPxCON1 register is set, and the buffer is not updated

### In I<sup>2</sup>C Host mode and SPI Host mode:

This bit is ignored.

### In I<sup>2</sup>C Client mode:

- 1 = SSPxBUF is updated and ACK is generated for a received address/data byte, ignoring the state of the SSPOV bit only if the BF bit = 0.
- 0 = SSPxBUF is only updated when SSPOV is clear
- bit 3 SDAHT: SDA Hold Time Selection bit (I<sup>2</sup>C mode only)
  - 1 = Minimum of 300 ns hold time on SDA after the falling edge of SCL
  - 0 = Minimum of 100 ns hold time on SDA after the falling edge of SCL
- bit 2 SBCDE: Client Mode Bus Collision Detect Enable bit (I<sup>2</sup>C Client mode only)

If, on the rising edge of SCL, SDA is sampled low when the module is outputting a high state, the BCL1IF bit of the PIR3 register is set, and bus goes Idle

- 1 = Enable client bus collision interrupts
- 0 = Client bus collision interrupts are disabled
- bit 1 AHEN: Address Hold Enable bit (I<sup>2</sup>C Client mode only)
  - 1 = Following the eighth falling edge of SCL for a matching received address byte; CKP bit of the SSPxCON1 register will be cleared and the SCL will be held low.
  - 0 = Address holding is disabled
- bit 0 DHEN: Data Hold Enable bit (I<sup>2</sup>C Client mode only)
  - 1 = Following the eighth falling edge of SCL for a received data byte; client hardware clears the CKP bit of the SSPxCON1 register and SCL is held low.
  - 0 = Data holding is disabled
- Note 1: For daisy-chained SPI operation; allows the user to ignore all but the last received byte. SSPOV is still set when a new byte is received and BF = 1, but hardware continues to write the most recent byte to SSPxBUF.
  - 2: This bit has no effect in Client modes that Start and Stop condition detection is explicitly listed as enabled.
  - 3: The ACKTIM Status bit is only active when the AHEN bit or DHEN bit is set.

### REGISTER 32-5: SSPxMSK: SSPx MASK REGISTER

R/W-1/1	R/W-1/1 R/W-1/1 R/W-1/1 R/W-1/1 R/W-1/1 R/W-1/1										
	SSPxMSK<7:0>										
bit 7 bit											

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-1 SSPxMSK<7:1>: Mask bits

1 = The received address bit n is compared to SSPxADD<n> to detect I<sup>2</sup>C address match

0 = The received address bit n is not used to detect I<sup>2</sup>C address match

bit 0 SSPxMSK<0>: Mask bit for I<sup>2</sup>C Client mode, 10-bit Address

 $I^2$ C Client mode, 10-bit address (SSPM<3:0> = 0111 or 1111):

1 = The received address bit 0 is compared to SSPxADD<0> to detect I<sup>2</sup>C address match

0 = The received address bit 0 is not used to detect I<sup>2</sup>C address match

I<sup>2</sup>C Client mode, 7-bit address:

MSK0 bit is ignored.

# REGISTER 32-6: SSPxADD: MSSPx ADDRESS AND BAUD RATE REGISTER (I<sup>2</sup>C MODE)

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
|         |         |         | SSPxAD  | D<7:0>  |         |         |         |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

### Host mode:

bit 7-0 SSPxADD<7:0>: Baud Rate Clock Divider bits

SCL pin clock period = ((ADD<7:0> + 1) \*4)/Fosc

## 10-Bit Client mode - Most Significant Address Byte:

bit 7-3 Not used: Unused for Most Significant Address Byte. Bit state of this register is a "don't care". Bit

pattern sent by host is fixed by I<sup>2</sup>C specification and must be equal to '11110'. However, those bits

are compared by hardware and are not affected by the value in this register.

bit 2-1 SSPxADD<2:1>: Two Most Significant bits of 10-bit address

bit 0 Not used: Unused in this mode. Bit state is a "don't care".

# 10-Bit Client mode – Least Significant Address Byte:

bit 7-0 SSPxADD<7:0>: Eight Least Significant bits of 10-bit address

### 7-Bit Client mode:

bit 7-1 SSPxADD<7:1>: 7-bit address

bit 0 Not used: Unused in this mode. Bit state is a "don't care".

## REGISTER 32-7: SSPxBUF: MSSPx BUFFER REGISTER

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
			SSPxBl	JF<7:0>			
bit 7			_				bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 SSPxBUF<7:0>: MSSP Buffer bits

## TABLE 32-3: SUMMARY OF REGISTERS ASSOCIATED WITH MSSPx

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page	
INTCON	GIE	PEIE	1 <del></del> 3	_	=	-	_	INTEDG	121	
PIR3	RC2IF	TX2IF	RC1IF	TX1IF	BCL2IF	SSP2IF	BCL1IF	SSP1IF	133	
PIE3	RC2IE	TX2IE	RC1IE	TX1IE	BCL2IE	SSP2IE	BCL1IE	SSP1IE	125	
SSP1STAT	SMP	CKE	D/A	Р	S	R/W	UA	BF	417	
SSP1CON1	WCOL	SSPOV	SSPEN	CKP		SSPM	<3:0>		418	
SSP1CON2	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN	419	
SSP1CON3	ACKTIM	PCIE	SCIE	BOEN	SDAHT	SBCDE	AHEN	DHEN	417	
SSP1MSK	SSPMSK<7:0>									
SSP1ADD	SSPADD<7:0>									
SSP1BUF	SSPBUF<7:0>									
SSP2STAT	SMP	CKE	D/A	Р	S	R/W	UA	BF	417	
SSP2CON1	WCOL	SSPOV	SSPEN	CKP		SSPM	<3:0>		418	
SSP2CON2	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN	419	
SSP2CON3	ACKTIM	PCIE	SCIE	BOEN	SDAHT	SBCDE	AHEN	DHEN	417	
SSP2MSK				SSPMS	K<7:0>				421	
SSP2ADD				SSPAD	D<7:0>			A)	421	
SSP2BUF	88			SSPBU	JF<7:0>				422	
SSP1CLKPPS	<i>—</i> ∂	_			SSP1CLK	PPS<5:0>			199	
SSP1DATPPS	_				SSP1DATI	PPS<5:0>			199	
SSP1SSPPS	19—1	-			SSP1SSF	PS<5:0>			199	
SSP2CLKPPS	1	-			SSP2CLK	PPS<5:0>			199	
SSP2DATPPS	_	-			SSP2DAT	PPS<5:0>			199	
SSP2SSPPS	—-ii	-			SSP2SSF	PS<5:0>			199	
RxyPPS		_			F	RxyPPS<4:0>	4		200	

Legend: — = Unimplemented location, read as '0'. Shaded cells are not used by the MSSPx module

Note 1: When using designated I<sup>2</sup>C pins, the associated pin values in INLVLx will be ignored.

# 33.0 ENHANCED UNIVERSAL SYNCHRONOUS ASYNCHRONOUS RECEIVER TRANSMITTER (EUSART)

The Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART) module is a serial I/O communications peripheral. It contains all the clock generators, shift registers and data buffers necessary to perform an input or output serial data transfer independent of device program execution. The EUSART, also known as a Serial Communications Interface (SCI), can be configured as a full-duplex asynchronous system or half-duplex synchronous system. Full-Duplex mode is useful communications with peripheral systems, such as CRT terminals and personal computers. Half-Duplex Synchronous mode is intended for communications with peripheral devices, such as A/D or D/A integrated circuits, serial EEPROMs or other microcontrollers. These devices typically do not have internal clocks for baud rate generation and require the external clock signal provided by a host synchronous device.

Note: Two identical EUSART modules are implemented on this device, EUSART1 and EUSART2. All references to EUSART1 apply to EUSART2 as well.

The EUSART module includes the following capabilities:

- · Full-duplex asynchronous transmit and receive
- Two-character input buffer
- · One-character output buffer
- · Programmable 8-bit or 9-bit character length
- · Address detection in 9-bit mode
- · Input buffer overrun error detection
- · Received character framing error detection
- · Half-duplex synchronous host
- · Half-duplex synchronous client
- Programmable clock polarity in synchronous modes
- Sleep operation

The EUSART module implements the following additional features, making it ideally suited for use in Local Interconnect Network (LIN) bus systems:


- · Automatic detection and calibration of the baud rate
- · Wake-up on Break reception
- · 13-bit Break character transmit

Block diagrams of the EUSART transmitter and receiver are shown in Figure 33-1 and Figure 33-2.

The EUSART transmit output (TX\_out) is available to the TX/CK pin and internally to the following peripherals:

Configurable Logic Cell (CLC)

## FIGURE 33-1: EUSART TRANSMIT BLOCK DIAGRAM






FIGURE 33-2: **EUSART RECEIVE BLOCK DIAGRAM** 

The operation of the EUSART module is controlled through three registers:

- Transmit Status and Control (TXxSTA)
- · Receive Status and Control (RCxSTA)
- Baud Rate Control (BAUDxCON)

These registers are detailed in Register 33-1, Register 33-2 and Register 33-3, respectively.

The RX input pin is selected with the RXxPPS. The CK input is selected with the TXxPPS register. TX, CK, and DT output pins are selected with each pin's RxyPPS register. Since the RX input is coupled with the DT output in Synchronous mode, it is the user's responsibility to select the same pin for both of these functions when operating in Synchronous mode. The EUSART control logic will control the data direction drivers automatically.

## 33.1 EUSART Asynchronous Mode

The EUSART transmits and receives data using the standard non-return-to-zero (NRZ) format. NRZ is implemented with two levels: a VOH Mark state which represents a '1' data bit, and a Vol Space state which represents a '0' data bit. NRZ refers to the fact that consecutively transmitted data bits of the same value stay at the output level of that bit without returning to a neutral level between each bit transmission. An NRZ transmission port idles in the Mark state. Each character transmission consists of one Start bit followed by eight or nine data bits and is always terminated by one or more Stop bits. The Start bit is always a space and the Stop bits are always marks. The most common data format is eight bits. Each transmitted bit persists for a period of 1/(Baud Rate). An on-chip dedicated 8-bit/16bit Baud Rate Generator is used to derive standard baud rate frequencies from the system oscillator. See Table 33-3 for examples of baud rate configurations.

The EUSART transmits and receives the LSb first. The EUSART's transmitter and receiver are functionally independent, but share the same data format and baud rate. Parity is not supported by the hardware, but can be implemented in software and stored as the ninth data bit.

# 33.1.1 EUSART ASYNCHRONOUS TRANSMITTER

The EUSART transmitter block diagram is shown in Figure 33-1. The heart of the transmitter is the serial Transmit Shift Register (TSR), which is not directly accessible by software. The TSR obtains its data from the transmit buffer, which is the TXxREG register.

### 33.1.1.1 Enabling the Transmitter

The EUSART transmitter is enabled for asynchronous operations by configuring the following three control bits:

- TXEN = 1
- SYNC = 0
- SPEN = 1

All other EUSART control bits are assumed to be in their default state.

Setting the TXEN bit of the TXxSTA register enables the transmitter circuitry of the EUSART. Clearing the SYNC bit of the TXxSTA register configures the EUSART for asynchronous operation. Setting the SPEN bit of the RCxSTA register enables the EUSART and automatically configures the TX/CK I/O pin as an output. If the TX/CK pin is shared with an analog peripheral, the analog I/O function must be disabled by clearing the corresponding ANSEL bit.

Note: The TXxIF Transmitter Interrupt flag is set when the TXEN enable bit is set.

### 33.1.1.2 Transmitting Data

A transmission is initiated by writing a character to the TXxREG register. If this is the first character, or the previous character has been completely flushed from the TSR, the data in the TXxREG is immediately transferred to the TSR register. If the TSR still contains all or part of a previous character, the new character data is held in the TXxREG until the Stop bit of the previous character has been transmitted. The pending character in the TXxREG is then transferred to the TSR in one Tcy immediately following the Stop bit transmission. The transmission of the Start bit, data bits and Stop bit sequence commences immediately following the transfer of the data to the TSR from the TXxREG.

### 33.1.1.3 Transmit Data Polarity

The polarity of the transmit data can be controlled with the SCKP bit of the BAUDxCON register. The default state of this bit is '0' which selects high true transmit Idle and data bits. Setting the SCKP bit to '1' will invert the transmit data resulting in low true Idle and data bits. The SCKP bit controls transmit data polarity in Asynchronous mode only. In Synchronous mode, the SCKP bit has a different function. See Section 33.4.1.2 "Clock Polarity".

### 33.1.1.4 Transmit Interrupt Flag

The TXxIF interrupt flag bit of the PIR3 register is set whenever the EUSART transmitter is enabled and no character is being held for transmission in the TXxREG. In other words, the TXxIF bit is only clear when the TSR is busy with a character and a new character has been queued for transmission in the TXxREG. The TXxIF flag bit is not cleared immediately upon writing TXxREG. TXxIF becomes valid in the second instruction cycle following the write execution. Polling TXxIF immediately following the TXxREG write will return invalid results. The TXxIF bit is read-only, it cannot be set or cleared by

The TXxIF interrupt can be enabled by setting the TXxIE interrupt enable bit of the PIE3 register. However, the TXxIF flag bit will be set whenever the TXxREG is empty, regardless of the state of TXxIE enable bit.

To use interrupts when transmitting data, set the TXxIE bit only when there is more data to send. Clear the TXxIE interrupt enable bit upon writing the last character of the transmission to the TXxREG.

### 33.1.1.5 TSR Status

The TRMT bit of the TXxSTA register indicates the status of the TSR register. This is a read-only bit. The TRMT bit is set when the TSR register is empty and is cleared when a character is transferred to the TSR register from the TXxREG. The TRMT bit remains clear until all bits have been shifted out of the TSR register. No interrupt logic is tied to this bit, so the user has to poll this bit to determine the TSR status.

Note: The TSR register is not mapped in data memory, so it is not available to the user.

## 33.1.1.6 Transmitting 9-Bit Characters


The EUSART supports 9-bit character transmissions. When the TX9 bit of the TXxSTA register is set, the EUSART will shift nine bits out for each character transmitted. The TX9D bit of the TXxSTA register is the ninth, and Most Significant data bit. When transmitting 9-bit data, the TX9D data bit must be written before writing the eight Least Significant bits into the TXxREG. All nine bits of data will be transferred to the TSR shift register immediately after the TXxREG is written.

A special 9-bit Address mode is available for use with multiple receivers. See Section 33.1.2.7 "Address Detection" for more information on the Address mode.


### 33.1.1.7 Asynchronous Transmission Setup:

- Initialize the SPxBRGH, SPxBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see Section 33.3 "EUSART Baud Rate Generator (BRG)").
- Enable the asynchronous serial port by clearing the SYNC bit and setting the SPEN bit.
- If 9-bit transmission is desired, set the TX9 control bit. A set ninth data bit will indicate that the eight Least Significant data bits are an address when the receiver is set for address detection.
- Set SCKP bit if inverted transmit is desired.
- Enable the transmission by setting the TXEN control bit. This will cause the TXxIF interrupt bit to be set.
- If interrupts are desired, set the TXxIE interrupt enable bit of the PIE3 register. An interrupt will occur immediately provided that the GIE and PEIE bits of the INTCON register are also set.
- If 9-bit transmission is selected, the ninth bit may be loaded into the TX9D data bit.
- Load 8-bit data into the TXxREG register. This will start the transmission.





### FIGURE 33-4: ASYNCHRONOUS TRANSMISSION (BACK-TO-BACK)



# 33.1.2 EUSART ASYNCHRONOUS RECEIVER

The Asynchronous mode is typically used in RS-232 systems. The receiver block diagram is shown in Figure 33-2. The data is received on the RX/DT pin and drives the data recovery block. The data recovery block is actually a high-speed shifter operating at 16 times the baud rate, whereas the serial Receive Shift Register (RSR) operates at the bit rate. When all eight or nine bits of the character have been shifted in, they are immediately transferred to a two character First-In-First-Out (FIFO) memory. The FIFO buffering allows reception of two complete characters and the start of a third character before software must start servicing the EUSART receiver. The FIFO and RSR registers are not directly accessible by software. Access to the received data is via the RCxREG register.

# 33.1.2.1 Enabling the Receiver

The EUSART receiver is enabled for asynchronous operation by configuring the following three control bits:

- CREN = 1
- SYNC = 0
- SPEN = 1

All other EUSART control bits are assumed to be in their default state.

Setting the CREN bit of the RCxSTA register enables the receiver circuitry of the EUSART. Clearing the SYNC bit of the TXxSTA register configures the EUSART for asynchronous operation. Setting the SPEN bit of the RCxSTA register enables the EUSART. The programmer must set the corresponding TRIS bit to configure the RX/DT I/O pin as an input.

Note: If the RX/DT function is on an analog pin, the corresponding ANSEL bit must be cleared for the receiver to function.

### 33.1.2.2 Receiving Data

The receiver data recovery circuit initiates character reception on the falling edge of the first bit. The first bit, also known as the Start bit, is always a zero. The data recovery circuit counts one-half bit time to the center of the Start bit and verifies that the bit is still a zero. If it is not a zero then the data recovery circuit aborts character reception, without generating an error, and resumes looking for the falling edge of the Start bit. If the Start bit zero verification succeeds then the data recovery circuit counts a full bit time to the center of the next bit. The bit is then sampled by a majority detect circuit and the resulting '0' or '1' is shifted into the RSR. This repeats until all data bits have been sampled and shifted into the RSR. One final bit time is measured and the level sampled. This is the Stop bit, which is always a '1'. If the data recovery circuit samples a '0' in the Stop bit position then a framing error is set for this character, otherwise the framing error is cleared for this character. See Section 33.1.2.4 "Receive Framing Error" for more information on framing errors.

Immediately after all data bits and the Stop bit have been received, the character in the RSR is transferred to the EUSART receive FIFO and the RXxIF interrupt flag bit of the PIR3 register is set. The top character in the FIFO is transferred out of the FIFO by reading the RCxREG register.

Note: If the receive FIFO is overrun, no additional characters will be received until the overrun condition is cleared. See Section 33.1.2.5 "Receive Overrun Error" for more information on overrun errors.

### 33.1.2.3 Receive Interrupts

The RXxIF interrupt flag bit of the PIR3 register is set whenever the EUSART receiver is enabled and there is an unread character in the receive FIFO. The RXxIF interrupt flag bit is read-only, it cannot be set or cleared by software.

RXxIF interrupts are enabled by setting all of the following bits:

- RXxIE, Interrupt Enable bit of the PIE3 register
- PEIE, Peripheral Interrupt Enable bit of the INTCON register
- GIE, Global Interrupt Enable bit of the INTCON register

The RXxIF interrupt flag bit will be set when there is an unread character in the FIFO, regardless of the state of interrupt enable bits.

## 33.1.2.4 Receive Framing Error

Each character in the receive FIFO buffer has a corresponding framing error Status bit. A framing error indicates that a Stop bit was not seen at the expected time. The framing error status is accessed via the FERR bit of the RCxSTA register. The FERR bit represents the status of the top unread character in the receive FIFO. Therefore, the FERR bit must be read before reading the RCxREG.

The FERR bit is read-only and only applies to the top unread character in the receive FIFO. A framing error (FERR = 1) does not preclude reception of additional characters. It is not necessary to clear the FERR bit. Reading the next character from the FIFO buffer will advance the FIFO to the next character and the next corresponding framing error.

The FERR bit can be forced clear by clearing the SPEN bit of the RCxSTA register which resets the EUSART. Clearing the CREN bit of the RCxSTA register does not affect the FERR bit. A framing error by itself does not generate an interrupt.

Note: If all receive characters in the receive FIFO have framing errors, repeated reads of the RCxREG will not clear the FERR bit.

### 33.1.2.5 Receive Overrun Error

The receive FIFO buffer can hold two characters. An overrun error will be generated if a third character, in its entirety, is received before the FIFO is accessed. When this happens the OERR bit of the RCxSTA register is set. The characters already in the FIFO buffer can be read but no additional characters will be received until the error is cleared. The error must be cleared by either clearing the CREN bit of the RCxSTA register or by resetting the EUSART by clearing the SPEN bit of the RCxSTA register.

### 33.1.2.6 Receiving 9-Bit Characters

The EUSART supports 9-bit character reception. When the RX9 bit of the RCxSTA register is set the EUSART will shift nine bits into the RSR for each character received. The RX9D bit of the RCxSTA register is the ninth and Most Significant data bit of the top unread character in the receive FIFO. When reading 9-bit data from the receive FIFO buffer, the RX9D data bit must be read before reading the eight Least Significant bits from the RCxREG.

### 33.1.2.7 Address Detection

A special Address Detection mode is available for use when multiple receivers share the same transmission line, such as in RS-485 systems. Address detection is enabled by setting the ADDEN bit of the RCxSTA register.

Address detection requires 9-bit character reception. When address detection is enabled, only characters with the ninth data bit set will be transferred to the receive FIFO buffer, thereby setting the RXxIF interrupt bit. All other characters will be ignored.

Upon receiving an address character, user software determines if the address matches its own. Upon address match, user software must disable address detection by clearing the ADDEN bit before the next Stop bit occurs. When user software detects the end of the message, determined by the message protocol used, software places the receiver back into the Address Detection mode by setting the ADDEN bit.

### 33.1.2.8 Asynchronous Reception Setup:


- Initialize the SPxBRGH, SPxBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see Section 33.3 "EUSART Baud Rate Generator (BRG)").
- 2. Clear the ANSEL bit for the RX pin (if applicable).
- Enable the serial port by setting the SPEN bit. The SYNC bit must be clear for asynchronous operation.
- If interrupts are desired, set the RXxIE bit of the PIE3 register and the GIE and PEIE bits of the INTCON register.
- If 9-bit reception is desired, set the RX9 bit.
- 6. Enable reception by setting the CREN bit.
- The RXxIF interrupt flag bit will be set when a character is transferred from the RSR to the receive buffer. An interrupt will be generated if the RXxIE interrupt enable bit was also set.
- Read the RCxSTA register to get the error flags and, if 9-bit data reception is enabled, the ninth data bit.
- Get the received eight Least Significant data bits from the receive buffer by reading the RCxREG register.
- If an overrun occurred, clear the OERR flag by clearing the CREN receiver enable bit.

### 33.1.2.9 9-bit Address Detection Mode Setup

This mode is typically used in RS-485 systems. To set up an Asynchronous Reception with Address Detect Enable:

- Initialize the SPxBRGH, SPxBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see Section 33.3 "EUSART Baud Rate Generator (BRG)").
- Clear the ANSEL bit for the RX pin (if applicable).
- Enable the serial port by setting the SPEN bit. The SYNC bit must be clear for asynchronous operation.
- If interrupts are desired, set the RXxIE bit of the PIE3 register and the GIE and PEIE bits of the INTCON register.
- Enable 9-bit reception by setting the RX9 bit.
- Enable address detection by setting the ADDEN bit.
- 7. Enable reception by setting the CREN bit.
- The RXxIF interrupt flag bit will be set when a character with the ninth bit set is transferred from the RSR to the receive buffer. An interrupt will be generated if the RXxIE interrupt enable bit was also set.
- Read the RCxSTA register to get the error flags.
   The ninth data bit will always be set.
- Get the received eight Least Significant data bits from the receive buffer by reading the RCxREG register. Software determines if this is the device's address
- If an overrun occurred, clear the OERR flag by clearing the CREN receiver enable bit.
- If the device has been addressed, clear the ADDEN bit to allow all received data into the receive buffer and generate interrupts.





# 33.2 Clock Accuracy with Asynchronous Operation

The factory calibrates the internal oscillator block output (INTOSC). However, the HFINTOSC frequency may drift as VDD or temperature changes, and this directly affects the asynchronous baud rate. Two methods may be used to adjust the baud rate clock, but both require a reference clock source of some kind.

The first (preferred) method uses the OSCTUNE register to adjust the HFINTOSC output. Adjusting the value in the OSCTUNE register allows for fine resolution changes to the system clock source. See Section 9.2.2.2 "Internal Oscillator Frequency Adjustment" for more information.

The other method adjusts the value in the Baud Rate Generator. This can be done automatically with the Auto-Baud Detect feature (see Section 33.3.1 "Auto-Baud Detect"). There may not be fine enough resolution when adjusting the Baud Rate Generator to compensate for a gradual change in the peripheral clock frequency.

# 33.3 EUSART Baud Rate Generator (BRG)

The Baud Rate Generator (BRG) is an 8-bit or 16-bit timer that is dedicated to the support of both the asynchronous and synchronous EUSART operation. By default, the BRG operates in 8-bit mode. Setting the BRG16 bit of the BAUDxCON register selects 16-bit mode.

The SPxBRGH, SPxBRGL register pair determines the period of the free running baud rate timer. In Asynchronous mode the multiplier of the baud rate period is determined by both the BRGH bit of the TXxSTA register and the BRG16 bit of the BAUDxCON register. In Synchronous mode, the BRGH bit is ignored.

Table 33-1 contains the formulas for determining the baud rate. Example 33-1 provides a sample calculation for determining the baud rate and baud rate error.

Typical baud rates and error values for various Asynchronous modes have been computed for the user's convenience and are shown in Table 33-3. It may be advantageous to use the high baud rate (BRGH = 1), or the 16-bit BRG (BRG16 = 1) to reduce the baud rate error. The 16-bit BRG mode is used to achieve slow baud rates for fast oscillator frequencies.

Writing a new value to the SPxBRGH, SPxBRGL register pair causes the BRG timer to be reset (or cleared). This ensures that the BRG does not wait for a timer overflow before outputting the new baud rate.

If the system clock is changed during an active receive operation, a receive error or data loss may result. To avoid this problem, check the status of the RCIDL bit to make sure that the receive operation is Idle before changing the system clock.

### EXAMPLE 33-1: CALCULATING BAUD RATE ERROR

For a device with Fosc of 16 MHz, desired baud rate of 9600, Asynchronous mode, 8-bit BRG:

Desired Baud Rate = 
$$\frac{FOSC}{64([SPBRGH:SPBRGL] + 1)}$$

Solving for SPxBRGH:SPxBRGL:

Solving for SPXBRGH. SPXBRGL. 
$$X = \frac{Fosc}{\frac{Desired Baud Rate}{64}} - 1$$

$$= \frac{\frac{16000000}{9600}}{\frac{9600}{64}} - 1$$

$$= [25.042] = 25$$

$$Calculated Baud Rate = \frac{16000000}{64(25+1)}$$

$$= 9615$$

$$Error = \frac{Calc. Baud Rate - Desired Baud Rate}{Desired Baud Rate}$$

$$= \frac{(9615 - 9600)}{\frac{9600}{64}} = 0.16\%$$

9600

#### 33.3.1 AUTO-BAUD DETECT

The EUSART module supports automatic detection and calibration of the baud rate.

In the Auto-Baud Detect (ABD) mode, the clock to the BRG is reversed. Rather than the BRG clocking the incoming RX signal, the RX signal is timing the BRG. The Baud Rate Generator is used to time the period of a received 55h (ASCII "U") which is the Sync character for the LIN bus. The unique feature of this character is that it has five rising edges including the Stop bit edge.

Setting the ABDEN bit of the BAUDxCON register starts the auto-baud calibration sequence. While the ABD sequence takes place, the EUSART state machine is held in Idle. On the first rising edge of the receive line, after the Start bit, SPxBRG begins counting up using the BRG counter clock as shown in Figure 33-6. The fifth rising edge will occur on the RX pin at the end of the eighth bit period. At that time, an accumulated value totaling the proper BRG period is left in the SPxBRGH, SPxBRGL register pair, the ABDEN bit is automatically cleared and the RXxIF interrupt flag is set. The value in RCxREG needs to be read to clear the RXxIF interrupt. RCxREG content may be discarded. When calibrating for modes that do not use the SPxBRGH register the user can verify that the SPxBRGL register did not overflow by checking for 00h in the SPxBRGH register.

The BRG auto-baud clock is determined by the BRG16 and BRGH bits as shown in Table 33-1. During ABD, both the SPxBRGH and SPxBRGL registers are used as a 16-bit counter, independent of the BRG16 bit setting. While calibrating the baud rate period, the SPxBRGH and SPxBRGL registers are clocked at 1/

8th the BRG base clock rate. The resulting byte measurement is the average bit time when clocked at full speed.


- Note 1: If the WUE bit is set with the ABDEN bit, auto-baud detection will occur on the byte following the Break character (see Section 33.3.3 "Auto-Wake-up on Break").
  - 2: It is up to the user to determine that the incoming character baud rate is within the range of the selected BRG clock source. Some combinations of oscillator frequency and EUSART baud rates are not possible.
  - 3: During the auto-baud process, the auto-baud counter starts counting at one. Upon completion of the auto-baud sequence, to achieve maximum accuracy, subtract 1 from the SPxBRGH:SPxBRGL register pair.

TABLE 33-1: BRG COUNTER CLOCK RATES

BRG16	BRGH	BRG Base Clock	BRG ABD Clock
0	0	Fosc/64	Fosc/512
0	1	Fosc/16	Fosc/128
1	0	Fosc/16	Fosc/128
1	1	Fosc/4	Fosc/32

Note: During the ABD sequence, SPxBRGL and SPxBRGH registers are both used as a 16-bit counter, independent of the BRG16 setting.

FIGURE 33-6: AUTOMATIC BAUD RATE CALIBRATION



### 33.3.2 AUTO-BAUD OVERFLOW

During the course of automatic baud detection, the ABDOVF bit of the BAUDxCON register will be set if the baud rate counter overflows before the fifth rising edge is detected on the RX pin. The ABDOVF bit indicates that the counter has exceeded the maximum count that can fit in the 16 bits of the SPxBRGH:SPxBRGL register pair. The overflow condition will set the RXxIF flag. The counter continues to count until the fifth rising edge is detected on the RX pin. The RCIDL bit will remain false ('0') until the fifth rising edge at which time the RCIDL bit will be set. If the RCxREG is read after the overflow occurs but before the fifth rising edge then the fifth rising edge will set the RXxIF again.

Terminating the auto-baud process early to clear an overflow condition will prevent proper detection of the sync character fifth rising edge. If any falling edges of the sync character have not yet occurred when the ABDEN bit is cleared then those will be falsely detected as Start bits. The following steps are recommended to clear the overflow condition:

- Read RCxREG to clear RXxIF.
- If RCIDL is '0' then wait for RDCIF and repeat step 1.
- 3. Clear the ABDOVF bit.

### 33.3.3 AUTO-WAKE-UP ON BREAK

During Sleep mode, all clocks to the EUSART are suspended. Because of this, the Baud Rate Generator is inactive and a proper character reception cannot be performed. The Auto-Wake-up feature allows the controller to wake-up due to activity on the RX/DT line. This feature is available only in Asynchronous mode.

The Auto-Wake-up feature is enabled by setting the WUE bit of the BAUDxCON register. Once set, the normal receive sequence on RX/DT is disabled, and the EUSART remains in an Idle state, monitoring for a wake-up event independent of the CPU mode. A wake-up event consists of a high-to-low transition on the RX/DT line. (This coincides with the start of a Sync Break or a wake-up signal character for the LIN protocol.)

The EUSART module generates an RXxIF interrupt coincident with the wake-up event. The interrupt is generated synchronously to the Q clocks in normal CPU operating modes (Figure 33-7), and asynchronously if the device is in Sleep mode (Figure 33-8). The interrupt condition is cleared by reading the RCxREG register.

The WUE bit is automatically cleared by the low-to-high transition on the RX line at the end of the Break. This signals to the user that the Break event is over. At this point, the EUSART module is in Idle mode waiting to receive the next character.

#### 33.3.3.1 Special Considerations

#### **Break Character**

To avoid character errors or character fragments during a wake-up event, the wake-up character must be all zeros.

When the wake-up is enabled the function works independent of the low time on the data stream. If the WUE bit is set and a valid nonzero character is received, the low time from the Start bit to the first rising edge will be interpreted as the wake-up event. The remaining bits in the character will be received as a fragmented character and subsequent characters can result in framing or overrun errors.

Therefore, the initial character in the transmission must be all '0's. This must be ten or more bit times, 13-bit times recommended for LIN bus, or any number of bit times for standard RS-232 devices.

#### Oscillator Start-up Time


Oscillator start-up time must be considered, especially in applications using oscillators with longer start-up intervals (i.e., LP, XT or HS/PLL mode). The Sync Break (or wake-up signal) character must be of sufficient length, and be followed by a sufficient interval, to allow enough time for the selected oscillator to start and provide proper initialization of the EUSART.

#### **WUE Bit**


The wake-up event causes a receive interrupt by setting the RXxIF bit. The WUE bit is cleared in hardware by a rising edge on RX/DT. The interrupt condition is then cleared in software by reading the RCxREG register and discarding its contents.

To ensure that no actual data is lost, check the RCIDL bit to verify that a receive operation is not in process before setting the WUE bit. If a receive operation is not occurring, the WUE bit may then be set just prior to entering the Sleep mode.

### FIGURE 33-7: AUTO-WAKE-UP (WUE) BIT TIMING DURING NORMAL OPERATION



### FIGURE 33-8: AUTO-WAKE-UP (WUE) BIT TIMINGS DURING SLEEP



### 33.3.4 BREAK CHARACTER SEQUENCE

The EUSART module has the capability of sending the special Break character sequences that are required by the LIN bus standard. A Break character consists of a Start bit, followed by 12 '0' bits and a Stop bit.

To send a Break character, set the SENDB and TXEN bits of the TXxSTA register. The Break character transmission is then initiated by a write to the TXxREG. The value of data written to TXxREG will be ignored and all '0's will be transmitted.

The SENDB bit is automatically reset by hardware after the corresponding Stop bit is sent. This allows the user to preload the transmit FIFO with the next transmit byte following the Break character (typically, the Sync character in the LIN specification).

The TRMT bit of the TXxSTA register indicates when the transmit operation is Active or Idle, just as it does during normal transmission. See Figure 33-9 for the timing of the Break character sequence.

### 33.3.4.1 Break and Sync Transmit Sequence

The following sequence will start a message frame header made up of a Break, followed by an auto-baud Sync byte. This sequence is typical of a LIN bus host.

- Configure the EUSART for the desired mode.
- Set the TXEN and SENDB bits to enable the Break sequence.
- Load the TXxREG with a dummy character to initiate transmission (the value is ignored).
- Write '55h' to TXxREG to load the Sync character into the transmit FIFO buffer.
- After the Break has been sent, the SENDB bit is reset by hardware and the Sync character is then transmitted.

When the TXxREG becomes empty, as indicated by the TXxIF, the next data byte can be written to TXxREG.

### 33.3.5 RECEIVING A BREAK CHARACTER

The Enhanced EUSART module can receive a Break character in two ways.

The first method to detect a Break character uses the FERR bit of the RCxSTA register and the received data as indicated by RCxREG. The Baud Rate Generator is assumed to have been initialized to the expected baud rate


A Break character has been received when:

- RXxIF bit is set
- · FERR bit is set
- RCxREG = 00h

The second method uses the Auto-Wake-up feature described in Section 33.3.3 "Auto-Wake-up on Break". By enabling this feature, the EUSART will sample the next two transitions on RX/DT, cause an RXxIF interrupt, and receive the next data byte followed by another interrupt.

Note that following a Break character, the user will typically want to enable the Auto-Baud Detect feature. For both methods, the user can set the ABDEN bit of the BAUDxCON register before placing the EUSART in Sleep mode.

FIGURE 33-9: SEND BREAK CHARACTER SEQUENCE



### 33.4 EUSART Synchronous Mode

Synchronous serial communications are typically used in systems with a single host and one or more clients. The host device contains the necessary circuitry for baud rate generation and supplies the clock for all devices in the system. Client devices can take advantage of the host clock by eliminating the internal clock generation circuitry.

There are two signal lines in Synchronous mode: a bidirectional data line and a clock line. Clients use the external clock supplied by the host to shift the serial data into and out of their respective receive and transmit shift registers. Since the data line is bidirectional, synchronous operation is half-duplex only. Half-duplex refers to the fact that host and client devices can receive and transmit data but not both simultaneously. The EUSART can operate as either a host or client device.

Start and Stop bits are not used in synchronous transmissions.

#### 33.4.1 SYNCHRONOUS HOST MODE

The following bits are used to configure the EUSART for synchronous host operation:

- SYNC = 1
- CSRC = 1
- SREN = 0 (for transmit); SREN = 1 (for receive)
- CREN = 0 (for transmit); CREN = 1 (for receive)
- SPFN = 1

Setting the SYNC bit of the TXxSTA register configures the device for synchronous operation. Setting the CSRC bit of the TXxSTA register configures the device as a host. Clearing the SREN and CREN bits of the RCxSTA register ensures that the device is in the Transmit mode, otherwise the device will be configured to receive. Setting the SPEN bit of the RCxSTA register enables the EUSART.

### 33.4.1.1 Host Clock

Synchronous data transfers use a separate clock line, which is synchronous with the data. A device configured as a host transmits the clock on the TX/CK line. The TX/CK pin output driver is automatically enabled when the EUSART is configured for synchronous transmit or receive operation. Serial data bits change on the leading edge to ensure they are valid at the trailing edge of each clock. One clock cycle is generated for each data bit. Only as many clock cycles are generated as there are data bits.

### 33.4.1.2 Clock Polarity

A clock polarity option is provided for Microwire compatibility. Clock polarity is selected with the SCKP bit of the BAUDxCON register. Setting the SCKP bit sets the clock Idle state as high. When the SCKP bit is set, the data changes on the falling edge of each clock. Clearing the SCKP bit sets the Idle state as low. When the SCKP bit is cleared, the data changes on the rising edge of each clock.

### 33.4.1.3 Synchronous Host Transmission

Data is transferred out of the device on the RX/DT pin. The RX/DT and TX/CK pin output drivers are automatically enabled when the EUSART is configured for synchronous host transmit operation.

A transmission is initiated by writing a character to the TXxREG register. If the TSR still contains all or part of a previous character the new character data is held in the TXxREG until the last bit of the previous character has been transmitted. If this is the first character, or the previous character has been completely flushed from the TSR, the data in the TXxREG is immediately transferred to the TSR. The transmission of the character commences immediately following the transfer of the data to the TSR from the TXxREG.


Each data bit changes on the leading edge of the host clock and remains valid until the subsequent leading clock edge.

Note: The TSR register is not mapped in data memory, so it is not available to the user.


## 33.4.1.4 Synchronous Host Transmission Setup:

- Initialize the SPxBRGH, SPxBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see Section 33.3 "EUSART Baud Rate Generator (BRG)").
- Enable the synchronous host serial port by setting bits SYNC, SPEN and CSRC.
- Disable Receive mode by clearing bits SREN and CREN.
- 4. Enable Transmit mode by setting the TXEN bit.
- 5. If 9-bit transmission is desired, set the TX9 bit.
- If interrupts are desired, set the TXxIE bit of the PIE3 register and the GIE and PEIE bits of the INTCON register.
- If 9-bit transmission is selected, the ninth bit may be loaded in the TX9D bit.
- Start transmission by loading data to the TXxREG register.

### FIGURE 33-10: SYNCHRONOUS TRANSMISSION



### FIGURE 33-11: SYNCHRONOUS TRANSMISSION (THROUGH TXEN)



### 33.4.1.5 Synchronous Host Reception

Data is received at the RX/DT pin. The RX/DT pin output driver is automatically disabled when the EUSART is configured for synchronous host receive operation.

In Synchronous mode, reception is enabled by setting either the Single Receive Enable bit (SREN of the RCxSTA register) or the Continuous Receive Enable bit (CREN of the RCxSTA register).

When SREN is set and CREN is clear, only as many clock cycles are generated as there are data bits in a single character. The SREN bit is automatically cleared at the completion of one character. When CREN is set, clocks are continuously generated until CREN is cleared. If CREN is cleared in the middle of a character the CK clock stops immediately and the partial character is discarded. If SREN and CREN are both set, then SREN is cleared at the completion of the first character and CREN takes precedence.

To initiate reception, set either SREN or CREN. Data is sampled at the RX/DT pin on the trailing edge of the TX/CK clock pin and is shifted into the Receive Shift Register (RSR). When a complete character is received into the RSR, the RXxIF bit is set and the character is automatically transferred to the two character receive FIFO. The Least Significant eight bits of the top character in the receive FIFO are available in RCxREG. The RXxIF bit remains set as long as there are unread characters in the receive FIFO.

Note: If the RX/DT function is on an analog pin, the corresponding ANSEL bit must be cleared for the receiver to function.

#### 33.4.1.6 Client Clock

Synchronous data transfers use a separate clock line, which is synchronous with the data. A device configured as a client receives the clock on the TX/CK line. The TX/CK pin output driver is automatically disabled when the device is configured for synchronous client transmit or receive operation. Serial data bits change on the leading edge to ensure they are valid at the trailing edge of each clock. One data bit is transferred for each clock cycle. Only as many clock cycles may be received as there are data bits.

Note: If the device is configured as a client and the TX/CK function is on an analog pin, the corresponding ANSEL bit must be cleared.

### 33.4.1.7 Receive Overrun Error

The receive FIFO buffer can hold two characters. An overrun error will be generated if a third character, in its entirety, is received before RCxREG is read to access the FIFO. When this happens the OERR bit of the RCxSTA register is set. Previous data in the FIFO will not be overwritten. The two characters in the FIFO buffer can be read, however, no additional characters will be received until the error is cleared. The OERR bit can only be cleared by clearing the overrun condition. If the overrun error occurred when the SREN bit is set and CREN is clear then the error is cleared by reading RCxREG. If the overrun occurred when the CREN bit is set then the error condition is cleared by either clearing the CREN bit of the RCxSTA register or by clearing the SPEN bit which resets the EUSART.

### 33.4.1.8 Receiving 9-bit Characters


The EUSART supports 9-bit character reception. When the RX9 bit of the RCxSTA register is set the EUSART will shift nine bits into the RSR for each character

received. The RX9D bit of the RCxSTA register is the ninth, and Most Significant, data bit of the top unread character in the receive FIFO. When reading 9-bit data from the receive FIFO buffer, the RX9D data bit must be read before reading the eight Least Significant bits from the RCxREG.

### 33.4.1.9 Synchronous Host Reception Setup:

- Initialize the SPxBRGH, SPxBRGL register pair for the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- Clear the ANSEL bit for the RX pin (if applicable).
- Enable the synchronous host serial port by setting bits SYNC, SPEN and CSRC.
- 4. Ensure bits CREN and SREN are clear.
- If interrupts are desired, set the RXxIE bit of the PIE3 register and the GIE and PEIE bits of the INTCON register.
- 6. If 9-bit reception is desired, set bit RX9.
- Start reception by setting the SREN bit or for continuous reception, set the CREN bit.
- Interrupt flag bit RXxIF will be set when reception of a character is complete. An interrupt will be generated if the enable bit RXxIE was set.
- Read the RCxSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCxREG register.
- If an overrun error occurs, clear the error by either clearing the CREN bit of the RCxSTA register or by clearing the SPEN bit which resets the EUSART.





#### 33.4.2 SYNCHRONOUS CLIENT MODE

The following bits are used to configure the EUSART for synchronous client operation:

- SYNC = 1
- CSRC = 0
- SREN = 0 (for transmit); SREN = 1 (for receive)
- CREN = 0 (for transmit); CREN = 1 (for receive)
- SPEN = 1

Setting the SYNC bit of the TXxSTA register configures the device for synchronous operation. Clearing the CSRC bit of the TXxSTA register configures the device as a client. Clearing the SREN and CREN bits of the RCxSTA register ensures that the device is in the Transmit mode, otherwise the device will be configured to receive. Setting the SPEN bit of the RCxSTA register enables the EUSART.

### 33.4.2.1 EUSART Synchronous Client Transmit

The operation of the Synchronous Host and Client modes are identical (see Section 33.4.1.3 "Synchronous Host Transmission"), except in the case of the Sleep mode.

If two words are written to the TXxREG and then the SLEEP instruction is executed, the following will occur:

- The first character will immediately transfer to the TSR register and transmit.
- The second word will remain in the TXxREG register.
- 3. The TXxIF bit will not be set.
- After the first character has been shifted out of TSR, the TXxREG register will transfer the second character to the TSR and the TXxIF bit will now be set.
- If the PEIE and TXxIE bits are set, the interrupt will wake the device from Sleep and execute the next instruction. If the GIE bit is also set, the program will call the Interrupt Service Routine.

### 33.4.2.2 Synchronous Client Transmission Setup:

- Set the SYNC and SPEN bits and clear the CSRC bit.
- Clear the ANSEL bit for the CK pin (if applicable).
- 3. Clear the CREN and SREN bits.
- If interrupts are desired, set the TXxIE bit of the PIE3 register and the GIE and PEIE bits of the INTCON register.
- 5. If 9-bit transmission is desired, set the TX9 bit.
- 6. Enable transmission by setting the TXEN bit.
- If 9-bit transmission is selected, insert the Most Significant bit into the TX9D bit.
- Start transmission by writing the Least Significant eight bits to the TXxREG register.

### PIC16(L)F15354/55

### 33.4.2.3 EUSART Synchronous Client Reception

The operation of the Synchronous Host and Client modes is identical (Section 33.4.1.5 "Synchronous Host Reception"), with the following exceptions:

- Sleep
- CREN bit is always set, therefore the receiver is never Idle
- · SREN bit, which is a "don't care" in Client mode

A character may be received while in Sleep mode by setting the CREN bit prior to entering Sleep. Once the word is received, the RSR register will transfer the data to the RCxREG register. If the RXxIE enable bit is set, the interrupt generated will wake the device from Sleep and execute the next instruction. If the GIE bit is also set, the program will branch to the interrupt vector.

### 33.4.2.4 Synchronous Client Reception Setup:

- Set the SYNC and SPEN bits and clear the CSRC bit.
- Clear the ANSEL bit for both the CK and DT pins (if applicable).
- If interrupts are desired, set the RXxIE bit of the PIE3 register and the GIE and PEIE bits of the INTCON register.
- 4. If 9-bit reception is desired, set the RX9 bit.
- 5. Set the CREN bit to enable reception.
- The RXxIF bit will be set when reception is complete. An interrupt will be generated if the RXxIE bit was set.
- If 9-bit mode is enabled, retrieve the Most Significant bit from the RX9D bit of the RCxSTA register.
- Retrieve the eight Least Significant bits from the receive FIFO by reading the RCxREG register.
- If an overrun error occurs, clear the error by either clearing the CREN bit of the RCxSTA register or by clearing the SPEN bit which resets the EUSART.

### 33.5 EUSART Operation During Sleep

The EUSART will remain active during Sleep only in the Synchronous Client mode. All other modes require the system clock and therefore cannot generate the necessary signals to run the Transmit or Receive Shift registers during Sleep.

Synchronous Client mode uses an externally generated clock to run the Transmit and Receive Shift registers.

### 33.5.1 SYNCHRONOUS RECEIVE DURING SLEEP

To receive during Sleep, all the following conditions must be met before entering Sleep mode:

- RCxSTA and TXxSTA Control registers must be configured for Synchronous Client Reception (see Section 33.4.2.4 "Synchronous Client Reception Setup:").
- If interrupts are desired, set the RXxIE bit of the PIE3 register and the GIE and PEIE bits of the INTCON register.
- The RXxIF interrupt flag must be cleared by reading RCxREG to unload any pending characters in the receive buffer.

Upon entering Sleep mode, the device will be ready to accept data and clocks on the RX/DT and TX/CK pins, respectively. When the data word has been completely clocked in by the external device, the RXxIF interrupt flag bit of the PIR3 register will be set. Thereby, waking the processor from Sleep.

Upon waking from Sleep, the instruction following the SLEEP instruction will be executed. If the Global Interrupt Enable (GIE) bit of the INTCON register is also set, then the Interrupt Service Routine at address 004h will be called.

### 33.5.2 SYNCHRONOUS TRANSMIT DURING SLEEP

To transmit during Sleep, all the following conditions must be met before entering Sleep mode:

- The RCxSTA and TXxSTA Control registers must be configured for synchronous client transmission (see Section 33.4.2.2 "Synchronous Client Transmission Setup:").
- The TXxIF interrupt flag must be cleared by writing the output data to the TXxREG, thereby filling the TSR and transmit buffer.
- If interrupts are desired, set the TXxIE bit of the PIE3 register and the PEIE bit of the INTCON register.
- Interrupt enable bits TXxIE of the PIE3 register and PEIE of the INTCON register must set.

Upon entering Sleep mode, the device will be ready to accept clocks on TX/CK pin and transmit data on the RX/DT pin. When the data word in the TSR has been completely clocked out by the external device, the pending byte in the TXxREG will transfer to the TSR and the TXxIF flag will be set. Thereby, waking the processor from Sleep. At this point, the TXxREG is available to accept another character for transmission, which will clear the TXxIF flag.

Upon waking from Sleep, the instruction following the SLEEP instruction will be executed. If the Global Interrupt Enable (GIE) bit is also set then the Interrupt Service Routine at address 0004h will be called.

#### 33.6 Register Definitions: EUSART Control

#### REGISTER 33-1: TXxSTA: TRANSMIT STATUS AND CONTROL REGISTER

R/W-/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R-1/1	R/W-0/0
CSRC	TX9	TXEN <sup>(1)</sup>	SYNC	SENDB	BRGH	TRMT	TX9D
bit 7							bit 0

Legend: R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' u = Bit is unchanged -n/n = Value at POR and BOR/Value at all other Resets x = Bit is unknown '1' = Bit is set '0' = Bit is cleared

bit 7 CSRC: Clock Source Select bit

Asynchronous mode:

Unused in this mode - value ignored

Synchronous mode:

1 = Host mode (clock generated internally from BRG)

0 = Client mode (clock from external source)

bit 6 TX9: 9-bit Transmit Enable bit

> 1 = Selects 9-bit transmission 0 = Selects 8-bit transmission

TXEN: Transmit Enable bit (1) bit 5

> 1 = Transmit enabled 0 = Transmit disabled

bit 4 SYNC: EUSART Mode Select bit

> 1 = Synchronous mode 0 = Asynchronous mode

bit 3 SENDB: Send Break Character bit

Asynchronous mode:

1 = Send SYNCH BREAK on next transmission - Start bit, followed by 12 '0' bits, followed by Stop bit; cleared by hardware upon completion

0 = SYNCH BREAK transmission disabled or completed

Synchronous mode:

Unused in this mode - value ignored

bit 2 BRGH: High Baud Rate Select bit

> Asynchronous mode: 1 = High speed 0 = Low speed Synchronous mode:

Unused in this mode - value ignored

bit 1 TRMT: Transmit Shift Register Status bit

> 1 = TSR empty 0 = TSR full

bit 0 TX9D: Ninth bit of Transmit Data

Can be address/data bit or a parity bit.

Note 1: SREN/CREN overrides TXEN in Sync mode.

### REGISTER 33-2: RCxSTA: RECEIVE STATUS AND CONTROL REGISTER

R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R-0/0	R-0/0	R-0/0
SPEN <sup>(1)</sup>	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D
bit 7	, , , , , , , , , , , , , , , , , , ,	5	*				bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 SPEN: Serial Port Enable bit<sup>(1)</sup>

1 = Serial port enabled

0 = Serial port disabled (held in Reset)

bit 6 RX9: 9-Bit Receive Enable bit

1 = Selects 9-bit reception0 = Selects 8-bit reception

bit 5 SREN: Single Receive Enable bit

Asynchronous mode:

Unused in this mode - value ignored

Synchronous mode – Host: 1 = Enables single receive

0 = Disables single receive

This bit is cleared after reception is complete.

Synchronous mode - Client

Unused in this mode - value ignored

bit 4 CREN: Continuous Receive Enable bit

Asynchronous mode:

1 = Enables continuous receive until enable bit CREN is cleared

0 = Disables continuous receive

Synchronous mode:

1 = Enables continuous receive until enable bit CREN is cleared (CREN overrides SREN)

0 = Disables continuous receive

bit 3 ADDEN: Address Detect Enable bit

Asynchronous mode 9-bit (RX9 = 1):

1 = Enables address detection – enable interrupt and load of the receive buffer when the ninth bit in the receive buffer is set

0 = Disables address detection, all bytes are received and ninth bit can be used as parity bit

<u>Asynchronous mode 8-bit (RX9 = 0)</u>: Unused in this mode – value ignored

bit 2 FERR: Framing Error bit

1 = Framing error (can be updated by reading RCxREG register and receive next valid byte)

0 = No framing error

bit 1 OERR: Overrun Error bit

1 = Overrun error (can be cleared by clearing bit CREN)

0 = No overrun error

bit 0 RX9D: Ninth bit of Received Data

This can be address/data bit or a parity bit and must be calculated by user firmware.

Note 1: The EUSART module automatically changes the pin from tri-state to drive as needed. Configure the associated TRIS bits for TX/CK and RX/DT to 1.

### REGISTER 33-3: BAUDxCON: BAUD RATE CONTROL REGISTER

R/W-0/0	R-1/1	U-0	R/W-0/0	R/W-0/0	U-0	R/W-0/0	R/W-0/0
ABDOVF	RCIDL		SCKP	BRG16	62 <u>—-</u> 7)	WUE	ABDEN
bit 7	ž.	5-					bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 ABDOVF: Auto-Baud Detect Overflow bit

Asynchronous mode:

1 = Auto-baud timer overflowed 0 = Auto-baud timer did not overflow

Synchronous mode:

Don't care

bit 6 RCIDL: Receive Idle Flag bit

Asynchronous mode: 1 = Receiver is Idle

0 = Start bit has been received and the receiver is receiving

Synchronous mode:

Don't care

bit 5 Unimplemented: Read as '0'

bit 4 SCKP: Clock/Transmit Polarity Select bit

Asynchronous mode:

1 = Idle state for transmit (TX) is a low level 0 = Idle state for transmit (TX) is a high level

Synchronous mode:

1 = Idle state for clock (CK) is a high level 0 = Idle state for clock (CK) is a low level

bit 3 BRG16: 16-bit Baud Rate Generator bit

1 = 16-bit Baud Rate Generator is used 0 = 8-bit Baud Rate Generator is used

bit 2 Unimplemented: Read as '0' bit 1 WUE: Wake-up Enable bit

Asynchronous mode:

1 = USART will continue to sample the Rx pin – interrupt generated on falling edge; bit cleared in hardware on following rising edge.

0 = RX pin not monitored nor rising edge detected

Synchronous mode:

Unused in this mode – value ignored

bit 0 ABDEN: Auto-Baud Detect Enable bit

Asynchronous mode:

1 = Enable baud rate measurement on the next character – requires reception of a SYNCH field (55h):

cleared in hardware upon completion

0 = Baud rate measurement disabled or completed

Synchronous mode:

Unused in this mode - value ignored

### REGISTER 33-4: RCxREG<sup>(1)</sup>: RECEIVE DATA REGISTER

R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
			RCxRE	G<7:0>			
bit 7							bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-0 RCxREG<7:0>: Lower eight bits of the received data; read-only; see also RX9D (Register 33-2)

Note 1: RCxREG (including the 9<sup>th</sup> bit) is double buffered, and data is available while new data is being received.

### REGISTER 33-5: TXxREG<sup>(1)</sup>: TRANSMIT DATA REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
1000-0	10.00-0	10.00-0		G<7:0>	1000-0	10,00-0	1000-0
bit 7			<u></u>	ACCOUNTS DESCRIBED.			bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-0 TXxREG<7:0>: Lower eight bits of the received data; read-only; see also RX9D (Register 33-1)

Note 1: TXxREG (including the 9th bit) is double buffered, and can be written when previous data has started shifting.

### REGISTER 33-6: SPxBRGL<sup>(1)</sup>: BAUD RATE GENERATOR REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
			SPxBR	G<7:0>			
bit 7							bit 0

Legend:	2.0000	
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7-0 SPxBRG<7:0>: Lower eight bits of the Baud Rate Generator

Note 1: Writing to SP1BRG resets the BRG counter.

### REGISTER 33-7: SPxBRGH<sup>(1, 2)</sup>: BAUD RATE GENERATOR HIGH REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
			SPxBR	G<15:8>			
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 SPxBRG<15:8>: Upper eight bits of the Baud Rate Generator

Note 1: SPxBRGH value is ignored for all modes unless BAUDxCON<BRG16> is active.

2: Writing to SPxBRGH resets the BRG counter.

TABLE 33-2: SUMMARY OF REGISTERS ASSOCIATED WITH EUSART

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
INTCON	GIE	PEIE	_	-	1 <del></del> -	-	. <del></del>	INTEDG	121
PIE3	RC2IE	TX2IE	RC1IE	TX1IE	BCL2IE	SSP2IE	BCL1IE	SSP1IE	125
PIR3	RC2IF	TX2IF	RC1IF	TX1IF	BCL2IF	SSP2IF	BCL1IF	SSP1IF	133
RCxSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	443
TXxSTA	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	442
BAUDxCON	ABDOVF	RCIDL	_	SCKP	BRG16		WUE	ABDEN	444
RCxREG	EUSART Rec	eive Data Regis	ster						445*
TXxREG	EUSART Trai	nsmit Data Reg	gister						445*
SPxBRGL				SPxBR	G<7:0>			*	445*
SPxBRGH	2			SPxBR	G<15:8>				446*
RXPPS	-	_			RXPP	S<5:0>			199
CKPPS	s <del></del>	CXPPS<5:0>							
RxyPPS	× <u></u> -	_							
CLCxSELy	-	_			LCxDy	/S<5:0>			364

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used for the EUSART module.

Page with register information.

TABLE 33-3: BAUD RATE FORMULAS

C	Configuration Bit	ts		David Data Farmenta		
SYNC	BRG16	BRGH	BRG/EUSART Mode	Baud Rate Formula		
0	0	0	8-bit/Asynchronous	Fosc/[64 (n+1)]		
0	0	1	8-bit/Asynchronous	F#40 (4)1		
0	1	0	16-bit/Asynchronous	Fosc/[16 (n+1)]		
0	1	1	16-bit/Asynchronous			
1	0	x	8-bit/Synchronous	Fosc/[4 (n+1)]		
1	1	х	16-bit/Synchronous	and the same of th		

**Legend:** x = Don't care, n = value of SPxBRGH, SPxBRGL register pair.

TABLE 33-4: BAUD RATE FOR ASYNCHRONOUS MODES

					SYNC	= 0, BRGH	I = 0, BRC	G16 = 0					
BAUD	Fosc	Fosc = 32.000 MHz			Fosc = 20.000 MHz			Fosc = 18.432 MHz			Fosc = 11.0592 MHz		
RATE	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	
300			-	9	-		1 <del>1</del> -	1-1-1	·—	-	6 <del></del>	<del>5</del> 4	
1200	<del></del>		-	1221	1.73	255	1200	0.00	239	1200	0.00	143	
2400	2404	0.16	207	2404	0.16	129	2400	0.00	119	2400	0.00	71	
9600	9615	0.16	51	9470	-1.36	32	9600	0.00	29	9600	0.00	17	
10417	10417	0.00	47	10417	0.00	29	10286	-1.26	27	10165	-2.42	16	
19.2k	19.23k	0.16	25	19.53k	1.73	15	19.20k	0.00	14	19.20k	0.00	8	
57.6k	55.55k	-3.55	3		-	-	57.60k	0.00	7	57.60k	0.00	2	
115.2k	<u>=</u>	_	( <u>==</u> 5)	<u>1-1</u>	2-3	9 <del>1</del>	<u> </u>	( <u>—</u>	3	5 <del>-12</del>	<u></u>	<u>19-00</u>	

	SYNC = 0, BRGH = 0, BRG16 = 0												
BAUD	Fosc = 8.000 MHz			Fosc = 4.000 MHz			Fosc = 3.6864 MHz			Fosc = 1.000 MHz			
RATE	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	
300	<u>==</u> 8			300	0.16	207	300	0.00	191	300	0.16	51	
1200	1202	0.16	103	1202	0.16	51	1200	0.00	47	1202	0.16	12	
2400	2404	0.16	51	2404	0.16	25	2400	0.00	23	8 <del>2 - 18</del>	B	<del></del>	
9600	9615	0.16	12		-	-	9600	0.00	5	-	-	-	
10417	10417	0.00	11	10417	0.00	5	8 <u>48</u> 1	1 <u>5—2</u> 2	×	S <u>1118</u>	<u></u>	<u>15</u>	
19.2k	-	·	1 <del>2</del>	<del></del> -	<del></del>	0 <del></del>	19.20k	0.00	2	10 <del>1-10</del>	s <del>s</del>	-	
57.6k			_	_	2-0	( <u>)</u>	57.60k	0.00	0	102-123	Q <u>2—92</u>	<u> </u>	
115.2k	<del>83-3</del> 4		( <del>*****</del> )	<del></del>	<del>-</del>	2 <del>0 10</del>	· ·	( <del>= =</del>	85 83	88-39	-	100 mg/s	

TABLE 33-4: BAUD RATE FOR ASYNCHRONOUS MODES (CONTINUED)

					SYNC	C = 0, BRGH	1 = 1, BRC	316 = 0				
BAUD	Fosc	= 32.00	0 MHz	Fosc = 20.000 MHz			Fosc = 18.432 MHz			Fosc = 11.0592 MHz		
RATE	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)
300	55-54	·	5 <del>1. 1</del> 3	<del></del>	==4	22-37	8 <del></del>	(8-5)	82-30	24 <del>-37</del>	8-35	R-W
1200	<del></del>	_	-	<del></del> 3	-	8 <del></del>	12 <del>1 - 1</del>	i <del></del> -	-	6 <del></del>	i; <del></del>	<del></del> 3
2400	200		(2-2)	<u> 2000</u> 8	200	9 <u>1111</u>	<u> </u>	(2000)	-	22-27	N <del>-33</del>	<del>(6. 1</del> 6)
9600	9615	0.16	207	9615	0.16	129	9600	0.00	119	9600	0.00	71
10417	10417	0.00	191	10417	0.00	119	10378	-0.37	110	10473	0.53	65
19.2k	19.23k	0.16	103	19.23k	0.16	64	19.20k	0.00	59	19.20k	0.00	35
57.6k	57.14k	-0.79	34	56.82k	-1.36	21	57.60k	0.00	19	57.60k	0.00	11
115.2k	117.64k	2.12	16	113.64k	-1.36	10	115.2k	0.00	9	115.2k	0.00	5

					SYNC	= 0, BRGH	I = 1, BRG	S16 = 0					
BAUD	Fos	Fosc = 8.000 MHz			Fosc = 4.000 MHz			Fosc = 3.6864 MHz			Fosc = 1.000 MHz		
RATE	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	
300	22.27			<del></del> 8	5-1	8 <del>-18</del>	9 <del>7-53</del>	(5-5)	85 <del></del> 8	300	0.16	207	
1200	-	2	-	1202	0.16	207	1200	0.00	191	1202	0.16	51	
2400	2404	0.16	207	2404	0.16	103	2400	0.00	95	2404	0.16	25	
9600	9615	0.16	51	9615	0.16	25	9600	0.00	23	8 <u>===1</u>	9 <u></u>	<u>185—</u> 50	
10417	10417	0.00	47	10417	0.00	23	10473	0.53	21	10417	0.00	5	
19.2k	19231	0.16	25	19.23k	0.16	12	19.2k	0.00	11	10-12	9 <u></u>	<u>e</u> s	
57.6k	55556	-3.55	8	-	5	S <del>-11</del>	57.60k	0.00	3	0 <del></del>	8 <del>7 - 18</del>	<del></del>	
115.2k	<del></del>	_	-	-	-	_	115.2k	0.00	1	· —	-		

	SYNC = 0, BRGH = 0, BRG16 = 1													
BAUD	Fosc	Fosc = 32.000 MHz			Fosc = 20.000 MHz			Fosc = 18.432 MHz			Fosc = 11.0592 MHz			
RATE	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)		
300	300.0	0.00	6666	300.0	-0.01	4166	300.0	0.00	3839	300.0	0.00	2303		
1200	1200	-0.02	3332	1200	-0.03	1041	1200	0.00	959	1200	0.00	575		
2400	2401	-0.04	832	2399	-0.03	520	2400	0.00	479	2400	0.00	287		
9600	9615	0.16	207	9615	0.16	129	9600	0.00	119	9600	0.00	71		
10417	10417	0.00	191	10417	0.00	119	10378	-0.37	110	10473	0.53	65		
19.2k	19.23k	0.16	103	19.23k	0.16	64	19.20k	0.00	59	19.20k	0.00	35		
57.6k	57.14k	-0.79	34	56.818	-1.36	21	57.60k	0.00	19	57.60k	0.00	11		
115.2k	117.6k	2.12	16	113.636	-1.36	10	115.2k	0.00	9	115.2k	0.00	5		

TABLE 33-4: BAUD RATE FOR ASYNCHRONOUS MODES (CONTINUED)

					SYNC	C = 0, BRGH	I = 0, BRC	316 = 1				
BAUD	Fosc = 8.000 MHz			Fosc = 4.000 MHz			Fosc = 3.6864 MHz			Fosc = 1.000 MHz		
RATE	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)
300	299.9	-0.02	1666	300.1	0.04	832	300.0	0.00	767	300.5	0.16	207
1200	1199	-0.08	416	1202	0.16	207	1200	0.00	191	1202	0.16	51
2400	2404	0.16	207	2404	0.16	103	2400	0.00	95	2404	0.16	25
9600	9615	0.16	51	9615	0.16	25	9600	0.00	23	8 <del>2 - 8</del>	8 <del>1 - 1</del>	<del></del>
10417	10417	0.00	47	10417	0.00	23	10473	0.53	21	10417	0.00	5
19.2k	19.23k	0.16	25	19.23k	0.16	12	19.20k	0.00	11	lo <u>232</u>	9 <u></u>	<u></u> -1
57.6k	55556	-3.55	8	-	_	88-15	57.60k	0.00	3	2 <del>7 3</del>	·	<del></del>
115.2k	<del>20 - (</del> 3)	_	) <del></del> 0	<del></del> 3	-	8 <del>-18</del>	115.2k	0.00	1	a <del>- x</del>	-	<del></del> 3

				SYNC = 0	, BRGH	= 1, BRG16	= 1 or SY	NC = 1,	BRG16 = 1	79			
BAUD	Fosc	Fosc = 32.000 MHz			Fosc = 20.000 MHz			Fosc = 18.432 MHz			Fosc = 11.0592 MHz		
RATE	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	
300	300.0	0.00	26666	300.0	0.00	16665	300.0	0.00	15359	300.0	0.00	9215	
1200	1200	0.00	6666	1200	-0.01	4166	1200	0.00	3839	1200	0.00	2303	
2400	2400	0.01	3332	2400	0.02	2082	2400	0.00	1919	2400	0.00	1151	
9600	9604	0.04	832	9597	-0.03	520	9600	0.00	479	9600	0.00	287	
10417	10417	0.00	767	10417	0.00	479	10425	0.08	441	10433	0.16	264	
19.2k	19.18k	-0.08	416	19.23k	0.16	259	19.20k	0.00	239	19.20k	0.00	143	
57.6k	57.55k	-0.08	138	57.47k	-0.22	86	57.60k	0.00	79	57.60k	0.00	47	
115.2k	115.9k	0.64	68	116.3k	0.94	42	115.2k	0.00	39	115.2k	0.00	23	

		SYNC = 0, BRGH = 1, BRG16 = 1 or SYNC = 1, BRG16 = 1													
BAUD	Fos	Fosc = 8.000 MHz			Fosc = 4.000 MHz			Fosc = 3.6864 MHz			Fosc = 1.000 MHz				
RATE	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)			
300	300.0	0.00	6666	300.0	0.01	3332	300.0	0.00	3071	300.1	0.04	832			
1200	1200	-0.02	1666	1200	0.04	832	1200	0.00	767	1202	0.16	207			
2400	2401	0.04	832	2398	80.0	416	2400	0.00	383	2404	0.16	103			
9600	9615	0.16	207	9615	0.16	103	9600	0.00	95	9615	0.16	25			
10417	10417	0	191	10417	0.00	95	10473	0.53	87	10417	0.00	23			
19.2k	19.23k	0.16	103	19.23k	0.16	51	19.20k	0.00	47	19.23k	0.16	12			
57.6k	57.14k	-0.79	34	58.82k	2.12	16	57.60k	0.00	15	-	: <del></del>	<del>20-</del> 2			
115.2k	117.6k	2.12	16	111.1k	-3.55	8	115.2k	0.00	7	8-3	-	-			

# 34.0 REFERENCE CLOCK OUTPUT MODULE

The reference clock output module provides the ability to send a clock signal to the clock reference output pin (CLKR).

The reference clock output module has the following features:

- Selectable input clock
- Programmable clock divider
- · Selectable duty cycle

### 34.1 CLOCK SOURCE

The reference clock output module has a selectable clock source. The CLKRCLK register (Register 34-2) controls which input is used.

#### 34.1.1 CLOCK SYNCHRONIZATION

Once the reference clock enable (CLKREN) is set, the module is ensured to be glitch-free at start-up.

When the reference clock output is disabled, the output signal will be disabled immediately.

Clock dividers and clock duty cycles can be changed while the module is enabled, but glitches may occur on the output. To avoid possible glitches, clock dividers and clock duty cycles may be changed only when the CLKREN is clear.

## 34.2 PROGRAMMABLE CLOCK DIVIDER

The module takes the system clock input and divides it based on the value of the CLKRDIV<2:0> bits of the CLKRCON register (Register 34-1).

The following configurations can be made based on the CLKRDIV<2:0> bits:

- · Base clock value
- · Base clock value divided by 2
- Base clock value divided by 4
- Base clock value divided by 8
- Base clock value divided by 16
- Base clock value divided by 32
- Base clock value divided by 64
- Base clock value divided by 128

The clock divider values can be changed while the module is enabled; however, to prevent glitches on the output, the CLKRDIV<2:0> bits may only be changed when the module is disabled (CLKREN = 0).

### 34.3 SELECTABLE DUTY CYCLE

The CLKRDC<1:0> bits of the CLKRCON register can be used to modify the duty cycle of the output clock. A duty cycle of 25%, 50%, or 75% can be selected for all clock rates, with the exception of the undivided base Fosc value.


The duty cycle can be changed while the module is enabled; however, to prevent glitches on the output, the CLKRDC<1:0> bits may only be changed when the module is disabled (CLKREN = 0).

Note: The CLKRDC1 bit is reset to '1'. This makes the default duty cycle 50% and not 0%.


### 34.4 OPERATION IN SLEEP MODE

The reference clock output module clock is based on the system clock. When the device goes to Sleep, the module outputs will remain in their current state. This will have a direct effect on peripherals using the reference clock output as an input signal.

FIGURE 34-1: CLOCK REFERENCE BLOCK DIAGRAM



### FIGURE 34-2: CLOCK REFERENCE TIMING



### 34.5 Register Definition: Reference Clock Output Control

### REGISTER 34-1: CLKRCON: REFERENCE CLOCK CONTROL REGISTER

R/W-0/0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
CLKREN	_	·	CLKRD	C<1:0>	(	CLKRDIV<2:0>	>
bit 7		30		10	>		bit 0

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
u = Bit is unchanged	x = Bit is unknown	-n/n = Value at POR and BOR/Value at all other Resets
'1' = Bit is set	'0' = Bit is cleared	

bit 7	CLKREN: Reference Clock Module Enable bit							
	1 = Reference clock module enabled							
	0 = Reference clock module is disabled							
bit 6-5	Unimplemented: Read as '0'							
bit 4-3	CLKRDC<1:0>: Reference Clock Duty Cycle bits (1)							
	11 = Clock outputs duty cycle of 75%							
	10 = Clock outputs duty cycle of 50%							
	01 = Clock outputs duty cycle of 25%							
	00 = Clock outputs duty cycle of 0%							
bit 2-0	CLKRDIV<2:0>: Reference Clock Divider bits							
	111 = Base clock value divided by 128							
	110 = Base clock value divided by 64							
	101 = Base clock value divided by 32							
	100 = Base clock value divided by 16							
	011 = Base clock value divided by 8							
	010 = Base clock value divided by 4							
	001 = Base clock value divided by 2							
	000 = Base clock value							

Note 1: Bits are valid for reference clock divider values of two or larger, the base clock cannot be further divided.

### REGISTER 34-2: CLKRCLK: CLOCK REFERENCE CLOCK SELECTION REGISTER

U-0	U-0	U-0	U-0	R/W-0/0	R/W-0/0	R/W-0/0	R/W-0/0
· —	-	* <del>-</del> *	7		CLKRC	LK<3:0>	
bit 7	3n			nieki:			bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets '1' = Bit is set '0' = Bit is cleared

bit 7-4 Unimplemented: Read as '0' bit 3-0 CLKRCLK<3:0>: CLKR Input bits

Clock Selection
1111 = Reserved

•

1011 = Reserved

1010 = LC4 out

1001 = LC3\_out

1000 = LC2\_out

0111 = LC1\_out

0110 = NCO1\_out

0101 = SOSC

0100 = MFINTOSC (31.25 kHz)

0011 = MFINTOSC (500 kHz)

0010 = LFINTOSC

0001 = HFINTOSC

0000 = Fosc

### TABLE 34-1: SUMMARY OF REGISTERS ASSOCIATED WITH CLOCK REFERENCE OUTPUT

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Register on Page
CLKRCON	CLKREN	<del>-</del>	\ <del></del> \	CLKRE	C<1:0>	CLKRDIV<2:0>			453
CLKRCLK	_	-		-		454			
CLCxSELy	_			LCxDyS<5:0>					364
RxyPPS	-			RxyPPS<4:0>					200

Legend: — = unimplemented, read as '0'. Shaded cells are not used by the CLKR module.

# 35.0 IN-CIRCUIT SERIAL PROGRAMMING™ (ICSP™)

ICSP™ programming allows customers to manufacture circuit boards with unprogrammed devices. Programming can be done after the assembly process, allowing the device to be programmed with the most recent firmware or a custom firmware. Five pins are needed for ICSP™ programming:

- ICSPCLK
- ICSPDAT
- MCLR/VPP
- VDD
- Vss

In Program/Verify mode the program memory, User IDs and the Configuration Words are programmed through serial communications. The ICSPDAT pin is a bidirectional I/O used for transferring the serial data and the ICSPCLK pin is the clock input. For more information on ICSP™ refer to the "PIC16(L)F153XX Memory Programming Specification" (DS40001838).

### 35.1 High-Voltage Programming Entry Mode

The device is placed into High-Voltage Programming Entry mode by holding the ICSPCLK and ICSPDAT pins low then raising the voltage on MCLR/VPP to VIHH.

# 35.2 Low-Voltage Programming Entry Mode

The Low-Voltage Programming Entry mode allows the PIC® Flash MCUs to be programmed using VDD only, without high voltage. When the LVP bit of Configuration Words is set to '1', the low-voltage ICSP programming entry is enabled. To disable the Low-Voltage ICSP mode, the LVP bit must be programmed to '0'. The LVP bit can only be reprogrammed to '0' by using the High-Voltage Programming mode.

Entry into the Low-Voltage Programming Entry mode requires the following steps:

- 1. MCLR is brought to VIL.
- A 32-bit key sequence is presented on ICSPDAT, while clocking ICSPCLK.


Once the key sequence is complete,  $\overline{\text{MCLR}}$  must be held at V<sub>IL</sub> for as long as Program/Verify mode is to be maintained.

If low-voltage programming is enabled (LVP = 1), the  $\overline{\text{MCLR}}$  Reset function is automatically enabled and cannot be disabled. See **Section 8.5** "MCLR" for more information.

### 35.3 Common Programming Interfaces

Connection to a target device is typically done through an ICSP™ header. A commonly found connector on development tools is the RJ-11 in the 6P6C (6-pin, 6-connector) configuration. See Figure 35-1.

FIGURE 35-1: ICD RJ-11 STYLE CONNECTOR INTERFACE



Another connector often found in use with the PICkit™ programmers is a standard 6-pin header with 0.1 inch spacing. Refer to Figure 35-2.

For additional interface recommendations, refer to the specific device programmer manual prior to PCB design.

It is recommended that isolation devices be used to separate the programming pins from other circuitry. The type of isolation is highly dependent on the specific application and may include devices such as resistors, diodes, or even jumpers. See Figure 35-3 for more information.

FIGURE 35-2: PICkit™ PROGRAMMER STYLE CONNECTOR INTERFACE





FIGURE 35-3: TYPICAL CONNECTION FOR ICSP™ PROGRAMMING



### 36.0 INSTRUCTION SET SUMMARY

Each instruction is a 14-bit word containing the operation code (opcode) and all required operands. The opcodes are broken into three broad categories.

- Byte Oriented
- Bit Oriented
- · Literal and Control

The literal and control category contains the most varied instruction word format.

Table 36-3 lists the instructions recognized by the MPASM $^{\text{TM}}$  assembler.

All instructions are executed within a single instruction cycle, with the following exceptions, which may take two or three cycles:

- Subroutine entry takes two cycles (CALL, CALLW)
- Returns from interrupts or subroutines take two cycles (RETURN, RETLW, RETFIE)
- Program branching takes two cycles (GOTO, BRA, BRW, BTFSS, BTFSC, DECFSZ, INCSFZ)
- One additional instruction cycle will be used when any instruction references an indirect file register and the file select register is pointing to program memory.

One instruction cycle consists of 4 oscillator cycles; for an oscillator frequency of 4 MHz, this gives a nominal instruction execution rate of 1 MHz.

All instruction examples use the format '0xhh' to represent a hexadecimal number, where 'h' signifies a hexadecimal digit.

### 36.1 Read-Modify-Write Operations

Any instruction that specifies a file register as part of the instruction performs a Read-Modify-Write (R-M-W) operation. The register is read, the data is modified, and the result is stored according in either the working (W) register, or the originating file register, depending on the state of the destination designator 'd' (see Table 36-1 for more information). A read operation is performed on a register even if the instruction writes to that register.

TABLE 36-1: OPCODE FIELD DESCRIPTIONS

Field	Description
f	Register file address (0x00 to 0x7F)
W	Working register (accumulator)
b	Bit address within an 8-bit file register
k	Literal field, constant data or label
х	Don't care location (= 0 or 1).  The assembler will generate code with x = 0.  It is the recommended form of use for compatibility with all Microchip software tools.
d	Destination select; d = 0: store result in W, d = 1: store result in file register f.
n	FSR or INDF number. (0-1)
mm	Prepost increment-decrement mode selection

TABLE 36-2: ABBREVIATION DESCRIPTIONS

Field	Description
PC	Program Counter
TO	Time-Out bit
С	Carry bit
DC	Digit Carry bit
Z	Zero bit
PD	Power-Down bit

### 36.2 General Format for Instructions

TABLE 36-3: INSTRUCTION SET

	nonic,	Description	Cycles	14-Bit Opcode			Status	Notes	
Operands		Description		MSb			LSb	Affected	Notes
BYTE-ORIENTED FILE REGISTER OPERATIONS									
ADDWF	f, d	Add W and f	1	0.0	0111	dfff	ffff	C, DC, Z	2
ADDWFC	f, d	Add with Carry W and f	1	11	1101	dfff	ffff	C, DC, Z	2
ANDWF	f, d	AND W with f	1	00	0101	dfff	ffff	Z	2
ASRF	f, d	Arithmetic Right Shift	1	11	0111	dfff	ffff	C, Z	2
LSLF	f, d	Logical Left Shift	1	11	0101	dfff	ffff	C, Z	2
LSRF	f, d	Logical Right Shift	1	11	0110	dfff	ffff	C, Z	2
CLRF	f	Clear f	1	00	0001	lfff	ffff	Z	2
CLRW	- 100 - 100	Clear W	1	00	0001	0000	00xx	Z	
COMF	f, d	Complement f	1	00	1001	dfff	ffff	Z	2
DECF	f, d	Decrement f	1	00	0011	dfff	ffff	Z	2
INCF	f, d	Increment f	1	00	1010	dfff	ffff	Z	2
IORWF	f. d	Inclusive OR W with f	1	00	0100	dfff	ffff	Z	2
MOVE	f, d	Move f	1	0.0	1000		ffff	7	2
MOVWF	f	Move W to f	1	0.0	0000	1fff	ffff		2
RLF	f. d	Rotate Left f through Carry	1	00		dfff		C	2
RRF	f, d	Rotate Right f through Carry	1	00		dfff		C	2
SUBWF	f, d	Subtract W from f	l i	00		dfff		Paragraphic and	2
SUBWFB	f, d	Subtract with Borrow W from f	1	11		dfff			2
SWAPF	f, d	Swap nibbles in f	1	00	1110	dfff		0, 00, 2	2
XORWF	f, d	Exclusive OR W with f	11	00	0110	800 No. 100 No.	ffff	7	2
,,,,,,,,	., -	BYTE ORIENTED SKIF	OPERATION	ONS					-
DECFSZ	f, d	Decrement f, Skip if 0	1(2)	00	1011	dfff	ffff		1, 2
INCFSZ	f, d	Increment f, Skip if 0	1(2)	00	1111	dfff	ffff		1, 2
		BIT-ORIENTED FILE REGIS	STER OPER	RATION	IS		÷	8	7
BCF	f, b	Bit Clear f	1	01	00bb	bfff	ffff	£	2
BSF	f, b	Bit Set f	1	01	01bb	bfff	ffff	-	2
		BIT-ORIENTED SKIP	OPERATIO	NS					
BTFSC	f, b	Bit Test f, Skip if Clear	1 (2)	01	10bb	bfff			1, 2
BTFSS	f, b	Bit Test f, Skip if Set	1 (2)	01	11bb	bfff	ffff		1, 2
LITERAL C	PERATION	ONS							
ADDLW	k	Add literal and W	1	11	1110	kkkk	kkkk	C, DC, Z	-
ANDLW	k	AND literal with W	1	11	1001	kkkk	kkkk	Z	
IORLW	k	Inclusive OR literal with W	1	11	1000	kkkk	kkkk	Z	
MOVLB	k	Move literal to BSR	1	00	0001	01kk	kkkk		
MOVLP	k	Move literal to PCLATH	1	11	0001	1kkk	kkkk		
MOVLW	k	Move literal to W	1	11	0000	kkkk	kkkk		
SUBLW	k	Subtract W from literal	1	11	1100	kkkk	kkkk	C, DC, Z	
XORLW	k	Exclusive OR literal with W	1	11	1010	kkkk	kkkk	Z	

Note 1: If the Program Counter (PC) is modified, or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

<sup>2:</sup> If this instruction addresses an INDF register and the MSb of the corresponding FSR is set, this instruction will require one additional instruction cycle.

TABLE 36-3: INSTRUCTION SET (CONTINUED)

Mnemonic, Operands		Description		14-Bit Opcode				Status	12111
				MSb		LSb		Affected	Notes
		CONTROL OPERA	ATIONS						
BRA	k	Relative Branch	2	11	001k	kkkk	kkkk	-	
BRW	-	Relative Branch with W	2	00	0000	0000	1011		
CALL	k	Call Subroutine	2	10	0kkk	kkkk	kkkk		
CALLW		Call Subroutine with W	2	00	0000	0000	1010		
GOTO	k	Go to address	2	10	1kkk	kkkk	kkkk		
RETFIE	k	Return from interrupt	2	00	0000	0000	1001		
RETLW	k	Return with literal in W	2	11	0100	kkkk	kkkk		
RETURN	_	Return from Subroutine	2	00	0000	0000	1000		
		INHERENT OPER	ATIONS						
CLRWDT	===	Clear Watchdog Timer	1	00	0000	0110	0100	TO, PD	
NOP	<u></u>	No Operation	1	00	0000	0000	0000	že ili li	
RESET		Software device Reset	1	00	0000	0000	0001		
SLEEP	-	Go into Standby or Idle mode	1	00	0000	0110	0011	TO, PD	
TRIS	f	Load TRIS register with W	1	00	0000	0110	Offf		
		C-COMPILER OPT	IMIZED					•	
ADDFSR	n, k	Add Literal k to FSRn	1	11	0001	0nkk	kkkk		
MOVIW	n mm	Move Indirect FSRn to W with pre/post inc/dec	1	00	0000	0001	0nmm	Z	2, 3
		modifier, mm							50
	k[n]	Move INDFn to W, Indexed Indirect.	1	11	1111	0nkk	kkkk	Z	2
MOVWI	n mm	Move W to Indirect FSRn with pre/post inc/dec modifier, mm	1	00	0000	0001	1nmm		2, 3
	k[n]	Move W to INDFn, Indexed Indirect.	1	11	1111	1nkk	kkkk		2

Note 1:If the Program Counter (PC) is modified, or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

<sup>2:</sup> If this instruction addresses an INDF register and the MSb of the corresponding FSR is set, this instruction will require one additional instruction cycle.

<sup>3:</sup> See Section 36.3 "Instruction Descriptions" for detailed MOVIW and MOVWI instruction descriptions.

### 36.3 Instruction Descriptions

ADDFSR	Add Literal to FSRn			
Syntax:	[label]ADDFSR FSRn, k			
Operands:	$-32 \le k \le 31$ n $\in [0, 1]$			
Operation:	$FSR(n) + k \rightarrow FSR(n)$			
Status Affected:	None			
Description:	The signed 6-bit literal 'k' is added to the contents of the FSRnH:FSRnL register pair.			
	FSRn is limited to the range 0000h-			
	FFFFh. Moving beyond these bounds will cause the FSR to wrap-around.			

ANDLW	AND literal with W
Syntax:	[label] ANDLW k
Operands:	$0 \le k \le 255$
Operation:	(W) .AND. $(k) \rightarrow (W)$
Status Affected:	Z
Description:	The contents of W register are ANDed with the 8-bit literal 'k'. The result is placed in the W register.

ADDLW	Add literal and W			
Syntax:	[label] ADDLW k			
Operands:	$0 \le k \le 255$			
Operation:	$(W) + k \rightarrow (W)$			
Status Affected:	C, DC, Z			
Description:	The contents of the W register are added to the 8-bit literal 'k' and the result is placed in the W register.			

ANDWF	AND W with f
Syntax:	[label] ANDWF f,d
Operands:	0 ≤ f ≤ 127 d ∈ [0,1]
Operation:	(W) .AND. (f) $\rightarrow$ (destination)
Status Affected:	Z
Description:	AND the W register with register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f'.

ADDWF	Add W and f				
Syntax:	[label] ADDWF f,d				
Operands:	0 ≤ f ≤ 127 d ∈ [0,1]				
Operation:	(W) + (f) $\rightarrow$ (destination)				
Status Affected:	C, DC, Z				
Description:	Add the contents of the W register with register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f'.				

ASRF	Arithmetic Right Shift					
Syntax:	[label]ASRF f {,d}					
Operands:	$0 \le f \le 127$ $d \in [0,1]$					
Operation:	(f<7>)→ dest<7> (f<7:1>) → dest<6:0>, (f<0>) → C,					
Status Affected:	C, Z					
Description:	The contents of register 'f' are shifted one bit to the right through the Carry flag. The MSb remains unchanged. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f'.					

register f

ADDWFC	ADD W and CARRY bit to f
Syntax:	[ label ] ADDWFC f {,d}
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(W) + (f) + (C) \rightarrow dest$
Status Affected:	C, DC, Z
Description:	Add W, the Carry flag and data memory location 'f'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed in data memory location 'f'.

BCF	Bit Clear f
Syntax:	[label]BCF f,b
Operands:	$0 \le f \le 127$ $0 \le b \le 7$
Operation:	$0 \rightarrow (f < b >)$
Status Affected:	None
Description:	Bit 'b' in register 'f' is cleared.

BTFSC	Bit Test f, Skip if Clear
Syntax:	[ label ] BTFSC f,b
Operands:	$0 \le f \le 127$ $0 \le b \le 7$
Operation:	skip if $(f < b >) = 0$
Status Affected:	None
Description:	If bit 'b' in register 'f' is '1', the next instruction is executed.  If bit 'b', in register 'f', is '0', the next instruction is discarded, and a NOP is executed instead, making this a two-cycle instruction.

BRA	Relative Branch
Syntax:	[label]BRA label [label]BRA \$+k
Operands:	-256 ≤ label - PC + 1 ≤ 255 -256 ≤ k ≤ 255
Operation:	$(PC) + 1 + k \rightarrow PC$
Status Affected:	None
Description:	Add the signed 9-bit literal 'k' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 1 + k. This instruction is a two-cycle instruction. This branch has a limited range.

BTFSS	Bit Test f, Skip if Set
Syntax:	[label]BTFSS f,b
Operands:	0 ≤ f ≤ 127 0 ≤ b < 7
Operation:	skip if $(f < b >) = 1$
Status Affected:	None
Description:	If bit 'b' in register 'f' is '0', the next instruction is executed.  If bit 'b' is '1', then the next instruction is discarded and a NOP is executed instead, making this a two-cycle instruction.

BRW	Relative Branch with W
Syntax:	[ label ] BRW
Operands:	None
Operation:	$(PC) + (W) \rightarrow PC$
Status Affected:	None
Description:	Add the contents of W (unsigned) to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 1 + (W). This instruction is a two-cycle instruction.

BSF	Bit Set f	
Syntax:	[ label ] BSF f,b	
Operands:	$0 \le f \le 127$ $0 \le b \le 7$	
Operation:	$1 \rightarrow (f < b >)$	
Status Affected:	None	
Description:	Bit 'b' in register 'f' is set.	

CALL	Call Subroutine
Syntax:	[label] CALL k
Operands:	$0 \le k \le 2047$
Operation:	(PC)+ 1→ TOS, k → PC<10:0>, (PCLATH<6:3>) → PC<14:11>
Status Affected:	None
Description:	Call Subroutine. First, return address (PC + 1) is pushed onto the stack. The 11-bit immediate address is loaded into PC bits <10:0>. The upper bits of the PC are loaded from PCLATH. CALL is a two-cycle instruction.

CLRWDT	Clear Watchdog Timer
Syntax:	[label] CLRWDT
Operands:	None
Operation:	00h → WDT 0 → WDT prescaler, 1 → $\overline{10}$ 1 → $\overline{PD}$
Status Affected:	TO, PD
Description:	CLRWDT instruction resets the Watchdog Timer. It also resets the prescaler of the WDT. Status bits $\overline{\text{TO}}$ and $\overline{\text{PD}}$ are set.

CALLW	Subroutine Call With W
Syntax:	[ label ] CALLW
Operands:	None
Operation:	(PC) +1 → TOS, (W) → PC<7:0>, (PCLATH<6:0>) → PC<14:8>
Status Affected:	None
Description:	Subroutine call with W. First, the return address (PC + 1) is pushed onto the return stack. Then, the contents of W is loaded into PC<7:0>, and the contents of PCLATH into PC<14:8>. CALLW is a two-cycle

instruction.

COMF	Complement f
Syntax:	[label] COMF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(\overline{f}) \rightarrow (destination)$
Status Affected:	Z
Description:	The contents of register 'f are complemented. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f'.

CLRF	Clear f
Syntax:	[label] CLRF f
Operands:	$0 \le f \le 127$
Operation:	$00h \rightarrow (f)$ $1 \rightarrow Z$
Status Affected:	Z
Description:	The contents of register 'f' are cleared and the Z bit is set.
CLDW	Clear W

DECF	Decrement f
Syntax:	[label] DECF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) - 1 → (destination)
Status Affected:	Z
Description:	Decrement register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f'.

CLRW	Clear W
Syntax:	[label] CLRW
Operands:	None
Operation:	$00h \rightarrow (W)$ $1 \rightarrow Z$
Status Affected:	Z
Description:	W register is cleared. Zero (Z) bit is set.

DECFSZ	Decrement f, Skip if 0
Syntax:	[label] DECFSZ f,d
Operands:	0 ≤ f ≤ 127 d ∈ [0,1]
Operation:	(f) - 1 → (destination); skip if result = 0
Status Affected:	None
Description:	The contents of register 'f' are decremented. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is placed back in register 'f'. If the result is '1', the next instruction is executed. If the result is '0', then a NOP is executed instead, making it a two-cycle instruction.

INCFSZ	Increment f, Skip if 0
Syntax:	[label] INCFSZ f,d
Operands:	0 ≤ f ≤ 127 d ∈ [0,1]
Operation:	(f) + 1 → (destination), skip if result = 0
Status Affected:	None
Description:	The contents of register 'f' are incremented. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is placed back in register 'f'. If the result is '1', the next instruction is executed. If the result is '0', a NOP is executed instead, making it a two-cycle instruction.

GOTO	Unconditional Branch
Syntax:	[label] GOTO k
Operands:	$0 \le k \le 2047$
Operation:	$k \rightarrow PC<10:0>$ PCLATH<6:3> $\rightarrow PC<14:11>$
Status Affected:	None
Description:	GOTO is an unconditional branch. The 11-bit immediate value is loaded into PC bits <10:0>. The upper bits of PC are loaded from PCLATH<4:3>. GOTO is a two-cycle instruction

IORLW	Inclusive OR literal with W
Syntax:	[label] IORLW k
Operands:	$0 \le k \le 255$
Operation:	(W) .OR. $k \rightarrow (W)$
Status Affected:	Z
Description:	The contents of the W register are OR'ed with the 8-bit literal 'k'. The result is placed in the W register.

INCF	Increment f
Syntax:	[label] INCF f,d
Operands:	0 ≤ f ≤ 127 d ∈ [0,1]
Operation:	(f) + 1 → (destination)
Status Affected:	Z
Description:	The contents of register 'f' are incremented. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is placed back in register 'f'.

IORWF	Inclusive OR W with f
Syntax:	[label] IORWF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(W) .OR. (f) $\rightarrow$ (destination)
Status Affected:	Z
Description:	Inclusive OR the W register with register 'f'. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is placed back in register 'f'.

LSLF	Logical Left Shift
Syntax:	[label]LSLF f{,d}
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(f<7>) \rightarrow C$ $(f<6:0>) \rightarrow dest<7:1>$ $0 \rightarrow dest<0>$
Status Affected:	C, Z
Description:	The contents of register 'f' are shifted one bit to the left through the Carry flag. A '0' is shifted into the LSb. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f'.

LSRF	Logical Right Shift
Syntax:	[ label ] LSRF f {,d}
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$0 \rightarrow \text{dest}<7>$ $(f<7:1>) \rightarrow \text{dest}<6:0>,$ $(f<0>) \rightarrow C,$
Status Affected:	C, Z
Description:	The contents of register 'f' are shifted one bit to the right through the Carry flag. A '0' is shifted into the MSb. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f'.
	0 → register f → C

MOVF	Move f
Syntax:	[label] MOVF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(f) \rightarrow (dest)$
Status Affected:	Z
Description:	The contents of register f is moved to a destination dependent upon the status of d. If $d=0$ , destination is W register. If $d=1$ , the destination is file register f itself. $d=1$ is useful to test a file register since status flag Z is affected.
Words:	1
Cycles:	1
Example:	MOVF FSR, 0
	After Instruction  W = value in FSR register  Z = 1

MOVIW	Move INDFn to W
Syntax:	[ label ] MOVIW ++FSRn [ label ] MOVIWFSRn [ label ] MOVIW FSRn++ [ label ] MOVIW FSRn [ label ] MOVIW k[FSRn]
Operands:	$n \in [0,1]$ $mm \in [00,01, 10, 11]$ $-32 \le k \le 31$
Operation:	INDFn → W Effective address is determined by • FSR + 1 (preincrement) • FSR - 1 (predecrement) • FSR + k (relative offset) After the Move, the FSR value will be either: • FSR + 1 (all increments) • FSR - 1 (all decrements) • Unchanged
Status Affected:	Z

Mode	Syntax	mm
Preincrement	++FSRn	00
Predecrement	FSRn	01
Postincrement	FSRn++	10
Postdecrement	FSRn	11

Description:	This instruction is used to move data between W and one of the indirect
	registers (INDFn). Before/after this
	move, the pointer (FSRn) is updated by pre/post incrementing/decrementing it.
	Note: The INDFn registers are not

physical registers. Any instruction that accesses an INDFn register actually accesses the register at the address specified by the FSRn.

FSRn is limited to the range 0000h - FFFFh. Incrementing/decrementing it beyond these bounds will cause it to wrap-around.

### MOVLB Move literal to BSR

Syntax:	[ label ] MOVLB k
Operands:	$0 \le k \le 63$
Operation:	$k \rightarrow BSR$
Status Affected:	None
Description:	The 6-bit literal 'k' is loaded into

The 6-bit literal 'k' is loaded into the Bank Select Register (BSR).

MOVLP	Move literal to PCLATH	
Syntax:	[label]MOVLP k	
Operands:	$0 \le k \le 127$	
Operation:	$k \rightarrow PCLATH$	
Status Affected:	None	
Description:	The 7-bit literal 'k' is loaded into the PCLATH register.	
MOVLW	Move literal to W	
	CARROLLERS TO SELECT BEAUTY OF ANY ARCHIVE AND A	
Syntax:	[label] MOVLW k	
Syntax: Operands:	[ label ] MOVLW k 0 ≤ k ≤ 255	

Description:			is loaded into W reg- res" will assemble as
Words:	1		
Cycles:	1		
Example:	MOVLW	0x5A	
	After Instru	ction N =	0x5A

MOVWF	Move W to f	
Syntax:	[label] MOVWF f	
Operands:	0 ≤ f ≤ 127	
Operation:	$(W) \rightarrow (f)$	
Status Affected:	None	
Description:	Move data from W register to register f.	
Words:	1	
Cycles:	1	
Example:	MOVWF LATA	
	Before Instruction LATA = 0xFF	

After Instruction

LATA = 0x4F W = 0x4F

W = 0x4F

MOVWI	Move W to INDFn
Syntax:	[ label ] MOVWI ++FSRn [ label ] MOVWIFSRn [ label ] MOVWI FSRn++ [ label ] MOVWI FSRn [ label ] MOVWI k[FSRn]
Operands:	$n \in [0,1]$ $mm \in [00,01, 10, 11]$ $-32 \le k \le 31$
Operation:	W → INDFn Effective address is determined by • FSR + 1 (preincrement) • FSR - 1 (predecrement) • FSR + k (relative offset) After the Move, the FSR value will be either: • FSR + 1 (all increments) • FSR - 1 (all decrements) Unchanged
Status Affected:	None

Mode	Syntax	mm
Preincrement	++FSRn	00
Predecrement	FSRn	01
Postincrement	FSRn++	10
Postdecrement	FSRn	11

Description:

This instruction is used to move data between W and one of the indirect registers (INDFn). Before/after this move, the pointer (FSRn) is updated by pre/post incrementing/decrementing it.

**Note:** The INDFn registers are not physical registers. Any instruction that accesses an INDFn register actually accesses the register at the address specified by the FSRn.

FSRn is limited to the range 0000h-FFFFh. Incrementing/decrementing it beyond these bounds will cause it to wrap-around.

The increment/decrement operation on FSRn WILL NOT affect any Status bits.

NOP	No Operation	
Syntax:	[label] NOP	
Operands:	None	
Operation:	No operation	
Status Affected:	None	
Description:	No operation.	
Words:	1	
Cycles:	1	
Example:	NOP	
RESET	Software Reset	
Syntax:	[label] RESET	
Operands:	None	

RESET	Software Reset
Syntax:	[label] RESET
Operands:	None
Operation:	Execute a device Reset. Resets the RI flag of the PCON register.
Status Affected:	None
Description:	This instruction provides a way to execute a hardware Reset by software.

RETFIE	Return from Interrupt	
Syntax:	[label] RETFIE k	
Operands:	None	
Operation:	TOS $\rightarrow$ PC, 1 $\rightarrow$ GIE	
Status Affected:	None	
Description:	Return from Interrupt. Stack is POPed and Top-of-Stack (TOS) is loaded in the PC. Interrupts are enabled by setting Global Interrupt Enable bit, GIE (INTCON<7>). This is a two-cycle instruction.	
Words:	1	
Cycles:	2	
Example:	RETFIE	
	After Interrupt PC = TOS GIE = 1	

RETLW	Return with literal in W		
Syntax:	[label] RETLW k		
Operands:	0 ≤ k ≤ 255		
Operation:	$k \rightarrow (W);$ TOS $\rightarrow$ PC		
Status Affected:	None		
Description:	The W register is loaded with the 8-bit literal 'k'. The program counter is loaded from the top of the stack (the return address). This is a two-cycle instruction.		
Words:	1		
Cycles:	2		
Example:	CALL TABLE; W contains table ; offset value • ; W now has table value		
TABLE	ADDWF PC ;W = offset RETLW k1 ;Begin table RETLW k2 ;  RETLW kn ; End of table  Before Instruction W = 0x07  After Instruction W = value of k8		

RETURN	Return from Subroutine	
Syntax:	[label] RETURN	
Operands:	None	
Operation:	TOS → PC	
Status Affected:	None	
Description:	Return from subroutine. The stack is POPed and the top of the stack (TOS) is loaded into the program counter.  This is a two-cycle instruction	

RLF	Rotate Lef	t f throug	h Carry
Syntax:	[label]	RLF f,d	
Operands:	$0 \le f \le 127$ d $\in [0,1]$		
Operation:	See descript	ion below	
Status Affected:	С		
Description:	The contents of register 'f' are rotated one bit to the left through the Carry flag. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is stored back in register 'f'.		
Words:	1		
Cycles:	1		
Example:	RLF REG1,0		
	Before Instru	iction	
	RE	G1 =	1110 0110
	C	=	0
	After Instruct	tion	
	RE	G1 =	1110 0110
	W	=	1100 1100
	С	(i=	1
RRF	Rotate Righ	t f throug	h Carry
Syntax:	[label] RRF	f,d	

RRF	Rotate Right f through Carry	
Syntax:	[label] RRF f,d	
Operands:	$0 \le f \le 127$ $d \in [0,1]$	
Operation:	See description below	
Status Affected:	С	
Description:	The contents of register 'f' are rotated one bit to the right through the Carry flag. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is placed back in register 'f'.	
	C Register f	

SLEEP	Enter Sleep mode	
Syntax:	[label] SLEEP	
Operands:	None	
Operation:	00h → WDT, 0 → WDT prescaler, 1 → TO, 0 → PD	
Status Affected:	TO, PD	
Description:	The power-down Status bit, PD is cleared. Time-out Status bit, TO is set. Watchdog Timer and its prescaler are cleared.  See Section 11.2 "Sleep Mode" for more information.	

SUBWF	Subtract W from f [label] SUBWF f,d	
Syntax:		
Operands:	$0 \le f \le 127$ $d \in [0,1]$	
Operation:	(f) - (W) → (destination)	
Status Affected:	C, DC, Z	
Description:	Subtract (2's complement method) W register from register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f.	
	<b>C</b> = 0	W > f
	C = 1	W≤f
	DC = 0	W<3:0> > f<3:0>
	DC = 1	W<3:0> ≤ f<3:0>

SUBWFB  $f \{,d\}$  $0 \le f \le 127$ 

 $(f) - (W) - (\overline{B}) \rightarrow dest$ 

 $d \in [0,1]$ 

C, DC, Z

Subtract W from f with Borrow

Subtract W and the BORROW flag (CARRY) from register 'f' (2's complement method). If 'd' is '0', the

SUBWFB

Operands:

Operation:

Description:

Status Affected:

Syntax:

SUBLW	Subtract W from literal		
Syntax:	[label] SUBLW k		
Operands:	$0 \le k \le 255$		
Operation:	$k - (W) \rightarrow (W)$		
Status Affected:	C, DC, Z		
Description:	The W register is subtracted (2's complement method) from the 8-bit literal 'k'. The result is placed in the W register.		
	<b>C</b> = 0	W > k	
	C = 1	W≤k	
	DC = 0	W<3:0> > k<3:0>	
	DC = 1	W<3:0> ≤ k<3:0>	

	result is stored in W. If 'd' is '1', the result is stored back in register 'f'.  Swap Nibbles in f	
SWAPF		
Syntax:	[label] SWAPF f,d	
Operands:	$0 \le f \le 127$ $d \in [0,1]$	
Operation:	$(f<3:0>) \rightarrow (destination<7:4>),$ $(f<7:4>) \rightarrow (destination<3:0>)$	
Status Affected:	None	
Description:	The upper and lower nibbles of register 'f' are exchanged. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is placed in register 'f'.	

## PIC16(L)F15354/55

TRIS	Load TRIS Register with W
Syntax:	[label] TRIS f
Operands:	5 ≤ f ≤ 7
Operation:	(W) → TRIS register 'f'
Status Affected:	None
Description:	Move data from W register to TRIS register.
	When 'f' = 5, TRISA is loaded.
	When 'f' = $6$ , TRISB is loaded.
	When 'f' = 7 TRISC is loaded

XORLW	Exclusive OR literal with W	
Syntax:	[label] XORLW k	
Operands:	$0 \le k \le 255$	
Operation:	(W) .XOR. $k \rightarrow (W)$	
Status Affected:	Z	
Description:	The contents of the W register are XORed with the 8-bit literal 'k'. The result is placed in the W register.	

XORWF	Exclusive OR W with f	
Syntax:	[label] XORWF f,d	
Operands:	$0 \le f \le 127$ $d \in [0,1]$	
Operation:	(W) .XOR. (f) $\rightarrow$ (destination)	
Status Affected:	Z	
Description:	Exclusive OR the contents of the W register with register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f'.	

#### 37.0 ELECTRICAL SPECIFICATIONS

#### 37.1 Absolute Maximum Ratings(†)

Ambient temperature under bias	40°C to +125°C
Storage temperature	65°C to +150°C
Voltage on pins with respect to Vss	
on VDD pin	
PIC16F15354/55	0.3V to +6.5V
PIC16LF15354/55	0.3V to +4.0V
on MCLR pin	0.3V to +9.0V
on all other pins	0.3V to (VDD + 0.3V)
Maximum current	
on Vss pin <sup>(1)</sup>	
-40°C ≤ TA ≤ +85°C	350 mA
85°C < TA ≤ +125°C	120 mA
on VDD pin for 28-Pin devices <sup>(1)</sup>	
-40°C ≤ TA ≤ +85°C	250 mA
85°C < TA ≤ +125°C	85 mA
on VDD pin for 40-Pin devices <sup>(1)</sup>	
-40°C ≤ TA ≤ +85°C	350 mA
85°C < TA ≤ +125°C	120 mA
on any standard I/O pin	±50 mA
Clamp current, IK (VPIN < 0 or VPIN > VDD)	±20 mA
Total power dissipation <sup>(2)</sup>	800 mW

- Note 1: Maximum current rating requires even load distribution across I/O pins. Maximum current rating may be limited by the device package power dissipation characterizations, see Table 37-6 to calculate device specifications.
  - 2: Power dissipation is calculated as follows:

PDIS = VDD x {IDD -  $\Sigma$  IOH} +  $\Sigma$  {(VDD - VOH) x IOH} +  $\Sigma$  (VOI x IOL)

† NOTICE: Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure above maximum rating conditions for extended periods may affect device reliability.

#### 37.2 Standard Operating Conditions

The standard operating conditions for any device are defined as:

Operating Voltage:  $VDDMIN \le VDD \le VDDMAX$ Operating Temperature:  $Ta\_MIN \le Ta \le Ta\_MAX$ 


#### VDD — Operating Supply Voltage(1)


PIC16LF15354/55

TA —

PIC16LF15354/55	
VDDMIN (Fosc ≤ 16 MHz)	+1.8V
VDDMIN (Fosc ≤ 32 MHz)	+2.5V
VDDMAX	+3.6V
PIC16F15354/55	
VDDMIN (Fosc ≤ 16 MHz)	+2.3V
VDDMIN (Fosc ≤ 32 MHz)	+2.5V
VDDMAX	+5.5V
Operating Ambient Temperature Range	
Industrial Temperature	
Ta_min	40°C
Ta_max	
Extended Temperature	
TA MIN	40°C

Note 1: See Parameter Supply Voltage, DS Characteristics: Supply Voltage.






#### 37.3 DC Characteristics

TABLE 37-1: SUPPLY VOLTAGE

PIC16LF	F15354/5	5	Standard Operating Conditions (unless otherwise stated)								
PIC16F1	15354/55		Standa	rd Oper	ating Co	ndition	s (unless otherwise stated)				
Param. No.	Sym.	Characteristic	Min.	Typ.†	Max.	Units	Conditions				
Supply	Voltage			_							
D002	VDD		1.8 2.5		3.6 3.6	V	Fosc ≤ 16 MHz Fosc > 16 MHz				
D002	VDD		2.3 2.5	_	5.5 5.5	V	Fosc ≤ 16 MHz Fosc > 16 MHz				
RAM Da	ta Reten	tion <sup>(1)</sup>	122								
D003	VDR		1.5	10-0	e—e	V	Device in Sleep mode				
D003	VDR		1.7	14 14.	10.	V	Device in Sleep mode				
Power-o	on Reset	Release Voltage <sup>(2)</sup>	100								
D004	VPOR		(3	1.6	8 <del></del> 6	V	BOR or LPBOR disabled <sup>(3)</sup>				
D004	VPOR	2	12	1.6	: :::	V	BOR or LPBOR disabled <sup>(3)</sup>				
Power-c	on Reset	Rearm Voltage <sup>(2)</sup>									
D005	VPORR		333	0.8	p—	V	BOR or LPBOR disabled <sup>(3)</sup>				
D005	VPORR		\\ <del></del> :	1.5	-	٧	BOR or LPBOR disabled <sup>(3)</sup>				
VDD Ris	e Rate to	ensure internal Power-on	Reset si	gnal <sup>(2)</sup>							
D006	SVDD		0.05	80 <del></del> 05		V	BOR or LPBOR disabled <sup>(3)</sup>				
D006	SVDD		0.05	_		٧	BOR or LPBOR disabled <sup>(3)</sup>				

<sup>†</sup> Data in "Typ." column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

- Note 1: This is the limit to which VDD can be lowered in Sleep mode without losing RAM data.
  - 2: See Figure 37-3, POR and POR REARM with Slow Rising VDD.
  - 3: See Table 37-11 for BOR and LPBOR trip point information.
  - 4: = F device



- 2: TPOR 1 µs typical.
- 3: TvLow 2.7 µs typical.

TABLE 37-2: SUPPLY CURRENT (IDD)(1,2,4)

PIC16LF	F15354/55		Standard Operating Conditions (unless otherwise stated)							
PIC16F1	15354/55									
Param.	0 1 1	D. (1. 0)				1401.2	Conditions			
No.	Symbol	Device Characteristics	Min.	Typ.†	Max.	Units	<b>V</b> DD	Note		
D100	IDD <sub>XT4</sub>	XT = 4 MHz		360	470	μА	3.0V			
D100	IDD <sub>XT4</sub>	XT = 4 MHz		380	180	μΑ	3.0V			
D101	IDD <sub>HFO16</sub>	HFINTOSC = 16 MHz	- J	1.4	2.3	mA	3.0V	3		
D101	IDD <sub>HFO16</sub>	HFINTOSC = 16 MHz	-	1.5	2.3	mA	3.0V			
D102	IDD <sub>HFOPLL</sub>	HFINTOSC = 32 MHz	<u> </u>	2.6	3.6	mA	3.0V	32 MHz PIC16		
D102	IDD <sub>HFOPLL</sub>	HFINTOSC = 32 MHz		2.7	3.7	mA	3.0V	32 MHz PIC16		
D103	IDD <sub>HSPLL32</sub>	HS+PLL = 32 MHz	3==	2.6	3.6	mA	3.0V	32 MHz PIC16		
D103	IDD <sub>HSPLL32</sub>	HS+PLL = 32 MHz		2.7	3.7	mA	3.0V	32 MHz PIC16		
D104	IDD <sub>IDLE</sub>	Idle mode, HFINTOSC = 16 MHz	75	92.00	8 <del></del>	mA	3.0V			
D104	IDDIDLE	Idle mode, HFINTOSC = 16 MHz	-	_	S	mA	3.0V			
D105	IDD <sub>DOZE</sub> (3)	Doze mode, HFINTOSC = 16 MHz, Doze Ratio = 16		=	=	mA	3.0V	Typical value only.		
D105	IDD <sub>DOZE</sub> (3)	Doze mode, HFINTOSC = 16 MHz, Doze Ratio = 16	-	_	:	mA	3.0V	Typical value only.		

<sup>†</sup> Data in "Typ." column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

- Note 1: The test conditions for all IDD measurements in active operation mode are: OSC1 = external square wave, from rail-to-rail; all I/O pins are outputs driven low; MCLR = VDD; WDT disabled.
  - 2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.
  - 3:  $IDD_{DOZE} = [IDD_{IDLE}*(N-1)/N] + IDD_{HFO}16/N$  where N = DOZE Ratio (Register 11-2).
  - 4: PMD bits are all in the default state, no modules are disabled.
  - 5: = F device

TABLE 37-3: POWER-DOWN CURRENT (IPD)(1,2,3)

PIC16LF	15354/55			Standa	rd Opera	ating Con	ditions	(unless	otherwise stated)	
PIC16F1	5354/55			Standard Operating Conditions (unless otherwise stated) VREGPM = 1						
Param.	Symbol	Device Characteristics	Min.	Typ.†	Max.	K. Max.	Units		Conditions	
No.		Device Characteristics	Willi.	Typ.	+85°C	+125°C	Units	VDD	Note	
D200	IPD	IPD Base	I	0.05	2	6	μA	3.0V		
D200	IPD	IPD Base	_	0.4	2.5	9	μА	3.0V		
D200A			—	18	22	27	μА	3.0V	VREGPM = 0	
D201	IPD_WDT	Low-Frequency Internal Oscillator/ WDT	=	0.4	2.9	9	μA	3.0V		
D201	IPD_WDT	Low-Frequency Internal Oscillator/ WDT	-	0.5	3.3	13	μА	3.0V		
D202	IPD_SOSC	Secondary Oscillator (SOSC)		0.6	2.8	13	μA	3.0V		
D202	IPD_SOSC	Secondary Oscillator (SOSC)	-	0.8	3.2	15	μА	3.0V		
D203	IPD_FVR	FVR	-	33	47	47	μA	3.0V		
D203	IPD_FVR	FVR	_	28	44	44	μΑ	3.0V		
D204	IPD_BOR	Brown-out Reset (BOR)		10	17	19	μA	3.0V		
D204	IPD_BOR	Brown-out Reset (BOR)	_	14	18	20	μΑ	3.0V		
D205	IPD_LPBOR	Low-Power Brown-out Reset (LPBOR)		0.5	4	10	μA	3.0V		
D205	IPD_LPBOR	Low-Power Brown-out Reset (LPBOR)		0.7	5	11	μА	3.0V		
D206	IPD_ADCA	ADC - Active	_	250	9 <u>—</u> 8	57 TS	μА	3.0V	ADC is converting (4)	
D206	IPD_ADCA	ADC - Active	-	280	-	-	μА	3.0V	ADC is converting (4)	
D207	IPD_CMP	Comparator	=	30	90	93	μA	3.0V		
D207	IPD_CMP	Comparator	_	33	93	98	μΑ	3.0V		

<sup>†</sup> Data in "Typ." column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: The peripheral current is the sum of the base IDD and the additional current consumed when this peripheral is enabled. The peripheral Δ current can be determined by subtracting the base IDD or IPD current from this limit. Max. values may be used when calculating total current consumption.

- 2: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode with all I/O pins in high-impedance state and tied to Vss.
- 3: All peripheral currents listed are on a per-peripheral basis if more than one instance of a peripheral is available.
- 4: ADC clock source is FRC.
- 5: = F device

TABLE 37-4: I/O PORTS

Param.	Sym.	Characteristic	Min.	Typ†	Max.	Units	Conditions
NO.	VIL	Input Low Voltage	150		4		
	VIL	I/O PORT:					
D300		with TTL buffer	Т		0.8	V	4.5V ≤ VDD ≤ 5.5V
D301		with TE bullet			0.15 VDD	V	1.8V ≤ VDD ≤ 3.5V
D302		with Schmitt Trigger buffer		<del></del>	0.13 VDD	V	2.0V ≤ VDD ≤ 4.5V
D302		with I <sup>2</sup> C levels			0.2 VDD	V	2.0 \(\sigma\) \(\sigma\) \(\sigma\) \(\sigma\) \(\sigma\)
D303		with SMBus levels		===	0.3 VDD	V	2.7V ≤ VDD ≤ 5.5V
D304 D305		MCLR			0.2 VDD	V	2.7 V \( \sqrt{VDD} \( \sqrt{S} \).3 V
D303	VIH			<del></del> -3	0.2 000	V	
	VIH	Input High Voltage					
Dago				VAC CO		V	4.5V. < Von < 5.5V
D320		with TTL buffer	2		<u> </u>	- 0	4.5V ≤ VDD ≤ 5.5V
D321			0.25 VDD + 0.8	<del>(3-3)</del>	8 <del></del>	V	1.8V ≤ VDD ≤ 4.5V
D322		with Schmitt Trigger buffer	0.8 VDD	2-2	9 <u>—</u> 2	V	2.0V ≤ VDD ≤ 5.5V
D323		with I <sup>2</sup> C levels	0.7 VDD		8 <u></u> 2	V	
D324		with SMBus levels	2.1	<del>2010</del> 8	9 <del>-3</del>	V	2.7V ≤ VDD ≤ 5.5V
D325		MCLR	0.7 VDD	<del></del>	8 - 8	V	
	liL	Input Leakage Current <sup>(1)</sup>					
D340		I/O Ports	8—8	± 5	± 125	nA	Vss ≤ VPIN ≤ VDD, Pin at high-impedance, 85°C
D341			2—2	± 5	± 1000	nA	Vss ≤ VPIN ≤ VDD, Pin at high-impedance, 125°C
D342		MCLR <sup>(2)</sup>	85 <del></del> 3	± 50	± 200	nA	Vss ≤ VPIN ≤ VDD, Pin at high-impedance, 85°C
	IPUR	Weak Pull-up Current					
D350			25	100	200	μА	VDD = 3.0V, VPIN = VSS
	Vol	Output Low Voltage	PO1		(a) 10	451	
D360		I/O ports	) <del>_</del> 0	-	0.6	٧	IOL = 10.0 mA, VDD = 3.0V
	Voн	Output High Voltage					10 10 10 10 10 10 10 10 10 10 10 10 10 1
D370	11.111	I/O ports	VDD - 0.7	-	-	٧	IOH = 6.0 mA, VDD = 3.0V
D380	CIO	All I/O pins	_	5	50	pF	

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1:Negative current is defined as current sourced by the pin.

<sup>2:</sup> The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

TABLE 37-5: MEMORY PROGRAMMING SPECIFICATIONS

Param. No.	Sym.	Characteristic	Min.	Typ†	Max.	Units	Conditions
High Vo	Itage Entr	y Programming Mode Specifications	5	4.0		10.0	10
MEM01	V <sub>IHH</sub>	Voltage on MCLR/VPP pin to enter programming mode	8	_	9	٧	(Note 2, Note 3)
MEM02	I <sub>PPGM</sub>	Current on MCLR/VPP pin during programming mode	-	1		mA	(Note 2)
Progran	nming Mo	de Specifications	e:	100		200	200
MEM10	V <sub>BE</sub>	VDD for Bulk Erase	_	2.7	-	V	
MEM11	I <sub>DDPGM</sub>	Supply Current during Programming operation	<u>(2</u>		10	mA	
Progran	n Flash M	emory Specifications					
MEM30	E <sub>P</sub>	Flash Memory Cell Endurance	10k	-	( <del>jame</del> )	E/W	-40°C ≤ TA ≤ +85°C ( <b>Note 1</b> )
MEM32	T <sub>P_RET</sub>	Characteristic Retention	_	40	-	Year	Provided no other specifications are violated
MEM33	V <sub>P_RD</sub>	VDD for Read operation	VDDMIN	( <del></del> -	VDDMAX	V	
MEM34	V <sub>P_REW</sub>	VDD for Row Erase or Write operation	VDDMIN	( <del>1 = </del> )	VDDMAX	V	
MEM35	T <sub>P_REW</sub>	Self-Timed Row Erase or Self-Timed Write	-	2.0	2.5	ms	

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: Flash Memory Cell Endurance for the Flash memory is defined as: One Row Erase operation and one Self-Timed Write. HEF feature applies only to the last 128 words of the Program Flash Memory.

- 2: Required only if CONFIG4, bit LVP is disabled.
- 3: The MPLAB® ICD2 does not support variable VPP output. Circuitry to limit the ICD2 VPP voltage must be placed between the ICD2 and target system when programming or debugging with the ICD2.

#### TABLE 37-6: THERMAL CHARACTERISTICS

Standard Operating Conditions (unless otherwise stated)
Operating Temperature -40°C ≤ TA ≤ +125°C


Param. No.	Sym.	Characteristic	Тур.	Units	Conditions
TH01	θЈА	Thermal Resistance Junction to Ambient	60	°C/W	28-pin SPDIP package
		l T	80	°C/W	28-pin SOIC package
		I	90	°C/W	28-pin SSOP package
		l T	32	°C/W	28-pin QFN 6x6 mm package
		l [	48	°C/W	28-pin UQFN 4x4 mm package
TH02	θјС	Thermal Resistance Junction to Case	31.4	°C/W	28-pin SPDIP package
			24	°C/W	28-pin SOIC package
		Ī	24	°C/W	28-pin SSOP package
		l T	5	°C/W	28-pin QFN 6x6 mm package
		l [	12	°C/W	28-pin UQFN 4x4 mm package
TH03	TJMAX	Maximum Junction Temperature	150	°C	
TH04	PD	Power Dissipation	<u>150</u>	W	PD = PINTERNAL + PI/O
TH05	PINTERNAL	Internal Power Dissipation	5-3	W	PINTERNAL = IDD x VDD <sup>(1)</sup>
TH06	Pi/o	I/O Power Dissipation	15—11	W	$PI/O = \Sigma (IOL * VOL) + \Sigma (IOH * (VDD - VOH))$
TH07	PDER	Derated Power	===0	W	PDER = PDMAX - (TJ - TA)/θJA <sup>(2)</sup>

Note 1: IDD is current to run the chip alone without driving any load on the output pins.


<sup>2:</sup> TA = Ambient Temperature, TJ = Junction Temperature

#### 37.4 AC Characteristics

#### FIGURE 37-4: LOAD CONDITIONS



#### FIGURE 37-5: CLOCK TIMING



#### TABLE 37-7: EXTERNAL CLOCK/OSCILLATOR TIMING REQUIREMENTS

ı						
ı	Standard	Operating	Conditione	luniace	otherwise state	d

Param. No.	Sym.	Characteristic	Min.	Typ†	Max.	Units	Conditions
ECL Os	cillator	•					
OS1	F <sub>ECL</sub>	Clock Frequency		1 <u>63</u> 0	500	kHz	
OS2	T <sub>ECL_DC</sub>	Clock Duty Cycle	40	9 <u>6—1</u> 9	60	%	
ECM Os	cillator	26	122				
OS3	F <sub>ECM</sub>	Clock Frequency	_	_	4	MHz	
OS4	T <sub>ECM_DC</sub>	Clock Duty Cycle	40	-	60	%	
ECH Os	cillator	•				•	•
OS5	F <sub>ECH</sub>	Clock Frequency			32	MHz	
OS6	T <sub>ECH_DC</sub>	Clock Duty Cycle	40	- <del></del> -	60	%	
LP Osci	llator			33 Ca	4		10
OS7	F <sub>LP</sub>	Clock Frequency	_	-	100	kHz	Note 4
XT Osci	llator	•				•	•
OS8	F <sub>XT</sub>	Clock Frequency	7-3	9 <u>8 30</u> 0	4	MHz	Note 4
HS Osci	illator						
OS9	F <sub>HS</sub>	Clock Frequency		-	20	MHz	
System	Oscillator					•	
OS20	Fosc	System Clock Frequency		<u></u>	32	MHz	(Note 2, Note 3)
OS21	F <sub>CY</sub>	Instruction Frequency		Fosc/4	72_5	MHz	
OS22	T <sub>CY</sub>	Instruction Period	125	1/F <sub>CY</sub>	() 32 <u>—2</u> 2	ns	

- These parameters are characterized but not tested.
- † Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.
- Note 1: Instruction cycle period (TCY) equals four times the input oscillator time base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min" values with an external clock applied to OSC1 pin. When an external clock input is used, the "max" cycle time limit is "DC" (no clock) for all devices.
  - The system clock frequency (Fosc) is selected by the "main clock switch controls" as described in Section 9.0
    "Oscillator Module (with Fail-Safe Clock Monitor)".
  - The system clock frequency (Fosc) must meet the voltage requirements defined in the Section 37.2 "Standard Operating Conditions".
  - 4: LP, XT and HS oscillator modes require an appropriate crystal or resonator to be connected to the device. For clocking the device with the external square wave, one of the EC mode selections must be used.

TABLE 37-8: INTERNAL OSCILLATOR PARAMETERS(1)

Standar	d Operating	Conditions (unless otherwise st	ated)				
Param. No.	Sym.	Characteristic	Min.	Тур†	Max.	Units	Conditions
OS50	FHFOSC	Precision Calibrated HFINTOSC Frequency	_	4 8 12 16 32		MHz	(Note 2)
OS51	FHFOSCLP	Low-Power Optimized HFINTOSC Frequency	0.93 1.86	1 2	1.07 2.14	MHz MHz	
OS52	FMFOSC	Internal Calibrated MFINTOSC Frequency	<del>,</del>	500	8 <del></del> 8	kHz	(Note 3)
OS53	FLFOSC	Internal LFINTOSC Frequency	-	31	5 <del>-</del> 2	kHz	
OS54	THFOSCST	HFINTOSC Wake-up from Sleep Start-up Time	=	11 50	20 —	μs μs	VREGPM = 0 VREGPM = 1
OS56	TLFOSCST	LFINTOSC Wake-up from Sleep Start-up Time	-	0.2	27——77	ms	

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

- Note 1: To ensure these oscillator frequency tolerances, VDD and VSS must be capacitively decoupled as close to the device as possible. 0.1  $\mu$ F and 0.01  $\mu$ F values in parallel are recommended.
  - 2: See Figure 37-6: Precision Calibrated HFINTOSC Frequency Accuracy Over Device VDD and Temperature.

FIGURE 37-6: PRECISION CALIBRATED HFINTOSC FREQUENCY ACCURACY OVER DEVICE VDD AND TEMPERATURE




TABLE 37-9: PLL SPECIFICATIONS

Standar	Standard Operating Conditions (unless otherwise stated) VDD ≥ 2.5V									
Param. No.	Sym.	Characteristic	Min.	Тур†	Max.	Units	Conditions			
PLL01	FPLLIN	PLL Input Frequency Range	4	-	8	MHz				
PLL02	FPLLOUT	PLL Output Frequency Range	16	-	32	MHz	Note 1			
PLL03	TPLLST	PLL Lock Time from Start-up		200		μs				
PLL04	FPLLJIT	PLL Output Frequency Stability (Jitter)	-0.25	(2-2)	0.25	%				

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: The output frequency of the PLL must meet the Fosc requirements listed in Parameter D002.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

FIGURE 37-7: CLKOUT AND I/O TIMING




TABLE 37-10: I/O AND CLKOUT TIMING SPECIFICATIONS

Standar	d Operating	Conditions (unless otherwise stated)					
Param. No.	Sym.	Characteristic	Min.	Тур†	Max.	Units	Conditions
IO1*	T <sub>CLKOUTH</sub>	CLKOUT rising edge delay (rising edge Fosc (Q1 cycle) to falling edge CLKOUT	-	=	70	ns	
IO2*	T <sub>CLKOUTL</sub>	CLKOUT falling edge delay (rising edge Fosc (Q3 cycle) to rising edge CLKOUT	_	-	72	ns	
IO3*	T <sub>IO_VALID</sub>	Port output valid time (rising edge Fosc (Q1 cycle) to port valid)	-	50	70	ns	
IO4*	T <sub>IO_SETUP</sub>	Port input setup time (Setup time before rising edge Fosc – Q2 cycle)	20	_	<u>10 - 1</u> 0	ns	
IO5*	T <sub>IO_HOLD</sub>	Port input hold time (Hold time after rising edge Fosc – Q2 cycle)	50	_		ns	
IO6*	T <sub>IOR_SLREN</sub>	Port I/O rise time, slew rate enabled	( <del>5</del>	25	-	ns	V <sub>DD</sub> = 3.0V
107*	T <sub>IOR_SLRDIS</sub>	Port I/O rise time, slew rate disabled	( <del>)</del>	5	==4	ns	V <sub>DD</sub> = 3.0V
IO8*	T <sub>IOF_SLREN</sub>	Port I/O fall time, slew rate enabled	8 <del></del>	25	==	ns	V <sub>DD</sub> = 3.0V
109*	T <sub>IOF_SLRDIS</sub>	Port I/O fall time, slew rate disabled	2 <del>-3</del> -1	5	<del></del>	ns	V <sub>DD</sub> = 3.0V
IO10*	T <sub>INT</sub>	INT pin high or low time to trigger an interrupt	25	i.—	<del>20 - 1</del> 2	ns	
IO11*	T <sub>IOC</sub>	Interrupt-on-Change minimum high or low time to trigger interrupt	25			ns	

<sup>\*</sup>These parameters are characterized but not tested.

FIGURE 37-8: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING




FIGURE 37-9: BROWN-OUT RESET TIMING AND CHARACTERISTICS




TABLE 37-11: RESET, WDT, OSCILLATOR START-UP TIMER, POWER-UP TIMER, BROWN-OUT RESET AND LOW-POWER BROWN-OUT RESET SPECIFICATIONS

Standard	Operating	Conditions (unless otherwise stated)					
Param. No.	Sym.	Characteristic	Min.	Typ†	Max.	Units	Conditions
RST01*	TMCLR	MCLR Pulse Width Low to ensure Reset	2	S <del></del>	3 <del>2-2</del> 7	μs	
RST02*	TIOZ	I/O high-impedance from Reset detection	* ** <u> </u>	1 <u>2—2</u>	2	μs	8
RST03	TWDT	Watchdog Timer Time-out Period	(	16	19	ms	16 ms Nominal Reset Time
RST04*	TPWRT	Power-up Timer Period	8-3	65	12-12	ms	
RST05	Tost	Oscillator Start-up Timer Period <sup>(1,2)</sup>	3—3	1024	(1-1)	Iosc	3
RST06	VBOR	Brown-out Reset Voltage	2.55 2.30 1.80	2.70 2.45 1.90	2.85 2.60 2.10	V V	BORV = 0 BORV = 1 (F devices) BORV = 1 (LF devices)
RST07	VBORHYS	Brown-out Reset Hysteresis	*	40	<u> </u>	mV	
RST08	TBORDC	Brown-out Reset Response Time	19—10	3	(1 <u></u>	μs	
RST09	VLPBOR	Low-Power Brown-out Reset Voltage	1.8	2.0	2.2	V	LF Devices Only

- \* These parameters are characterized but not tested.
- † Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.
- Note 1: By design, the Oscillator Start-up Timer (OST) counts the first 1024 cycles, independent of frequency.
  - 2: To ensure these voltage tolerances, VDD and Vss must be capacitively decoupled as close to the device as possible. 0.1 μF and 0.01 μF values in parallel are recommended.

#### TABLE 37-12: ANALOG-TO-DIGITAL CONVERTER (ADC) ACCURACY SPECIFICATIONS(1,2):

	d Opera .0V, TA =	ting Conditions (unless otherwise 25°C	e stated)				
Param. No.	Sym.	Characteristic	Min.	Тур†	Max.	Units	Conditions
AD01	NR	Resolution	_	-	10	bit	
AD02	EIL	Integral Error		±0.1	±1.0	LSb	ADCREF+ = 3.0V, ADCREF-= 0V
AD03	EDL	Differential Error		±0.1	±1.0	LSb	ADCREF+ = 3.0V, ADCREF-= 0V
AD04	EOFF	Offset Error	_	0.5	2.0	LSb	ADCREF+ = 3.0V, ADCREF-= 0V
AD05	EGN	Gain Error		±0.2	±1.0	LSb	ADCREF+ = 3.0V, ADCREF-= 0V
AD06	VADREF	ADC Reference Voltage (ADREF+)(3)	1.8	1 <del></del>	VDD	٧	
AD07	VAIN	Full-Scale Range	ADREF-	-	ADREF+	٧	
AD08	ZAIN	Recommended Impedance of Analog Voltage Source	<u>18_4</u> 7	10	<u></u>	kΩ	
AD09	RVREF	ADC Voltage Reference Ladder Impedance		50	<u></u>	kΩ	Note 3

- \* These parameters are characterized but not tested.
- † Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.
- Note 1: Total Absolute Error is the sum of the offset, gain and integral nonlinearity (INL) errors.
  - 2: The ADC conversion result never decreases with an increase in the input and has no missing codes.
  - 3: This is the impedance seen by the VREF pads when the external reference pads are selected.

TABLE 37-13: ANALOG-TO-DIGITAL CONVERTER (ADC) CONVERSION TIMING SPECIFICATIONS

Standa	d Ope	rating Conditions (unless other	wise stated)				
Param. No.	Sym.	Characteristic	Min.	Тур†	Max.	Units	Conditions
AD20	TAD	ADC Clock Period	1	<u>15</u> 28	9	μs	The requirement is to set ADCCS correctly to produce this period/ frequency.
AD21			1	2	6	μs	Using FRC as the ADC clock source ADOSC = 1
AD22	TCNV	Conversion Time	2-	11	8	TAD	Set of GO/DONE bit to Clear of GO/DONE bit
AD23	TACQ	Acquisition Time		2		μs	
AD24	THCD	Sample and Hold Capacitor Disconnect Time	8 <u>7 ×</u>	<u></u>	<u> </u>	μs	Fosc-based clock source FRC-based clock source

<sup>\*</sup> These parameters are characterized but not tested.

FIGURE 37-10: ADC CONVERSION TIMING (ADC CLOCK Fosc-BASED)





FIGURE 37-11: ADC CONVERSION TIMING (ADC CLOCK FROM FRC)



<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### **TABLE 37-14: COMPARATOR SPECIFICATIONS**

Standard Operating Conditions (unless otherwise stated) VDD = 3.0V, TA = 25°C

*	1	<del>-</del>	_		ř –	1	
Param. No.	Sym.	Characteristics	Min.	Тур.	Max.	Units	Comments
CM01	VIOFF	Input Offset Voltage		===0	±50	mV	VICM = VDD/2
CM02	VICM	Input Common Mode Range	GND		VDD	V	8
CM03	CMRR	Common Mode Input Rejection Ratio		50	<u> </u>	dB	
CM04	VHYST	Comparator Hysteresis	15	25	35	m∨	
CM05	TRESP <sup>(1)</sup>	Response Time, Rising Edge		300	600	ns	
		Response Time, Falling Edge	-	220	500	ns	
CMOS6	TMCV2VO(2)	Mode Change to Valid Output	-	===0	10	μs	

- \* These parameters are characterized but not tested.
- Note 1: Response time measured with one comparator input at VDD/2, while the other input transitions from Vss to VDD.
  - 2: A mode change includes changing any of the control register values, including module enable.

#### TABLE 37-15: 5-BIT DAC SPECIFICATIONS

Standard Operating Conditions (unless otherwise stated) VDD = 3.0V, TA = 25°C

Description Engineering	regions exposes		-				
Param. No.	Sym.	Characteristics	Min.	Тур.	Max.	Units	Comments
DSB01	VLSB	Step Size	-	(VDACREF+ -VDACREF-) /32	9 <u>1</u>	V	
DSB01	VACC	Absolute Accuracy	_		± 0.5	LSb	
DSB03*	RUNIT	Unit Resistor Value	75	5000		Ω	
DSB04*	Tst	Settling Time <sup>(1)</sup>	\$ <del>7 -</del> 8	\$ <del></del>	10	μs	

- \* These parameters are characterized but not tested.
- † Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: Settling time measured while DACR<4:0> transitions from '00000' to '01111'.

#### TABLE 37-16: FIXED VOLTAGE REFERENCE (FVR) SPECIFICATIONS

Standard	Operating Condition	ons (unless otherwise stated)					
Param. No.	Symbol	Characteristic	Min.	Тур.	Max.	Units	Conditions
FVR01	VFVR1	1x Gain (1.024V)	-4	-	+4	%	VDD ≥ 2.5V, -40°C to 85°C
FVR02	VFVR2	2x Gain (2.048V)	-4	_	+4	%	VDD ≥ 2.5V, -40°C to 85°C
FVR03	VFVR4	4x Gain (4.096V)	-6	( <u>)</u> (	+6	%	VDD ≥ 4.75V, -40°C to 85°C
FVR04	TFVRST	FVR Start-up Time	<u></u> 8	25	800	us	
FVR05	FVRA1x/FVRC1x	FVR output voltage for 1x setting stored in the DIA	-	1024	· ==	m∨	
FVR06	FVRA2x/FVRC2x	FVR output voltage for 2x setting stored in the DIA	_	2048	3 <u></u>	m∨	
FVR07	FVRA4x/FVRC4x	FVR output voltage for 4x setting stored in the DIA	-	4096	8_2	m∨	Note 1

Note 1: Available only on PIC16F15354/55.


#### TABLE 37-17: ZERO-CROSS DETECT (ZCD) SPECIFICATIONS

Standard Operating Conditions (unless otherwise stated)  $\mbox{VDD} = 3.0\mbox{V, TA} = 25\mbox{°C}$ 

Param. No.	Sym.	Characteristics	Min.	Тур†	Max.	Units	Comments
ZC01	ZPCINV	Voltage on Zero Cross Pin	15	0.75	<u>9-8</u> 1	٧	
ZC02	ZCDRV	Maximum source or sink current	y5 <del></del> 80	_	600	μА	
ZC04	ZCISW	Response Time, Rising Edge	r0	1	1 <u>6 3</u> 6	μs	
		Response Time, Falling Edge	9	1	-	μs	
ZC05	ZCOUT	Response Time, Rising Edge	10 <u>—</u> 8	1	9 <u>5 3</u> 5	μs	
		Response Time, Falling Edge	10	1	2-2	μs	

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### FIGURE 37-12: TIMER0 AND TIMER1 EXTERNAL CLOCK TIMINGS



#### TABLE 37-18: TIMER0 AND TIMER1 EXTERNAL CLOCK REQUIREMENTS


Standard Operating Conditions (unless otherwise stated)

Operating Temperature -40°C ≤ TA ≤ +125°C Param Sym. Characteristic Units Min. Typ† Max. Conditions No. 40\* Тт0Н T0CKI High-Pulse Width No Prescaler 0.5 Tcy + 20ns With Prescaler 10 ns 41\* T0CKI Low-Pulse Width TT0L No Prescaler 0.5 Tcy + 20ns With Prescaler 10 ns 42\* TT0P T0CKI Period Greater of: 20 ns N = prescale value or (Tcy +40)\*N (2, 4, ... 256)45\* TT1H T1CKI High Synchronous, No Prescaler 0.5 Tcy + 20ns Time Synchronous, with Prescaler 15 ns 30 Asynchronous ns 46\* TT1L T1CKI Low 0.5 Tcy + 20Synchronous, No Prescaler ns Time Synchronous, with Prescaler 15 ns Asynchronous 30 ns T1CKI Input 47\* TT1P Synchronous Greater of: 30 N = prescale value ns Period or (Tcy +40)\*N (2, 4, ... 256)60 Asynchronous ns 48 FT1 Timer1 Oscillator Input Frequency Range 32.4 32.768 33.1 kHz (oscillator enabled by setting bit T1OSCEN) 49\* TCKEZTMR1 Delay from External Clock Edge to Timer 2 Tosc 7 Tosc Timers in Sync Increment mode

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### FIGURE 37-13: CAPTURE/COMPARE/PWM TIMINGS (CCP)




#### TABLE 37-19: CAPTURE/COMPARE/PWM REQUIREMENTS (CCP)

		ating Conditions (unlesserature -40°C≤Ta≤+		d)		: 5	22	
Param. No.	Sym.	Character	ristic	Min.	Typ†	Max.	Units	Conditions
CC01*	TccL	CCPx Input Low Time	No Prescaler	0.5Tcy + 20			ns	
		111 1111	With Prescaler	20	-	( <del></del> )	ns	
CC02*	TccH	CCPx Input High Time	No Prescaler	0.5Tcy + 20	-	-	ns	
			With Prescaler	20	=	-	ns	
CC03*	TccP	CCPx Input Period		(3Tcy +40)*N	3 <del></del> 3	3	ns	N = prescale value (1,4 or 16)

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### FIGURE 37-14: CLC PROPAGATION TIMING



#### TABLE 37-20: CONFIGURABLE LOGIC CELL (CLC) CHARACTERISTICS


	and the same and the same a	ng Conditions (unless otherwise stated) uture -40°C ≤ TA ≤ +125°C					
Param. No.	Sym.	Characteristic	Min.	Typ†	Max.	Units	Conditions
CLC01*	TCLCIN	CLC input pin (CKCxIN) to CKC Module Input select (LCx_IN) propagation time		7	IO5	ns	(Note 1)
CLC02*	TCLC	CLC Module input to output propagation delay	1 [	24 12	_	ns ns	VDD = 1.8V VDD > 3.6V
CLC03*	TCLCOUT	CLC Module output time		107		<u> 15—15</u>	Rise Time (Note 1)
				IO8	_	-	Fall Time (Note 1)
CLC04*	FCLCMAX	CLC Maximum switching frequency	===	32	Fosc	MHz	

<sup>\*</sup> These parameters are characterized but not tested.

Note 1:See Table 37-10 for IO5, IO7 and IO8 rise and fall times.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.


#### FIGURE 37-15: EUSART SYNCHRONOUS TRANSMISSION (HOST/CLIENT) TIMING



#### TABLE 37-21: EUSART SYNCHRONOUS TRANSMISSION CHARACTERISTICS

		nditions (unless otherwise stated) -40°C ≤ TA ≤ +125°C				
Param. No.	Symbol	Characteristic	Min.	Max.	Units	Conditions
US120	TCKH2DTV	SYNC XMIT (Host and Client)	-	80	ns	3.0V ≤ VDD ≤ 5.5V
		Clock high to data-out valid	_	100	ns	1.8V ≤ VDD ≤ 5.5V
US121	TCKRF	Clock out rise time and fall time	4_2	45	ns	3.0V ≤ VDD ≤ 5.5V
		(Host mode)	_	50	ns	1.8V ≤ VDD ≤ 5.5V
US122	TDTRF	Data-out rise time and fall time	<u> </u>	45	ns	3.0V ≤ VDD ≤ 5.5V
			=	50	ns	1.8V ≤ VDD ≤ 5.5V

#### FIGURE 37-16: EUSART SYNCHRONOUS RECEIVE (HOST/CLIENT) TIMING



#### TABLE 37-22: EUSART SYNCHRONOUS RECEIVE REQUIREMENTS

Standard Operating Conditions (unless otherwise stated) Operating Temperature -40°C ≤ TA ≤ +125°C									
Param. No.	Symbol	Characteristic	Min.	Max.	Units	Conditions			
US125	TDTV2CKL	SYNC RCV (Host and Client) Data-setup before CK ↓ (DT hold time)	10	_	ns				
US126	TCKL2DTL	Data-hold after CK ↓ (DT hold time)	<mark>1</mark> 5	<u></u>	ns				

FIGURE 37-17: SPI HOST MODE TIMING (CKE = 0, SMP = 0)




FIGURE 37-18: SPI HOST MODE TIMING (CKE = 1, SMP = 1)




FIGURE 37-19: SPI CLIENT MODE TIMING (CKE = 0)





FIGURE 37-20: SPI CLIENT MODE TIMING (CKE = 1)




**TABLE 37-23: SPI MODE REQUIREMENTS** 

Param. No.	Symbol	Characteristic	Min.	Тур†	Max.	Units	Conditions
SP70*	TssL2scH, TssL2scL	SS↓ to SCK↓ or SCK↑ input	2.25*TcY	) <del></del>	<del></del>	ns	
SP71*	TscH	SCK input high time (Client mode)	Tcy + 20		-	ns	
SP72*	TscL	SCK input low time (Client mode)	Tcy + 20		-	ns	
SP73*	TDIV2scH, TDIV2scL	Setup time of SDI data input to SCK edge	100	5 <del>.</del>	=	ns	
SP74*	TSCH2DIL, TSCL2DIL	Hold time of SDI data input to SCK edge	100	7 <u></u> -	==3	ns	
SP75*	TDOR	SDO data output rise time	200	10	25	ns	3.0V ≤ VDD ≤ 5.5V
			<del>2-</del> 8	25	50	ns	1.8V ≤ VDD ≤ 5.5V
SP76*	TDOF	SDO data output fall time	<del></del>	10	25	ns	
SP77*	TssH2DoZ	SS↑ to SDO output high impedance	10	-	50	ns	
SP78*	TscR	SCK output rise time	<del>20 -</del> 0	10	25	ns	$3.0 \text{V} \le \text{VDD} \le 5.5 \text{V}$
		(Host mode)	<u>82_7</u> 7	25	50	ns	1.8V ≤ VDD ≤ 5.5V
SP79*	TscF	SCK output fall time (Host mode)	-	10	25	ns	
SP80*	TscH2DoV,	SDO data output valid after SCK edge	<u>~</u>	% <del></del>	50	ns	$3.0 \text{V} \le \text{VDD} \le 5.5 \text{V}$
	TscL2DoV			(=)	145	ns	$1.8V \le VDD \le 5.5V$
SP81*	TDOV2scH, TDOV2scL	SDO data output setup to SCK edge	1 Tcy	-	-	ns	
SP82*	TssL2DoV	SDO data output valid after SS↓ edge	<u>22—</u>	-	50	ns	
SP83*	TscH2ssH, TscL2ssH	SS ↑ after SCK edge	1.5 Tcy + 40	-	===	ns	

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested

#### FIGURE 37-21: I<sup>2</sup>C BUS START/STOP BITS TIMING



#### TABLE 37-24: 12C BUS START/STOP BITS REQUIREMENTS

Param. No.	Symbol	Characteristic		Min.	Тур	Max.	Units	Conditions	
SP90*	TSU:STA	Start condition	100 kHz mode	4700	-	-	ns	Only relevant for Repeated State condition	
		Setup time	400 kHz mode	600	=	=			
SP91*	THD:STA	Start condition	100 kHz mode	4000	B 3	-		After this period, the first clock	
		Hold time	400 kHz mode	600		-		pulse is generated	
SP92*	Tsu:sto	Stop condition	100 kHz mode	4700	2=3		ns		
		Setup time	400 kHz mode	600	-	_			
SP93	THD:STO	Stop condition	100 kHz mode	4000	200	<u>==</u> 0	ns		
		Hold time	400 kHz mode	600	5-3	_	1		

<sup>\*</sup> These parameters are characterized but not tested.

#### FIGURE 37-22: I<sup>2</sup>C BUS DATA TIMING




TABLE 37-25: I<sup>2</sup>C BUS DATA REQUIREMENTS

Param. No.	Symbol	Characteristic		Min.	Max.	Units	Conditions		
SP100*	THIGH	Clock high time	100 kHz mode	4.0		μS	Device must operate at a minimum of 1.5 MHz		
		***	400 kHz mode	0.6		μs	Device must operate at a minimum of 10 MHz		
			SSP module	1.5TcY	<u>12—2</u> 3	î.			
SP101*	TLOW	Clock low time	100 kHz mode	4.7	-	μs	Device must operate at a minimum of 1.5 MHz		
			400 kHz mode	1.3		μs	Device must operate at a minimum of 10 MHz		
			SSP module	1.5 TCY	, <del>, , , , , , , , , , , , , , , , , , </del>				
SP102*	TR	SDA and SCL rise time	100 kHz mode	<del>-</del> -s	1000	ns			
			400 kHz mode	20 + 0.1 CB	300	ns	CB is specified to be from 10-400 pF		
SP103*	TF	SDA and SCL fall time	100 kHz mode	<u></u>	250	ns			
			400 kHz mode	20 + 0.1 CB	250	ns	CB is specified to be from 10-400 pF		
SP106*	THD:DAT	AT Data input hold time	100 kHz mode	0	_ <del>_</del>	ns			
			400 kHz mode	0	0.9	μs			
SP107*	TSU:DAT	Data input setup time	100 kHz mode	250		ns	(Note 2)		
			400 kHz mode	100		ns	1		
SP109*	TAA	Output valid from clock	100 kHz mode	===0	3500	ns	(Note 1)		
			400 kHz mode			ns			
SP110*	TBUF	Bus free time	100 kHz mode	4.7		μs	Time the bus must be free		
			400 kHz mode	1.3	: <del></del> :	μs	before a new transmission can start		
SP111	Св	Bus capacitive loading			400	pF			

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCL to avoid unintended generation of Start or Stop conditions.

2: A Fast mode (400 kHz) I<sup>2</sup>C bus device can be used in a Standard mode (100 kHz) I<sup>2</sup>C bus system, but the requirement TSU:DAT ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the low period of the SCL signal. If such a device does stretch the low period of the SCL signal, it must output the next data bit to the SDA line TR max. + TSU:DAT = 1000 + 250 = 1250 ns (according to the Standard mode I<sup>2</sup>C bus specification), before the SCL line is released.

#### **TABLE 37-26: TEMPERATURE INDICATOR REQUIREMENTS**

Standard Operating Conditions (unless otherwise stated)										
Param No.	Symbol	Characteri	Min.	Typ†	Max.	Units	Conditions			
TS01	TACQMIN	Minimum ADC Acquisit	_	25	_	μs				
TS02	M∨	Voltage Sensitivity	High Range	12 <del>-1</del> 6	-3.684	-	mV/°C	TSRNG = 1		
		2000	Low Range	1-	-2.456	_	mV/°C	TSRNG = 0		

<sup>\*</sup> These parameters are characterized but not tested.

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

# 38.0 DC AND AC CHARACTERISTICS GRAPHS AND CHARTS

The graphs and tables provided in this section are for design guidance and are not tested.

In some graphs or tables, the data presented are **outside specified operating range** (i.e., outside specified VDD range). This is for **information only** and devices are ensured to operate properly only within the specified range.

Unless otherwise noted, all graphs apply to both the L and LF devices.

Note: The graphs and tables provided following this note are a statistical summary based on a limited number of samples and are provided for informational purposes only. The performance characteristics listed herein are not tested or guaranteed. In some graphs or tables, the data presented may be outside the specified operating range (e.g., outside specified power supply range) and therefore, outside the warranted range.

"Typical" represents the mean of the distribution at 25°C. "Maximum", "Max.", "Minimum" or "Min." represents (mean + 3 $\sigma$ ) or (mean - 3 $\sigma$ ) respectively, where  $\sigma$  is a standard deviation, over each temperature range.

## PIC16LF15354/55

Note: Unless otherwise noted, VIN = 5V, Fosc = 300 kHz, CIN = 0.1 µF, TA = 25°C.




FIGURE 38-1: ADC 10-bit Mode, Single-Ended DNL, VDD = 3.0V, VREF = 3.0V,  $TAD = 1 \mu s$ ,  $25^{\circ}C$ .




FIGURE 38-2: ADC 10-bit Mode, Single-Ended DNL, VDD= 3.0V, VREF = 3.0V, TAD = 4 µs, 25°C.




FIGURE 38-3: ADC 10-bit Mode, Single-Ended DNL, VDD= 3.0V, VREF = 3.0V, TAD = 8 µs, 25°C.




FIGURE 38-4: ADC 10-bit Mode, Single-Ended INL, VDD= 3.0V, VREF = 3.0V, TAD = 1 µs, 25°C.




FIGURE 38-5: ADC 10-bit Mode, Single-Ended INL, VDD= 3.0V, VREF = 3.0V, TAD = 4 µs, 25°C.




FIGURE 38-6: ADC 10-bit Mode, Single-Ended INL, VDD= 3.0V, VREF = 3.0V, TAD = 8 µs, 25°C.

Note: Unless otherwise noted, VIN = 5V, Fosc = 300 kHz, CIN = 0.1 µF, TA = 25°C.




FIGURE 38-7: ADC 10-bit Mode, Single-Ended DNL, VDD= 3.0V, VREF = 3.0V




FIGURE 38-8: ADC 10-bit Mode, Single-Ended INL, VDD= 3.0V, VREF = 3.0V




FIGURE 38-9: ADC 10-bit Mode, Single-Ended DNL, VDD= 3.0V, TAD = 1 µs




FIGURE 38-10: ADC 10-bit Mode, Single-Ended INL, VDD= 3.0V, TAD = 1 μs




FIGURE 38-11: ADC 10-bit Mode, Single-Ended Gain Error, VDD= 3.0V, TAD = 1 µs




FIGURE 38-12: ADC 10-bit Mode, Single-Ended Offset Error, VDD= 3.0V, TAD = 1 µs

### PIC16LF15354/55

Note: Unless otherwise noted, VIN = 5V, FOSC = 300 kHz, CIN = 0.1  $\mu F$ , TA = 25°C.




FIGURE 38-13: ADC 10-bit Mode, Single-Ended DNL, VDD= 3.0V, TAD = 4 μs.




FIGURE 38-14: ADC 10-bit Mode, Single-Ended INL, VDD= 3.0V, TAD = 4 μs.




FIGURE 38-15: ADC 10-bit Mode, Single-Ended Gain Error, VDD= 3.0V, TAD = 4 μs




FIGURE 38-16: ADC 10-bit Mode, Single-Ended Offset Error, VDD= 3.0V, TAD = 4 µs




FIGURE 38-17: ADC 10-bit Mode, Single-Ended Gain Error, VDD= 3.0V, VREF = 3.0V, -40°C to 85°C.




FIGURE 38-18: ADC 10-bit Mode, Single-Ended Offset Error, VDD= 3.0V, VREF = 3.0V, -40°C to 85°C





FIGURE 38-19: ADC RC Oscillator Period, PIC16F15354/55 devices only.



**FIGURE 38-20:** ADC RC Oscillator Period, PIC16F15354/55 devices only.




FIGURE 38-21: Band Gap Ready




FIGURE 38-22: Brown-out Reset Response Time, PIC16LF15354/55 devices only.




FIGURE 38-23: Brown-out Reset Response Time, PIC16F15354/55 devices only.




FIGURE 38-24: Brown-out Reset Voltage, Trip Point (BORV = 00)

## PIC16LF15354/55




FIGURE 38-25: Brown-out Reset
Hysteresis, Low-Trip Point (BORV = 00)




FIGURE 38-26: Brown-out Reset Voltage, Trip Point (BORV = 01)




FIGURE 38-27: Brown-out Reset Hysteresis, Trip Point (BORV = 01)




FIGURE 38-28: LPBOR Reset Voltage




FIGURE 38-29: LPBOR Reset Hysteresis




FIGURE 38-30: Comparator Response Time Falling Edge, PIC16LF15354/55 devices only.




FIGURE 38-31: Comparator Response Time Falling Edge, PIC16F15354/55 devices only.




FIGURE 38-32: Comparator Response Time Rising Edge, PIC16LF15354/55 devices only.




FIGURE 38-33: Comparator Response Time Rising Edge, PIC16F15354/55 devices only.




FIGURE 38-34: Comparator Hysteresis, Normal Power Mode (CxSP = 1), VDD = 3.0V, Typical Measured Values




FIGURE 38-35: Comparator Offset, Normal Power Mode (CxSP = 1), VDD = 3.0V, Typical Measured Values at 25°C.




FIGURE 38-36: Comparator Offset, Normal Power Mode (CxSP = 1), VDD = 3.0V, Typical Measured Values from -40°C to 125°C.

## PIC16LF15354/55




FIGURE 38-37: Comparator Hysteresis, Normal Power Mode (CxSP = 1), VDD = 5.5V, Typical Measured Values, PIC16F15354/55 devices only.




FIGURE 38-39: Comparator Offset, Normal Power Mode (CxSP = 1), VDD = 5.5V, Typical Measured Values from -40°C to 125°C, PIC16F15354/55 devices only.




FIGURE 38-41: Comparator Response Time Over Voltage, Normal Power Mode (CxSP = 1), Typical Measured Values, PIC16F15354/55 devices only.




FIGURE 38-38: Comparator Offset, Normal Power Mode (CxSP = 1), VDD = 5.0V, Typical Measured Values at 25°C, PIC16F15354/55 devices only.




FIGURE 38-40: Comparator Response Time Over Voltage, Normal Power Mode (CxSP = 1), Typical Measured Values, PIC16F15354/55 devices only.




FIGURE 38-42: Comparator Output Filter Delay Time Over Temperature, Normal Power Mode (CxSP = 1), Typical Measured Values, PIC16F15354/55 devices only.




FIGURE 38-43: Comparator Output Filter
Delay Time Over Temperature, Normal Power
Mode (CxSP = 1), Typical Measured Values,
PIC16F15354/55 devices only




FIGURE 38-44: Typical DAC DNL Error, VDD = 3.0V, VREF = External 3V




FIGURE 38-45: Typical DAC INL Error, VDD = 3.0V, VREF = External 3V




FIGURE 38-46: Absolute Value of DAC DNL Error, VDD = 3.0V, VREF= VDD




FIGURE 38-47: Absolute Value of DAC INL Error, VDD = 3.0V, VREF= VDD




FIGURE 38-48: FVR Stabilization Period, PIC16LF15354/55 devices only

## PIC16LF15354/55





FIGURE 38-49: Typical FVR Voltage 1X, PIC16LF15354/55 devices only



**FIGURE 38-50:** FVR Voltage Error 1X, PIC16F15354/55 devices only




FIGURE 38-51: FVR Voltage Error 2X, PIC16LF15354/55 devices only




FIGURE 38-52: FVR Voltage Error 2X, PIC16F15354/55 devices only




FIGURE 38-53: FVR Voltage Error 4X, PIC16F15354/55 devices only




FIGURE 38-54: HFINTOSC Typical Frequency Error, PIC16LF15354/55 devices only




FIGURE 38-55: IDD, XT Oscillator 4 MHz, PIC16LF15354/55 devices only




FIGURE 38-56: IDD, XT Oscillator 4 MHz, PIC16F15354/55 devices only




FIGURE 38-57: IDD, HS Oscillator 32 MHz, PIC16LF15354/55 devices only




FIGURE 38-58: IDD, HS Oscillator 32 MHz, PIC16F15354/55 devices only




FIGURE 38-59: IDD, HFINTOSC Mode, Fosc = 32 MHz, PIC16LF15354/55 devices only




FIGURE 38-60: IDD, HFINTOSC Mode, FOSC = 32 MHz, PIC16F15354/55 devices only

## PIC16LF15354/55




FIGURE 38-61: IDD, HFINTOSC Mode, Fosc = 16 MHz, PIC16LF15354/55 devices only




FIGURE 38-62: IDD, HFINTOSC Mode, Fosc = 16 MHz, PIC16LF15354/55 devices only




FIGURE 38-63: IDD, HFINTOSC Idle Mode, Fosc = 16 MHz, PIC16LF15354/55 devices only




FIGURE 38-64: IDD, HFINTOSC Idle Mode, Fosc = 16 MHz, PIC16F15354/55 devices only




FIGURE 38-65: IDD, HFINTOSC Doze Mode, Fosc = 16 MHz, PIC16LF15354/55 devices only




FIGURE 38-66: IDD, HFINTOSC Doze

Mode, Fosc = 16 MHz, PIC16F15354/55 devices
only




FIGURE 38-67: Schmitt Trigger High Values




FIGURE 38-68: Schmitt Trigger Low Values




FIGURE 38-69: Input Level TTL Trip
Thresholds




FIGURE 38-70: Rise Time, Slew Rate Control Enabled




FIGURE 38-71: Fall Time, Slew Rate Control Enabled




FIGURE 38-72: Rise Time, Slew Rate Control Disabled

## PIC16LF15354/55




FIGURE 38-73: Control Disabled

Rise Time, Slew Rate




FIGURE 38-74: IPD Base, Low-Power Sleep Mode, PIC16LF15354/55 devices only




FIGURE 38-75: IPD, Watchdog Timer (WDT), PIC16LF15354/55 devices only




FIGURE 38-76: IPD, Watchdog Timer (WDT), PIC16F15354/55 devices only




FIGURE 38-77: IPD, Fixed Voltage Reference (FVR), PIC16LF15354/55 devices only




FIGURE 38-78: IPD, Fixed Voltage Reference (FVR), PIC16F15354/55 devices only




FIGURE 38-79: IPD, Brown-out Reset (BOR), BORV = 1, PIC16LF15354/55 devices only




FIGURE 38-80: IPD, Brown-out Reset (BOR), BORV = 1, PIC16F15354/55 devices only




FIGURE 38-81: IPD, Low-Power Brown-out Reset (LPBOR = 0), PIC16LF15354/55 devices only




FIGURE 38-82: IPD, Low-Power Brown-out Reset (LPBOR = 0), PIC16F15354/55 devices only




FIGURE 38-83: IPD, Comparator, PIC16LF15354/55 devices only




FIGURE 38-84: IPD, Comparator, PIC16F15354/55 devices only

## PIC16LF15354/55




FIGURE 38-85: Ipd Base, 01, PIC16F15354/55 devices only




FIGURE 38-86: Ipd Base, 11, PIC16F15354/55 devices only




FIGURE 38-87: LFINTOSC Frequency, PIC16LF15354/55 devices only




FIGURE 38-88: LFINTOSC Frequency, PIC16F15354/55 devices only




FIGURE 38-89: OCSTUNE Center Frequency, PIC16LF15354/55 devices only




FIGURE 38-90: Power-on Reset Release Voltage





FIGURE 38-91: Power-on Reset Rearm Voltage, Normal Power Mode, PIC16F15354/55 devices only



**FIGURE 38-92:** PWRT Period, PIC16F15354/55 devices only




FIGURE 38-93: PWRT Period, PIC16LF15354/55 devices only




FIGURE 38-94: VOH Vs. IOH Over
Temperature, VDD = 5.5V, PIC16F15354/55
devices only




FIGURE 38-95: VOL Vs. IOL Over
Temperature, VDD = 5.5V, PIC16F15354/55
devices only




FIGURE 38-96: VOH Vs. IOH Over Temperature, VDD = 3.0V

## PIC16LF15354/55




FIGURE 38-97: Vol. Vs. Iol Over Temperature, VDD = 3.0V




FIGURE 38-98: VOH Vs. IOH Over Temperature, VDD = 1.8V, PIC16LF15354/55 devices only




FIGURE 38-99: VOL Vs. IOL Over
Temperature, VDD = 3.0V, PIC16LF15354/55
devices only




FIGURE 38-100: Wake From Sleep, VREGPM = 0, HFINTOSC = 4 MHz, PIC16F15354/55 devices only




FIGURE 38-101: Wake from Sleep, VREGPM = 1, HFINTOSC = 4 MHz, PIC16F15354/55 devices only




FIGURE 38-102: Wake from Sleep, VREGPM = 1, HFINTOSC = 16 MHZ, PIC16F15354/55 devices only




FIGURE 38-103: Wake from Sleep, VREGPM = 1, HFINTOSC = 16 MHz, PIC16F15354/55 devices only




FIGURE 38-104: Wake from Sleep, VREGPM = 1, PIC16F15354/55 devices only




FIGURE 38-105: Wake from Sleep, PIC16LF15354/55 devices only




FIGURE 38-106: Wake from Sleep, VREGPM = 1, LFINTOSC, PIC16F15354/55 devices only




FIGURE 38-107: Wake from Sleep, LFINTOSC, PIC16LF15354/55 devices only




FIGURE 38-108: Watchdog Timer Time-out Period, PIC16F15354/55 devices only

## PIC16LF15354/55




FIGURE 38-109: Watchdog Timer Time-out Period, PIC16LF15354/55 devices only




FIGURE 38-110: Weak Pull-up Current, PIC16F15354/55 devices only




FIGURE 38-111: Weak Pull-up Current, PIC16LF15354/55 devices only




FIGURE 38-112: High Range Temperature Indicator Voltage Sensitivity Across Temperature




FIGURE 38-113: Low Range Temperature Indicator Voltage Sensitivity Across Temperature

# PIC16(L)F15354/55

## 39.0 DEVELOPMENT SUPPORT

Move a design from concept to production in record time with Microchip's award-winning development tools. Microchip tools work together to provide state of the art debugging for any project with easy-to-use Graphical User Interfaces (GUIs) in our free MPLAB® X and Atmel Studio Integrated Development Environments (IDEs), and our code generation tools. Providing the ultimate ease-of-use experience, Microchip's line of programmers, debuggers and emulators work seamlessly with our software tools. Microchip development boards help evaluate the best silicon device for an application, while our line of third party tools round out our comprehensive development tool solutions.

Microchip's MPLAB X and Atmel Studio ecosystems provide a variety of embedded design tools to consider, which support multiple devices, such as  $PIC^{@}$  MCUs,  $AVR^{@}$  MCUs, SAM MCUs and  $dsPIC^{@}$  DSCs. MPLAB X tools are compatible with Windows $^{@}$ , Linux $^{@}$  and Mac $^{@}$  operating systems while Atmel Studio tools are compatible with Windows.


Go to the following website for more information and details:

https://www.microchip.com/development-tools/


### 40.0 PACKAGING INFORMATION

## 40.1 Package Marking Information


28-Lead SPDIP (.300")




Example




28-Lead SOIC (7.50 mm)




Example



28-Lead SSOP (5.30 mm)



Example



Legend: XX...X Customer-specific information

Y Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')

NNN Alphanumeric traceability code


Pb-free JEDEC® designator for Matte Tin (Sn)

\* This package is Pb-free. The Pb-free JEDEC designator (e3) can be found on the outer packaging for this package.


Note: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available characters for customer-specific information.

## 40.1 Package Marking Information (Continued)


28-Lead UQFN (4x4x0.5 mm)




Example



28-Lead QFN and VQFN (6x6 mm)



Example




Legend: XX...X Customer-specific information
Y Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')
NNN Alphanumeric traceability code
Pb-free JEDEC® designator for Matte Tin (Sn)
\* This package is Pb-free. The Pb-free JEDEC designator (©3)
can be found on the outer packaging for this package.

Note: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available characters for customer-specific information.

The following sections give the technical details of the packages.

### 28-Lead Skinny Plastic Dual In-Line (SP) - 300 mil Body [SPDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		INCHES		
Din	nension Limits	MIN	NOM	MAX	
Number of Pins	N		28		
Pitch	е		.100 BSC		
Top to Seating Plane	Α	1.00		.200	
Molded Package Thickness	A2	.120	.135	.150	
Base to Seating Plane	A1	.015	400		
Shoulder to Shoulder Width	E	.290	.310	.335	
Molded Package Width	E1	.240	.285	.295	
Overall Length	D	1.345	1.365	1.400	
Tip to Seating Plane	L	.110	.130	.150	
Lead Thickness	С	.008	.010	.015	
Upper Lead Width	b1	.040	.050	.070	
Lower Lead Width	b	.014	.018	.022	
Overall Row Spacing §	еВ	-	8==	.430	

#### Notes:


- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.


Microchip Technology Drawing C04-070B

## 28-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging








Microchip Technology Drawing C04-052C Sheet 1 of 2

## 28-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS		
Dimensi	on Limits	MIN	NOM	MAX	
Number of Pins	N		28		
Pltch	е		1.27 BSC		
Overall Helght	Α	-	340	2.65	
Molded Package Thickness	A2	2.05	128 j	420	
Standoff §	A1	0.10	120	0.30	
Overall Wldth	E	10.30 BSC			
Molded Package Width	E1	7.50 BSC			
Overall Length	D	17.90 BSC			
Chamfer (Optional)	h	0.25	(#3)	0.75	
Foot Length	L	0.40	(50)	1.27	
Footprint	L1	1.40 REF			
Lead Angle	Θ	0°	878	10.00	
Foot Angle	φ	0°	-	8°	
Lead Thickness	С	0.18		0.33	
Lead Width	b	0.31		0.51	
Mold Draft Angle Top	α	5°	120	15°	
Mold Draft Angle Bottom	β	5°	-	15°	


### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic
- DImension D does not include mold flash, protrusions or gate burrs, which shall not exceed 0.15 mm per end. Dimension E1 does not include interlead flash or protrusion, which shall not exceed 0.25 mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
  - REF: Reference Dimension, usually without tolerance, for information purposes only.
- 5. Datums A & B to be determined at Datum H.

Microchip Technology Drawing C04-052C Sheet 2 of 2

## 28-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



#### RECOMMENDED LAND PATTERN

	Units		MILLIMETER:	S
Dimens	sion Limits	MIN	NOM	MAX
Contact Pitch	E		1,27 BSC	
Contact Pad Spacing	С		9.40	
Contact Pad Width (X28)	X			0.60
Contact Pad Length (X28)	Υ			2.00
Distance Between Pads	Gx	0.67		
Distance Between Pads	G	7.40		

### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2052A

## 28-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS		
Di	Dimension Limits		NOM	MAX	
Number of Pins	N		28	*	
Pitch	е		0.65 BSC	20.5	
Overall Height	Α	100	-	2.00	
Molded Package Thickness	A2	1.65	1.75	1.85	
Standoff	A1	0.05	<del></del> 0		
Overall Width	E	7.40	7.80	8.20	
Molded Package Width	E1	5.00	5.30	5.60	
Overall Length	D	9.90	10.20	10.50	
Foot Length	L	0.55	0.75	0.95	
Footprint	L1		1.25 REF		
Lead Thickness	С	0.09	<u>~</u> a	0.25	
Foot Angle	ф	0°	4°	8°	
Lead Width	b	0.22		0.38	

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.20 mm per side.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-073B

## 28-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		<b>MILLIMETER</b>	S
Dimension Limits		MIN	MOM	MAX
Contact Pitch	E		0.65 BSC	0
Contact Pad Spacing	С		7.20	
Contact Pad Width (X28)	X1			0.45
Contact Pad Length (X28)	Y1			1.75
Distance Between Pads	G	0.20		

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2073A

## 28-Lead Plastic Ultra Thin Quad Flat, No Lead Package (MV) - 4x4x0.5 mm Body [UQFN]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-152A Sheet 1 of 2

## 28-Lead Plastic Ultra Thin Quad Flat, No Lead Package (MV) - 4x4x0.5 mm Body [UQFN]

ote: For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units	MILLIMETERS		
	Dimension Limits		NOM	MAX
Number of Plns	N		28	
Pitch	е	,	0.40 BSC	2
Overall Helght	A	0.45	0.50	0.55
Standoff	A1	0.00	0.02	0.05
Contact Thickness	A3	0.127 REF		9
Overall Width	E	4,00 BSC		
Exposed Pad Wldth	E2	2.55	2.65	2.75
Overall Length	D	4.00 BSC		
Exposed Pad Length	D2	2.55	2.65	2.75
Contact Width	b	0.15	0.20	0.25
Contact Length	L	0.30	0.40	0.50
Contact-to-Exposed Pad	K	0.20	-	(A.=.)


#### Notes:

- 1. Pln 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated.
- 3. Dimensioning and tolerancing per ASME Y14.5M.
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
  - REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-152A Sheet 2 of 2

28-Lead Ultra Thin Plastic Quad Flat, No Lead Package (MV) - 4x4 mm Body [UQFN] With 0.40 mm Contact Length

Note: For the most current package drawlings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units **MILLIMETERS Dimension Limits** MIN NOM MAX Contact Pltch E 0.40 BSC Optional Center Pad Width W2 2.35 Optional Center Pad Length T2 2,35 Contact Pad Spacing C1 4.00 Contact Pad Spacing C2 4.00 Contact Pad Width (X28) X1 0.20 Contact Pad Length (X28) Y1 0.80 0.20 Distance Between Pads G

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2152A

# 28-Lead Very Thin Plastic Quad Flat, No Lead Package (5N) - 6x6x1.0 mm Body [VQFN] 4.10x4.10 mm Exposed Pad, Wettable Flanks (Stepped)


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-401C Sheet 1 of 2

# 28-Lead Very Thin Plastic Quad Flat, No Lead Package (5N) - 6x6x1.0 mm Body [VQFN] 4.10x4.10 mm Exposed Pad, Wettable Flanks (Stepped)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS		
Dimens	sion Limits	MIN	NOM	MAX	
Number of Terminals	N	114000	28		
Pitch	е		0.65 BSC		
Overall Height	Α	0.80	0.90	1.00	
Standoff	A1	0.00	0.02	0.05	
Terminal Thickness	A3		0.20 REF		
Step Height	A4	0.05	0.12	0.19	
Overall Width	E	6.00 BSC			
Exposed Pad Width	E2	4.00 4.10 4.2			
Overall Length	D	6.00 BSC			
Exposed Pad Length	D2	4.00	4.10	4.20	
Terminal Width	b	0.25	0.30	0.35	
Terminal Length	L	0.50	0.60	0.70	
Step Length	L1	0.035	0.060	0.085	
Terminal-to-Exposed Pad	K		0.35 REF		

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated
- 3. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-401C Sheet 2 of 2

# 28-Lead Very Thin Plastic Quad Flat, No Lead Package (5N) - 6x6x1.0 mm Body [VQFN] 4.10x4.10 mm Exposed Pad, Wettable Flanks (Stepped)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



### RECOMMENDED LAND PATTERN

Units			MILLIMETER:	S
Dimension Limits		MIN	NOM	MAX
Contact Pitch	E		0.65 BSC	
Optional Center Pad Width	X2			3.80
Optional Center Pad Length	Y2			3.80
Contact Pad Spacing	C1		5.90	
Contact Pad Spacing	C2		5.90	
Contact Pad Width (X28)	X1			0.35
Contact Pad Length (X28)	Y1			0.85
Contact Pad to Center Pad (X28)	G1	0.20		
Thermal Via Diameter	V		0.30	
Thermal Via Pitch	EV		1.00	


#### Notes

- Dimensioning and tolerancing per ASME Y14.5M
   BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- For best soldering results, thermal vias, if used, should be filled or tented to avoid solder loss during reflow process

Microchip Technology Drawing C04-2401B

# 28-Lead Plastic Quad Flat, No Lead Package (ML) - 6x6 mm Body [QFN] With 0.55 mm Terminal Length

Note: For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging




**BOTTOM VIEW** 

Microchip Technology Drawing C04-105C Sheet 1 of 2

0.05(M)

# 28-Lead Plastic Quad Flat, No Lead Package (ML) - 6x6 mm Body [QFN] With 0.55 mm Terminal Length

For the most current package drawlngs, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units	1	<b>MILLIMETER</b>	S
Dimer	sion Limits	MIN	NOM	MAX
Number of Pins	N		28	0
Pitch	е		0.65 BSC	2000
Overall Height	Α	0.80	0.90	1.00
Standoff	A1	0.00	0.02	0.05
Terminal Thickness	A3		0.20 REF	1000
Overall Wldth	E	6,00 BSC		
Exposed Pad Wldth	E2	3,65	3,70	4.20
Overall Length	D	6.00 BSC		
Exposed Pad Length	D2	3.65	3.70	4.20
Terminal Width	b	0.23	0.30	0.35
Terminal Length	L	0.50	0,55	0.70
Terminal-to-Exposed Pad	K	0.20	250	-

#### Notes:

Note:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package Is saw singulated
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-105C Sheet 2 of 2

# 28-Lead Plastic Quad Flat, No Lead Package (ML) – 6x6 mm Body [QFN] with 0.55 mm Contact Length

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

Units			MILLIM	ETERS
Dimension Limits		MIN	NOM	MAX
Contact Pltch	E		0.65 BSC	·
Optional Center Pad Width	W2			4.25
Optional Center Pad Length	T2			4.25
Contact Pad Spacing	C1		5.70	
Contact Pad Spacing	C2		5.70	
Contact Pad Wldth (X28)	X1			0.37
Contact Pad Length (X28)	Y1			1.00
Distance Between Pads	G	0.20		

#### Notes:

1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2105A

# APPENDIX A: DATA SHEET REVISION HISTORY

### Revision D (11/2021)

Updated terminology used throughout the data sheet: "master" replaced by "host", and "slave" replaced by "client". Replaced ADCRC appearances with FRC.

Updated package information to include QFN and VQFN (6x6 mm) packaging; replaces PDIP with SPDIP packaging.

Updated Figures 30-1, 30-2, 30-3 and 30-4: CWGxISM replaced with CWG1DAT. Updated Tables 4-10, 29-2, 31-2, 31-4, 36-3 and 37-6, and Figures 37-5, 37-9 and 37-10.

### Revision C (01/2018)

Updated Table 3, 4-5 and 6-1. Updated Register 5-4. Added second Indirect addressing figure in memory chapter. Updated Equation 19-1 (sensor Temperature) Updated Register 18-1 (FVRCON), Updated 19.2.1.1, Removed Example 19-1 (Temp Sens)

Replaced PGC/PGD with ICSPCLK/ICSPDAT; Revised Section 9.2.2.3 LFINSTOSC; Revised Table 15-1 and 15-2 (PPS Input Signal Routing Options); Table 15-6 Summary of Registers/PPS Module; Revised Example 20-1 ADC Conversion; Added note to Section 20.1.2 Channel Selection; Revised Section 27.0 Timer2 Module; Table 37-11, revised RST06.

Removed Section 20.2.3 (Terminating a Conversation)

Added char graphs. Updated the Electrical Specs chapter: Absolute Maximum Ratings and Tables 37-1, 37-2, 37-3, 37-4, 37-5, 37-6, 37-7, 37-8, 37-11, 37-12, 37-14, 37-16, 37-17, 37-18, 37-19, 37-20, 37-21, 37-22. General typo and formatting corrections.

### Revision B (09/2016)

Updated SFR table. Updated cover page.

Added Figure 4-2. Updated Example 13-5; Figures 4-1, 4-3, 7-1, 8-3, 13-4,13-8, 17-1, 18-1 and 22-1; Registers 5-3, 5-4, 5-7, 9-5, 10-13, 11-4, 13-1, 13-3, 13-5, 14-5, 14-9, 14-11, 14-13, 14-26,15-3, and 20-3; Sections 1.0, 3.0, 3.4, 4.1.1, 4.2, 4.2.5, 4.3, 4.3.1, 4.3.2, 4.3.2.1, 5.1, 5.4, 6.1, 6.2, 6.3, 7.0, 7.1, 7.14, 8.4, 8.4.2, 8.5.1, 8.11, 8.12, 10.1, 13.2.2., 13.3.2, 13.3.6, 14.8, 14.8.1, 14.8.2, 16.0, 18.2, 19.5, 29.0, 29.1.1, and 33.0; Tables 3-4, 4-2, 4-4, 4-5, 4-6, 4-7, 4-8, 4-10, 5-1, 7-3, 7-4, 13-2, 13-3, 15-2, 15-3 and 37-6. Added Section 3.2.5. Removed Figure 13-7.

General typo and formatting corrections.

#### Revision A (07/2016)

Initial release of the document.

#### THE MICROCHIP WEBSITE

Microchip provides online support via our WWW site at www.microchip.com. This website is used as a means to make files and information easily available to customers. Accessible by using your favorite Internet browser, the website contains the following information:

- Product Support Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQ), technical support requests, online discussion groups, Microchip consultant program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# CUSTOMER CHANGE NOTIFICATION SERVICE

Microchip's customer notification service helps keep customers current on Microchip products. Subscribers will receive e-mail notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, access the Microchip website at www.microchip.com. Under "Support", click on "Customer Change Notification" and follow the registration instructions.

#### CUSTOMER SUPPORT

Users of Microchip products can receive assistance through several channels:

- · Distributor or Representative
- Local Sales Office
- Field Application Engineer (FAE)
- Technical Support

Customers should contact their distributor, representative or Field Application Engineer (FAE) for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in the back of this document.

Technical support is available through the website at: http://microchip.com/support

## PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

Device: PIC16F15354, PIC16LF15354 PIC16F15355, PIC16LF15355  Tape and Reel Option: T = Tape and Reel <sup>(1)</sup> Temperature I = -40°C to +85°C (Industrial) Range: E = -40°C to +125°C (Extended)  Package: A = -40°C to +125°C (Extended)  Package: A = -40°C to +125°C (Extended)  ML = 28-lead QFN 6x6mm 5N = 28-lead VQFN 6x6mm MV = 28-lead VQFN 6x6mm MV = 28-lead SOIC SP = 28-lead SOIC SP = 28-lead SPDIP SS = 28-lead SSOP  Pattern: QTP, SQTP, Code or Special Requirements (blank otherwise)  Pattern: QTP, SQTP, Code or Special Requirements (blank otherwise)	Device: PIC16F15354, PIC16LF15354 PIC16F15355, PIC16LF15355  Tape and Reel Option: T = Tape and Reel(1)  Temperature Range: I = -40°C to +85°C (Industrial) E = -40°C to +125°C (Extended)  Package: (2)  ML = 28-lead OFN 6x6mm MV = 28-lead UQFN 6x6mm MV = 28-lead UQFN 4x4mm SO = 28-lead SOIC SP = 28-lead SPDIP SS = 28-lead SSOP  Pattern: QTP, SQTP, Code or Special Requirements (blank otherwise)  Note 1: Tape and Reel identifier only appears in the catalog part number description. This identifier is used for ordering purposes and is not printed on the device package. Check with your Microchip Sales Office for package availability with the Tape and Reel option.  2: Small form-factor packaging options may be available. Check www.microchip.com/packaging for small-form factor package availability, or contact	PART NO. Device	[X] <sup>(1)</sup> - X /XX XXX Tape and Reel Temperature Package Pattern Option Range	Examples:  a) PIC16F15354- E/SP Extended temperature SPDIP package
Package: (2)  ML = 28-lead QFN 6x6mm 5N = 28-lead VQFN 6x6mm MV = 28-lead UQFN 4x4mm SO = 28-lead SOIC SP = 28-lead SPDIP SS = 28-lead SSOP  Pattern:  QTP, SQTP, Code or Special Requirements (blank otherwise)  Mote 1: Tape and Reel identifier only appears in the catalog part number description. This identifier is used for ordering purposes an is not printed on the device package. Check with your Microchip Sales Office for package availability with the Tape an Reel option.  2: Small form-factor packaging options may be available. Check www.microchip.com/packaging for small form factor package availability, or contains.	Package: (2)  ML = 28-lead QFN 6x6mm 5N = 28-lead VQFN 6x6mm MV = 28-lead UQFN 4x4mm SO = 28-lead SOIC SP = 28-lead SPDIP SS = 28-lead SSOP  Pattern:  QTP, SQTP, Code or Special Requirements (blank otherwise)  Mote 1: Tape and Reel identifier only appears in the catalog part number description. This identifier is used for ordering purposes and is not printed on the device package. Check with your Microchip Sales Office for package availability with the Tape and Reel option.  2: Small form-factor packaging options may be available. Check www.microchip.com/packaging for small-form factor package availability, or contact	Tape and Reel Option:	PIC16F15355, PIC16LF15355  Blank = Standard packaging (tube or tray) T = Tape and Reel <sup>(1)</sup> I = 40°C to +85°C (Industrial)	
form factor package availability, or contain	form factor package availability, or contact	Package: <sup>(2)</sup>	ML = 28-lead QFN 6x6mm 5N = 28-lead VQFN 6x6mm MV = 28-lead UQFN 4x4mm SO = 28-lead SOIC SP = 28-lead SPDIP SS = 28-lead SSOP  QTP, SQTP, Code or Special Requirements	the catalog part number description. This identifier is used for ordering purposes and is not printed on the device package. Check with your Microchip Sales Office for package availability with the Tape and Reel option.  2: Small form-factor packaging options may be available. Check
			(Dialik Oulei Wise)	form factor package availability, or contact

#### Note the following details of the code protection feature on Microchip products:

- · Microchip products meet the specifications contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is secure when used in the intended manner, within operating specifications, and under normal conditions.
- Microchip values and aggressively protects its intellectual property rights. Attempts to breach the code protection features of Microchip product is strictly prohibited and may violate the Digital Millennium Copyright Act.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of its code. Code protection does not
  mean that we are guaranteeing the product is "unbreakable". Code protection is constantly evolving. Microchip is committed to
  continuously improving the code protection features of our products.

This publication and the information herein may be used only with Microchip products, including to design, test, and integrate Microchip products with your application. Use of this information in any other manner violates these terms. Information regarding device applications is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. Contact your local Microchip sales office for additional support or, obtain additional support at https://www.microchip.com/en-us/support/design-help/client-support-services.

THIS INFORMATION IS PROVIDED BY MICROCHIP "AS IS". MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION INCLUDING BUT NOT LIMITED TO ANY IMPLIED WARRANTIES OF NON-INFRINGEMENT, MERCHANTABILITY, AND FITNESS FOR A PARTICULAR PURPOSE, OR WARRANTIES RELATED TO ITS CONDITION, QUALITY, OR PERFORMANCE.

IN NO EVENT WILL MICROCHIP BE LIABLE FOR ANY INDIRECT, SPECIAL, PUNITIVE, INCIDENTAL, OR CONSEQUENTIAL LOSS, DAMAGE, COST, OR EXPENSE OF ANY KIND WHATSOEVER RELATED TO THE INFORMATION OR ITS USE, HOWEVER CAUSED, EVEN IF MICROCHIP HAS BEEN ADVISED OF THE POSSIBILITY OR THE DAMAGES ARE FORESEEABLE. TO THE FULLEST EXTENT ALLOWED BY LAW, MICROCHIP'S TOTAL LIABILITY ON ALL CLAIMS IN ANY WAY RELATED TO THE INFORMATION OR ITS USE WILL NOT EXCEED THE AMOUNT OF FEES, IF ANY, THAT YOU HAVE PAID DIRECTLY TO MICROCHIP FOR THE INFORMATION.

Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights unless otherwise stated.

For information regarding Microchip's Quality Management Systems, please visit www.microchip.com/quality.

#### Trademarks

The Microchip name and logo, the Microchip logo, Adaptec, AnyRate, AVR, AVR logo, AVR Freaks, BesTime, BitCloud, CryptoMemory, CryptoRF, dsPIC, flexPWR, HELDO, IGLOO, JukeBlox, KeeLoq, Kleer, LANCheck, LinkMD, maXStylus, maXTouch, MediaLB, megaAVR, Microsemi, Microsemi logo, MOST, MOST logo, MPLAB, OptoLyzer, PIC, picoPower, PICSTART, PIC32 logo, PolarFire, Prochip Designer, QTouch, SAM-BA, SenGenuity, SpyNIC, SST, SST Logo, SuperFlash, Symmetricom, SyncServer, Tachyon, TimeSource, tinyAVR, UNI/O, Vectron, and XMEGA are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

AgileSwitch, APT, ClockWorks, The Embedded Control Solutions Company, EtherSynch, Flashtec, Hyper Speed Control, HyperLight Load, IntelliMOS, Libero, motorBench, mTouch, Powermite 3, Precision Edge, ProASIC, ProASIC Plus, ProASIC Plus logo, Quiet-Wire, SmartFusion, SyncWorld, Temux, TimeCesium, TimeHub, TimePictra, TimeProvider, TrueTime, WinPath, and ZL are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Adjacent Key Suppression, AKS, Analog-for-the-Digital Age, Any Capacitor, Anyln, AnyOut, Augmented Switching, BlueSky, BodyCom, CodeGuard, CryptoAuthentication, CryptoAutomotive, CryptoCompanion, CryptoController, dsPICDEM, dsPICDEM.net, Dynamic Average Matching, DAM, ECAN, Espresso T1S, EtherGREEN, GridTime, IdealBridge, In-Circuit Serial Programming, ICSP, INICnet, Intelligent Paralleling, Inter-Chip Connectivity, JitterBlocker, Knob-on-Display, maxCrypto, maxView, memBrain, Mindi, MiWi, MPASM, MPF, MPLAB Certified logo, MPLIB, MPLINK, MultiTRAK, NetDetach, NVM Express, NVMe, Omniscient Code Generation, PICDEM, PICDEM.net, PICkit, PICtail, PowerSmart, PureSilicon, QMatrix, REAL ICE, Ripple Blocker, RTAX, RTG4, SAM-ICE, Serial Quad I/O, simpleMAP, SimpliPHY, SmartBuffer, SmartHLS, SMART-I.S., storClad, SQI, SuperSwitcher, SuperSwitcher II, Switchtec, SynchroPHY, Total Endurance, TSHARC, USBCheck, VariSense, VectorBlox, VeriPHY, ViewSpan, WiperLock, XpressConnect, and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

SQTP is a service mark of Microchip Technology Incorporated in the U.S.A.

The Adaptec logo, Frequency on Demand, Silicon Storage Technology, Symmcom, and Trusted Time are registered trademarks of Microchip Technology Inc. in other countries.

GestIC is a registered trademark of Microchip Technology Germany II GmbH & Co. KG, a subsidiary of Microchip Technology Inc., in other countries.

All other trademarks mentioned herein are property of their respective companies.

© 2016-2021, Microchip Technology Incorporated and its subsidiaries.

All Rights Reserved.

ISBN: 978-1-5224-9218-4



## Worldwide Sales and Service

#### **AMERICAS**

Corporate Office 2355 West Chandler Blvd. Chandler, AZ 85224-6199

Tel: 480-792-7200 Fax: 480-792-7277 Technical Support:

http://www.microchip.com/ support

Web Address: www.microchip.com

Atlanta Duluth, GA

Tel: 678-957-9614 Fax: 678-957-1455

Austin, TX Tel: 512-257-3370

Boston

Westborough, MA Tel: 774-760-0087 Fax: 774-760-0088

Chicago Itasca, IL

Tel: 630-285-0071 Fax: 630-285-0075

Dallas

Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

Detroit Novi. MI

Tel: 248-848-4000

Houston, TX

Tel: 281-894-5983 Indianapolis

Noblesville, IN Tel: 317-773-8323 Fax: 317-773-5453 Tel: 317-536-2380

Los Angeles

Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608 Tel: 951-273-7800

Raleigh, NC Tel: 919-844-7510

New York, NY Tel: 631-435-6000

**San Jose, CA** Tel: 408-735-9110 Tel: 408-436-4270

Canada - Toronto Tel: 905-695-1980 Fax: 905-695-2078

#### ASIA/PACIFIC

Australia - Sydney Tel: 61-2-9868-6733

China - Beijing Tel: 86-10-8569-7000

China - Chengdu Tel: 86-28-8665-5511

China - Chongqing Tel: 86-23-8980-9588

China - Dongguan Tel: 86-769-8702-9880

China - Guangzhou Tel: 86-20-8755-8029

China - Hangzhou Tel: 86-571-8792-8115

China - Hong Kong SAR Tel: 852-2943-5100

China - Nanjing Tel: 86-25-8473-2460

China - Qingdao Tel: 86-532-8502-7355

China - Shanghai Tel: 86-21-3326-8000

China - Shenyang Tel: 86-24-2334-2829

China - Shenzhen Tel: 86-755-8864-2200

China - Suzhou Tel: 86-186-6233-1526

China - Wuhan Tel: 86-27-5980-5300

China - Xian Tel: 86-29-8833-7252

China - Xiamen Tel: 86-592-2388138

China - Zhuhai Tel: 86-756-3210040

#### ASIA/PACIFIC

India - Bangalore Tel: 91-80-3090-4444

India - New Delhi Tel: 91-11-4160-8631

India - Pune Tel: 91-20-4121-0141

Japan - Osaka Tel: 81-6-6152-7160

Japan - Tokyo Tel: 81-3-6880- 3770

Korea - Daegu

Tel: 82-53-744-4301

Korea - Seoul Tel: 82-2-554-7200

Malaysia - Kuala Lumpur Tel: 60-3-7651-7906

Malaysia - Penang Tel: 60-4-227-8870

Philippines - Manila Tel: 63-2-634-9065

Singapore Tel: 65-6334-8870

**Taiwan - Hsin Chu** Tel: 886-3-577-8366

Taiwan - Kaohsiung Tel: 886-7-213-7830

Taiwan - Taipei Tel: 886-2-2508-8600

Thailand - Bangkok Tel: 66-2-694-1351

Vietnam - Ho Chi Minh Tel: 84-28-5448-2100

#### **EUROPE**

Austria - Wels Tel: 43-7242-2244-39 Fax: 43-7242-2244-393

**Denmark - Copenhagen** Tel: 45-4485-5910 Fax: 45-4485-2829

Finland - Espoo Tel: 358-9-4520-820

France - Paris Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

Germany - Garching Tel: 49-8931-9700

Germany - Haan Tel: 49-2129-3766400

Germany - Heilbronn Tel: 49-7131-72400

Germany - Karlsruhe Tel: 49-721-625370

**Germany - Munich** Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

Germany - Rosenheim Tel: 49-8031-354-560

Israel - Ra'anana Tel: 972-9-744-7705

Italy - Milan Tel: 39-0331-742611 Fax: 39-0331-466781

Italy - Padova Tel: 39-049-7625286

**Netherlands - Drunen** Tel: 31-416-690399 Fax: 31-416-690340

Norway - Trondheim Tel: 47-7288-4388

Poland - Warsaw Tel: 48-22-3325737

Romania - Bucharest Tel: 40-21-407-87-50

**Spain - Madrid** Tel: 34-91-708-08-90 Fax: 34-91-708-08-91

**Sweden - Gothenberg** Tel: 46-31-704-60-40

Sweden - Stockholm Tel: 46-8-5090-4654

**UK - Wokingham** Tel: 44-118-921-5800 Fax: 44-118-921-5820

#### Affected Catalog Part Numbers(CPN)

PIC16F15354-E/5NVAO

PIC16F15354-E/ML

PIC16F15354-E/MV

PIC16F15354-E/SO

PIC16F15354-E/SP

PIC16F15354-E/SS

PIC16F15354-E/SSVAO

PIC16F15354-I/ML

PIC16F15354-I/MV

PIC16F15354-I/SO

PIC16F15354-I/SP

PIC16F15354-I/SS

PIC16F15354T-E/5NVAO

PIC16F15354T-E/ML

PIC16F15354T-E/SSVAO

PIC16F15354T-I/ML

PIC16F15354T-I/MV

PIC16F15354T-I/SO

PIC16F15354T-I/SS

PIC16F15354T-I/SSC01

PIC16F15355-E/ML

PIC16F15355-E/MV

PIC16F15355-E/SO

PIC16F15355-E/SP

PIC16F15355-E/SS

PIC16F15355-E/SSVAO

PIC16F15355-I/ML

PIC16F15355-I/MV

PIC16F15355-I/SO

PIC16F15355-I/SP

PIC16F15355-I/SS

PIC16F15355-I/SSVAO

PIC16F15355T-E/ML

PIC16F15355T-E/MV

PIC16F15355T-E/SS

PIC16F15355T-E/SSV01

PIC16F15355T-E/SSVAO

PIC16F15355T-I/ML

PIC16F15355T-I/MV

PIC16F15355T-I/SO

PIC16F15355T-I/SS

PIC16F15355T-I/SSVAO

PIC16LF15354-E/ML

PIC16LF15354-E/MV

PIC16LF15354-E/SO

PIC16LF15354-E/SP

PIC16LF15354-E/SS

PIC16LF15354-I/ML

PIC16LF15354-I/MV

PIC16LF15354-I/SO

PIC16LF15354-I/SP

PIC16LF15354-I/SS

PIC16LF15354T-E/ML

PIC16LF15354T-I/ML

PIC16LF15354T-I/MV

PIC16LF15354T-I/SO

PIC16LF15354T-I/SS

PIC16LF15355-E/5NVAO

PIC16LF15355-E/ML

PIC16LF15355-E/MV

PIC16LF15355-E/SO

PIC16LF15355-E/SP

PIC16LF15355-E/SS

PIC16LF15355-I/ML

PIC16LF15355-I/MV

PIC16LF15355-I/SO

PIC16LF15355-I/SP

PIC16LF15355-I/SS

PIC16LF15355T-E/5NVAO

PIC16LF15355T-E/ML

PIC16LF15355T-E/MV021

PIC16LF15355T-I/MV

PIC16LF15355T-I/MV020

PIC16LF15355T-I/SO

PIC16LF15355T-I/SS