



Product Change Notification

Current Date: 29-Apr-2022

TE Connectivity

Product Change Notification: PCN-22-136405

PCN Date: 23-APR-22

Customer: Future Electronics(0000080100)

Location: WORLDWIDE

Agreement: Agreement Unknown

TE would like to inform you of the following change(s) to the listed TE Connectivity Product. In case of any further questions about this change(s), please contact your TE Connectivity Sales Engineer. Affected part, drawing and/or specification numbers are listed on the attached sheet(s).

General Product Description:

8P Mod jack , SE

Description of Changes

Bulk Package to Tray Package

Current package method



New package method



Other attachments:

[Drop test report](#)[Package change from bulk package to soft tray](#)

Reason for Changes:

Packaging improvement

PCN Attributes:

Product Category:

Connectors

Kind of Change:

Specification

Change Feature:

Packaging Specification TE

Potential Customer Impact:

No Customer Impact

Remarks:

Estimated Dates:

Last Order Date (Obsolete Parts Only):

First Ship Date of Changed Items (Changed Parts Only):

18-JUL-2022

Last Ship Date of Changed Items (Obsolete Parts Only):

Last Date for Mixed Shipments: (Changed Parts Only):

No Mixed Shipments

Effectivity Date:

Date of First Samples:

Part Number(s) being Modified:

Part Number	Part Discontinued per PCN	Customer Drawing	Customer Part Number	Alias Part Number(s)	Substitute Part Number	Substitute Alias Part Number(s)	Description Of Difference
100190-2	NO						

Customer: Future Electronics Inc (184927)

Location: Pointe Claire

Agreement Number: Agreement Unknown

Part Number(s) being Modified:

Part Number	Part Discontinued per PCN	Customer Drawing	Customer Part Number	Alias Part Number(s)	Substitute Part Number	Substitute Alias Part Number(s)	Description Of Difference
100190-2	NO						

Customer: Future Electronics Inc (1290208)

Location: Southaven

Agreement Number: Agreement Unknown

Part Number(s) being Modified:

Part Number	Part Discontinued per PCN	Customer Drawing	Customer Part Number	Alias Part Number(s)	Substitute Part Number	Substitute Alias Part Number(s)	Description Of Difference
100190-2	NO						



TEST RECORD Tyco Electronics AMP GUANGDONG LTD.	Title of Test <input type="checkbox"/> Vibration <input checked="" type="checkbox"/> Free Drop Test <input type="checkbox"/> Transportation		Test Number CPK-202204001	
	Tester Hero Cheng		Date Started 13/Apr/2022	Date Complete 13/Apr/2022
	Checker Trustin Zhang			
Requester QE(Juan Wu)	Test Location Test Lab, Tyco / AMP Guangdong Ltd		Product Weight 4.52 kg	Quantity per Box 1260 pcs/box
Product Description PN 3-215877-1, MODULAR JACK SIDE ENTRY, 8 POS			Part No 3-215877-1	No of Boxes 1

TEST PROCEDURE:

- ISTA 1A
 10kg less than ; 760mm, 10-19kg less than ;610mm
 (10 locations ; 1-corner, 2-btm edge(W), 3-btm-edge(L), 4-edge(H), 5,6,7,8,9,10-6 panels)
- ISTA 2A
 10kg less than ; 970mm, 10-19kg less than ;810mm
 (10 locations ; 1-corner, 2-btm edge(W), 3-btm-edge(L), 4-edge(H), 5,6,7,8,9,10-6 panels)
- 109-132-2 Tyco Electronics, Test specification
 Up to 9.06kg incl. ; Assurance level –1(609mm),level-2(381mm),level-3(229mm)
 (6 locations ; 1-btm, 2-btm edge(W), 3-btm-edge(L),4-btm corner, 5-btm corner,6-top)
- JIS Z 0200
 Up to 10kg incl. ; Assurance level –1(800mm),level-2(600mm),level-3(400mm)
 (10 locations ; 1-corner, 2-btm edge(W), 3-btm-edge(L), 4-edge(H), 5,6,7,8,9,10-6 panels)

CONDITIONS:

Drop height **760 mm**
 Temperature 26.3 degrees
 Humidity 60%
 Box Size **380L-380W-200H (mm)**
 Box Type RSC FOL
 Impact Surface Concrete floor
 Remarks weather : Sunny

PRODUCT DESCRIPTION:

Pkg method: 210 pcs/bag x 6 =1260 Pcs/shipping box
 The detail packaging instruction is according to PS 107-107766 Rev A.
---Test result: There are no any products damaged and defect after drop test.
---The corner of shipping box impacted were distorted, but not damaged

RESULTS:

Test Result: Passed Failed

NG Ratio

0%, 0 pcs (NG) / 1260 pcs (OK) : 1 BOX



Photo






Packaging Change from bag to Soft Tray for MODULAR JACK SIDE ENTRY, 8 POS

18-Apr-2022

EVERY CONNECTION COUNTS





Change from bag to Soft Tray for MODULAR JACK SIDE ENTRY, 8 POS

Bulk in bag packaging

Soft Tray packaging



Affected PNs : 3-215877-1 and 100190-2

Reason for change:- Connector Deformation may happen during transportation so changing to soft tray Package to avoid deformation.